

THE WATERLILIES



NYMPHÆA GIGANTEA VIOLACEA.

THE WATERLILIES

A MONOGRAPH OF THE GENUS NYMPHAEAE

BY

HENRY S. CONARD

*Senior Harrison Fellow in Botany
University of Pennsylvania*



PUBLISHED BY
THE CARNEGIE INSTITUTION OF WASHINGTON
1905

CARNEGIE INSTITUTION OF WASHINGTON

PUBLICATION No. 4

SL.760,041272

The Lord Baltimore Press
THE FRIEDENWALD COMPANY
BALTIMORE, MD., U. S. A.

18365

PREFACE.

This work is the outcome of four years' study on the Harrison Foundation in the University of Pennsylvania. It would have been difficult or impossible without the generous support given by the Provost and the Board of Trustees. In the University Botanic Garden over thirty species and varieties of waterlily were cultivated, and several hybrids originated. These and other collections of living plants furnished excellent material for the present review of the group.

Nothing like a complete synopsis of the Waterlilies has hitherto been put before the English-speaking world. DeCandolle made a special study of the genus *Nymphaea* for his *Prodromus*, and both Lehmann and Planchon gave much attention to the genus from 1850 to 1853. Beginning in 1855 and continuing until 1888, a number of exhaustive treatises by Robert Caspary went far toward perfecting our knowledge of these plants. Indeed, had the learned doctor of Königsberg assembled his vast knowledge into one connected whole, the present work would be needed chiefly as a translation. Since his day, however, great strides have been made in the culture and hybridization of waterlilies, with the result that they now appear in almost every collection of plants. Already by crossing and recrossing and the use of horticultural names, serious confusion exists concerning the identities of the parent species. It has therefore seemed important to bring together the knowledge of the genus in all of its botanical relations and in its bearings on human life and history. In the present attempt there may be many omissions, in spite of the utmost efforts in collating the material, but the paper may serve to show how incomplete is our knowledge of any one group of plants, and it is hoped that it may make the way of the future investigator easier.

In the adoption of the generic name *Nymphaea*, the writer regrets that he is at variance with a number of American botanists for whom he has the utmost respect; but a glance at the synonymy of *Nymphaea*,

page 125, shows the leading facts. It seemed patent to the writer that all of the general, and several special, arguments against a change of name are particularly cogent in the present example. The new code, however, proposed by a committee of the Botanical Club of the American Association for the Advancement of Science, seems to sanction the nomenclature here chosen.¹ In the use of specific names, authorities have been omitted wherever possible, since the names adopted in Chapter V are followed. Citations of literature are based on the bibliography on pages 243 to 263.

Throughout the time occupied by the preparation of this work, I have been deeply indebted to Professor John M. Macfarlane, to whom I desire to express my gratitude.

To Mr. William Tricker, formerly of Riverton, N. J., and through him to the Henry A. Dreer Co., of Philadelphia, I am under obligation for the privilege of studying their magnificent collection of waterlilies. Acknowledgment is also due to Dr. J. W. Harshberger, of the University of Pennsylvania, and Dr. J. N. Rose, of the National Herbarium, for suggestions and herbarium material; to Mr. A. J. Mela, of Helsingfors, Finland; J. J. Soar, of Little River, Fla.; Wm. Gollan, Saharanpur, India; Wm. Fawcett, of Kingston, Jamaica; R. M. Gray, gardener to O. Ames, North Easton, Mass.; Gopal Chandradatta, Calcutta, India; Sr. Alberto Löfgren, director of the Botanical Garden of Sao Paulo, Brazil; the director of the Royal Botanic Garden of Tokyo, Japan; to the Gray Herbarium, Boston Natural History Society, Massachusetts Horticultural Society, Columbia University; to the Academy of Natural Sciences of Philadelphia for library facilities; and to John B. Lieberg, Joseph H. Painter, Chas. C. Abbott, Prof. Conway MacMillan, Albert J. Edmunds, E. D. Sturtevant, and C. G. Pringle for various courtesies. Mr. Frederick V. Coville and Mr. J. C. Bay, of Washington, D. C., have also given helpful aid and criticism while the matter was going through the press.

In order to give the greatest possible accuracy to the taxonomic portion of the monograph, I was enabled by the trustees of the Carnegie Institution of Washington to examine important type material in several European herbaria, viz, in Kew, British Museum, Linnaean Society, Muséum d' Histoire Naturelle, the herbaria of De Candolle, Delessert, and Barbey-Boissier, and the herbaria of Munich, Berlin, and Copenhagen. The results of this trip were very valuable, thanks to the courteous assistance

¹ Bulletin Torr. Bot. Club, 31: 249-290. May, 1904.

of those in charge of the various collections. The principal changes resulting in the manuscript were in the addition of a few species.

That the book appears in its present form is also due to the Carnegie Institution, on account of their acceptance of the manuscript for publication. Were it not for this privilege, much of the illustrative material must have been omitted. These many obligations I have felt keenly, and have tried in a measure to meet by conscientious care in the execution of every detail.

UNIVERSITY OF PENNSYLVANIA,
PHILADELPHIA, December 1, 1904.

HENRY S. CONARD,
Senior Harrison Fellow.

CONTENTS.

	PAGE
PREFACE	iii-v
DESCRIPTION OF PLATES	ix-xi
LIST OF TEXT FIGURES	xii-xiii
I. HISTORY	3
Oriental Literature	3
Pre-Linnaean Literature	10
II. STRUCTURE	27
The Root	28
The Stem	37
The Leaf	54
The Flower, Fruit, and Seed	77
III. DEVELOPMENT	95
Organogeny and Embryology	95
Germination and Early Growth	106
IV. PHYSIOLOGY	113
V. TAXONOMY	125
Nymphaeae Apocarpiae	127
Anecphyta	127
<i>N. gigantea</i>	128
Bogachyceras	131
<i>N. elegans</i>	131
<i>N. ampla</i>	134
<i>N. flavo-virens</i>	137
<i>N. stellata</i>	140
<i>N. caerulea</i>	141
<i>N. micrantha</i>	146
<i>N. heudelotii</i>	147
<i>N. ovalifolia</i>	150
<i>N. calliantha</i>	151
<i>N. capensis</i>	153
<i>N. sulfurea</i>	161
<i>N. stuhlmanni</i>	161

	PAGE
V. TAXONOMY—Continued.	
Nymphaeae Syncarpiae	163
Castalia	163
<i>Xanthantha</i>	163
<i>N. mexicana</i>	163
Chamaenymphaea	167
<i>N. tetragona</i>	167
<i>N. fennica</i>	170
Eucastalia	171
<i>N. candida</i>	172
<i>N. alba</i>	175
<i>N. odorata</i>	179
<i>N. tuberosa</i>	189
Lotos	192
<i>N. lotus</i>	194
<i>N. zenkeri</i>	197
<i>N. pubescens</i>	198
<i>N. rubra</i>	199
Hydrocallis	200
<i>N. amazonum</i>	200
<i>N. rudgeana</i>	204
<i>N. blanda</i>	206
<i>N. lasiophylla</i>	207
<i>N. gardneriana</i>	208
<i>N. jamesoniana</i>	209
<i>N. stenaspikota</i>	209
<i>N. tenerinervia</i>	210
<i>N. oxypetala</i>	210
<i>N. gibertii</i>	210
VI. DISTRIBUTION	213
Geographical	213
Geological	215
VII. HYBRIDS AND GARDEN VARIETIES	219
General	219
Taxonomic	225
VIII. CULTURE AND USES	235
BIBLIOGRAPHY	243
INDEX	265

DESCRIPTION OF PLATES.

- PLATE 1. Frontispiece. *Nymphaea gigantea violacea*. From a painting made by Mrs. E. Rowan, in the Cape York Peninsula, Australia.
- PLATE 2. *Nymphaea odorata*. 1-7, development of leaf and stipules; 1, 2, front and back views of the same rudiment; 3, older; 4, 5, front and side views of one rudiment; 6, 7, front and back views; 8, rhizome with roots and leaves trimmed off, natural size; 9, transverse section of rhizome, natural size. A. Koronski del.
- PLATE 3. *Nymphaea gigantea*. Under side of leaf and details of flower. 1, anterior sepal; 2, outermost stamen; 3, inner stamens; 4, median petal; 5, vertical section of ovary; 6, outermost petal. Photograph from plant grown at University of Pennsylvania.
- PLATE 4. *Nymphaea elegans*. Flower and under side of leaf. From plant grown at University of Pennsylvania; stock of the Dreer Co. A. Koronski del.
- PLATE 5. *Nymphaea ampla*, from Caspary, 1878, pl. 28. 1, flower from hb. St. Petersburg, coll. B. Jaeger, No. 233, Hayti, with 149 stamens, 24 carpels; 2, leaf from hb. Geo. Engelmann, coll. Wright, No. 1857, Cuba; 3, flower, seen from the side; 4, rays of stigma and carpellary styles; 5, stamens (2-5 from the same specimen); 6, two carpels of a flower in hb. St. Petersburg, coll. Karwinski, 1841, in Colipa River, Mexico.
- PLATE 6. *Nymphaea flavo-virens* (*N. gracilis* Hort, not Zucc., 1832). Flower and under side of leaf. Photo. from plant grown at University of Pennsylvania, from stock obtained from the Dreer Co.
- PLATE 7. *Nymphaea stellata versicolor*. Under surface of leaf and details of flower. a, sepal; b-e, petals of successive whorls; f, stamens; g, closed flower. From plant grown by the Dreer Co. (Mr. W. Tricker), from seed sent by W. Gollan, Saharanpur, India.
- PLATE 8. *Nymphaea caerulea*. Flower and under side of leaf. From plant grown at University of Pennsylvania.
- PLATE 9. *Nymphaea micrantha*. 1, under side of leaf; 2, upper side with young plant developing; 3 caudex, with a branch; 4, scars of leaves and of a flower, from surface of a caudex, enlarged; 5, cross section of caudex; 6, longitudinal section of a caudex; 7, superficial tangential section through leaf cushions of Fig. 4; l, base of a petiole; f, base of a peduncle; 8, section a little deeper than 7; 9, same as 8, a little deeper. From a drawing in color by R. Caspary, now in hb. Berlin, by kind permission of the Directors.
- PLATE 10. *Nymphaea capensis*. Under side of leaf. From plant grown at University of Pennsylvania; stock from Dreer Co.
- PLATE 11. *Nymphaea capensis sansibariensis*. Flower and leaf. Plant grown at University of Pennsylvania; stock of Dreer Co. A. Koronski del.

- PLATE 12.** *Nymphaea sulfurea*. 1, 5, leaves viewed from the upper surface; 2, under side of leaf; 3, a closed flower; 4, fully open flower; 6, rhizome. From a co-type in hb. British Museum, by courtesy of the Curators. P. Highly del.
- PLATE 13.** *Nymphaea mexicana*. Flower and leaf, natural size. From plants grown at University of Pennsylvania, from roots collected in Little River, Fla., by Prof. J. M. Macfarlane. A. Koronski del.
- PLATE 14.** *Nymphaea tetragona*. Flower and under side of leaf, natural size. From plants grown by the Dreer Co.
- PLATE 15.** *Nymphaea alba rubra*, 1-21; *N. candida*, 22. *Nymphaea alba rubra*. 1, partly opened flower; 2, fully open flower on its last day; 3-8, petals; 9-12, stamens of successive whorls from outside inward, viewed from front, side and back; 13, ovary stripped of sepals, petals and stamens, from the side; 14 stigma and styles from above; 15, section of ovary; 16, pollen, from pole and from side; 17-19, fruits; 20, petal; 21, stigmatic lobes. *Nymphaea candida*. 22, flower cut in half. From drawings in color by R. Caspary, now in hb. Berlin, by kind permission of the Directors.
- PLATE 16.** *Nymphaea lotus*. Leaf, flower, transverse and vertical section of fruit. Photographed by P. Highley from a specimen coll. Schweinfurth, Nov., 1887, at Damietta, Egypt, in hb. British Museum, by courtesy of the Curators.
- PLATE 17.** *Nymphaea pubescens*. Flower and under side of leaf. From a plant grown by the Dreer Co. (Mr. Wm. Tricker), from seed sent by Mr. W. Gollan, Saharanpur, India.
- PLATE 18.** *Nymphaea rubra*. 1, flower of second day, between 9 and 9.30 a. m.; 2, flower at same time of third day; 3, flower at same time of first day; 4, flower of fourth day, between 8.45 and 9 a. m.; 5, sepal from outer and inner sides; 6, petals of first (at left) and second whorls; 7, petal of innermost whorl; 8-10, stamens from outer and inner sides; 11, 12, dry pollen; 13-15, pollen germinating in sugar solution; 16, 17, pollen, examined in citron-oil, 18, 19, in water, 20, in dilute sulphuric acid; 21, germinating pollen; 22, section of carpellary style; 23-26, hairs of ovary, 24 treated with potash; 27, pistil seen from above; 28, ovary of Fig. 3, with stamens; 29, ovary on second day. From color drawings by R. Caspary, in hb. Berlin, by kind permission of the Directors.
- PLATE 19.** *Nymphaea amazonum*. 1, closed flower after its first night; 2, fully open flower, second night between 4.30 and 4.45 a. m.; 3, the same flower on the first night between 4.30 and 5 a. m.; 4, sepal, inner side; 5, petal of outermost whorl, from without; 6, 7, 8, 9 petals of the next four whorls; 10-13, stamens of successive whorls; 14, 15, side and section views of ovary after the second night; 16, ovary after the first night; 17, transverse section of ovary; 18, 19, pollen, dry and in water; 20, epidermis of ovary. From color drawings by R. Caspary, in hb. Berlin, by kind permission of the Directors.
- PLATE 20.** *Nymphaea rudgeana*. 1, flower on its first night, 10.15 p. m.; 2, the same between 9.20 and 9.40 p. m.; 3, 4, ripe fruits; 5, closed flower after first night; 6, flower with 3 outer whorls of floral leaves removed; 7, sepal from within; 8, petal of outermost whorl; 9, petal of second whorl; 10, petal of fourth whorl; 11, stamen of outermost whorl of four; 12, stamen of second whorl of four; 13, stamen of third whorl of seven or eight; 14, 15, inner and innermost stamens; 16-19, views of ovary; 20, 21, 22, pollen in dilute sulphuric acid, dry, and in water; 23, ripe fruit with floral leaves removed; 24, transverse section of ovary; 25-27, sections of carpellary style at apex, just below the club-shaped apex, and at base; 28, papillæ of stigma. From color drawings by R. Caspary, in hb. Berlin, by kind permission of the Directors.

- PLATE 21.** *Nymphaea blanda*, *N. blanda fenzliana*, *N. tenerinervia*, *N. stenaspidota*. From Caspary, 1878, pl. 36. 1-7, *N. tenerinervia*, from a specimen coll. Martius at Joazeiro, Province of Bahia, Brazil. 1, flower; 2, lower surface of leaf; 3, apex of outer stamen; 4, of innermost stamen; 5, carpellary style; 6, upper surface of leaf, near the point of insertion of the petiole, showing series of raised dots and short raised lines; the arrow points to the insertion of the petiole; 7, outer surface of sepal showing short crowded raised lines; 8, outer surface of sepal of *N. stenaspidota* with raised dots between the rather long raised lines; 9-12, *N. blanda fenzliana*, specimen from San Juan de Nicaragua, in hb. Vienna. 9, young fruit; 10, 11, outer and median stamens, from hb. Bentham; 12, leaf; 13-16, *N. blanda*. 13, flower viewed from side, coll. Parker in British Guiana; 14, leaf of the same; 15, part of upper surface of same leaf, showing raphid-like lines and raised dots; 16, leaf of Meyer's type, coll. Dr. Rodscheid in the Essequibo River (from hb. Grisebach).
- PLATE 22.** *Nymphaea lasiophylla* and *N. rudgeana*, from Caspary, 1878, pl. 34. 1-7, *N. lasiophylla*. 1, 2, flower from face and back; 3, leaf, showing lower side, with distant lobes; 4, part of a larger leaf seen from above, lobes touching; 5, 6, outermost and innermost stamens; 7, part of lower surface of leaf marked with raised dots and branching lines; 8-19, *N. rudgeana*. 8, leaf of a plant from Jamaica, cult. in Berlin Botanical Garden; 9, 10, 11, stipules of three leaves of a Jamaica plant, cult. in Königsberg Botanical Garden; 12, fruit, raised at Königsberg; 13, another fruit, raised at Königsberg, with persistent sepals and petals; 14, Königsberg fruit in median section; 15, small flower, coll. Poeppig, No. 3033, 1832, in the Island of Colares of the Amazon, in hb. Berlin; 16, sepal of a flower, coll. Sello at Victoria, Brazil; 17, 18, stamens of this flower; 19, apices of median and innermost stamens showing a narrow rim of the connective, but no appendage.
- PLATE 23.** *Nymphaea jamesoniana*, from Caspary, 1878, pl. 32. 1, 2, flower from front and back, in hb. Boissier; 3, sepal; 4, 5, innermost, outer and outermost stamens; 6, 7, leaves, from hb. St. Petersburg and hb. Lehm; 8, part of leaf from beneath, showing forked branching lines and raphid-like idioblasts.
- PLATE 24.** *Nymphaea stenaspidota* and *N. gardneriana*, from Caspary, 1878, pl. 33. 1-3, *N. stenaspidota*. 1, whole plant from type of hb. Lehm; 2, flower; 3, part of leaf, upper surface, showing raised dots, the arrow points toward point of insertion of petiole; 4-11, *N. gardneriana*. 4, flower, from hb. Vienna; 5, sepal; 6, 7, upper part of outermost, median and innermost stamens; 8, 9, 10, leaves; 11, upper surface of leaf showing series of raised dots, with raphid-like lines interspersed, the arrow as in Fig. 3.
- PLATE 25.** *Nymphaea oxypetala*, from Caspary, 1878, pl. 31. 1, 2, flower, from hb. Boissier, from face and back; 3, 4, outermost and innermost stamens; 5, three carpellary styles, with surface of stigma and axile process; 6, 7, leaves from hb. Lehm. and St. Petersburg; 8, globose idioblasts of inner face of anther at the point of Fig. 3.
- PLATE 26.** *Nymphaea pennsylvania* = *N. caerulea* × *zansibariensis*. From the original plant grown at University of Pennsylvania. A. Koronski del.
- PLATE 27.** *Nymphaea capensis* × *zansibariensis*. Flower and under side of leaf. From plants raised at University of Pennsylvania.
- PLATE 28.** *Nymphaea elegans* × *zansibariensis*. Flower and under side of leaf. From plants raised at University of Pennsylvania.
- PLATE 29.** *Nymphaea flavo-virens* × *zansibariensis*. Flower and under side of leaf. From plants raised and bred at University of Pennsylvania.
- PLATE 30.** *Nymphaea omarana*, hybrid. Stock from Dreer Co. A. Koronski del.

LIST OF TEXT FIGURES.

	PAGE
Tail-piece.—Guest at a feast, with lotus (after Wilkinson)	1
Figure 1.—Nefer Tûm (after Wilkinson)	6
2.—Egyptian lotus (designs after Wilkinson)	7
3.—Pleasure boat in a pond of lotuses (after Wilkinson)	7
4.—"Taba Aegyptia." Facsimile from Matthiolus	15
5.—"Nymphaea alba." Facsimile from Lobelius	15
6.—Longitudinal section of root tip of <i>N. caerulea</i>	29
7.—True and false epidermis of roots	30
8.—Root of <i>N. odorata</i> , transverse section	32
9.—Contractile root of <i>N. flavo-virens</i> , transverse section	33
10.—Vascular bundles of the roots of <i>N. odorata</i>	36
11.—Development of air-canals	37
12.—Diaphragms in the air-canals of roots	38
13.—Rhizome of <i>N. tuberosa</i>	39
14.—Tubers	40
15.—Perennating body of <i>N. mexicana</i>	42
16.—Rhizome of <i>N. odorata</i> ; transverse section of internode	43
17.—Microscopic section of rhizome of <i>N. odorata</i>	44
18.—Caudex of <i>N. caerulea</i> ; transverse section	46
19.—Cork formation at base of root scar	47
20.—Details of leaf scar	48
21.—Transverse section of caudex of <i>N. flava</i>	50
22.—Course of vascular bundles at node of <i>Nymphaea flava</i>	51
23.—Vascular system of stolon of <i>N. rubra</i> ? at a node	52
24.—Stipules	55
25.—Collenchyma in petioles	57
26.—Sections of petioles and peduncles	59
27.—Types of vascular bundle	63
28.—Leaf of <i>N. flava</i>	65
29.—Epidermis of leaf, <i>N. tetragona</i>	67
30.—Leaf of <i>N. rubra</i> , vertical section	68
31.—Arrangement of vascular bundles in veins of leaf	71
32.—Development of mucilage hair of <i>N. alba</i>	72
33.—Hairs and hair-bases	73
34.—First leaves from germinating tubers	75
35.—Transverse sections of petioles of water-leaves	76
36.—Floral diagram for <i>Nymphaea</i>	80
37.—Details of anther and stigma	84
38.—Pollen	85
39.—Diagram of ovary (Brachyceras) in longitudinal section	86
40.—Diagram of ovary in transverse section	86
41.—The aril	91
42.—Sections of outer cell-layer of testa (after Weberbauer)	92
43.—Distribution of vascular bundles from the chalaza (after Chiffolot)	93

	PAGE
Figure 44.—Longitudinal section of seed	94
45.—Development of flower	99
46.—Ovule of <i>N. odorata</i> from a half-grown bud	102
47.—Embryo sac of <i>N. odorata</i>	102
48.—Embryology	105
49.—Seedlings of a hybrid <i>Nymphaea</i> of the Lotos group	108
50.—Seedling leaves	110
51.—First broad (submerged) leaf of <i>N. lotus</i> seedling	112
52.—A strong-growing waterlily in shallow water	119
53.— <i>Nymphaea elegans</i> , details of flower	132
54.— <i>Nymphaea flavo-virens</i> , details of flower	138
55.— <i>Nymphaea caerulea</i> , details of flower and fruit	142
56.— <i>Nymphaea heudelotii</i> , flower and leaves	148
57.— <i>Nymphaea heudelotii nana</i> , leaf and flowers	149
58.— <i>Nymphaea ovalifolia</i> , leaf and flower	150
59.— <i>Nymphaea calliantha</i> , leaf and flower	151
60.— <i>Nymphaea capensis</i> , details of flower	154
61.— <i>Nymphaea capensis zanzibariensis</i> , details of flower	158
62.— <i>Nymphaea stuhlmannii</i> , leaf and flower	162
63.— <i>Nymphaea mexicana</i> , details of flower and fruit	164
64.— <i>Nymphaea mexicana</i> , seedling leaves	165
65.— <i>Nymphaea tetragona</i> , details of flower	168
66.— <i>Nymphaea candida</i> , leaf	173
67.— <i>Nymphaea odorata</i> , details of flower and leaf	181
68.— <i>Nymphaea odorata minor</i> , details of flower	184
69.— <i>Nymphaea odorata gigantea</i> , details of flower	187
70.— <i>Nymphaea tuberosa</i> , details of flower	189
71.— <i>Nymphaea tuberosa</i> , tubers and water-leaves	190
72.— <i>Nymphaea tuberosa</i> , details of leaf	191
73.—Floral organs of the Lotos group	193
74.—Early leaves of the Lotos group, from germinating tuber	195
75.— <i>Nymphaea zenkeri</i> , flower and leaf	197
76.— <i>Nymphaea dumasii</i> , leaf (after Schenck)	216
77.— <i>Nymphaea pulcherrima</i> , details of flower	224
78.— <i>Nymphaea pennsylvanica</i> , details of flower	225
79.— <i>Nymphaea capensis</i> × <i>zanzibariensis</i> , details of flower	226
80.— <i>Nymphaea elegans</i> × <i>zanzibariensis</i> , details of flower	226
81.— <i>Nymphaea</i> "Wm. Stone," details of flower	227
82.— <i>Nymphaea</i> "Mrs. C. W. Ward," details of flower	228

THE WATERLILIES

BY

HENRY S. CONARD



CHAPTER I.

HISTORICAL.

ORIENTAL LITERATURE.

Man was probably impressed from the first with the grace and beauty of the waterlilies ; for their distribution is worldwide. There is evidence enough that the seeds and roots (tubers) of various species have been used for food by many savage races, as in Australia, Madagascar, West Africa and Central America ; but naturally it remained for more civilized peoples to rise to anything like an æsthetic interest. A Chinese writer of the eleventh century A. D., Chou Tun-I, is thus quoted in Giles's "Gems of Chinese Literature,"—

Since the opening days of the T'ang dynasty [600 A. D.], it has been fashionable to admire the paeony ; but my favorite is the waterlily. How stainless it rises from its slimy bed ! How modestly it reposes on the clear pool—an emblem of purity and truth !* Symmetrically perfect, its subtle perfume is wafted far and wide ; while there it rests in spotless state, something to be regarded reverently from a distance, and not to be profaned by familiar approach.

In my opinion, the chrysanthemum is the flower of retirement and culture ; the paeony, the flower of rank and wealth ; the waterlily, the Lady Virtue *sans pareille*.

Alas ! few have loved the chrysanthemum since T'ao Yüan-ming ; and none now love the waterlily like myself ; whereas the paeony is a general favorite with all mankind.

The waterlily of China is the little *Nymphaea tetragona*, which, though pure white and of pleasant scent, never attains to much more than a pigmy size ; and its odor is not nearly so rich as that of our own *N. odorata*. It is interesting also to note that our author is expressing only a personal opinion, one which is not at all general, and which indeed may be regarded as heretical.

India is much richer in gorgeous varieties of waterlily than any other portion of the globe. By day the blue *N. stellata* exhibits several shades of color, even running off by degrees into pink in parts of Bengal. At night and early in the morning the great white *N. lotus* and the deep crimson *N. rubra* expand their flowers 6 to 10 inches in

diameter, and the display is enriched by every shade of color connecting the one form with the other. That these have found place in the rich literature of the Hindus is quite certain. But some confusion has arisen on account of the presence and importance of *Nelumbo nucifera*, the pink-tipped sacred lotus of India. *Nelumbo* is unquestionably the sacred plant of the Buddhists, the flower upon which Buddha sits, the *padma* of the Hindu prayer. The only question is whether the few statements assigning a religious value to *Nymphaea* are to be entirely disregarded, or whether plants of this genus did really receive a minor degree of worship. "Lotus-eyed," "lotus-hearted" and the figure of water on the lotus leaf, all so frequent in Sanskrit literature, certainly refer to *Nelumbo*.¹ But when we read in the Mahabharata (Vana Parva, ch. 307, 19) of a hero "possessed of a complexion bright as the copper-colored lotus leaves," we think at once of *N. rubra* or its varieties. An examination of the Sanskrit, however,² reveals that the root *padma* occurs here (*padmatâmradalajjvalam*), showing that the plant in the poet's mind was *Nelumbo*, and we may translate "lotus-petals" in place of "lotus-leaves," improving the simile. Again in Adi Parva (ch. 1, 86) we read "As the Full-Moon with its mild light opens the buds of the waterlily, so does this *Purana* with the light of *Sruti* expand the human intellect." This waterlily is probably *N. lotus* or *N. rubra*, as they are night bloomers. Kâlidâsa makes a similar reference in *Sakuntala*,

"And now
While the round Moon withdraws his looming disc
Beneath the western sky, the full-blown flower
Of the night-loving lotus sheds her leaves
In sorrow for his loss, bequeathing naught
But the sweet memory of her loveliness
To my bereaved sight:" (Williams, 1856, p. 92.)

There is some poetic license here; for *Nelumbo* does not open at night, but does shed its petals when full-blown, while *Nymphaea lotus* opens at night, but retreats under water after three nights, taking its petals with it! It seems, however, that *N. lotus* is the plant referred to; for Williams adds in a note (p. 14) that "the moon is often called the 'lover or lord of the lotuses'."

¹ Cf. Dhammapada, ch. iv, 58, 9; ch. xxvi, 401; Müller 1881. Mahabharata, Adi Parva, ch. 122, 29; ch. 199, 11; Vana parva, ch. 5, 16; ch. 231, 13; ch. 307, 23; Dutt 1895.

² Kindly made for me by my learned friend Albert J. Edmunds of Philadelphia.

Nymphaea stellata is alluded to in the same poem (p. 15) thus—

“—— thoughtlessly attempts
To cleave in twain the hard acacia's stem
With the soft edge of a blue lotus leaf.”

Graceful and appreciative as are these literary references, and many such might be added, they cannot be regarded as having any religious significance. The Sanskrit words *utpala* and *kamala* for the blue lotus (*N. stellata*), *kumuda* the white night lotus (*N. lotus*) and *pundarika* white lotus flower, so far as we know, have no religious associations (Macdowell, Elwell, Lanman). Williams (p. 5, *notes*) states very pertinently that the lotus “is as favorite a subject of allusion and comparison with Hindu poets as the rose is with Persian.”

On the other hand, it is stated in an early number of the “Botanical Magazine” (1805) that when a Hindu once entered the study of Sir William Jones where a flower of *Nymphaea lotus* chanced to lie for examination, he “made prostrations before it” as though this were an act of piety. This reverence is further said to “pervade Hindostan, Tibet and Nepal.” Tratinnick (1822) considers the same species to be the sacred lotus of India, without giving evidence. Pickering (1879) records that *N. stellata* is said to be “distinctly figured in the cave-temples of Adjunta,” and that he himself saw it figured in Braminical cave-temples elsewhere in India. *Nymphaea rubra* appears as the “autumn lotus” in Dhammapada, 285, according to Pickering, and he thinks that this species may be the *padma* of the Hitopadesa and Vetala panchavinsati I; Graham is quoted as having observed it around Bombay, “in tanks, particularly in the neighborhood of caves or temples.” But to the writer, none of these records present any certain evidence of the religious importance of Nymphaeas in India. The account in the “Botanical Magazine” is the most suggestive, but is by no means conclusive, and the use of the flowers as decorative designs for temples indicates no more than an appreciation of their beauty. The presence of the plants themselves “especially near temples,” if the observation is trustworthy, may be explained both by the beauty of the flowers and the food-value of seeds and tubers. In the absence, therefore, of any direct evidence that waterlilies are regarded as sacred in India, I believe we have no sufficient reason for attributing this regard to them.

EGYPTIAN ARCHÆOLOGY.

In Egypt the relations of the waterlilies to the social and religious life were more extended. But after an impartial examination of the facts available, I am strongly of opinion that they received no worship or even reverence here. The teachings of archæological research were brought together long ago by Duppa (1813–1816), and to some extent by Tratinnick (1822), and more recently by Dr. Pleyte (1875), whereas the critical observations of Schweinfurth from 1882 to 1886 have added many interesting facts, and placed many points beyond the reach of doubt. In spite of a complete unanimity among scholars, considerable confusion exists in the popular mind as to the identity of the so-called Sacred Lotus of Egypt. In America, at least, *Nelumbo nucifera* is commonly styled




FIG. 1.—Nefer Tûm (after Wilkinson).

Sacred or Egyptian Lotus. But Pickering, Pleyte, Joret and Schweinfurth from the botanical side, and Wilkinson, at least, among archæologists, unite in the opinion that *Nelumbo* is never found on the ancient monuments, and that it was not known in Egypt before the advent of the Persians. Not until the Roman period did it find a place in Egyptian art; it does become more or less prominent at this time. But this comes within the limit of recorded history and is discussed in another place.

We must understand, therefore, that the “lotus” of the palmy days when Egypt was truly Egyptian was a waterlily native to the Nile Valley and Delta. Two species are figured on the monuments and tombs, *N. lotus*, the white night-lotus, and *N. caerulea*, the blue diurnal one; of these the latter occurs very much more frequently. Pleyte found the white lotus only on a single tomb, belonging to the XII dynasty, about 2500 B. C.;¹ this example, however, was plainly distinguishable from the allied species. Schweinfurth (1884 c) found petals of the white lotus along with those of the blue in the funeral wreaths of Ramses II and Amenhotep I, but he never observed any carvings or pictures of this plant, though he says Unger found such at Beni-Hassan. The lotus borne on the head of Nefer Tûm in one of his manifestations (Wilkinson, 1883, 2: 180; Wiedemann, 1897, p. 138) is long and obtuse and suggests

¹ Petrie's dates are followed throughout.

N. lotus rather than *N. caerulea*, but it is too much conventionalized to offer any conclusive argument (Fig. 1, *b*).

Since the leaves of the blue species are entire and its petals acute, whereas the white one has sharply dentate leaves and broad petals rounded at the apex, the difference is usually evident even in very crude representations (Fig. 2). We recognize the blue one easily in manifold applications. It occurs, according to Schweinfurth (1883 *b*), on all the ancient monuments of Egypt. The use of its tuberous rhizome for food, is said to have been given to the people by Menes, or perhaps even by Isis (Pickering; Diodorus). At convivial meetings a flower of the blue lotus was presented to each of the guests, and in feasts for the dead, the feasters delighted themselves with the color and odor of this lotus (Buckley). In a carving figured by Wilkinson, the guests are distin-




FIG. 2.—Egyptian lotus (designs after Wilkinson).




FIG. 3.—Pleasure boat in a pond of lotuses (after Wilkinson).

guished from the hosts and servants partly by their lotuses (see page 1, underneath title). In most of these picturings the flowers are considerably conventionalized, but Schweinfurth saw them in the temple of Ramses II at Abydos, and on coffins of the Ptolemaic period, distinctly painted blue. One of Champollion's figures shows a lotus with green sepals, blue outer petals and red inner petals, all of the parts being tipped with black; the red and black must have been inserted for love of variety! An interesting Theban picture shows a pleasure boat, being towed round a pond by three slaves; the water is represented by the characteristic wavy lines, and is made more vivid by a liberal sprinkling of lotuses, both leaf and flower, over the water-surface¹ (Fig. 3).

Just as the blue lotus appears in figures of social life and in recreation, it occurs as a favorite flower in religious observances. It is figured among offerings to the gods in the IV dynasty (Pickering;

¹ This lotus has also been found depicted on the pavement of the palace of Sardanapalus, but has evidently been copied by the Assyrian artists from Egyptian sources (Bonavia, 1894).

Pleyte), and stands in front of Osiris at the judgment of the dead (Buckley). "When the Egyptians approached the place of divine worship," Diodorus tells us, "they held the flower of the 'agrostis' in their hand, indicating that man had proceeded from a well-watered or marshy land, and that he required a moist rather than a dry aliment" (Wilkinson, 1: 428). This "agrostis" Wilkinson considers to be another name for the lotus (l. c. 3: 350). The god Nefer Tûm "was figured as a man crowned with an upspringing lotus flower (Fig. 1), a symbol of the resurrection, and of his power to grant continuous life in the world to come" (Wiedemann, p. 138). In one manifestation this is distinctly the blue lotus (Fig. 1, a). Ahi, an infant deity is "sometimes represented as sitting on the lotus flower," the vase from which the plant grows representing a lake of water (Wilkinson 3: 132-3). "Osiris, too, swam on a lotus leaf, and Harpocrates was cradled in one" (Whewell). Hâpi, or the Nile, a god widely known and honored, "was sometimes resolved into the Nile of Upper and the Nile of Lower Egypt, the lotus being considered emblematic of the former, and the papyrus of the latter; a design consisting of both plants tied together formed a favorite subject for the decoration of the royal throne, as typifying the king's rule over Upper and Lower Egypt" (Wiedemann, p. 145-6).

The use of flowers in funeral decorations seems to have been very prominent in the XIX to XXI dynasties. The custom was to lay wreaths and semicircles of flowers on the breast of the enwrapped corpse until the sarcophagus was quite packed with these floral tributes. Flowers of *Nymphaea caerulea* on petioles 18 to 20 inches long were fastened between the bands encircling the mummies of Ramses II and the priest Nisboni, scattered singly all over them (Schweinfurth 1883 *b*). Breast-wreaths consisting mostly of petals and sepals of the same plant, sometimes also with petals of *N. lotus*, were found in the coffins of Ramses II, Amenhotep I, Ahmes I (1580 B. C.), the priest Nisboni, the princess Nzi-Khonsu, and the mummy of the case marked KENT, from the XX and XXI dynasties, found at Deir-el-Bahari (Thebes) in July 1881. These are probably the "Egyptian wreaths" of Pliny and Plutarch, the "lotus garlands" of Athenæus. Most of these plant-remains date from nearly 2000 B. C., but those of Ramses II were renewed about 1100 B. C.; for in moving these sarcophagi at that time into their secret resting-place in the Valley of the Tombs of the Kings, to avoid the marauding hordes from the desert, that of Ramses was accidentally broken; a new coffin and new floral decorations were therefore supplied. The wreaths of

Amenhotep are perhaps older than the Trojan war ! (Schweinfurth, 1883 *b*). In every case the preservation of the vegetable relics was as perfect as in newly-dried herbarium specimens ; they were easily soaked out in water, and Schweinfurth was able not only to identify them beyond doubt and to find out the manner in which the wreaths were fastened together, but also to prepare and mount examples for the Boolak Museum, where his success is attested by eleven cases of plants. Specimens were also sent to the British and several continental museums. A wreath of lotus petals from the coffin of Ramses II was figured in *Nature*, in 1883 (Schweinfurth, 1883 *b*). Such a wreath consists of foliage leaves of *Mimusops schimperi* folded in two or in four and stitched together with fibers from the date-palm in such a manner as to clamp and hold the lotus petals without piercing them ; the whole was then strung on strips of leaves of the date-palm. The mummy marked KENT had small whole flowers of *N. caerulea* woven in the wreaths by means of papyrus threads. Sometimes, as in the case of the princess Nzi-Khonsu, the whole body of the mummy was covered several layers deep with these garlands laid in concentric semicircles from the chin downward. It is interesting to note in passing, that Schweinfurth was not able to detect the slightest difference between these ancient plant remains and the species now growing in Egypt. Either these species are not suffering transmutations, or the changes are infinitely slow. Of real importance, however, is the conclusion that since the species are unchanged, the climate also of Egypt must be very nearly the same as it was four thousand years ago. If this be true, the absence of Nelumbo and Papyrus from modern Egypt cannot be attributed to meteorological changes, but we are strengthened in the conclusion that these plants only existed there in ancient times through artificial, i. e. human, agencies, namely by cultivation.

Several additional references to the Egyptian lotus are unquestionably meant for a species of *Nymphaea*, but whether the blue or the white, the writer cannot now say. Bes, probably a god adopted from the negro tribes, was, at the end of the New Kingdom (500 B. C. ?) "fused with . . . and endowed with all the attributes of the young sun-god, and represented like him as sitting upon a lotus flower" (Wiedemann, p. 167). Plutarch says the Egyptians "characterize the sun as though it sprang every day fresh out of the lotus plant" (Wilkinson, 3: 132-3), and Proclus pretends that the lotus was particularly typical of the sun, which it appeared to honor by the expansion and contraction of its petals (l. c., p. 350). Wilkinson indicates that this lotus is always *N. lotus* L. (p. 132-3), but

in this he is certainly mistaken ; for the one referred to by Proclus is evidently diurnal, and therefore must be *N. caerulea*. The reader may also be warned against the statement of Prichard that "*Nymphaea lotus* and *N. Nelumbo* [= *Nelumbo nucifera*] appear plentifully on the sculptures of Thebes." The unanimous voice of later observers sufficiently negatives this.

So it appears that the lotus was enjoyed in many ways, but especially as an ornament, a thing of beauty. It was the emblem of the Nile God, for it was the evident product of the river. It was offered to Osiris as any treasured object is consigned to the gods. It was laid upon the bodies of the dead, but other plants could take its place at seasons of the year when the lotus was out of bloom. Thus we see no decided evidence that it was a sacred flower, or an object of worship. It was the "favorite flower in the hands of the Egyptians" (Wilkinson, 3: 132-3) as the rose or others might be in the hands of any modern people. It was the symbol of Nefer Tûm and the resurrection just as *Lilium longiflorum* has a similar significance with us and is used for decoration at Easter.

PRE-LINNÆAN LITERATURE.

The facts of the foregoing account are drawn from the researches of scholars during the past hundred years, and have had no influence upon the growth of botanical science. The beginnings of our present knowledge of the waterlilies are to be found in early Greek and Roman literature, from which a growth can be continuously traced. 'It is true, however, that classic writers became acquainted with one or two African species of *Nymphaea* by traveling in Egypt and noting the customs of the people and the plants which surrounded them. For example, Herodotus (Bk. 2, § 92) tells us that when the Nile "is full and has made the plains like a sea, great numbers of lilies (*χρίνον*), which the Egyptians call lotus (*λῶτος*), spring up in the water: these they gather and dry in the sun, then having pounded the middle of the lotus, which resembles a poppy, they make bread of it and bake it. The root also of this lotus is fit for food, and is tolerably sweet, and is round, and of the size of an apple." This evidently refers to a *Nymphaea*, probably to *N. lotus* L.; for the white-flowered form would be more likely to appeal to the writer as a "lily" than the blue *N. caerulea*. The description applies equally well to either species; perhaps, like most other early writers, Herodotus did not distinguish between the two, or did not notice

that there were two varieties. He goes on to mention other "lilies, like roses," with fruit "like a wasp's nest," and edible seeds "of the size of an olive stone"; this is evidently *Nelumbo nucifera*. He also uses the word "lotus" in book iv, par. 177, to designate a tree whose fruit is the food of the Lotophagi (Lotus-eaters) and their neighbors the Machyles, tribes of Northern Africa. This, the Forgetful Lotus, is a species of *Zizyphus*.

Theophrastus (Bk. 9, ch. 13), in a chapter dealing with various plants and roots, speaks of some which are "sour, others bitter, others sweet." "The sweet [one] called *nymphaea* (νυμφαία) is accustomed to grow in pools and marshes, as in the Orchomenian country, and Marathon, and the island of Crete. The Bœotians call it *madonia*, and eat the fruit. It bears large leaves upon (*supra*) the water; [these] ground and placed on wounds are said to stop blood. It is useful also as a drink for intestinal disorders." This has been generally accepted, I think correctly, to refer to *Nymphaea alba*, the common white waterlily of Europe. Theophrastus also describes *Nelumbo*, under the name of κύαμος.

A brief mention of the "lotus" of Egypt, evidently *Nymphaea*, occurs in the Historical Library of Diodorus Siculus, written about the beginning of our era. He says (Bk. I, ch. 3) it grows in great plenty in the delta of the Nile, and is used for bread. He too speaks of *Nelumbo*, but under the name of κβάριον. Celsus gives "lotus" in a list of therapeutic agents for "cooling the body." The word may not belong to the original manuscript, but may have been added in later copies. It is considered to stand for the Egyptian lotus as above.

Dioscorides, in his *Materia Medica*, devotes a chapter (112) in book iv to "the Egyptian lotus (λωτός δ' ἐν Αἰγύπτῳ γεννώμενος), which grows in plains flooded by the water" of the Nile. "The stem resembles that of κύαμος [*Nelumbo*], having a white flower like a lily (κρίνον) which, they say, opens at sunrise, and closes at sunset, and the head is altogether hidden under water, and again emerges at sunrise. The head is like a very large poppy; in it is seed (καμπός; *grana*) like millet, which the Egyptians dry and beat into bread. It has a root like a quince, which is also eaten both raw and cooked; when cooked it resembles the yolk of an egg." The identity of this with our *Nymphaea lotus* L. can scarcely be doubted. We find a difficulty in that *N. lotus* is a night-bloomer, and therefore could not possibly be thought by those familiar with it to sink under water at night. But *N. caerulea* grows with *N. lotus* in Egypt, and is a day-bloomer, closing into a very insignificant bud by

evening ; its flowers, however, are not white, but pale blue. We think, however, that *N. lotus* is the one meant by Dioscorides, as its tubers are larger than those of *N. caerulea*, it fruits more freely, and the fruits when ripening are devoid of all the floral envelopes except the bases of the outer stamens, exposing a large poppy-like ovary. The fruit of *N. caerulea* is surrounded by its four sepals and four alternating sepaloid petals, so that its ovary, though equally poppy-like, remains hidden. The story of its behavior at night is a traveler's tale, enlarged upon, as we shall see, by Pliny, and copied many times afterward. Three other kinds of "lotus" are given in Dioscorides : one is the tree of Herodotus' Lotophagi ; the other two are leguminous plants near to or part of our present genus *Lotus*. *Nymphaea* (νυμφαία) appears in book III, chapter 138. He says it grows in marshes and standing water ; has leaves like κιβώριον [Nelumbo], but smaller and more oblong, several from the same root, some floating and some submerged ; flower white, like a lily (κρίνον), with a bulb (χροκιδες) in the middle. "But when done blooming, there comes a round black body of the shape of an apple or a poppy-head, which contains copious, black, crowded seed, of a glutinous taste. Stem smooth, slender, black, like the stem of κιβώριον. Root (ρίζα) [Rhizome] black, rough, like a club (ριφαλοίδης) ; gathered in autumn." Dried and taken with wine, it is recommended for dysentery and bowel complaints ; it is also powerfully anaphrodisiac.¹ For all these uses the seeds are also good. It is called *Nymphaea* because it "loves a watery place" ; it is found plentifully (πολλή) in Elis in the river Anigros, and in Aliartia of Bœotia. This description all together is quite recognizable for *Nymphaea alba* ; the black ovary is the only discrepancy. There is, continues Dioscorides, another *nymphaea* [which is called *nymphona* (νυμφῶνα), and its flower *nouphar* (νοῦφαρ)] with leaves like the former, but the root [rhizome] white and rough, flowers yellow, brilliant, resembling a rose. This can be no other than a species of *Nuphar*. He describes further, in book II, two kinds of κύαμος, the Greek and the Egyptian ; the former appears to be a kind of bean, the latter *Nelumbo* ; the fruit of this (which is used for food) he calls κιβώριον or κιβώτιον, and the root, which is like that of a cane, is also eaten both raw and cooked, and is called κολοκᾶσια.

Pliny in several places in his *Natural History*, uses the word "lotos" for four different plants, the herb lotos, the Egyptian lotos, a shrub lotos (perhaps the pomegranate) and the tree lotos. The fruit of the second of

¹ "Eadem contra veneris insomnia bibitur, quae adimit : quin et aliquot diebus continuo pota, genitale flaccidum et enerve reddit." Edit. Sprengel, I: 479.

these (Bk. 22, chap. 21) he calls "lotometra" and states that the Egyptian bakers knead the flour of its seed with milk or water to make bread. He adds, to give the quaint English of Philemon Holland's free translation (p. 125). "There is not any bread in the world (by report) more wholesome and lighter than this, so long as it is hot; but being once cold, it is harder of digestion and becommeth weightie and ponderous." In book XIII (ch. 17) the "Egyptian lotus" (a *Nymphaea*) is described in almost the same words as those of Dioscorides: its occurrence and habitat, its poppy-like head, and seed resembling millet. He tells us that the Egyptians gather the heads, lay them in heaps until they putrefy, then wash the seeds clean, dry and grind them. Pliny repeats the story of the closing of the flower at sunset, stating only that it is covered with leaves until sunrise; also that the flower is white. But though he is more reserved in statement here than is Dioscorides, he goes farther in telling of the behavior of the "Egyptian lotus" in the Euphrates (chap. 18). There, he says, the flower is plunged beneath the water at evening, so deep that a man cannot reach any part of it with his hand; but after midnight it rises slowly, appearing above water again at sunrise. He tells us in addition that its root is covered with a black rind, and is good to eat, especially when boiled or roasted, and that it is excellent for fattening hogs. *Nelumbo* is mentioned by Pliny in two places under the names "*colocasia*," "*cyamos*" and Egyptian bean (*faba*). The description of *Nymphaea* in Bk. 25, ch. 7, reads much like that of Dioscorides. A few new features are introduced. The name and the plant, it is said, originated from a nymph who died of jealousy through love of Hercules; hence the plant is called by some Heraclion; but by others it is called *rhipsalos*, for its club-like rhizome (*radix*). It grows in water and has broad, floating leaves. The other features of the plant, its names, localities, and uses, and the yellow Thessalian variety are exactly as given by Dioscorides, and the identities of all these are subject to the same doubts and assurances as those given in discussing that writer.

At that remarkable banquet imagined by Athenæus, the conversation turned on Alexandria, whereupon one of the feasters tells about the "lotus" which grows in the marshes near that city in summer; "it bears flowers of two colors, one like that of the rose, and it is the garlands woven of the flowers of this color which are properly called garlands of Antinous; but the other kind is called the lotus garland, being of a bluish (*παύτα*) color" (Bk. 15, ch. 21). The first plant is probably *Nelumbo*, the second *Nymphaea caerulea* Sav.; we have here the first

mention of *Nelumbo* under the name of lotus, and the earliest Latin or Greek record of a blue Egyptian lotus. *Nelumbo* is frequently mentioned elsewhere by Athenæus, once again under the name of lotus, but more often as *κιβώριον*, *κύαμος αἰγύπτιος*, or *κολοzaσία* (Bk. 3, ch. 2). He says, at variance with all other writers, that the Egyptians call this plant lotus, but quotes the other names from Nicander, Theophrastus, Diphilus the Siphnian, and Phylarchus.

Galenus adds nothing to the facts and theories of his predecessors concerning these plants. He recognizes three kinds of lotus (Bk. 7, ch. 11), the herb, the tree and the Egyptian lotus (*Nymphaea*), and two kinds of *Nymphaea* (Bk. 7, ch. 13), one with black rhizomes and one with white; these correspond with Dioscorides' descriptions of *Nymphaea alba* and Nuphar. He simply mentions *Nelumbo*, under the name of *faba Aegyptia* (Bk. 1, ch. 20).

From this time onward we find nothing of note for our science until it revived with the Revival of Learning. William Turner in 1548 gives this quaint note in his catalogue of "The Names of Herbes:—"

"Nymphaea is also named in greeke nymphaia & madonais & is called in english water Roses, & some with the Potecaries cal it nenufar. The duch mē cal thys herbe Seeblumen. Boeth the kyndes of water Roses growe in standyng waters."

Mr. Britten (cf. Turner, 1548, p. 130) has identified "boeth the kyndes" as *Nymphaea alba* L. and *Nuphar lutea* Sm.

Three years later Fuchsius and Hieronymus Bock* (Tragus) in Germany published their botanical classics. The former has a rude woodcut of the white waterlily with the Latin name *Nymphaea candida* and the Greek *Νυμφαία λεύκη*. On the next page occurs "*Nymphaea lutea*," with a figure which identifies it with Nuphar.

Tragus goes into the subject much more extensively and shows evidences of personal observation. There are two kinds of "Seeblümen," the white and the yellow, of which the former is commoner. He compares the flower of this to a beautiful double (*gefüllt*) lily or rose, with each petal shaped like one's thumb; and in the midst of the flower is a golden yellow sun (*ein schöne goltgäle Sonnen*), and it is odorless. He describes the shape of the bud, and its green "outer leaves." The broad, round, disc-like foliage leaves, he says, are stiff and leathery, and grow on smooth hollow (*lucken*) stems. His figures are quite crude but recognizable, the "Weiss Seeblümen," as *Nymphaea alba*, the other

as Nuphar. A long list of common names is given: Wasser Gilgen, Haarwurz, Haarstrang, Nenuphar in apothecary books, Clavus Veneris, Digitus Veneris, Alga palustris, Papaver palustre. The account of the medicinal virtues of these plants does not materially differ from those previously given.

Matthioli, in his Commentary on Dioscorides (1554), transcribes the chapter on Nymphaea from that writer with numerous slight verbal




FIG. 4.—“*Faba Aegyptia*.”
Facsimile from Matthioli.




FIG. 5.—“*Nymphaea alba*.”
Facsimile from Lobelius.

changes. He understands “Nymphaea” to signify our *N. alba*, and gives “Nymphaea altera,” also called “blephara,” for Nuphar. The two are figured side by side in rude but quite recognizable cuts; but these may have been inserted by C. Bauhin, whose notes were added to the original in the edition which I have seen. On the identity of the Egyptian Nymphaea and Nelumbo, Matthioli was hopelessly at sea; for Nelumbo had been so long extinct in Egypt that nothing could be found there to correspond with the descriptions given by the classic writers. So, after much weighing of evidence, our author invented

a unique figure (Fig. 4) to show what this confused plant must be—a figure which formed the basis of a heated discussion for the next three quarters of a century. We can only refer to this in passing, since *Nelumbo*, and *Arum*, and *Colocasia* are the genera most nearly concerned.

Lobelius' "Observations of Plants" (1576) figures two "*Nymphaeas*," *alba* and *lutea*, and gives their medicinal virtues at length. The cuts are rude, but original and easily recognized (Fig. 5) as the species still bearing those specific names. In the "Adversaria Nova," *Nymphaea lutea* is given before *alba*, with most of the synonyms used by Tragus and in addition *Nenuphar officinarum*, *plompen* (Dutch), *Escudetes del Rio* and *Higos del Rio* (Spanish), *Water lilie*, *blanc d'eau* and *Lis d'estang*. From this time forward, *waterlily* is a term consistently used as a synonym for *Nymphaea* to the present day, except that in Devonshire, Eng., *Iris pseud-acorus* has shared the same common name (Friend, 1882). *Nymphaea alba* is not directly given any common name by Lobelius, but it is evident that some of those given above apply to it; he says it is sometimes called "major" to distinguish it from "*N. alba minor*," by which some small white flower, probably *Limnanthemum*, is designated. A "*Nymphaea lutea minor Septentrionalium*" is also figured; it may be our *Heteranthera*. "*Nymphaea*," therefore, would seem to be definable as an aquatic plant with evident flowers and floating leaves; the idea represented by the word is acquiring a more distributed content. "*Lotus Aegyptia*" (*Nymphaea lotus* L.) is discussed on pages 385 and 386, but Lobelius is unable to interpret the descriptions given by the older writers, and regards the whole thing as a fabrication. He seems to have no idea of such a plant as *Nelumbo*.

Lyte's Herball (1578) (*vide* Britten and Holland, 1879) gives a single name for the white and yellow waterlilies, viz., *nenuphar*. This name was also corrupted into "*ninnyvers*."

In 1589, Petrus Bellonus published observations from Greece, Asia, Egypt, &c.; he found nothing in Egypt to correspond with the old descriptions of *Nelumbo*, but found the word "*colocasia*" used for the root of an aroid which was used for food, as was already known by Matthioli. So he concluded that *Colocasia*, *Lotus*, and *Faba Aegyptia* were synonyms, and made vain endeavors to interpret Herodotus, Theophrastus, Dioscorides and Pliny in harmony with this view.

A great beam of light was shed on the subject, however, by Alpinus (1592), who made a special study of the Egyptian lotus. Finding no sign of *Nelumbo*, but only *nymphaeas* and aroids in Egypt, he considered the

ancient writers wrong in their synonymy ; colocasia, he said, was an aroid. "Lotus Aegyptia" he believed to be the white flower which, from its resemblance to the European waterlily, he had no hesitation in calling a "larger nymphaea" ; in fact he regards it as practically identical with the species so familiar about Venice. For both have the poppy-like head, and seed like millet, and both, he said, retreat under water at sundown to emerge again in the early morning, "as is observed by everyone in the common nymphaea" (*quae in communi nymphaea ab omnibus animadvertitur*). Indeed he was surprised that Pliny and others thought this behavior strange in the Egyptian lotus. Both flowers and leaves are submerged at night, according to Alpinus, the flowers emerging first, at sunrise, and a little later all the leaves appear. Of course this does not really occur ; but the flower of *Nymphaea alba* closes into a tight bud during the afternoon and is covered by the dull green sepals, to open again with the light of the next day ; the disappearance of the leaves, however, must have been purely owing to darkness, and their reappearance after the flower must have been due to their darker color. Alpinus stated that the white Egyptian lotus was called by the Arabs "nuphar," and by the Hebrews "Arais el Nil." After the publication of the work just discussed, Alpinus received numerous tubers of the Egyptian lotus from a Venetian doctor in Cairo ; they were of the size of a walnut, ovate, with fibrous roots, blackish outside, yellowish within ; they were said to be eaten freely by the Egyptians, both raw and cooked ; the sender also said that the plant resembled the lesser nymphaea (*N. alba* L.) except that the flowers were blue. "The which, if it be true, this is the lotus niloticus of Athenæus." Alpinus figures it with entire leaves, insuring its identity with *N. caerulea* Sav. At a still later date (1735 *b*), the same writer summed up the knowledge of the Egyptian lotus ("*Lotus Aegyptia*") in a "dissertation" on the subject. As synonyms are given *Lotus niliacum*, *Nymphaea*, and *Nuphar Aegyptium*. The flower and its stalk are called Arais el Nil, the leaf and petiole Bis el Nil, the root (tuber) Biarum. Four plates are devoted to it ; one shows the whole plant, with its dentate leaves, ovoid tuber and the fruit devoid of floral leaves ; another shows the calyx and fruit on a larger scale ; the third shows two fully open flowers, and the fourth gives an enlarged view of a leaf and a tuber. The flower is described as having the four outer leaves green outside and white within, each with five to seven or more longitudinal nerves, spreading wide open when in bloom. Within these are about 12 smaller leaves [petals], pure white ; then 25 to 40 long acute leaves [outer stamens],

white below and yellow above; then a fourth series of slender yellow leaves [stamens] and a fifth series of almost capillary members [innermost stamens], followed by a row of narrow incurved bodies [carpellary styles]. At the middle is a small, hard globule, and a head containing the seed. The fruit is round like that of *Nymphaea alba*, with a green cortex, and seed like that of cabbage. The peduncles are hollow, and of the size of one's finger. The leaves are crenate (the crucial point of the description), of a dark green color, and so numerous as to cover the whole surface of the water; they die away in November, so that Alpinus considered the plant annual, in spite of the fact that it comes up again at the next flooding of the Nile. The root, he says, is ovate, of the size of a hen's egg, blackish outside, yellowish inside, and tastes at once sweetish and astringent. This excellent description of *Nymphaea lotus* deserves permanent recognition. It represents a masterly attempt to bring order out of the chaos which then existed, and that by the true scientific method of observation. Had subsequent descriptions been as well written, many of our difficulties in nomenclature would not have arisen.

We may mention here, following the chronological order, that Philemon Holland, in 1601, translates the word *nymphaea* used by Pliny as "Nemphar"; this name for the waterlily must have been more or less common, therefore, in England at that time.

Clusius in his earlier works (1576 and 1601) continues the fruitless discussion of the relations of *Lotus*, *Faba Aegyptia* and *Colocasias*. Concerning *Lotus Aegyptia*, however, he quotes at length from the valuable text of Alpinus; but, ignoring the latter's excellent illustrations, he copies the crude figure of the white waterlily from Matthioli (in fact, the same block was evidently used in the printing), and introduces confusion by labeling it "*Nymphaea alba*. *Lotus Aegyptia Alpini*." Beside it appears Matthioli's cut of *Nuphar*, marked "*Nymphaea lutea major*." In 1605, however, he raised the cloud which obscured the Egyptian bean of classic writers by figuring and describing a fruit of *Nelumbo*, brought from Java by an intelligent sea-captain.

Dodonæus (1583) recognizes only two species of *Nymphaea*, namely *alba* and *lutea*. His figures of these are almost if not quite identical with those given by Lobelius, and his description and synonymy bear a striking resemblance to the text of Hieronymus Bock. The white species (*candida*), he says, has great, broad and nearly round, smooth, floating leaves on long, terete, smooth, porous petioles; flowers solitary, on similar stalks, composed of many oblong and acuminate leaves, in

the midst of which are many yellow stamens. After the flower, a round head is produced, in which are very many black, shining seeds, like millet. The rhizomes are thick, nodular, black outside, white and spongy within, fastened in the mud by many fibrous roots. In addition to the synonyms given by Lobelius, Dodonæus tells us that *Nymphaea* is *Nenuphar* of the shops, and that Apuleius gives the Latin names "*mater Herculania*," "*alga palustris*," "*clavum Veneris*," "*digitum Veneris*," and the Gallic name *Baditin*. To these Dodonæus adds *Wassermahnen* and *Haar-strang* of the Germans. The medicinal powers of the herb are discussed and the subject is then dismissed without any reference to the Egyptian species.

Besler's magnificent folio (1613) illustrates in color three kinds of *Nymphaea*: *N. alba major*, *N. alba minor*, and *N. lutea*, known now as *Nymphaea alba*, *N. candida*, and *Nuphar lutea* respectively. The description of "*N. alba major*" is given with singular accuracy in many details: leaves broad, smooth, thick, green, cleft to the petiole, etc.; *radix* spongy within, and marked with blackish scars (*foliorum vestigiis*), etc. In the figure, the characteristic round root-scars are very plain.

The material is now in hand for a satisfactory summing up of the knowledge of botany as determined by the progressive increase of accuracy and the widening horizon of science up to this time; and the summing up was duly made by Caspar Bauhin. In the *Pinax* (1623) he divides *Nymphaea* into two "genera," one with white flowers and black rhizome, the other with yellow flowers and white rhizome; the latter, called "*Nymphaea lutea*" includes *Nuphar* and some other types. The former, "*Nymphaea alba*," is divided into four species. The first of these, with its synonymy, is:

"*Nymphaea alba major*

Nenuphar album, Brunfelsius.

Nymphaea alba, Brunf. Matth. Ang. Dodon. Cord. hist. Lon. Ad. Lobel.

Taber. Thal. Ger. Clus. hist.

Nymphaea candida, Trag. Fuch. Tur. Caes.

Nymphaea major alba, Lugd. Cast. Eyst.

Lotus Aegyptia, Alpini."

The last synonym is unquestionably wrongly placed. The second species of Bauhin is "*Nymphaea alba minor*," being "*Nymphaea parva*, Matth." Whatever the plant may be, it is not a *Nymphaea* in the present sense; and the same may be said of the third and fourth species of Bauhin. The consideration reduces for our present purposes to a single species, in which, however, two, and possibly three, quite distinct plants are

included, namely, the European species *N. alba*, and perhaps *N. candida*, and the Egyptian white lotus, *N. lotus* L. The blue Egyptian lotus, *N. caerulea* Sav., mentioned by Athenæus and Alpinus, is quite left out.

A unique volume is Gerard's "Herball or Generall Historie of Plantes" published in 1636. Of his five "Water Lillies" only the first would now be placed in the genus *Nymphaea*; this is "*Nymphaea alba*, White Water Lillie," given in the index of the work, however, as "*N. alba major*." The second species is "*Nymphaea lutea*," our Nuphar; the others have no relationship with the *Nymphaeaceae*. The figures of the first, second, fourth and fifth species were apparently printed from the same blocks as were those of Matthiolus, and the text is but an abbreviated translation of the same writer. The Egyptian lotus is not mentioned at all by Gerard.

Vesling, editing Alpinus in 1640, recognized the difference between the European and Egyptian white waterlilies and discussed their relationships. He tells us also that the white lotus flower is woven into triumphal crowns.

In the same year Parkinson's fascinating "Theatrum" appeared; his archaic English is most entertaining. He gives a burning paragraph on the "Egyptian bean" question, having full knowledge of that plant (which we know as *Nelumbo*), and arraigning Matthiolus for his "false" and imaginary figure of it (Fig. 4). At no point does he refer to this plant as "lotus." In chapter 29 he gives "*Nymphaea*, the Water Lilly," with seven species:

1. *N. alba major vulgaris*, The great common white Water Lilly.
2. *N. alba major Aegyptiaca sive Lotus Aegyptia*, The great white Water Lilly of Egypt.
3. *N. alba minor* [Not a *Nymphaea* as now understood].
4. *N. alba minima quae et Morsus ranae vocatur*.
5. *N. lutea major* [Nuphar].
6. *N. minima lutea*
7. *N. lutea flore minore* } [Not *Nymphaea* as now understood].

The first is of course our *N. alba* L.; it is illustrated by a copy of Lobel's figure (Fig. 5). The second is our *N. lotus* L., and is accompanied by Alpinus' figure of the whole plant. Referring to the resting period of this plant in winter, Parkinson suggests—perhaps in criticism of Alpinus—that the plant has been therefore "called annual, but I would call it restible."

A compilation of former observations with valuable comments, was made by Bodaeus à Stapel in the 1644 (Amsterdam) edition of Theophras-

tus. He considered the word *Nenuphar* a corruption of the older Greek *nouphar*. But his description of the European waterlily is the valuable feature. The leaves, he says, are on long, terete, glabrous, porous peduncles, are approximately round, firm, almost coriaceous, for the most part floating on the water; upper surface smooth, distinctly veined beneath. Those which lie concealed below the water are thinner and softer. Flowers solitary, on stems like the petioles, made of many floral leaves, so that sometimes a single flower is composed of twenty-five to thirty or even forty leaves, each of the shape of one's thumb or a leaf of the greater *Sedum*. From the middle of the flower many yellow stamens project. Bud oblong, its outer leaves [sepals] purplish green. Flowers scentless, shining like the sun. Here, curiously enough, reappears the myth of its retreat below the water at evening and emergence at sunrise. The account continues: After the flower, there is produced a head like a poppy or round apple, with black shining seed, larger than millet. The rhizome (*radix*) is about as thick as one's arm, knotty, black outside, white and spongy within, odorless, tasteless, beset with and fastened in the mud by fibrous roots. Bodæus calls this plant "*Nymphaea alba major*." Two other varieties of "*N. alba*" and four of "*N. lutea*" are next described, but they are all outside our present genus *Nymphaea* and need not be considered here. At another place *Nymphaea lotus* is fully treated under the name of "*Lotus Aegyptia*," giving all of Alpinus' figures. Bodæus thinks this plant should not be classed with *Nymphaea* on account of its bulbous root. He thus differs in opinion from Alpinus, and especially from C. Bauhin.

Piso (1648) gives us the earliest account of an American *Nymphaea*, in a Brazilian species. "Among those plants," he says, "which are common to Europe and the western world is *Nymphaea*, called by the Brazilians *Aguapé*, by the Portuguese *Galvaon*, which is noticed everywhere floating on the surface of pools and still waters. The leaves are similar to our *Nymphaea*, with a great network of veins beneath." The flower has a pleasant odor, and consists of four green sepals and about twelve narrowly oblong, acute, white petals. Its medicinal virtues are also detailed. Just what species is here referred to cannot be positively identified, nor does the crude figure accompanying assist. But from the character and number of the petals, and the fact that we know of but one white day-blooming waterlily in Brazil, we have but little hesitation in referring it, as did Caspary (1878), to *N. ampla* DC.

Bontius, whose accounts of the East Indies were bound in with Piso's

of the West Indies in 1658, devotes considerable space to "*Nymphaea Indica flore purpureo*"; the figure and description relate very clearly to *Nelumbo* and may be omitted here.

Another new feature is introduced by Flacourt (1661) in his "History of the Great Island of Madagascar." He found there a blue waterlily, which was considered a delicious food. It is called by the natives "Tamtamou." Instead of being anaphrodisiac like the European species, this one provokes to excesses. The white waterlily, says Flacourt, is called in this country "Laze-Laze," and the yellow flowered one "Talifouc." The roots of all three are used for food. The identities of all of these are in the highest degree uncertain. The blue is probably *N. capensis* or *N. madagascariensis*. The white may be *N. lotus*, or a mere variety of the blue. The yellow one may be a *Nuphar*; at any rate, no yellow *Nymphaea* is known at present from that island.

Returning to the European flora, we may gather a few points from J. Bauhin's "Histoire des Plantes" (1670). Curiously enough he quotes the name *Nymphaea alba minor*, with the synonym *N. parva* Matth. from C. Bauhin, as signifying the European white waterlily, and adds a number of the common names given by Lobelius. The real identity of the plant is rendered certain by a crude picture. The peculiar mixing of the names remains unexplained.

Chabræus (1677) records five species of *Nymphaea*, viz.: *N. alba vulgaris*, *N. lutea*, *N. minor lutea Lobelii*, *N. minor lutea flore fimbriato*, *N. alba minor*. The last four would not now be classed in the genus *Nymphaea* at all. The figure of *N. alba vulgaris*, is an enlarged and very slightly modified copy from Fuchsius.

John Ray's "Catalogue of Plants of England" (1670) mentions five *Nymphaeas*, of which only the first, "*Nymphaea alba*," belongs in the genus as now constituted. The only information given in addition to the name is the words "*In fluviis. Florem habet plenum.*" The "Methodus Plantarum" of the same author (1682) is especially interesting for its freedom from slavery to the classic writers. The twenty-fifth genus contains "Anomalous herbs and those of uncertain position"; the first section of these is headed "Anomalaë Aquaticae," and the first of these is *Nymphaea*, plants with round to oblong, floating leaves, differing in their flowers. Three varieties are mentioned, of which "*N. alba vulgaris*" is the only true waterlily, the common white one of Europe. The "Historia Plantarum" (1688) follows the classification of the "Methodus" in general, but describes the European white water-

lily as *N. alba* simply. In many points the description is only a repetition of earlier writers; the flowers are said to be odorless, with the outer leaves greenish as in *Ornithogalum* (*ut Ornithogali*). A "*Nymphaea Brasiliensis*," known to the natives as *Aguapé*, and described in nearly the same words as used by Piso, is given here, on the authority of Marggrav's observations, and classed as belonging to *N. alba*. A fifth species is added, *N. alba major Aegyptiaca*. The specific description of this refers to the "crenate leaves" which identify it with *N. lotus* L., and the statement is added, "flores . . . semper supra superficiem aquae." The object of this addition comes out when in the succeeding paragraph the stories of Theophrastus, Pliny, and Alpinus are given regarding the retirement of the flower far under water at night, and the writer boldly concludes, "Nobis certe incredibilia videntur."

Jacobus Breynius (1680) is one of the few among the early botanists who considered new and foreign plants. His second *Prodromus* gives "*Nymphaea flore coeruleo odoratissimo*, Cap. bonae spei; nobis," and "*Nymphaea flore suave purpurascente Japonica*; nobis." The former is doubtless *N. capensis* Thunb., the latter *Nelumbo*.

The magnificent "*Flora Malabarica*" of Van Rhee (1692) contains figures of a number of water plants. In vol. II, plates 26, 27, 28 and 29 represent plants with floating leaves, all under the general Malabar name of *Ambel*. The first, called simply *Ambel*, is *Nymphaea pubescens*; the second, *Cit-Ambel* is the source of Willdenow's *Nymphaea stellata*, a blue-flowered waterlily. The other two, *Nedel-Ambel* and *Tsjeroa-Ambel* are *Limnanthemums*. All are quite fairly recognizable from the engravings, at least as to their generic position. It is interesting to note that the natives of the Malabar coast classed *Nymphaea* and *Limnanthemum* under the same type or genus, just as did their European contemporaries. The text accompanying the plates refers chiefly to the medicinal properties of the plants.

In 1696 Commelin published Latin names and synonymy for the species illustrated by Van Rhee. To *Ambel* he gave the title "*Nymphaea indica, flore candido, folio in ambitu serrato*," although he regarded it as identical with the Egyptian white lotus according to Parkinson, Alpinus, and Vesling. *Cit-Ambel* was dubbed "*Nymphaea malabarica minor, folio serrato*" and was a new species to European botany.

Perhaps the most magnificent and exhaustive botanical work of the pre-Linnæan period is the "*Phytographia*" of Plukenet (1691-96), with its exquisite engravings and its several companion volumes of text. We

cannot tell exactly what this writer understood by the term *Nymphaea*; for of the four varieties figured in the *Phytographia*, one appears to be *Trientalis*, another is plainly *Marsilia*, a third is *Nelumbo*, and the fourth *Limnanthemum*. The genus is still more comprehensive in the "*Amaltheum*" (1705), including in addition to those above mentioned our *Nymphaea alba* and *N. lotus* as well as *Nuphar*, *Hydrocharis*, *Podophyllum*, and some others whose brief descriptions are unrecognizable. Several of these had been much more scientifically disposed of by earlier authors with whose writings Plukenet was fully conversant. In the "*Mantissa*" (1700) *Brasenia* and *Pistia* are added as species of *Nymphaea*, additions which one can easily understand. *Nymphaea capensis* is also given under the name and on the authority of Breynius as quoted above, but it is confused with *Nelumbo*. Finally an American terrestrial plant classed by previous writers as a *Brassica*, is here classed as a species of *Nymphaea*. The white *Nymphaea* or Laze-Laze of Flacourt is referred by Plukenet in the "*Amaltheum*" to his "*Nymphaea Indiae*" (*Nelumbo*). Plukenet brings in no new information for our subject.

In 1707 Sloane described a white flowered *Nymphaea* with the edges of the leaves "deeply cut," from the "Fresh River" in Jamaica; he says its leaves agree with the description of the white lotus of India, and hence he speaks of it as "*N. Indica flore candido folio in ambitu serrato*" of Commelin. The identity must have been mistaken, since none of the Old World species are native in the new. Caspary has rightly identified this with *N. ampla* DC. In discussing the names, Sloan suggests that the Indian and Egyptian white lotus seem to him to differ very little; English botanists now rank them as one species. He also states, quoting authority, that his Jamaica waterlily was carried to the Indies by way of merchandise. Perhaps this is an attempt to explain its supposed identity with the Egyptian plant.

By all odds the best pre-Linnæan classification of plants, as is well known, was that of Tournefort (1700). The waterlilies are placed in his Sixth Class, "herbs and suffruticose plants with rosaceous flowers." *Nymphaea* is the last (eleventh) genus in the fourth section of this class, while *Nelumbo* is separated from it as the first genus in section five. In this respect Tournefort came nearer our present ideas than Linnaeus, who made *Nelumbo* a species of *Nymphaea*. The genus *Nymphaea* is defined in the "*Institutiones*" as having a circle of many petals, and a pistil rising from the midst which forms a globose or conical multilocular fruit filled with many oblong seeds. The floral leaves and the fruit are putrescent, and

the genus is "easily recognized" by the broad sub-rotund floating leaves. "Nenufar" is given as a generic synonym. Four species are named :

1. "*Nymphaea alba, major* C. B. Pin.," our *N. alba*.
2. "*Nymphaea Americana, foliis circinatis, maximis, acute crenatis, subtus purpureis, flore albo* Plum."
3. "*Nymphaea Americana, foliis circinatis, minoribus, obtuse crenatis, subtus viridibus, flore albo* Plum."
4. "*Nymphaea lutea, major*," our *Nuphar luteum*.

In vol. 2, p. 137-8, the flowers, petals, ovary, fruit and seed of *Nymphaea alba* and *Nuphar* are figured, with also a cross-section of the fruit of each. We are not prepared to settle the identity of Plumier's American species ; it seems likely that No. 2 may be referred to *N. ampla* DC., and No. 3 to *N. rudgeana* Mey.; Caspary so placed them (1878). We cannot explain the absence of *N. lotus* from the list, unless it was meant to be included under the species *N. alba major*, as classed by C. Bauhin, who is quoted as authority for this name.

Finally Ludwig's (1737) arrangement of the genera may be mentioned. He separated *Nymphaea* from *Nelumbo*, as did Tournefort, and described the former genus as having five sepals and many small petals ; this is doubtless our genus *Nuphar*. He made an additional genus "*Leuconymphaea*" which has many petaloid stamens, and covers our present genus *Nymphaea*, as was recognized by Kuntze (1891) and MacMillan (1892).

The early plant anatomists seem to have neglected *Nymphaea* entirely. Grew and Malpighi make no mention of the genus. Vaillant in his essay on the structure of flowers (1717), refers to the "Grand Nenufar-blanc" as illustrating the condition where the stamens arise from the sides (*reins*) of the ovary. Older writers, as we have noted, referred occasionally to the "spongy" rhizomes and the "porous" petioles and peduncles. The Linnæan and post-Linnæan literature will be cited throughout the course of the present paper.

CHAPTER II.

STRUCTURE.

The habits of waterlilies are too well known to need more than a brief statement here. These plants are found in the shallows of slow streams or still water all around the world. The long rhizomes of the *Castalia* group creep along in or upon the mud bottom of ponds or in a tangle of vegetation overlying this, in a depth of water from a few centimeters to as much as 5 or 6 meters, branching here and there, and dying off behind as they advance by apical growth. By far the greater number, however, have an erect, tuberous stem or caudex, which never acquires any considerable length, but stands with its growing apex about on a level with the mud in which its lower portion is buried. From the stem in every case a great many stout, fibrous roots pass downward and anchor the plant in place, while the leaves and flowers rise upward. The former lie flat upon the water surface, the upper side being dry and exposed to the air. Under some conditions the petioles may be strong enough to hold up the leaves and make them totally aerial. All of the species, at certain periods of growth (germination and beginning of each annual growing season), produce small, thin leaves which lead a submerged existence. The flowers of about half of the species open at the surface of the water and seem to float upon it, those of the other half are raised on strong peduncles some distance above the water level. Only in one or two species (*N. rudgeana*, *N. amazonum*) is cleistogamy known to occur. The flowers in such cases never reach the air, or only do so for a few hours, after self-pollination has been effected. After anthesis the fertile flowers are drawn down into the water by movements of the peduncle, and here the seeds ripen. By means of a buoyant aril, the ripe seeds from the irregularly bursting fruits rise to the water-surface and are floated far and wide.

These peculiar conditions of life have impressed themselves strongly upon the forms and functions of the waterlilies. Manifold adaptations have arisen in every part of the plant. We shall discuss these in order in the succeeding pages, taking up first the gross morphology, then the finer anatomy of root, stem, leaf, and flower, and finally the physiology of the genus.

THE ROOT.

The primary root in Nymphaeaceae is of short duration ; in *Nelumbo*, indeed, it never becomes more than an embryonic rudiment. The entire root-system, therefore, of mature plants of this family is adventitious. The following description relates to conditions in mature Nymphaeas, the course of affairs at germination and immediately afterward being reserved for a later chapter. On digging out a well-grown rhizome of a waterlily, we find it beset by a great number of long, terete, white, spongy roots. In large tropical species (*N. caerulea*, *lotus*, *flavo-virens*, *zanzibariensis*, *capensis*, and hybrids) these may be a centimeter or more in diameter, and they are nearly as large in strong specimens of *N. alba* ; in *N. odorata* they measure usually 0.3 to 0.6 cm. in diameter. Each root is decidedly contracted at its point of junction with the stem, but reaches its greatest diameter about 5 cm. out, or less ; thence it tapers almost imperceptibly to its apex 30 to 60 or 100 cm. away.

In species with a short caudex (Apocarpiae ; *Lotos*, *Hydrocallis*) these roots may be so numerous and close together as to be deformed at the base into prismatic shapes ; in *Eu-castalia* the internodes are so elongated as to cause the roots to appear much more scattered. For the roots all arise from the bases of the petioles, or (in *Eu-castalia*) from an upraised cushion-like portion of the rhizome upon which also the petiole is inserted (Fig. 20). In *N. flavo-virens* and its hybrids, a thick irregular excrescence remains after the decay of the petiole, projecting from the tuber a centimeter or more, on the lower side of which the roots are borne, to the number of 5 to 13. In *N. odorata* 3 to 5 or 6 roots occupy a triangular area on the cushion behind each petiole ; the apex of the triangle is farthest from the petiole and is occupied by the first formed root ; this one is of medium size. Next to it is a second and much larger root, and the base of the triangular area is covered with a few much smaller ones. Some of the roots of young plants, and of adult specimens of *N. flavo-virens*, are transversely wrinkled in their upper parts, showing a contractile power. No co-ordinate branches are given off by the roots as a rule, but they are all clothed with a great number of slender rootlets, and the larger of these may again be beset with capillary branchlets ; this arrangement may compensate for the total absence of root-hairs throughout the adult plants. A root-cap is present on the tip of every root and rootlet, often showing the long, thimble-like shape so frequent in water plants ; it may be black or brown in color, but is frequently colorless or whitish on the smallest rootlets.

The root-cap is said by Henslow (1892, p. 507-8) and Van Tieghem (1898) to resemble in structure that of monocotyls rather than dicotyls. In *N. flavo-virens* and *N. caerulea*, however, the tip of the root agrees exactly with the fourth type of structure given by De Bary (1884, p. 12),




FIG. 6.—Longitudinal section of root-tip of *N. caerulea*. a, air-canal; s, space between root and upper portion of cap. From a photomicrograph.

i. e., there is a transverse layer of initial cells from which all of the tissues are developed (Fig. 6). Caspary and Nicolai assert that the cap continues to grow only for a very short period, after which no farther addition to it is made, though it is persistent, and not deciduous as in *Nuphar* (De Bary 1884, p. 413). In a root of *N. flavo-virens* from a plant just breaking from a strong tuber, the cap is short-conical and rounded at apex, with

long thimble-like prolongation around the root. Its outer surface is bounded by a distinct, smooth layer of cells, which are much larger than the underlying ones (cf. Fig. 6). At the apex these outer cells are columnar in shape and arrangement and are removed from the region of initial cells by 12 or 13 elongated elements (columella); they become nearly cubical opposite the initial region, where the cap is five to six cells thick, and elongated in the upper free portion of the cap, where for some distance this layer alone is present.

The relative size of the root-cap in this species is shown by the following measurements. The cap extends 0.035 mm. beyond the initial cells, and 1.33 mm. above this around the root; its diameter opposite the initials is 0.51 mm., the same as the diameter of the root above

the cap. A somewhat larger root-tip of *N. caerulea*, (Fig. 6), taken from a young root of a mature plant, shows a structure exactly similar to that of *N. flavo-virens*; in one specimen, however, the apical portion of the cap had been worn away in irregular fashion so that the primitive outer layer of large clear cells is visible only on the sides. All of the cells of the cap are arranged in longitudinal rows. The peripheral portion of the cap is continuous with the upper, sheathing part, and is composed of narrower cells than those below the




FIG. 7.—True and false epidermis of roots. *N. marliacea chromatella*. (a) from very young, (b) older, (d) mature root in transverse section; (c) surface view of (b), e, epidermis, h, hypodermal layer, c, cortex.

body of the root. The root-meristem and root-cap are formed by a transverse row of cells as described above.

A regular epidermis of columnar cells is found near the apex of the roots (Fig. 7 (a) e); the outer walls of these cells are cutinized, but their partition walls are quite thin. They increase somewhat in size as the root enlarges, but their outer ends become rounded and somewhat drawn apart (Fig. 7 (b) e). In most of the species examined (*N. flava*, *tuberosa*, *odorata minor*, *marliacea-chromatella*, *lotus*) they become almost cubical in shape (i. e., in cross section; they are elongated in the direction of the axis of the root), then are ruptured in their outer walls, the radial walls remaining as a black, irregular fringe on the surface of the root (Fig. 7 (d) e), giving it a powdery appearance. In *N. elegans* × *zanzibariensis*, the epidermal cells become greatly flattened and epithelioid before rupturing.

In all cases, however, the epidermis persists on the narrower portion of the root within about 2.5 cm. of the rhizome. Its loss is the direct result of the great expansion of the root, caused by the enlarging and maturing of the air-canals.

Meanwhile the subjacent outermost layer of cortex has developed in an especial manner (see Fig. 7 *h*). At a very early stage this layer is composed of columnar cells closely resembling the epidermis at the same period. But as its cells become broader and more nearly cubical, the walls become collenchymatously thickened, as also do those of the next one or two layers below (*N. lotus*, *tuberosa*, *marliacea-chromatella*). The outer walls of the hypodermal cells unite to form a fairly even surface, but the inner walls meet at various angles, owing to the varying depths of the cells. Thus an even hypodermal covering is formed in place of the lost epidermis.

The cortex may be divided into five layers : (1) the single hypodermal layer ; (2) exo-cortex, a layer of from one to three or four tiers of closely packed cells without intercellular spaces ; (3) medio-cortex, a tissue composed chiefly of large air-canals and constituting nine-tenths of the bulk of the root ; (4) endo-cortex, consisting of one or two layers of cells closely set together, lying adjacent to (5) the endodermis (Figs. 8, 9).

The first of these layers has already been described. The exo-cortex is continuous, between the air-canals, with the medio-cortex. In *N. odorata* (Fig. 8) there are between the outermost air-canals and the hypodermis two series of cortical cells with thin walls and in size of lumen equal to or larger than the hypodermal cells. *N. tuberosa* and *N. marliacea-chromatella* have usually three series of cells in the exo-cortex ; they are rounded, with collenchymatous walls, and larger by half than the hypodermal cells. The exo-cortex in *N. lotus* consists of a single row of cells (four or five near the base of a mature root), in *N. flava* of one or two rows. In *N. elegans* \times *zanzibariensis* there are two or three series of cells which are thin-walled and three or four times as large in cross-section as the hypodermal cells ; in longitudinal section, however, the hypodermal cells are much the longer, being about 0.025 mm. long ; the exo-cortical cells are only 0.0175 mm. in length, and the cells of the medio-cortex about 0.0076 mm. *N. flavo-virens*, at least near the proximal end of the root, has five or six cell-layers in the exo-cortex.

The outstanding characteristic of the medio-cortex is the presence of large air-canals. These are elliptic or rounded or more or less hexagonal in cross-section, and run parallel throughout the length of the root,

beginning in the meristem immediately back of the initial layer of cells (Fig. 6 a). They appear to be without communication of any kind with

one another, i. e., the cells bounding them fit together without transverse intercellular spaces. A single perforation 0.0025 mm. in diameter has been observed in the side wall of a canal in a root of *N. tuberosa*, but this must for the present be considered exceptional. At more or less frequent intervals (0.127 mm. to 3.0 mm. for *N. tuberosa*, 1.2 mm. to 5 mm. for *N. elegans* × *zanzibariensis*) diaphragms lie directly or obliquely across the canals. A diaphragm is a very thin plate of epithelioid cells (0.0076 mm. to 0.013 mm. thick for *N. tuberosa*) with sinuous margins; the protuberances of the margins of the cells meet one another, leaving spaces between the sinuses (Fig. 12 f). In *N. lotus* the cells are more even in outline, with large, round, intercellular spaces. Thus the passage of gases is left practically unimpeded. The walls of the canals are a single cell-layer thick, and bear stellate cells (idioblasts) here and there. In *N. tuberosa* these occur about 0.32 cm. apart on the average along each canal; in *N. elegans* × *zanzibariensis* they are




FIG. 8.—Root of *N. odorata*, transverse section. From photomicrograph; e, remnants of epidermis; h, false epidermis.

beginning in the meristem immediately back of the initial layer of cells (Fig. 6 a). They appear to be without communication of any kind with one another, i. e., the cells bounding them fit together without transverse intercellular spaces. A single perforation 0.0025 mm. in diameter has been observed in the side wall of a canal in a root of *N. tuberosa*, but this must for the present be considered exceptional. At more or less frequent intervals (0.127 mm. to 3.0 mm. for *N. tuberosa*, 1.2 mm. to 5 mm. for *N. elegans* × *zanzibariensis*) diaphragms lie directly or obliquely across the canals. A diaphragm is a very thin plate of epithelioid cells (0.0076 mm. to 0.013 mm. thick for *N. tuberosa*) with sinuous margins; the protuberances of the margins of the cells meet one another, leaving spaces between the sinuses (Fig. 12 f). In *N. lotus* the cells are more even in outline, with large, round, intercellular spaces. Thus the passage of gases is left practically unimpeded. The walls of the canals are a single cell-layer thick, and bear stellate cells (idioblasts) here and there. In *N. tuberosa* these occur about 0.32 cm. apart on the average along each canal; in *N. elegans* × *zanzibariensis* they are

two or three times as frequent, but somewhat more slender, and, though of nearly the same actual size, are much smaller in proportion to the size of the canals; they are few in the root of *N. flavo-virens*, numerous in *N. flava* and *N. odorata*, very plentiful and of massive build in *N. marliacea-chromatella*. Transverse sections show that they occur only in angles where three partition walls meet, and their arms project into the three adjoining canals (Fig. 8).

The canals vary in actual and relative size in the different species, but are always largest at the middle of the medio-cortex and smaller toward exo- and endo-cortex. *N. odorata* (Fig. 8) has six or seven concentric rings of canals, i. e., that number can be counted along any radius of the root; they are all quite large and distinct. *N. tuberosa* has seven to ten rows, very irregularly placed; the middle and outer ones are approximately circular in outline, those near the endo-cortex are greatly elongated radially, and the innermost and outermost ones are scarcely more than large intercellular spaces. *N. flava* and *N. lotus* have six or seven rows of rounded and quite regular canals in the main part of the root, becoming irregular in *N. lotus* near the stem. *N. marliacea-chromatella* has nine rows, arranged much as in *N. tuberosa*; the radial elongation of the inner canals causes the partition walls in this region to look like radial bead-like strings of cells. *N. elegans* × *zanzibariensis* has eight or nine rows of large canals, each of a rounded-hexagonal shape; *N. flavo-virens* shows a similar structure in its nutritive roots.

The cells of the partition walls are nearly square in side view (longitudinal section). The angles of the canals are occupied mostly by rounded-hexagonal cells; three alternate sides of these face the canals, the other three are joined to the neighboring partition cells. Between two angle-cells is usually a single square or rectangular cell; but often




FIG. 9.—Contractile root of *N. flavo-virens*, transverse section; en, endodermis; h, false epidermis; t, latex or tannin cell.

this divides into two smaller ones. Occasionally the angle is formed not by a single cell but by three partition cells which meet at a point and are connected by beveled ends. In *N. flavo-virens*, *N. tuberosa*, and to some extent in *N. marliacea-chromatella*, all of these cells are greatly rounded out and turgescient, but their areas of union with one another (common wall) are narrow and bounded by slightly curved lines; in transverse sections these lines give the appearance of small tubular and branched cells lying between larger rounded cells; longitudinal sections reveal the true state of affairs. The contents of the medio-cortex cells may be very small indeed, as in *N. flavo-virens* and *N. elegans* \times *zanzibariensis*, or there may be starch in the inner parts, as in *N. tuberosa* and *N. marliacea-chromatella*, or the whole medio-cortex may be loaded with starch, as in *N. flava*. *N. marliacea-chromatella* is intermediate in this respect between *tuberosa* and *flava*. The grains of starch are rounded and simple or elongate and double.

The endo-cortex is an ill-defined layer, most distinct in *N. flava* and *N. elegans* \times *zanzibariensis*; in the former it consists of one or two cell-layers, in the latter of but one; it is composed of small cubical cells, and has rather large intercellular spaces, both between its own cells and between these and the endodermis on the one side and the medio-cortex on the other; it should not, perhaps, be separated in the description from the medio-cortex.

Bounding the cortical tissues on the inner side, an endodermis with thickened radial walls may always be recognized. Its circular outline is interrupted by occasional slight sinuosities; it is most evident in *N. lotus*, *odorata* (Fig. 8) and *elegans* \times *zanzibariensis*, least so in *N. flavo-virens* and *tuberosa*. Its cells contain starch in *N. flava* and *marliacea-chromatella*.

Name.	No. of rays of xylem.
<i>N. odorata</i> minor	7
<i>N. ?</i>	8, 8
<i>N. flava</i>	6, 7
<i>N. flavo-virens</i> \times <i>zanz.</i>	5
<i>N. elegans</i> \times <i>zanz.</i>	7, 7, 7, 7
<i>N. caerulea</i> \times <i>zanz.</i>	6, 6
<i>N. tuberosa</i>	8
<i>N. caerulea</i>	6, 7, 7
<i>N. flavo-virens</i>	5, 7-8
<i>N. lotus</i>	6, 6, 9, 4
<i>N. amazonum</i>	7, 7
<i>N. rudgeana</i>	7
<i>N. marl.-chrom.</i>	8, 8, 8

A typical radial bundle system passes along the middle of the root. Its outermost cell-layer constitutes the pericambium. Against this the xylem and phloem patches abut; their number in different species is shown in the accompanying table.

In the center of the bundle an area of pith remains; this may extend over one-third of the diameter of the bundle in

N. odorata and *lotus*, one-fourth in *N. flava*, *tuberosa*, and *marliacea-chromatella*, or one-sixth in *N. elegans* \times *zanzibariensis*. In a general way this

shows a greater amount of xylem tissue in species with a greater extent of leaf surface. The first-formed and smallest xylem tracheæ are in contact with the pericambium; one such trachea occurs in each xylem plate, and from it a single row of tracheæ continues radially inward. These are in direct contact with one another in *N. tuberosa*, *elegans-zanzibariensis*, *flavo-virens* \times *zanzibariensis*, and sometimes in *N. odorata*; parenchyma cells may be interposed between them in *N. marliacea* \times *chromatella*, *lotus*, and *odorata*; in *N. flava* the radial lines are quite irregular and difficult to follow, the tracheæ having much the appearance of being scattered throughout the parenchyma. Only spiral and spiro-reticulate tracheæ have been observed (*N. tuberosa*, *elegans* \times *zanzibariensis*). Large phloem patches with sieve-tubes and companion cells, but no fibers, lie between the xylem plates; they are rounded on the inner side and do not extend so far toward the center of the bundle as the xylem plates; that is, the innermost tracheæ project more deeply into the pith than do the inner boundaries of the phloem masses. All of the cells of the bundle appear polygonal and nearly isodiametric in transverse section, but even the parenchyma is much elongated in the direction of the axis of the root.

Contractile roots differ from the more numerous nutritive roots in that the xylem is less in quantity in the former, and the air-canals of the cortex are much smaller in proportion to the cells bounding them. In a root of an adult plant of *N. flavo-virens* (Fig. 9) taken up in October, the false epidermis and exo-cortex are apparently normal. The outer part of the medio-cortex is collapsed wherever a transverse wrinkle occurs, but it consists for the most part of comparatively dense tissue, in which the intercellular spaces are not larger than the surrounding cells. The vascular system is cut off from the cortex by a distinct endodermis. Each of the 5 to 9 xylem rays consists of a single line of tracheæ occupying about one-third of the diameter of the vascular cylinder. The pith in the center of the cylinder is sharply marked off from the surrounding tissues by an endodermis with very distinct radial thickenings. This occurrence of an intrafascicular endodermis seems very anomalous in a flowering plant, but was constantly found in contractile roots of adults of *N. flavo-virens*. In non-contractile roots of this species the xylem rays are often two cells wide, they extend farther toward the center of the vascular cylinder, and there is no inner endodermis. In none of the roots of other species was an inner endodermis found.

As stated before, a radial-vascular bundle system traverses the entire

length of each adventitious root. Branches are given off from it at right angles and pass straight out through the cortex to the side rootlets. Where the root joins the stem, the root-bundle passes in and bends sharply backward (away from the stem apex) and runs more or less obliquely into the plexus of bundles of the stem. In *N. odorata* the bundles of all of the roots from a single leaf-base unite in the peripheral region of the stem into one strong trunk (Fig. 10); the appearance of a pith in the midst of this trunk in *N. alba candidissima* gives rise to the "root-bearing stele" of Gwynne-Vaughan (1896 *b*). In *N. lotus* each root-bundle passes in separately and breaks up into a number of branches before joining the plexus of the stem. It is notable that there is no direct connection between the bundles of any leaf and the roots which spring from its base, close as their proximity is.




FIG. 10.—Vascular bundles of the roots of *N. odorata*. Longitudinal section of leaf-base.

The innumerable small rootlets which cover the main roots seem to repeat entirely the structure of the latter. The vascular system (in *N. elegans* \times *zanzibariensis*) is hexarch, with uniseriate pericambium and a tiny central pith; endodermis and endo-cortex are uniseriate and distinct; the meso-cortex has only one or two series of very small and irregular air-canals; hypodermis and epidermis occur as above described.

The rudiments of roots are laid down below the bases of the petioles at a very early period. In a strong rhizome of *N. odorata* a leaf bud less than 0.3 cm. long, including the petiole, had four subtending roots already laid down in the tissues of the cushion just below it; the posterior two of these had the root-cap well defined and had destroyed some of the overlying cortical cells of the stem. After this time, however, their development is very slow; at the base of a petiole over 8 cm. long the root apices had just penetrated the epidermis, but were still concealed in the short pubescence of the leaf-cushion. No pericambial tissue has yet been distinguished in Nymphaeaceous stems for the source of adventitious roots.

Reference has been made to cell-multiplication in the apex of growing roots, and to the early origin of the air-canals. These canals are at first surrounded by six cells. Between every two of these another cell is cut off, giving one at each angle of the canal, and one on each side (Fig. 11 *b*).

The angle-cells are, in this stage, triangular and nearly equilateral (Fig. 11 *a*); the lateral cells are narrow and brick-shaped, with their ends abutting on the canals. It is largely by the great extension of the lateral cells that the air-canals and the roots themselves increase in diameter; for the shortest side of the young cell becomes much the longest in maturity; meanwhile the angle-cells have expanded also, their three points becoming first rounded, then flattened, to give the cell its hexagonal shape (cf. Fig. 8 and 11).

A diaphragm of an air-canal may be traced back (Fig. 12) to a single lateral cell near the tip of the root; this extends out into the lumen of the canal, by distension of its wall, as a rounded papilla. The papilla is cut off, and soon divides longitudinally; each half then divides transversely, and again longitudinally. Thus by growth a plate of cells is formed, extending across the

canal. As these cells enlarge, inter-cellular spaces are formed between them until the mature diaphragm is produced. Stellate cells develop from the angle-cells in the usual way, viz., by extension of the wall at several




FIG. 11.—Development of air-canals. Transverse section of root-tip of *N. flavovirens*. From photomicrograph. *a*, earliest stage; *b*, division of one angle-cell; *c*, cell divisions nearly completed; *e*, epidermis; *h*, hypodermal layer; (*a*) is farther from apex than (*b*), but from the same root.

points, with subsequent thickening and deposition of crystals. This is exactly as described for *Nuphar lutea* by Trécul (1845).

Lateral rootlets take their origin while the root tissues are still very young, even within the root cap. They spring from the pericambial layer opposite each xylem ray, and make their exit in the usual way, but not until a considerable time after their inception; they do not occur in a mature state near to the root apex.

THE STEM.

Externally the stems of *Nymphaeas* offer some striking differences, which are at times characteristic of subgenera or even of species. Members of the *Eu-castalia* group have always a stout, spongy, horizontal rhizome which decays in its older parts as it elongates by apical growth.

In *N. tuberosa* (var. *parva* Abbot) and *N. odorata minor* this may be only 5 to 10 cm. long and 1.2 to 2 cm. in diameter, but in the typical forms of these species it becomes 30, 60 or even 100 cm. long and 4 cm. in diameter, while in the larger forms of *N. alba* and *candida* it may reach a diameter of 10 cm. In general shape these rhizomes are terete, though the largest one I have seen (*N. alba candidissima*) was somewhat flattened dorso-ventrally. In the American species they are of a dull whitish color, though this is nearly obscured by fine black hairs; in the European




FIG. 12.—Diaphragms in the air-canals of roots; a, d, e, early stages from transverse; b, c, from longitudinal microtome sections of the root of *N. flavo-virens*; f, mature diaphragm with beadlike intercellular spaces from the root of *N. elegans* x *zanzibariensis*.

species the color is brownish or nearly black. All of the species of this group except *N. tuberosa* branch rather infrequently in their stems, and the branches are stout and attached to the main shoot by a broad base. In *N. tuberosa*, however, the rhizome (Fig. 13) is often crowded with short, tuber-like shoots from 1.2 to 8 cm. long and 1.2 to 2 cm. in diameter, attached to the parent axis by a short and very slender isthmus, sometimes only 0.3 cm. in diameter. In external appearance these do not differ from the main rhizome, except in size and a darker color. One such tuber often has others, one, two, three or four, of nearly equal size, growing out from its sides and base, so that bunches of tubers are formed. Being light enough

to float on water and easily detached from the parent plant and from one another by reason of the brittleness of the tissues of the isthmus, these tubers serve to distribute the plant widely. Waterlily leaves ("lily-pads") are eaten by large herbivorous animals (deer, &c.), which wade about in the shallow water; these must detach numberless tubers and leave them floating about, as a person does when wading among them. Doubtless also wading birds, turtles, bull-frogs and many kinds of fish accomplish the same end. Special mention of the structure of these tubers will be made later.

Each of the Nymphaeas except the group just mentioned possesses a short, thick, erect caudex. Where this remains throughout the year




FIG. 13.—Rhizome of *N. tuberosa*. Natural size.

in a wet and more or less vegetative condition, it dies off in the lower part as it elongates above, about keeping pace in its elongation with the amount of sedimentation taking place around it. Such conditions habitually surround the Xanthanthae and Chamaenymphaeae, and these cannot otherwise survive. Species of the Hydrocallis group often have a like perennial growth, as also sometimes have the Lotos and apocarpous groups in cultivation. But the habit of all of the truly tropical members (Lotos, Hydrocallis, Apocarpiae) is to be dried off completely at one season of the year. In this case the large mature blooming plants die and rot away. *N. flavo-virens* alone, with some of its hybrids, is able to withdraw from vigorous flowering growth into a dry, resting tuber. Young plants, however, readily store away all of their nourishment in the caudex, which then forms a tuber from the size of a pea to that of a hen's egg (or much larger in *N. flavo-virens*). Such resting

tubers are usually of an ellipsoid shape, or spheroidal in *N. gigantea* and *elegans* (Fig. 14). They are of a brownish black color, smooth and rounded in the lower half, but more or less acute above, because the apical region is protected by a dense upward growth of long fine hairs intermingled with dried and shriveled bases of petioles. These tubers live through the dry season without injury, and begin growth again in a characteristic manner on the return of sufficient moisture and heat. Mature stems of the types under discussion are, like the tubers, of an ellipsoid shape, and have grown in our Botanic Garden to a length of



FIG. 14.—Tubers: a, *N. amazonum*; b, b', *N. gigantea*, from two sides 90 degrees apart; c, c', *N. capensis*, two specimens; d, d', *N. elegans*, two specimens; e, *N. zanzibariensis rosea*; f, *N. lotus*, seedling; g, *N. lotus*, lateral tuber from mature plant. All natural size.

20 cm., and a diameter of 10 cm. in *N. rubra* var., 12.7 by 7.5 cm. in *N. dentata*, *caerulea* and *zanzibariensis*; I have seen a resting tuber of *N. Mrs. C. W. Ward* (*N. flavo-virens* × *zanzibariensis rosea*) in the Dreer Nurseries which measured 21 cm. by 10 cm. All of these are of a brownish black color. With us *N. flava* has not exceeded 7.6 cm. long by 1.6 cm. broad, and has a yellowish color, but Mrs. Treat (1877) records the length of an old caudex in the St. Johns River, Florida as 60 cm., and diameter 10 cm. *N. tetragona* stem is rather slender, 7 to 12 cm. long by 2.5 cm. in diameter, and is of a blackish color; *N. fennica* is similar in appearance but stouter, 10 cm. long by 3.75 cm. in diameter.

No branching of the stem, that is, no development of vegetative buds, occurs in *N. tetragona*, and none in any of the apocarpous species

(neglecting some hybrids), except in breaking out from the resting tuber. *N. fennica* may rarely fork, as one of our specimens shows. The Lotos and Hydrocallis species, however, give rise more or less freely to buds from the lower part of the stem, and these develop into young plants entangled among the roots and leaves of the parent. On the approach of winter or the dry season, these lateral shoots harden off into resting tubers for the perennation of the plant. Tubers thus produced (in *N. lotus*) are very irregular in shape (Fig. 14 g), appearing knotty and gnarly, but they still show in their lower half a smooth surface, and on the upper parts a dense growth of long protective hairs intermingled with remains of dead petioles. A remarkable development of lateral shoots occurs in *N. mexicana*. Long stolons originate from the lower part of the stem, even in very young plants, and run horizontally just beneath the surface of the mud to form a new plant at a distance of 15 to 60 cm. from the parent. No sooner has the young member established a few roots and leaves than it in turn sends out runners, and so on. Three or more such runners may be found attached to a single plant. Their minuter details will be described in another place. In autumn the ends of these runners develop a peculiar form of perennating stem (Fig. 15); it consists of an axis 1 to 1.6 cm. long and 0.48 cm. in diameter lying horizontally or obliquely in the soil; on its upper surface is a continuous row of 3 to 6 small leaf buds, while from the under surface depends a bunch of thick, swollen, starch-laden roots 1 to 3.5 cm. long and 0.3 to 0.6 cm. in diameter; these lie crowded over each other somewhat in rows like bananas on a bunch; at the tip of each a flattened and distended root-cap remains.

A last type of stem exhibited by *Nymphaea* is that produced from resting tubers when they resume growth. From the center of the upper end of the tuber, in apocarpous species, a short, smooth, white stem (stolon), 0.16 to 0.3 cm. in diameter, rises a centimeter or so, and at its summit a tuft of leaves and roots is formed; this may now be broken off and will grow into a perfect plant, while the tuber will repeat the process, if strong enough, as many as 8 or 10 times (*N. flavo-virens* and hybrids). In Lotos species a much greater area of the tuber, in fact nearly all of its upper surface, develops a very large number of tiny shoots, crowded all over it. One, two, three or four of these start forward at nearly the same time and each develops a long internode 1.2 to 8 or 10 cm. in length—a smooth, slender, white or reddish, often much curved stolon 0.16 to 0.3 cm. in diameter—bearing a simple lanceolate or subulate bract 0.6 to 2.5 cm.

long at its summit. This is followed by a second internode, much shorter, 0.3 to 1.3 cm. long, and this bears the tuft of leaves and roots which are the beginning of a new plant. If these shoots are detached, other shoots develop, and so on almost indefinitely, even from a tuber no bigger than the end of one's thumb.

Phyllotaxy in the *Nymphaeas* presents some peculiarities. As might be expected, forms with elongated rhizomes (*Eu-castalia*) have the simpler orders of leaf arrangement, and where dorso-ventrality appears leaf scars are only half as numerous on the lower as on the upper side. In *N. tuberosa* and *odorata*, the phyllotaxy seems to be as low as $\frac{2}{5}$ or $\frac{3}{8}$, and the internodes are 1.3 cm. or more long. *N. alba* shows a much higher order, probably $\frac{2}{11}$ or $\frac{3}{17}$ (Raciborski 1894). But the erect tuberous

stems are so densely crowded with leaf attachments as to leave only narrow, sinuous lines of stem-surface visible; the order of the spirals I have not determined.

One can speak of a definite anthotaxy also in the genus *Nymphaea*, since a plant once in flower produces its bloom continuously until it dies. In *N. gigantea* the peduncular attachments form separate and distinct secondary spirals




FIG. 15.—Perennating body of *N. mexicana*. Seen from nearly opposite sides. Natural size.

alternating with two parallel spirals of leaves (Caspary, 1865). In other species the flowers occur in the place of leaves, as members of the leaf-spirals. In every case the peduncles arise entirely independently of any leaf axil and there is no visible trace of a bract. The relation of leaves and flowers in the primary leaf-spirals is shown in the following series taken from Raciborski (1894). The numbers represent leaves, the letter *f* stands for a flower. A rhizome of *N. alba* taken up in autumn gave 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, *f*, 12, 13, *f*, 14, 15, *f*, 16, 17, *f*, 18, 19, *f*, 20, 21, *f*, 22, 23, 24, 25, 26, 27, 28, 29, *f*, 30, 31, *f*, 32, 33, *f*, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, *f*, 44, 45, *f*, 46, 47, *f*, 48, 49, *f*, 50, 51, *f*, 52, 53, *f*, 54, 55, *f*, 56, 57, *f*, 58, 59, *f*, 60, 61, *f*, 62, 63, *f*, 64, &c.; the flowers up to 45 have already bloomed, the others would come out the next season. In *N. zanzibariensis*, a very floriferous species, leaf and flower alternate regularly after the plant once begins to bloom. "*N. stellata*" gave 1, 2, *f*, 3, 4, 5, *f*, 6, 7, 8, *f*, 9, 10, 11, *f*,

12, 13, 14, f, 15, 16, 17, f, 18, 19, 20, f, 21, 22, 23, f, 24, 25, 26, f, &c; the primary spiral seemed to be sometimes $\frac{1}{11}$, sometimes higher. *N. rubra* in the Munich garden (which Raciborski considered was more probably a hybrid) showed 1, 2, f, 3, 4, 5, 6, f, 7, 8, f, 9, 10, 11, 12, f, 13, 14, 15, 16, f, 17, 18, f, 19, 20, 21, 22, f, 23, 24, 25, 26, f, 27, 28, f, 29, 30, 31, 32, f, 33, 34, 35, 36, f, 37, 38, f, 39, 40, 41, 42, f, 43, 44, 45, 46, f, 47, 48, f, 49, 50, 51, 52, f, 53, 54, 55, 56, f, 57, 58, f, 59, 60, 61, 62, f, &c.¹

The structure of the stem in Nymphaeaceae has long been a puzzle, and for the most part still remains so. A transverse section of any vegetative stem of Nymphaea (Fig. 16) shows to the unaided eye three well-marked regions, viz., (1) an outer wall of dense cellular tissue, about 0.16 cm. thick, consisting of epidermis and exo-cortex, (2) a medio-cortex full of large lacunæ or air-spaces, (3) a dense central core traversed in every direction by vascular bundles. The second layer is traversed by numerous trabeculæ of denser tissue connecting the exo-cortex with the central core. The following description applies only to normal vegetative stems, not to stolons or resting tubers.




FIG. 16.—Rhizome of *N. odorata*; transverse section of internode. Dotted portion represents the spongy medio-cortex; heavy lines are vascular bundles. Natural size,

Microscopically examined, a well-marked epidermis is always present. In *N. lotus* and *odorata* (Fig. 17) this is an irregular layer as to the level of the cells on the outer and inner sides, and as to their size, though they are approximately cubical in shape. The walls are equally thin on all sides. In *N. flava* the cells are much shallower than long or broad (about 2:1) and form a more even surface. With the exception of a very minute area at the growing point of the stem, its whole surface is covered with hairs. Where these first appear outside the naked area, every epidermal cell bears one. At a short distance back of this point, however, many of the epidermal cells undergo an oblique division, cutting off a wedge-shaped segment with its apex at the outer surface on one side of the cell, and a base nearly equal to half the base of the mother cell; the apex of the wedge widens out, and soon the new cell is cubical. A single cell thus comes to intervene between two formerly contiguous

¹ Raciborski's *N. flava*, having no runners, but an ordinary branching rhizome as in other Nymphaeas, was almost certainly *N. odorata sulfurea* (*N. odorata* × *flava*) and not the true *N. flava*. His *N. stellata* was probably *N. caerulea* Sav.

hairs. Such hairs are slender lines of terete cells, of almost even diameter throughout, but tapering at the apex, and attaining a length of 0.48 cm. in *N. caerulea*; 0.6 cm. in *N. tuberosa*, or 1 cm. to 1.3 cm. in *N. lotus*. The basal epidermal cell is cubical in shape, and if we represent its depth by unity, the lengths of the succeeding cells will be approximately 0.8 to 1.3, 0.5 to 2.2, 2.2 to 10, and so on up to 15 or 20 times as long as broad. The relative and

Species.	Diameter of hairs at apex of stem.
<i>N. caerulea</i>	0.024-0.030 mm.
<i>N. tuberosa</i>	0.035 mm.
<i>N. lotus</i>	0.021-0.028 mm.
<i>N. flava</i>	0.021-0.033 mm.
<i>N. odorata</i>	0.028-0.033 mm.

actual diameters of these hairs in different species is shown in the accompanying table. In addition to these, hairs with thick multicellular base and slender shaft occur in *N. tuberosa* and *lotus*. The lower part of such a hair consists of 1 to 3 tiers of polygonal cells about one-third to one-half the diameter of the basal column of the hair; then follow 2 to 5 short cells in linear series, and finally a row of long cells as in the hairs first described. These complex hairs may arise from the simpler type by upgrowth of the tissues supporting them. Those of *N. lotus* are much larger than of *N. tuberosa*; indeed in the former species the surface of the stem is completely occupied by these hair-protuberances.




FIG. 17.—Microscope section of rhizome of *N. odorata*; showing exo-cortex and 8 chains of the spongy medio-cortex, e, epidermis; t, tannin (latex) cell. Camera lucida sketch.

Much more sharply than in the root, we recognize in the stem three cortical regions (Figs. 16, 17, 18), an outer, dense, sub-epidermal layer 0.16 to 0.3 cm. thick, a median spongy layer 0.6 to 2 cm. thick, and an inner dense layer continuous with the parenchyma which makes up the central core of the stem. The spongy layer is not continuous, but is cut into irregular disconnected blocks by plate-like trabeculae of dense tissue passing radially from outer to inner cortex. The cells of the outer cortex in *N. odorata* (Fig. 17) are nearly isodiametric, thin-walled, and contain 6 to 8 starch grains each; there are 12 to 14 layers of

such cells, with occasionally a small intercellular space, and here and there a typical stellate cell many times as large as the cortical cells. In *N. lotus* the exo-cortex is 23 or 24 cells thick; each cell is ellipsoidal, the radial axis (with regard to the stem) being shortest, and the horizontal tangential axis longest. The walls appear thickened, and probably are colloid. There are no starch grains, no intercellular spaces and no stellate cells.

The relative amount of lacunar cortex is very different in the different types of stem. In the *Castalia* group it is quite prominent (Fig. 16), in the others rather insignificant; the following table shows the relation in five types examined. "Central core" includes endo-cortex and all within it.

Species.	Width of exo-cortex	Medio-cortex	Central core.
<i>N. flava</i>	0.1 cm.	0.4 cm.	0.48 cm.
<i>N. tuberosa</i>	0.16	0.8	0.8
<i>N. odorata</i>	0.13	0.3	1
<i>N. alba candidissima</i>	0.16	1	4.5×3.8
<i>N. lotus</i>	0.2	0.8	6.4

In *N. lotus* (cf. Fig. 18 *m*) the lacunar cortex might be said to occur in isolated patches of irregular shape around the periphery of the stem. The greater part of these regions is air space, and this is traversed in every direction by anastomosing chains of cells, after the manner of a loose, spongy parenchyma of a leaf. The cells are thin-walled, small, and nearly isodiametric in *N. odorata* and *alba candidissima*, and the chains may consist of one or more rows of these (Fig. 17), being sometimes rather plate-like; the nodes of the network are always multicellular. In *N. lotus*, on the contrary, the cells are three to four times longer than broad, or they may have a rounded body with slender arms reaching out to connect with neighboring cells.

The inner cortex and the tissue forming the groundwork of the central core of the stem alike consist of medium-sized spherical cells, containing numerous starch grains, and enclosing large intercellular spaces. There are about 25 cells radially outside the vascular region in *N. alba candidissima*, constituting the endo-cortex. In *N. lotus* the endo-cortex may be 0.4 cm. deep in a large stem, and consists of very many cell layers. The cells are wide apart, reaching out toward each other by short, narrow processes, and are surrounded by a large amount of air space; the tissue is of a whitish color. The cells and spaces are smaller, but otherwise it does not differ from parts of the brown medio-cortex.

The endo-cortex contains some starch. The ground tissue of the central core of the stem consists of spherical cells with large intercellular spaces, as in *N. alba candidissima*, and is densely filled with starch, even in a large vegetative stem taken up in autumn and otherwise destined only to decay. In *N. flava* (Fig. 21) the endo-cortex and ground-tissue are constituted as in *N. alba-candidissima*, but the cortex cells seem more crowded together than the central tissue of the core, and more densely laden with large starch grains. Stellate cells are occasional in the central core, and very plentiful in the cortex of this species.

The trabeculæ which cross the medio-cortex (Fig. 16) are composed for the most part of tissue similar to the endo-cortex, but at the outer ends

they gradually take on the characteristics of the exo-cortex. The number of trabeculæ in a cross-section is about 5 in *N. flava*, 7 or 8 in *N. odorata*, 8 in *N. tuberosa*, 14 to 15 in a very large rhizome of *N. alba candidissima*, 15 or 16 in a large caudex of *N. lotus*.

On stripping off the exo-cortex of a stem of *N. odorata*, I found eight bands of trabecular tissue running longitudinally throughout the length of the portion studied, connected by transverse or oblique cross-trabeculæ at intervals of a half-inch or more. The petioles and peduncles are always situated over a longitudinal trabecula,



FIG. 18.—Caudex of *N. caerulea*; transverse section. Heavy lines represent vascular tissue; e, exo-cortex; f, peduncle; m, medio-cortex; n, endo-cortex; p, petiole; r, root; s, stipule. Natural size.

in which the vascular bundles travel to join the central vascular plexus; but these leaf and flower insertions stood in no discoverable relation to the transverse and oblique trabeculæ; in two cases carefully dissected there were no cross-trabeculæ near the insertion of the leaf. In *N. flava* slender trabeculæ divide the medio-cortex into fusiform areas, each lying with its longer axis horizontal and tangential to the stem; a leaf or flower or stolon stands over each such area, and a stout vertical trabecula crossing the short diameter of the area bears the central leaf trace to the vascular cylinder of the stem, while the lateral traces travel inward near the points of the fusiform area, surrounded by a thin layer of dense cortex. Caspary (1857 *b*) states that such a division of the spongy cortex into areas is common to *Victoria*, *Euryale* and *Nymphaea*.

In waterlilies which are adapted to enduring a dry season, the resting tubers differ markedly from the vegetative caudex. In the case of young seedling plants, which alone form resting tubers in most apocarpous species, the tuber acquires a smooth, corky bark on its lower parts. The leaf and root scars are obliterated by intrusion of cortical cells, which absorb the spiral thickenings of the xylem (Caspary, 1859) and give rise to several layers of typical cork. Although I have never found these in section to have the regularity of arrangement shown in some trees with a well-developed cork cambium (Ginkgo), I have often with my hands peeled off the bark from a living tuber, and found it to separate as smoothly as the bark of a willow twig in April. The interior tissues are dense and hard with their load of starch, and the vascular system remains intact except in its peripheral parts. The irregular lateral tubers produced upon the sides of large plants of the *Lotos* group seem to possess much less vascular tissue than the vegetative caudex and to have much more cortex, heavily laden with starch. The lacunar cortex is wholly absent from resting tubers, probably because, as in *N. flavo-virens*, the cork layer is formed inside the lacunar tissue, and all of this region dries or decays away.




FIG. 19.—Cork formation at base of root scar, *N. alba candidissima*.

In *Eu-castalia* and *Chamaenymphaea*, suberization takes place only over the scars of petioles, peduncles and roots, and on the boundary of the living and dead tissues at the old decaying end of the stem. The root scars are healed over by a curved surface, concave on the outer side, in the middle of which the vascular bundle projects slightly. The cortical cells along this concave surface (which lies four or five cells farther in than the proximal ends of the air-canals of the root) undergo one to three parallel divisions (Fig. 19) to form the cork layer, and not until some time afterward do the adjoining root tissues decay away. I do not know how the vascular bundle of the root is closed. In *N. alba candidissima*, where the above facts were observed, the old rhizome, decaying at its posterior end, seems to have its epidermis shriveled and more or less disintegrated and its exo-cortex suberized in its cell-walls, but usually without cell-division. When this layer peels off, carrying with it the leaf scars, a rounded corky invagination or pouch is seen (Fig. 20 *b*) at the base of each main air-canal of the petioles and peduncles. The largest pouches extend inward a quarter of an inch, and point slightly backward; they are hollow, and wide open to the exterior, and are usually full of mud. The whole surface of the

scar is suberized in a manner identical with that of the root. In one case (Fig. 20 *c*) the spiro-reticulate elements of a bundle in a leaf scar were closed by large thyloses from the neighboring parenchyma. Since but 3 to 5, usually 3, layers of cork are formed, the protection is only temporary; and when the water breaks through into the underlying tissues, a thin corky layer is thrown across the cortex in front of it, sometimes simply by modification of the cell-walls without division of their contents. Soon the water breaks through this, and again a partition is thrown across farther forward. So in the older parts of the stem, the plant keeps up a continually losing conflict with death, resulting in a gradually advancing decay of the tissues.




FIG. 20.—(a) Old leaf cushion on rhizome of *N. alba candidissima*, showing base of petiole with air-canals, insertion of stipule, *s*, and root scars, *r*; (b) transverse section of (a) through the two largest air-canals; (c) thyloids closing spiral vessel in old leaf scar.

or they may be surrounded by a bunch of needles projecting from the middle line toward either end, or they may present much the appearance of bundles of raphides. Similar crystals and crystal masses are found in the suberized exocortex of the older parts of the stem. They are very resistant to reagents, and consist probably of calcium oxalate. They are often imbedded in masses of mucilage which becomes pinkish in chlor-zinc-iodide. The irregular, crystal-like bodies blacken with ferric chloride solution, and doubtless contain tannin. Throughout this research cork has been tested by its yellow color when treated directly with chlor-zinc-iodide, and by a blue color with the same reagent after boiling in potash solution and washing in hot alcohol (Meyer 1898).

Before taking up the vascular system of the stem it will be of advantage to describe some special types of stem-structure. The remarkably developed stolons of *N. flava* and the lesser ones of *N. lotus* have the same general structure. Inside of a thin but cuticularized epidermis of small cubical cells, and about eight layers (*N. flava*) of closely fitting cortical cells (two to three layers in *N. rubra* var.), the

In the outer, corky cells of the scars, and to a less extent in the inner ones, crystals are found. Some of these are irregular and rounded in outline, but most are beautifully rectangular, prismatic or tabular. The regular crystals may be transparent, homogeneous and sharp-angled,

space is filled with longitudinal air-canals separated by partitions of a single cell-layer in thickness. Throughout the length of the stolon three to five vascular strands pass along, each surrounded by endodermis with the characteristic thickenings on the radial walls. Gwynne-Vaughan (1896, *a*, *b*) called these strands "steles," and considered the stolons polystelic. He states that the narrow isthmus connecting the tubers of *N. tuberosa* with the parent axis are similarly polystelic. I am not prepared to express an opinion upon the stelar nature of these strands, especially since the present idea of a "stele" seems to be of doubtful value, and, to say the least, needs more accurate definition. It will suffice to describe the appearance of the vascular strands in transverse section, and to mention their constituents. In *N. flava* a strand has at center a large, regular and thickly cuticularized air-canal, with two or three (usually three) projecting vascular lobes. Each lobe has one to three (sometimes none) spiral xylem cells next to the cells bounding the air-canal; the rest of the area consists of phloem, with large sieve-tubes and small companion cells. The vascular strands of *N. rubra* stolons have the large air-canal with only one or two vascular lobes.

In *N. tuberosa* the very short stolon resembles the rhizome in its epidermis and superficial hairs, and the large, starch-laden cells of the interior; these latter cells include very large intercellular spaces. There are about three vascular strands, bounded by endodermis. At the middle of each, or near one side, is a large group of spiral elements, corresponding in size and position to the air-canal in *N. flava*. A moderate amount of phloem lies about this, either concentrated in four phloem lobes, or half surrounding the xylem and bearing two or three lesser lobes, or completely surrounding the xylem and scarcely lobed. Two or three of these conditions are seen in a single section.

The vascular system of nymphaeaceous stems has always been described as consisting of scattered bundles (astelic), resembling monocotyledonous structure. In most cases this is about all that can be said (cf. Figs. 16, 18). Trécul (1845) studied the stem of *Nuphar* for a year with considerable success, but was far from being satisfied with his results. Nor do his researches shed much light upon the vascular structure of *Nymphaea*. Although we can not yet unravel the complicated network of tracheae and phloem strands, which seem to run in every imaginable direction and position throughout the inner tissues of the stem, some points are brought out by an examination of the stolons and young plants of *N. rubra*, and the general and nodal structure of *N. flava*. This latter

species has an additional interest as representing probably the most primitive member of the syncarpous series.

In a transverse section of the caudex of *N. flava* (Fig. 21), one finds a pretty well marked cortex, a broad vascular ring with one to three leaf-gaps, and a well defined pith which is continuous with the cortex through the leaf-gaps. The vascular ring, however, presents a most peculiar




FIG. 21.—Transverse section of caudex of *N. flava*. *b*, base of leaf with bundles and air-canals; *e*, exocortex; *g*, leaf gap; *l*, point of branching of leaf trace; *m*, medio-cortex; *n*, endocortex; *p*, pith (medulla); *r*, root trace; *t*, central leaf trace.

structure. Projecting slightly into the pith from the inside of the ring are seen seven or eight vascular bundles, *t*, of varying size, cut transversely, each with its phloem against the pith, and its xylem (of equal or greater amount) next to the vascular ring; these are the central leaf-traces. The greater part of the "ring" consists of horizontal or oblique elongated elements, mostly of phloem, but with some spiral tracheae; these are derived from root-traces and lateral leaf-traces. In this ring and sometimes on the outer side of it, next the cortex, are additional bundles

cut transversely, with xylem inside and phloem next the cortex; their origin or end I was unable to learn. On the surface of the stem at each node or point of union of a petiole with the caudex, there is in *N. flava* a prominent conical projection, on the upper face of which the petiole is attached, and on the lower face the roots. Within the tissues of this projection the bundles from the attached roots unite into a single trace, and this passes horizontally through the cortex to the lower edge of the leaf-gap. A few cells join the vascular cylinder of the stem directly, but most of the trace is contained in two large lateral forks, one right and one left, which start almost horizontally into the vascular cylinder and could not be followed. The petiolar




FIG. 22.—Course of vascular bundles at node of *Nymphaea flava*. (a) base of petiole; (b) base of poduncle; g, leaf gap; rr, roots; v, vascular cylinder of stem, semi-diagrammatic; (c) diagrammatic projection of (a); p, petiole.

bundles are nine in number, three in a median vertical plane, and six smaller lateral ones. Of the first three, one is anterior, one median, and one posterior. The others are right and left antero- and postero-lateral, with one directly right and one left of the centre of the petiole. On entering the stem, the posterior and median bundles fuse, and are shortly joined by the anterior, the whole forming a large central leaf-trace. The right and left antero-lateral bundles are joined at about the same level as the above, by the directly right and left bundles, and the two fused bundles then join the central leaf-trace. This trace passes horizontally in through the cortex and comes in contact with the root-trace, then passes over the brink of the leaf-gap and turns sharply downward next to the pith, giving the appearance noted in the cross-section. About midway on its course through the cortex, the central leaf-trace

gives off a strong branch to either side. Each branch passes about 45 degrees around the stem and then runs obliquely into the vascular cylinder. Meanwhile each has been joined near the middle of its course by a postero-lateral bundle from the petiole, which, on first entering the stem, bent sharply away from the other bundles and ran along horizontally in the exo-cortex to the corner of the leaf-area before turning inward. The whole is made reasonably clear by a glance at Fig. 22, (a), (c).

A very similar arrangement of bundles was found at the node of a stolon of *N. rubra*. It is usual in the Lotos group to find a slender




FIG. 23.—Vascular system of stolon of *N. rubra*? at a node; *b*, *c*, lateral leaf traces; *c*, central leaf trace; *r*, root bundle. The lower end is toward apical region of stolon.

leaf a short distance below the young plant near the apex of the stolons. This is the only place in any *Nymphaea*, I believe, where a leaf can be found at sufficient distance from others to admit of simplicity in the arrangement of the bundles. At some distance below the leaf in question there are four bundles (steles of Gwynne-Vaughan) passing longitudinally in the stolon. Nearer the leaf one of these forks, making five bundles, nearly equidistant from one another (Fig. 23, upper end). Opposite the leaf-base, the bundle on that side of the stolon divides into two parts which run almost in contact through the node. A single root is present here, and its trace, *r*, passes obliquely inward toward the space between the recently split bundle, and part joins

each half. Three bundles enter the stolon from the leaf, a central, *c*, and two lateral, *b*, *c*. The central bundle passes in parallel to the root-trace, and a part joins each half of the split stem-bundle. Midway of its course inward, however, it gives off a large branch right and left and these join the next nearest stem-bundles on either side. Each lateral leaf-trace is joined by another small bundle (probably stipular) just within the stem tissues, and the two unite with the right and the left branches respectively of the central bundle. Above this leaf (below, in Fig. 23) the two parts of the split bundle move farther apart, and finally they fuse successively, each with its nearest neighbor, giving rise to five and then the original four bundles of the stolon. Shortly, however, these fused bundles again divide in making ready for the insertion of the next two leaves. The bundles from these leaves are in number and mutual relations identical with those of the first leaf; but the leaves here become crowded and the details of the course of the bundles

can only be traced so far as to show that all of the four stolon-bundles are sooner or later joined by leaf-traces, and therefore that all of the bundles of the stem are common.

Concerning the origin and distribution of the bundles in the stolon of *N. flava*, we can only say that at the distal end of the stolon the vascular strands branch and anastomose, in fusing with leaf and root traces, to form the vascular cylinder or plexus of the new caudex. The strands of the stolon originate from the four sides of a ramular gap in the vascular system of the parent plant similar to a leaf-gap, and the stolons occur in the place of leaves in the leaf-spirals of the surface of the stem. The above evidently refers to a stolon with four vascular strands, which seems to be the normal number. I have examined one specimen with five strands, one central and four peripheral. In this the central strand fused with the lowest peripheral one before entering the parent stem, so that both passed in as a single strand over the brink of the ramular gap exactly like a central leaf-trace.

It would seem from these accounts that the bundles of the stolon are scarcely to be called steles, and that the behavior of the leaf-traces is more in line with dicotyledonous than with monocotyledonous structures. Prof. Nägeli remarked in 1857 (Caspary, 1857, *b*) that "of the five vascular bundles which enter each leaf in *N. alba*, the two lateral pairs in the interior of the stem go to the sides of the stem, but the middle one sends a branch inward to form a central strand, and only in this latter point does *N. alba* differ in structure from the characteristics of a dicotyledonous stem."¹

The relations of the bundles of the flower stalk in joining the stem have been most accurately worked out in *N. flava*. Seventeen longitudinal bundles were found in the peduncle, viz, a central bundle; four large ones 90 degrees apart around the periphery, of which one is anterior, one posterior, one right and one left; alternating with these are four smaller bundles, and eight tiny ones alternate with the last two sets. The last eight were not traced into the stem, but they doubtless unite with their larger neighbors at the base of the peduncle. Great variation exists in the details of the fusion and anastomosis of the remaining bundles, Fig. 22, (*b*). However, it seems constant for the four oblique bundles to

¹ " — dass von den 5 Gefässbündeln, die bei *N. alba* in jedes Blatt eintreten, die beiden seitlichen Paare im Innern des Stammes nach dessen Rande zuziehen, *das mittlere jedoch einen Zweig nach Innen entsende, um einen centralen Strang zu bilden*, und nur in diesem letzteren Punkte weiche der Bau von *N. alba* von dem Charakter des Dicotyledonenstammes ab." p. 791-2.

fuse with one or both of the adjacent large bundles, leaving, with the central one, five strong vascular trunks. Shortly the central and posterior trunks unite, leaving four, and then the anterior and right trunks unite, leaving but three traces. The left trunk may now join the fused right and anterior, or these may remain separate and pass to opposite sides of the gap in the vascular cylinder of the stem which is prepared to receive them. This gap is identical in size and shape with those for the leaves and stolons; since a peduncle is a form of stem, this should probably be called a ramular gap. The fused posterior and central trace passes in over the lower edge of the gap and turns downward after the manner of a central leaf-trace, with its phloem uppermost (innermost after turning downward). Some analogy between the bundles of peduncle and petiole would be desirable, but opinions on this would as yet be premature.

THE LEAF.

The three types of waterlily leaf mentioned on a previous page have been designated by Arcangeli (1890, *b*) hydrophylls (*idrofilli*), aerophylls (*aerofilli*) and aérohydrophylls (*aeridrofilli*); the last includes all of those commonly seen and familiarly known as lily-pads. It will be more convenient, however, to speak in plain English of submerged or water leaves, aerial leaves and floating leaves. The aerial type is altogether exceptional. It occurs in *N. odorata*, *alba*, *tuberosa*, *mexicana* and *marliacea-chromatella* when the plants are much crowded, or in *N. odorata minor* where the rhizome is bedded in deep peat or sphagnum from which the surface water entirely dries away in summer. In the last case, specimens from Atco, N. J. have shown a few stomata on the under side of the leaf near the apex, and such leaves are always firmer and tougher in texture than floating leaves; but other than this no difference has been noted, and no further mention of them will be made.

Floating leaves are present in all Nymphaeas, excepting *N. alba*, when growing in deep, swift streams (which is a rare occurrence), and perhaps in *N. amazonum submersa* (Sagot, 1881) and *N. oxypetala*. A mature flowering plant will have at one time from 4 of these in *N. tetragona* to 6 or 8 in *N. odorata* or 10 to 15 in the large tropical species. They are produced in rapid succession throughout the growing season, and after functioning for a few weeks, turn yellow and decay.

At the base of the petiole occur stipules of characteristic shapes (Fig. 24). In *Castalia* the two "stipules are inserted on the edge of the dilated pedestal of the leaf-stalk, and below the articulation of the latter;

and are connate in one plate-like piece in front of the petiole. They are therefore intrapetiolar" (Lubbock, 1894). The insertion is usually a little oblique in *Eu-castalia*, the curved line of attachment extending farther back on one side of the petiole than on the other. The fused stipular plate persists for some time after the decay of the leaf. It is about 2.5 cm. long, more or less, and lies closely appressed to the rhizome; in general outline it is broadly oval, with emarginate apex. A shallow furrow exists along the line of fusion, into which the petiole fits, and from the ridges on either side of this the tissues taper out to an extremely thin margin. The stipular plate of *N. flava* is erect, lanceolate, 2.5 cm. or more in length, thin, rounded at apex, and not persistent. In *Brachyceras* the stipules are fused at base, with distinct and more or less long-attenuate apices. The other subgenera have distinct, slightly unequal stipules, consisting each of a long (2.5 to 4 cm.), narrow (0.3 cm.) wing, adnate to the side of the petiole, with free acuminate apex. In all cases the stipules are whitish or semi-transparent, and soft in texture, and covered on both sides, but especially on the back, with deciduous mucilage-hairs. Interspersed with these on the backs of the stipules in *N. odorata* and




FIG. 24.—Stipules.

a, *N. zanzibariensis* X; b, *N. flava*; c, *N. odorata*.

lotus are short fibrous hairs, one to three cells long in the shaft in the former species, much longer, but still few celled, in the latter. Both kinds of hair rest on similar bases of disc-like cells, as will be described shortly. I have observed no vascular supply to the adult stipules of *N. lotus*, but *N. odorata* has a principal vein running longitudinally in each ridge of the stipular plate, with about nine smaller ones parallel and nearer the margin. *N. flava* has also a midrib in each ridge, and may have one parallel vein outside of this. No others have been examined. The cellular structure is very simple. The epidermis of the two sides is continuous around the margins of the stipules, very even on its outer surface, but irregular and angular next to the parenchyma; it consists of more or less cubical cells in *N. odorata* and *lotus*, but in *N. flava* the cells are wider than deep and longer (in the direction of the length of the stipules) than wide. The interior is filled with nearly uniform, thin-walled cells, roundish or oval, with evident intercellular spaces in

N. odorata and *lotus*, polygonal and with extremely minute intercellulars in *N. flava*. In thickness this parenchyma reaches about eleven cells next to the petiole in *N. lotus*, tapering to one cell at the margin; *N. flava* has about 9 cells in thickness at the ridges; *N. odorata* has 16 cells at the ridges, and throughout its tissues are many very thin-walled, two-pointed or variously forked idioblasts. Numerous small starch grains were observed in the parenchyma of a young stipule of *N. lotus*. In this species also the stipules are much more prominent when young than on mature leaves, lending weight to Lubbock's (1894) statement that they are throughout the genus of especial use in protecting the young leaves and flowers.

The petioles of *Nymphaeas* necessarily vary in length according to the depth of water in which the plant grows, being always long enough to allow the leaf some freedom in floating about; the range is therefore from a few centimeters to 5 or 6 meters, and that in the same species (*N. alba*, *odorata*). In diameter the smallest are those of *N. tetragona*, 0.3 cm. through, and the largest are found in *N. lotus*, 1.9 cm. through. They vary very little from a cylindrical shape, being, near the ends, slightly flattened on the upper side. Of a uniform green in most species, many of the cells contain a blue-purple pigment in the blue-flowering species, or red-purple in the *Lotos* group; *N. odorata* has usually deep crimson-brown petioles, and in *N. tuberosa* they are quite characteristically marked with longitudinal brown stripes in the upper part. Always pubescent when young, the hairs persist only at the base in most species, but are permanent in the majority of the *Lotos* group, and in occasional specimens of *N. odorata*; Caspary (1865) had such from New York State on which he founded his variety *villosa*, and we have cultivated such a plant, sent from Florida by Mr. Soar of Little River, in the Botanic Garden of the University of Pennsylvania. A plentiful growth of short filamentous algae on the petioles and under surfaces of leaves has been mistaken for pubescence by some writers.

Surface sections of the petiole reveal an epidermis composed of four-sided cells arranged in fairly regular longitudinal rows, mostly with the longest dimension lengthwise of the petiole; the cross-walls are often oblique. At intervals of 1 or 2 to 15 or 20 cells, the rows are interrupted by circular, thick-walled cells, the bases of the hairs mentioned above. In the *Castalia* group, hair-bases seem to be most plentiful in *N. odorata*, though in all species they differ in number at different levels on the petioles. In transverse section, the epidermal cells vary in shape from

slightly wider than deep to slightly deeper than wide. In *N. tuberosa* the latter shape occurs near each end of the petiole, while near the middle the cells are approximately square in section. The bases of the hairs, Fig. 25, (a), (b) are now seen to consist of a short epidermal cell whose inner end is about flush with its neighbors, surmounted by one or two shallow, disc-like cells which come up level with the outer surface. Two disc-like cells are constant in *N. rubra* and *zanzibariensis* \times and occasional in *N. tuberosa* and *amazonum*, only one being found elsewhere. The disc-like cells are very shallow, one-third to one-fourth the depth of the epidermis in *N. odorata* and its varieties, but in other species they occupy about half




FIG. 25.—Collenchyma in petioles.
(a) *N. sturtevantii*; (b) *N. flava*; b, basal cells of a hair.

the depth of the epidermis. A thick cuticle is always present, and was seen in *N. tetragona* to be distinctly lamellate.

Beneath the epidermis there is a single subepidermal layer, distinguishable in all but *N. tetragona* by its thin walls, and in *N. rubra* by the larger size and somewhat columnar arrangement of the cells. Under this layer is a zone of collenchyma (Fig. 25), whose cells remain of small or medium size but are followed internally by much larger fundamental cells in *N. mexicana*, *flava*, *rubra*, *amazonum*, and the middle parts of the petiole of *N. zanzibariensis* \times , but which become gradually larger inward and pass more or less insensibly into the fundamental tissue in *N. odorata*, *tuberosa*, *tetragona* and the lower part of petiole of *N. zanzibariensis* \times . This zone is about 3 cells wide in *N. flava* (a small petiole), 4 in *N. tetragona*, *mexicana*, *amazonum*, 5 or 6 in the upper and lower ends of *N. tuberosa* petiole and the middle of *N. zanzibariensis* \times , 6 or 7 in the middle of *N. tuberosa*, and 8 in *N. odorata*, *rubra*, and the two ends

of *N. zanzibariensis* \times . In *N. tetragona* the subepidermal layer is decidedly colloid, and in other species it may be slightly so in its inner walls. These colloid tissues are of the type usually described in text-books for collenchyma; the thickenings are massed in the angles where three or more cells meet, sometimes from their great amount seeming to extend along the narrower sides. The appearance is often that of a group of round dull bodies (the cell-cavities) in a highly refractive but homogeneous medium; in less pronounced cases the likeness is more that of a network with large knots. In Müller's (1890) valuable classification of collenchyma, *Nymphaea* is cited as an example of his first class, "Corner-collenchyma" (*Eckencollenchym*), and as having the colloid matter sometimes convex and sometimes concave to the cell-lumen; the latter is most common, but the former may be seen in *N. rubra*. The greatest amount of thickening occurs about the middle of the colloid zone.

The remaining tissue of the petiole, designated already as fundamental tissue, consists of larger or smaller rounded, thin-walled cells, with large intercellular spaces; it is traversed longitudinally by numerous lysigenous air-canals and by vascular bundles. In *N. odorata* these cells are of fairly uniform size, but in *N. rubra* the cells bounding the air-canals, and those between the canals, are much smaller than those between the canal-region and the collenchyma. Many of the large fundamental cells are bi-nucleate, and in *N. flava* and *N. zanzibariensis* \times contain starch.

For many years the air-canals of waterlily petioles and peduncles have attracted the attention of botanists on account of their large size and constant and characteristic arrangement. Thus Mackintosh (1876), Parlato (1881) and Masters (1902, *a*, *b*), as well as Planchon, Caspary and others have written of them. Two principal types may be distinguished in petioles of mature plants; (1) that of *Eu-castalia*, with four nearly equal, large canals placed in a square near the middle of the petiole, two anterior and two posterior, and (2) that of *Lotos*, *Hydrocallis* and *Xanthantha*, with two greatly predominant canals and two lesser ones at each end of these (anterior and posterior). Other species, as shown in the diagrams (Fig. 26), approach one or other type more or less, or show intermediate conditions. Starting from such an arrangement as is shown in *N. tetragona* (19) or *gigantea* (11), we can easily imagine specialization leading in two directions to the well-marked types above mentioned. Each canal is bounded by an even layer of small cells, with walls slightly convex toward the canal, and is lined with a thick cuticular coating, whose function, if the researches of Barthélemy (1874) are of weight, is to aid in




FIG. 26.—Sections of Petioles and Peduncles.

No.	Name.	Organ.	Distance from end.	Natural size (centimeters).
1	<i>N. odorata gigantea</i>	petiole	4 cm. from leaf	0.9 × 0.64
2	<i>N. rudgesana</i>	"	7.6 " " "	0.48
3	<i>N. amazonum</i>	"	1.8 " " "	0.63 × 0.48
4	<i>N. mexicana</i>	"	7.0 " " "	0.48 × 0.42
5	<i>N. odorata</i>	peduncle	midway	0.55
6	<i>N. odorata sulfurea</i> (hybr.)	petiole	9.6 cm. from leaf	0.47
7	<i>N. flava</i>	"	" " "	0.8
8	"	peduncle	7.6 " " flower	0.48
9	<i>N. tetragona</i>	"	" " "	0.42
10	<i>N. zanzibariensis</i>	petiole	9.6 " " leaf	0.8
11	<i>N. gigantea</i>	"	0.2 " " "	0.48
12	<i>N. caerulea</i>	peduncle	7.6 " " flower	0.64
13	<i>N. dentata</i> ?	"	" " "	0.8
14	<i>N. lotus</i> ?	petiole	9.6 " " leaf	0.95
15	<i>N. gracilis</i>	"	" " "	0.8 × 0.95
16	<i>N. caerulea</i>	"	" " "	0.8
17	<i>N. tuberosa</i>	peduncle	46 cm. from rhizome	0.48
18	"	petiole	9.6 cm. from leaf	0.63 × 0.48
19	<i>N. tetragona</i>	"	9.6 " " "	0.47
20	<i>N. caerulea</i> ×	"	9.6 " " "	0.82

Nos. 1, 2, 6, 7, 14, 15, 16, 18, 19 are placed with ventral (upper) side uppermost.

the exchange of gases between the air in the canals and the surrounding tissues. For, following Goebel (1893), it seems generally accepted that the air-spaces of aquatic plants are for the purpose of internal breathing; and the researches of Lechartier (1867) as well as those cited by Goebel (l. c.) are in favor of this view. Such an internal cuticle can hardly be for protection in the same sense as this function is attributed to it on the outer surfaces of plants, though it might be simply a chemical product of the contact of air upon an otherwise unmodified living cell-wall. Similar arguments apply to the cuticular coatings on the surfaces of mesophyll-cells where in contact with air, as in the air-chambers connected with the stomata in most plants. Russow (1884) and Mellinck (1886) regarded these coatings as intercellular protoplasm; but Kny (1900), working over the same ground very recently, considers the presence of living extracellular protoplasm in the large air-canals of water plants improbable; the writer favors this view for *Nymphaea*. Kohl (1889) found on the walls of the air-canals of *N. alba* small free crystals of calcium oxalate.

Between two adjacent air-canals there is often but a single layer of cells (e. g., *N. flava*, *tetragona*, and small leaves of *rubra*, *amazonum*, etc.); usually, however, the partitions are 2 to 6 or even 12 cells thick. The thickness varies slightly in different parts of the same petiole, since the canals taper a little at each end. The largest ones, at least, open at the proximal end into the lacunar mediocortex of the stem by pores in the end-wall; at the distal end they connect similarly with a mass of similar lacunar tissue which again makes communication with the air-canals of the veins of the leaf. At each of these points of opening the walls of the canals and the lacunar tissues are loaded with stellate idoblasts; indeed, the lacunar tissue in *N. flava*, *odorata* and *tuberosa* seems to be little else than a tangled mass of such cells, with their arms interlacing in every direction. Diaphragms do not occur in the air-canals of the petioles and peduncles.

It will be well here to dispose of some matters relating to the internal hairs of *Nymphaea*. We have adopted for them the Sachsian term "idioblast" as used by Weiss (1878).¹ Their common features are the great induration of the walls, and the presence of numberless small

¹ The earlier terms "pachycyst" of Caspary (1865), "pneumatocyst" of Planchon (1850, *e*) and "Knorpelzelle" of Hanstein, have never come into general use. Solereder's (1898) "Sclerenchymzelle" is a good term, but a little too broad. Ischirch (1889) has proposed the term "astroclereide," but Arcangeli (1890, *a*) rightly objects to this because so many forms are found in addition to the stellate-cell; he therefore proposes "cladosclereide."

more or less cubical or rhombohedral crystals of calcium oxalate embedded in the wall. Schenck (1884) states that the completed crystals are formed on the inside of the primary walls of the cell, followed in the usual way by deposits of layers of secondary thickening. Kohl (1889) and Arcangeli (1890, *a*) support this view, in opposition to Molisch (1882) who thought the crystals were only partly embedded in the wall, and to Van Tieghem (*Traité de Bot.*, 12 ed., p. 644-5) who considers them to be simply incrustations and not crystals at all. That they are truly embedded is shown by the fact that a protuberance still remains after the salt is dissolved out by acid. Kohl (l. c.) gives a copious list of plants in which such "tertiary" calcium oxalate is found. Idioblasts are derived from ordinary young parenchyma cells; these become distended on one or more sides into the air-canals or smaller intercellular spaces. In a narrow canal, the further extension of the cell takes place in two directions, resulting in a long, double-pointed (bipolar) idioblast, attached somewhere on one side. This type is very plentiful all through the petioles of the *Eucastalia* species; a row of such idioblasts occurs in these petioles next to or near the epidermis; a similar row was seen in *N. zanzibariensis* and in a hybrid of this near the leaf, but in no other species were they observed. If a cell bears two such elongated outgrowths, its shape resembles a long narrow H. But where the future idioblast lies next to a broad air-canal, it usually puts out several arms in different directions, giving the well-known stellate form; all possible shapes from the simple two-pointed fiber to a star with 8 or more arms may be found. These have been frequently observed and figured heretofore. They vary in number at different levels in the petiole. Thus, in *N. tuberosa*, near the rhizome the marginal ring of bipolar idioblasts numbered about 18, near the middle of the same petiole 100, near the leaf 60; in *N. odorata* there were none at the rhizome, 60 to 70 midway, and 100 near the leaf; *N. zanzibariensis* × had about 100 near the leaf. A comparison of the number of idioblasts of all kinds in different species was made by counting those visible in a single field of the microscope (Leitz, oc. 2, obj. 3) at the center of the petiole (between the four main air-canals); the results are shown in the subjoined table. The varieties of *N. odorata*, viz, *minor*, *rosea*, and *N. exquisita* Hort., are like the type in this respect. *N. flava* and *mexicana* agree in having no bipolar idioblasts, but many small, short-armed, stellate cells in the canals.

In addition to idioblasts, there are found rather plentifully (one every 6 to 15 cm.) in the air-canals of petioles (and peduncles) of Apocarpiae,

and less frequently in *Lotos*, irregular cell-masses projecting from the walls; these appear as whitish specks to the unaided eye, and are found to consist of numerous oval, thin-walled, turgid cells with one end free in the canal and the other attached. They develop from a single wall cell, much after the manner of the diaphragms of the canals of roots. Similar outgrowths were found by Mellinck (1886) filling up the air-

	NUMBER OF IDIOBLASTS IN CENTRAL QUADRANGLE.	
	Of Petiole.	Of Peduncle.
<i>N. odorata</i> , near rhizome....	43	21
midway.....	61
near leaf.....	110	38
<i>N. tuberosa</i> , near rhizome....	42	12
midway.....	31	24
near leaf.....	42
<i>N. zanzibariensis</i> , near leaf..	20	1 near base
<i>Lotos</i>	0*	none.†
<i>N. marliacea chromatella</i>	0 bipolar, few stellate	

* 3 species and varieties examined. † 7 species and varieties examined.

spaces of petioles of *N. alba* which had been wounded as far in as the large air-canals. We shall speak of them hereafter as thyll-like bodies.

The course of the vascular bundles in the petiole is longitudinal and parallel from end to end. Their manner of entering the stem has already been referred to. In joining the leaf, all of the bundles are connected in the uppermost end of the petiole (or in the base of the leaf as one chooses to call it) by transverse commissures, forming a ring of vascular tissue parallel to the surface of the leaf. In *Lotos* this causes a circular swelling of striking prominence, which I have called the "collar"; it is less prominent in *Apocarpiae*, and not noticeable in the other groups. From this ring the primary veins radiate out into the leaf. In general, the bundles of the anterior and antero-lateral parts of the petiole supply the lobes of the leaf, the lateral and postero-lateral its sides, and the posterior and median form the midrib.

The arrangement of the vascular bundles in the petiole differs according to that of the air-canals and the size of the petiole, but follows an easily definable plan. Details may be gathered from the diagrams (Fig. 26). Where there are two main air-canals, we find a large double-bundle at each end of the partition between the canals, that is, in the median plane anteriorly and posteriorly, and two smaller bundles on each

side of the canals equidistant from each other and from the former two. According to the size of the petiole there may be an additional, still smaller bundle in the middle of each space between the six just located ;




FIG. 27.—Types of vascular bundle; (a) simple bundle; (b) small bundle with air-canal from petiole of *N. tuberosa*; (c) double bundle from peduncle of *N. zanzibariensis*; (d) double bundle with two canals, petiole of *N. dentata*. a, air-canal; s, sieve tube; sp, spiral trachea; t, tannin or latex cell.

and still another series of twelve very slender ones may alternate with all of the preceding ones. Where four main air-canals are present, there is always a large bundle in the middle of the petiole where the four partition walls meet ; the peripheral bundles are arranged on the same principle as before, though usually there is but one large lateral bundle on each side ; thus the number of peripheral bundles will be a multiple of four instead of six.

In structure the vascular bundles of the petiole (and peduncle) of *Nymphaea* show that extreme reduction of xylem which usually characterizes water plants. In the absence of any distinguishable endodermis, the bundles are sheathed by ordinary, large, fundamental cells ; occasional inter-cellular spaces occur between these and the bundle-cells, but this is not common ; the outer side of the sheathing-cells, however, joins with the

surrounding fundamental tissue with the looseness common to that tissue. Three types of bundle may be distinguished :

(1) The smallest bundles, Fig. 27, (a), consist of a strand of phloem, with perhaps five or six sieve-tubes and a number of companion-cells, and on the inner (central) side there may or may not be one or two spiral elements.

(2) Medium-sized bundles, Fig. 27, (b), like the former but larger as to the amount of phloem, and accompanied on the inner side by a small but extremely regular and round air-canal.

(3) Still larger bundles, Fig. 27, (c), differing from (2) in having a phloem strand on the inner side of the air-canal as well as on the outer side ; the inner strand is usually smaller than the outer.

Sometimes two air-canals intervene between the phloem strands, Fig. 27, (d), while in the center of a large petiole (or peduncle) there may be three phloem strands about a single air-canal. The four or six large peripheral bundles of the petiole usually have two phloem strands and one or two canals. These air-canals are quite small, scarcely visible to the naked eye, and are bounded by a very regular row of clear cells, whose walls next to the lumen of the canal are convex and strongly cuticularized. In very young petioles remnants of spiral elements may be seen in these canals, showing that they bear the same relation to the bundle as the well-known canals in the xylem of monocotyls, *Zea mays*, etc. Where the petiole joins the leaf several spirals are found at the sides of the canals, and these rapidly increase in number as we approach the collar until the canal is wholly obliterated, and there is, instead, a mass of spiral elements nearly or quite as large in cross-section as the phloem strands. The neat wall of the canal disappears *pari passu* with the encroachment of the spirals (cf. Caspary, 1858, p. 382, 385 ; 1888, p. 2 ; Solereder, 1898).

The lamina of the waterlily leaf (Fig. 28) varies in size from 5 to 7 cm. in diameter in *N. tetragona* and *odorata minor* to 40 cm. or 60 cm. in the large tropical forms. It is cleft nearly to the center where the petiole is attached, and has been termed fissi-cordate. Nearly orbicular in most species, it is somewhat oval in *N. caerulea*, and decidedly so in *N. elegans*, *pubescens*, and *tetragona*. The margin is entire in *Eu-castalia* and *Chamaenymphaea*, slightly wavy at base in *Xanthantha* ; in *Hydrocallis* and *Brachyceras* it varies from entire in *N. amazonum* and *elegans* to deeply sinuate in *N. rudgeana*, *ampla*, *flavo-virens*, *capensis*, and *zanzibariensis* ; in *N. gigantea* and the *Lotos* group the leaves are sinuate-dentate, with

wide rounded sinuses and sharp, almost acuminate teeth. The apex is usually rounded, but somewhat emarginate in *N. caerulea* and sometimes in *N. odorata*, especially the variety *gigantea*. In the sinuate-margined Apocarpiae, the tendency is for the apex to lie in a sinus, while in *Lotos* the midrib is continued out into one of the serrations. At base the two lobes may overlap or just touch or divaricate in the same plant or species, so that this feature is of very little systematic value. Near the petiole the lobes may be fused by their edges for a distance of 2.5 to 5 cm. in *Lotos*, 1.3 cm. in some Apocarpiae, or almost none in *Castalia*; this causes the leaf to be more or less peltate, and the fused portion I have called the *pelta* (Fig. 28, *p*). At the apex of the lobes they tend to develop distinct points marking off the borders of the sinus (the space between the lobes) from the rest of the margin of the leaf; this point is acuminate and sharp in *N. gigantea*, *capensis*, and the *Lotos* group, obtuse but still produced and evident in *Castalia*, altogether absent and the lobes broadly rounded in *N. amazonum*.




FIG. 28.—Leaf of *N. flava*, showing upper surface on right, lower surface on left half; *a*, angle of lobe; *l*, lobe; *p*, pelta; *r*, principal area; *s*, sinus; *t*, stomatic area; 1, 2, 3, 4, 5, primary veins.

The thickness of the leaves of most species gives them a leathery feeling, but they are rather brittle and easily torn. Mostly lying flat upon the water, we have exceptions in the crisped margins of *N. flavo-virens*, *capensis*, *zanzibariensis* and the *Lotos* group. *N. odorata gigantea* often has the margin of the distal half of the leaf turned up at right angles to the water-surface to the height of 2 or 3 cm., somewhat after the manner of *Victoria*. A rich chlorophyll-green is the usual color of the upper surface of the leaves. In *N. flava*, *mexicana*, *tetragona*, *rubra-rosea*, *amazonum* and *zanzibariensis*, however, there is more or less of brownish-red blotching, and in *N. rubra* the whole leaf is of a bronzy-red hue. The under surface of the leaf is quite different. Dull green in *N. tuberosa*, it is

reddish to dark crimson-brown in *N. odorata*, *alba*, *tetragona* and *flava*, dull brownish in the Lotos group, and blue-purple in *N. zanzibariensis* and *gigantea*. Dark brownish or blackish blotches and specks mark the under surface in *N. flava*, *caerulea*, *ampla*, *elegans* and *amazonum*. The leaves are rolled inward from the sides (involute) in venation. They come up through the water in a more or less erect position, and only on reaching the surface does the lamina bend over at right angles to the petiole (Frank, 1872).

The venation, as inferred above, is in general palmate, but there is a distinct midrib with pinnate branching. The lowest pair of veins turn backward into the lobes, and others radiate out at various angles; it is sometimes difficult to decide whether the most anterior of these are distinct or branches of the midrib. Five (*N. flava*, *tetragona*) to twelve (*N. zanzibariensis*) veins on either side of the midrib originate thus directly from the base of the leaf, and were called by Caspary (1865) primary veins (Fig. 28, 1-5). They give off small branches along their course, but sooner or later fork into two nearly equal parts. A strong cross-vein soon connects the forks of adjacent veins, enclosing a distinct area between each pair of veins. The area whose long axis stands most nearly at right angles to the midrib was called by Caspary (l. c.) the *principal area* (Fig. 28, *r*), and its length in relation to the radius of the leaf was used as a standard measurement in all of his taxonomic work. The vein below it is the *principal vein* (Fig. 28, 3). Beyond these primary areas there is a series of similar meshes, becoming rapidly smaller out to the margin of the leaf. Here the outer boundaries of the ultimate meshes make an irregular, submarginal vein in all but the Lotos group; in these, three or four veinlets run together to a point in the apex of each tooth of the leaf-margin. Great variety exists in regard to the prominence of the veins on the under side of the leaves. In *Castalia* the veins are easily seen, but they are marked by very slight and gradual elevations of the leaf surface. In *N. amazonum* (Hydrocallis) the veins are prominent beneath as narrow, low, but quite abruptly raised lines. Among the Apocarpiae, *N. gigantea* has the veins quite abruptly raised above the leaf surface, and standing out as a prominent reticulum; *N. zanzibariensis* is similar save that the ultimate veinlets at the leaf margin do not project, and so we pass through *N. flavo-virens* to *N. caerulea*, in which the primary veins alone are markedly prominent, and the tertiary branches are raised very little if any above the leaf surface. The Lotos group, however, has an extremely prominent network of veins. The

midrib near the base forms a ridge a centimeter high and 0.3 to 0.5 cm. wide, with vertical, parallel sides and rounded summit. The primary veins are but little lower; the ultimate branches also, especially where they run out into the serrations, stand out like little cords. Thus by a system of underlying rafters the lamina is rendered firm and stiff. In the large leaves of *Euryale* and the gigantic foliage of *Victoria* this method of strengthening is carried to a remarkable degree of development.

In describing leaf-structure we may speak of (1) the upper epidermis, (2) the palisade layer, (3) spongy parenchyma, (4) idioblasts, (5) vein-structure, (6) lower epidermis, and (7) external hairs.




FIG. 29.—Epidermis of leaf, *N. tetragona*: (a), lower epidermis with bases of hairs; (b), upper epidermis with average stomata; (c), upper epidermis with very large stoma from margin of astomatic area.

The upper epidermis is perfectly smooth and even and somewhat cuticularized on its outer surface. The cells are square or polygonal and from 0.0127 to 0.0178 mm. across (in eight species and varieties). Their outlines are quite wavy in *N. flava*, and *mexicana*, less so in *N. tetragona* and *alba candidissima*, and nearly straight in *N. amazonum*, *odorata*, *tuberosa* and *zanzibariensis* \times . The cells vary in depth, but are about 0.01 mm. deep in *N. rubra* and *odorata*, 0.01 to 0.013 mm. in *N. tuberosa*, 0.013 in *N. amazonum*, 0.01 to 0.0178 mm. in *N. tetragona*, and 0.0178 to 0.02 mm. in *N. zanzibariensis* \times . Stomata are present only on the upper surfaces of the floating leaves. They are usually small and round, Fig. 29, (b), and separated from one another by two to three or four epidermal cells; their openings are comparatively large. The guard-cells stand on a level

with the surrounding epidermis. The size is quite constant in the eight species studied, namely about 0.0176 mm. in diameter; those of *N. tetragona*, however, are slightly oval and 0.02 to 0.025 mm. wide by 0.025 to 0.028 mm. in length. The average number of stomata per square centimeter is, in round numbers, 340 for *N. tetragona* and *odorata*, 390 for *N. tuberosa*, 500 for *N. zanzibariensis* \times , 530 for *N. mexicana*, 720 for *N. amazonum*, 960 for *N. alba candidissima*, 1,000 for *N. flava*. Immediately over the insertion of the petiole there is an area totally devoid of stomata, Fig. 28, (t); it is of a rounded shape with a slender prolongation over




FIG. 30.—Leaf of *N. rubra*, vertical section; a, air chamber; id, idioblast; p, palisade layer; s, stoma; sp, spongy parenchyma; v, a small vein.

each primary vein, and varies in size from 1.2 cm. to 3.8 cm. across. Here the epidermal cells are slightly larger than elsewhere. At the edge of this area the stomata are at first far apart and extremely large, Fig. 29, (c); in *N. tetragona* I found them 0.05 to 0.052 mm. long by 0.038 to 0.045 mm. wide, in *N. alba candidissima* 0.045 mm. long by 0.038 mm. wide, in *N. odorata* 0.043 to 0.045 mm. long by 0.038 to 0.043 mm. wide, in *N. zanzibariensis* \times 0.038 to 0.05 mm. long by 0.031 mm. wide, in *N. amazonum* 0.031 to 0.038 mm. long by 0.028 to 0.033 mm. wide. From these exceptionally large dimensions the stomata rapidly become smaller at greater distances from the petiole, reaching the average size within the length of 0.5 to 0.7 cm. A border of about 0.16 cm. in width around the margin of the leaf is also devoid of stomata, but there is no increase in size of those nearest the margin.

The palisade layer of waterlily leaves is very deep, and composed of parallel strings of cylindrical cells. Between these are long, narrow air-chambers, opening through the stomata above, and connecting with the lacunae of the spongy mesophyll below. In *N. tetragona* the palisade layer is about 0.09 mm. deep, in *N. rubra* (Fig. 30) 0.1 to 0.14 mm. in depth, being in each case one-half the thickness of the whole mesophyll, and consisting of two to three series of long, narrow cells. In *N. odorata* the palisade occupies a little more than one-third of the thickness of the mesophyll and consists of five to seven series of cells with an aggregate depth of 0.14 to 0.15 mm. In *N. tuberosa* there are four or five series of cells with a depth of about 0.16 mm., or about one-half of the mesophyll. *N. zanzibariensis* × has five series of cells, making about 0.14 mm., or a little less than half the mesophyll; finally, *N. amazonum* has four series of cells, altogether about 0.14 mm. deep, or half the depth of the mesophyll. Where the palisade layer is more than two cells thick, the uppermost ones are shorter than the rest, often but little longer than wide. Ameling (1893, p. 189) gives 0.0166 mm. as the average diameter of a cell of the palisade parenchyma of *N. alba*, and points out the interesting fact that this is exactly the same in a leaf 230 mm. in diameter and in one only 95 mm. across. In another table (p. 198) a leaf 190 mm. across had the palisade cells 0.019 mm. in diameter, and this is compared with a like measurement of 0.0197 mm. in a leaf of *Victoria regia* 900 mm. across. The close agreement in size of cells is striking. The lower ends of the strings of palisade cells rest against a very loose, irregular layer of mesophyll cells, the upper members of the spongy parenchyma (Fig. 30). They are large, thin-walled and turgid, and of the most varied forms; they connect with trabeculae or rods and plates of soft cells which pass vertically from this layer to the lower epidermis. Great air-chambers lying between the trabeculae occupy five-sixths of the space of the spongy layer. Bounding and supporting the lower epidermis in *N. odorata*, *tuberosa*, *flava*, *marliacea chromatella*, and *zanzibariensis* × is a 1 to 3 seriate layer of smaller, fairly regular, and close-fitting parenchyma cells. This layer may be absent in *N. rubra*, *amazonum*, and *tetragona*, the air-spaces of the mesophyll being bounded below only by the epidermis. Immediately over the insertion of the petiole the mesophyll cells are nearly cubical, with walls evenly colloid-thickened, and without intercellular spaces.

A very striking feature of the mesophyll is the presence of innumerable idioblasts. In the spongy layer these are usually of the multipolar or stellate form. They project from every side into the air-spaces, and

assume the most grotesque shapes; one might truly say that of the thousands one sees, no two are alike. Since most of the arms end freely in open cavities, as do those in the air-canals of the roots, petioles, and peduncles, it is impossible to assign to them any function of strengthening the tissues as Arcangeli (1890, *a*) suggested, although bipolar and H-shaped idioblasts in leaves may have that use in a measure. Arcangeli's additional opinion that they serve as depositories for waste calcium oxalate seems to be a good one, although Kohl (1889) reverses the case and considers that in all such cases the salt is a by-product of the deposition of thickening carbohydrates on the cell-wall; he imagines that the glucose or dextrose is transported as a calcium compound. There are, however, great numbers of idioblasts in the leaf, of still another type, which seem to have a definite supporting office. These are cells of great size, with one end spread out in three or four lobes against the inner side of the upper epidermis; from this broad base a stout shaft runs down between the strings of palisade cells (Fig. 30, *id*). Reaching the spongy parenchyma, it may break up at once into several radiating arms, or may continue straight on down to the lower epidermis and attach itself there by a narrow base; all imaginable intermediate conditions may be found. The walls of such idioblasts are extremely heavily thickened. In dried specimens these make prominences on the upper surface of the leaves, and since their number differs according to the species, they were used by Caspary (pachycysts, 1865) for systematic distinctions.

The veins which ramify copiously throughout the leaf present several interesting features. The midrib is marked by a line of modified parenchyma. In the palisade region this line is three to five cells wide. The cells are nearly cubical and very poor in chlorophyll; the upper ones have thickened walls. These grade off insensibly into a plate of larger, close-fitting parenchyma cells which runs through the leaf to the lower epidermis. There is a broad arc of corner-collenchyma just within the epidermis on the lower side of the rib. Embedded in the plate of parenchyma are the vascular bundles, and along its sides are two (*N. odorata*) to several (*N. rubra*, *zanzibariensis* ×) air-canals. Each vascular bundle is surrounded by a sheath of parenchyma cells much smaller than those of the neighboring tissue. Although a well-developed xylem of spiral tracheae and companion cells is present, it is less in amount than the phloem. Near the base of the midrib several types and positions of bundle are met with (Fig. 31). In *N. odorata* there is shortly below the epidermis a tiny bundle, and just below this a much larger one, both with xylem above and

phloem below. Under this is a double bundle with xylem in the middle and phloem above and below, then another double bundle, placed transversely, and finally a simple bundle with xylem uppermost. The lowest bundle is underlaid by a transverse band of thin yellowish collenchyma. Near the apex of the same midrib the lowest bundle with its band of collenchyma still persists; above it is an inverted simple bundle, and above this again, near the base of the palisade layer, is a simple bundle with normal orientation. Lateral bundles seem to arise along the midrib from the median double bundles, and as they go farther from the rib they swing round so as to present a normal orientation of xylem and phloem. At a point nearer the petiole than the section first described, the place of the transverse double bundle is taken by an irregular vascular mass,




FIG. 31.—Arrangement of vascular bundles in veins of leaf: (a) section near the base; (b) near apex of midrib, *N. odorata*; (c), (d) from *N. capensis* \times ; e, upper epidermis; p, parenchyma; pal, palisade layer; pe, lower epidermis and parenchyma; ph, phloem; sp, spongy parenchyma; x, xylem.

consisting of one or two xylem areas, each surrounded by two to four phloem lobes; each phloem lobe represents a bundle which emanates from the vascular collar, several of which fuse to form the transverse double bundle of the rib.

The primary veins are traversed by a lower large simple bundle with phloem below and xylem above, and a similar smaller bundle above this. In all of the lesser veins the orientation of bundle tissues is strictly normal. The lower curve of the vein also is lined within with corner-collenchyma, but there is no interruption in the palisade layer above; the bundle has a close sheath of small cells, and a wider investment of parenchyma. In all but the finest ramifications the veins lie nearer to the lower surface of the leaf and are made fast there by the continuity of their surrounding parenchyma with that which lines the lower epidermis; for there is such a lining layer near the veins, even in *N. rubra*. The smallest veins lie just beneath the palisade layer (Fig. 30, v), where the exchange of crude and elaborated materials takes place. I have not observed any free endings of veins; anastomosis seems to be universal.

The lower epidermis (Fig. 29, *a*) has been frequently referred to in previous pages. It is a perfectly continuous layer, 0.01 to 0.018 mm. thick, quite smooth on the outer surface, and consisting for the most part of polygonal cells, many of which are about twice as long as broad (0.018 × 0.036 mm.). In these is located the pigment which colors the under side of the leaf. More or less plentifully interspersed with them are thickened circular cells (suberized, according to Schilling, 1894) representing the bases of hairs. Frequently the other epidermal cells are arranged around these in a radial manner. This caused Barthélemy (1874) to speak of them as pseudostomata, and he thought he could see in the center of some of them a small perforation. His opinion lacks confirmation.




FIG. 32.—Development of mucilage hair of *N. alba*; 1-5, successive stages. (After Schilling.)

The circular cells are about 0.02 mm. across in *N. flava*, *mexicana*, *amazonum*, *odorata*, *o. rosea*, and *tuberosa*; 0.02 to 0.028 mm. in *N. zanzibariensis* × and *alba candidissima*, and 0.025 to 0.029 mm. in *N. tetragona*. Their relative number is shown by the following figures, representing the number visible in a single field of my microscope (Leitz, oc. 2, obj. 7):

N. flava 32, *mexicana* 19-20, *amazonum* 52, *tetragona* 21, *odorata* 36, *o. rosea* 34, *tuberosa* 28, *rubra* 46. In the last-named species permanent hairs stand on many of these basal cells. Hofmeister in 1868 mentioned *N. alba* in company with *Fagus*, *Salix*, *Quercus*, &c., as having hairy leaves only in the bud.

From what has already been said concerning the occurrence of basal cells of hairs in the epidermis of the petioles and lower leaf-surface, it will be seen that hair structures always occur on these parts at some time in their history; the main ribs of the leaves and their upper surface are alone totally devoid of them. On a leaf rudiment of *N. flava* a trifle over 0.16 cm. long, some of these hairs are already complete, but others continue to develop, so that on a leaf three times as long all stages may still be found. A young epidermal cell swells outward beyond its neighbors and is cut in half by a transverse wall; the outer cell continues to swell, and is soon divided by a wall which is strongly concave outward, making a terminal spherical cell (Fig. 32). A second concave wall may follow the first in the apical cell. Now, according to Schilling (1894), who investigated *N. alba* and other aquatics, the cellulose walls of this cell become mucilaginated, the cuticle is ruptured, and the outer cell breaks down into a mass of

mucilage. Cylindrical and clavate mucilage hairs are common in *N. alba* (Schilling, l. c.), and appressed finger-like ones occur in *N. rubra*. They are shed as soon as the tissues of the leaf begin to elongate rapidly and become mature, being of use only to keep the developing organs embedded in a coat of slime. This phenomenon was noted by Irmisch in 1859. Subsequent to the development of mucilage hairs, or along with and among them, longer hairs are formed in most Nymphaeas. The early stages of these are exactly as just described; the apical cell, however, instead of remaining spherical, elongates and may undergo division




FIG. 93.--Hairs and hair bases: (a) on petiole of *N. odorata*; (b) on petiole of *N. rubra*, the shaft being shed; (c) on petiole of *N. tetragona*, showing also the collenchyma immediately below the epidermis; (d), (e), from rhizome of *N. tuberosa*.

into a number of cylindrical elements as in *Eu-castalia*. The terminal cell is bluntly rounded in *Eu-castalia* or acute in *Lotos*. These longer hairs are persistent all over in members of the *Lotos* group, but only at the bases of the petioles in *Eu-castalia*, and as a specially developed ring of long hairs at the summit of the petiole in *N. amazonum*. In *Lotos* the shaft of the hair is unicellular. Its base may be very much wider than the basal epidermal cells in the petiole of *N. rubra* and *sturtevantii*, or but little wider, as on the under side of the leaves of *N. rubra*. The hairs of the ring on *N. amazonum* consist of 12 to 15 cells, and reach a length of 0.48 cm. Stahl (1888) considered the mucilage and other hairs as intended for protection against animals (snails, &c.), and Goebel (1893) suggested that they served to prevent contact of the young organs with one another in the bud; but Schilling (1894) regards them rather as useful in preventing

the access of water to the embryonic tissues. The first idea could apply to the hairs on mature leaves as well as to the younger. It would be useless to assert that either purpose is unimportant.

In a few cases the leaves of *Nymphaea* have been viviparous. Planchon (1852, *c*) records this for "*N. stellata*" (probably *N. micrantha*) as grown by Van Houtte. The plant came from English cultivators, with whom it had never shown this tendency. The new plant springs from the upper surface of the leaf just over the insertion of the petiole. "Already visible," says Planchon, "though very small on the young leaf, the axis but a tubercle with very rudimentary leaves, [the bud] remains almost stationary on the adult and functional leaf so long as this retains its connection with the living plant. If the leaf is detached artificially or by decay of the petiole, it puts out roots, develops its leaves rapidly, and seems to hasten to live an independent life."¹ Further details of the process have not been recorded. It was observed in *N. micrantha* Guill. & Perr. and given thus in the description of the species: "Folia . . . inter lobos saepius bulbifera, bulbillis sphaericis pubescentibus." Hooker (1850) also records the fact in a few words in describing *N. micrantha* in the Botanical Magazine, where the leaf figured is viviparous, and Paxton (1853, *a*) mentions it in his "Flower Garden." Lehmann (1853, *a*) went so far as to establish a "Tribe III Bulbophyllon" for his *N. vivipara*, *N. guineensis* Thonn., and *N. micrantha* Guill. & Perr. We have not considered these as specifically distinct.

Water-leaves are produced in all seedling *Nymphaeas* to the number of 2 (*N. flava*) to 15 or 16 before any floating leaves. Of these more will be said in another chapter. In species which have dry resting tubers the first leaves produced on resuming growth are also entirely submerged. *N. flavo-virens* alone, with its huge tubers, is at times an exception to this rule; small tubers follow the rule. The perennating bodies of *N. flava* (doubtless also of *N. mexicana*) begin the growth of each bud with a few water-leaves, and the other *Castalia* species produce them either in late fall or early spring, or both. These members also lose their floating leaves and produce only water-leaves in unfavorable conditions² of culture,

¹ Déjà visibles, mais très-petits sur la jeune feuille, pourvus d'un axe en forme de tubercule, mais avec des feuilles encore très-rudimentaires, sur la feuille adulte et pleine de vie, ils restent presque stationnaires tant que la feuille tient à son pied nourricier. Qu'on détache artificiellement cet organe ou qu'il s'isole spontanément par la décomposition de son pétiole, aussi tôt le bourgeon pousse des racines, développe rapidement ses feuilles et semble se hâter de vivre d'une vie indépendante. (Flore des Serres, 8: 285.)

² Bonnier (1890) found in several lakes of the Alps shoots of *N. alba* without floating leaves, but with an unusually large number of submerged leaves, "as is often seen in streams with rapid current."

while the tuberous species in like circumstances lose all of their foliage and form tubers, from which they come out again first with water-leaves.




FIG. 94.—First leaves from germinating tubers: 1, first, 2, second submerged leaf; 3, first, 4, third floating leaf of *N. gigantea*; 5, second floating, 6, first, 7, second submerged leaf of *N. flavo-virens*; 8, first, 9, second, 10, third submerged leaf of *N. caerulea*; 11, 12, first submerged leaf from brood body of *N. mexicana* and *N. flava*, respectively; 13, second floating, 14, second, 15, first submerged leaf of *N. elegans*; 16, first, 17, second, 18, third submerged, 19, first floating leaf of *N. zanzibariensis rosea*; 20, 21, first and second submerged leaves of *N. "Mrs. C. W. Ward"* (*N. flavo-virens* \times *zanzibariensis*). All natural size.

Wächter's (1897) observations on *N. stellata*, *dentata*, *rubra*, *thermalis*, and *alba* showed, by cutting off the roots or leaves from growing plants, that production of water-leaves could be induced by enfeebled nutrition,

especially by lack of elaborated materials in the absence of mature foliage; cutting off the roots had a much less marked effect. I have noted also in *N. rubra* that young shoots acquire floating leaves much sooner if left attached to the parent tuber than if early broken off and planted out. It seems quite certain, therefore, that the occurrence of water-leaves in fall and spring in *Castalia* is directly due to the cutting off of the leaves by frost, and the suspension of vitality in very cold water; and, except in the large and powerful tubers of *N. flavo-virens*, the young shoots of other species must gather strength in themselves before they are able to produce floating leaves. In other words, a leaf-rudiment will, up to a certain




FIG. 35.—Transverse sections of petioles of water-leaves; a, *N. rubra*, from tuber; b, *N. odorata*, from rhizome in spring; c, *N. tuberosa*, from tuber.

age, develop into a submerged or a floating leaf according to nutritive conditions.

Such submerged leaves as are now under discussion assume a more or less deltoid shape, varying to hastate (*Lotos*), cordate, or nearly orbicular (Fig. 34). Specific shapes, so far as known, are given in the taxonomic section. The petioles are usually 2.5 to 7 or 8 cm. long, though sometimes longer, and rather stout in proportion. Structurally they show but slight differences from the petioles of floating leaves. The thickly cutinized epidermal cells contain many bright-green chloroplasts in the upper part of the petiole, where it is not covered by mud. The fundamental tissue, too, is rich in chlorophyll throughout. Its outer two to four layers are more or less colloid in the angles, but only slightly so at most; here also chloroplasts are most plentiful. The arrangement of air-canals differs from that of petioles of floating leaves, but in the larger water-leaves this character approaches nearer and nearer to the typical arrangement for the species. The tendency in petioles of water-leaves is toward the condition with two main canals (Fig. 35) and a great many smaller ones around and between these, with partitions but one cell thick. This approaches the adult structure of *N. flava* and *tetragona*, and points also to a probable primitive state in which, like *Nuphar* and the roots of

Nymphaea and Nuphar, the fundamental tissue of the petioles was traversed by innumerable small and equal canals. Specialization has enlarged some of these at the expense of others in Nymphaea, Euryale, and Victoria. The distribution of vascular bundles in petioles of water-leaves follows the plan laid down for floating leaves. Stellate cells occur in the air-canals, but no thyll-like bodies have been found.

The lamina is of a reddish color in Lotos and Eu-castalia, but is plain green in *N. tetragona*, *fennica*, and *amazonum*, and Apocarpiae. Its texture is extremely thin and fragile in Lotos, much firmer, though still very thin, in Castalia, Hydrocallis, and Apocarpiae. The upper epidermis is composed of rather larger, somewhat sinuous cells, and possesses a few stomata. Arcangeli noted stomata on water-leaves of *N. alba* in 1890 (*b*), but Brand (1894) failed to find them, and considered Arcangeli's specimens to be arrested floating leaves. Wächter (1897) corroborated Arcangeli's observation by examining leaves in chloral hydrate, and extended the work to *N. rubra*, *dentata*, *stellata*, and *thermalis*, in all of which a few stomata were found on the upper surface of the leaves. The lower epidermis is like that of floating leaves. Great reduction has taken place, however, in the mesophyll. Arcangeli (*l. c.*) found the palisade layer in *N. alba* reduced to two strata of globular or ovoid cells, and Wächter found a single layer of crescent-shaped cells representing the palisade in *N. rubra* and *thermalis*. The spongy parenchyma is greatly reduced in quantity, and consists of loose cells with large intercellular spaces. Idioblasts are present, but few in number, and the vascular network is simple. The ordinary involute veneration is found in the water-leaves. They are, therefore, to be considered as reduced floating leaves, and no indication is offered of the wholly aerial habits which must have belonged to the distant ancestors of the Nymphaeaceae. Even the large aerial leaves of Nelumbo, from having stomata still restricted to the upper surface, must be considered as derived from floating leaves, and in no close relation to those of the probable terrestrial ancestors of the order.

THE FLOWER, FRUIT, AND SEED.

Few genera of plants offer such variety in size and color of flowers as is found among the waterlilies. The primitive yellow, but of a rich hue, is preserved in Xanthantha and the newly discovered *N. sulfurea* and *stuhlmanni*; white prevails in Castalia, varying to pink in *N. fennica*, *odorata rosea*, and *alba rubra*. All shades from pure white (*N. dentata*) to deep crimson (*N. rubra*) occur in the Lotos group, and from white

(*N. ampla*) to pink (*N. versicolor*) and royal blue (*N. zanzibariensis*) in Apocarpiae. In Hydrocallis a creamy white prevails. Orange tints have been obtained in hybrids of *N. flava* and *alba rubra* (*N. aurora, seignoreti*). In size, *N. tetragona, fennica*, and *odorata minor* stand at one end of the line, with flowers 3.5 to 5 cm. across, and at the other end are *N. rubra, dentata, zanzibariensis*, and *gigantea*, whose flowers measure 30 cm. or more in diameter. There is, of course, great variation within a single species, according to the food supply and other conditions. Other general characters will be brought out in the following description of the flower and flower-stalk.

So close is the resemblance between petiole and peduncle in Nymphaea that we shall greatly abbreviate the present section by referring back to the previous one. The peduncles are always terete, and in color and presence or absence of pubescence are like the petioles of the same species (no brown stripes occur on the peduncles of *N. tuberosa*). In Eu-castalia the likeness extends to the length, diameter, and number of air-canals of the two organs. In Chamaenymphaea the likeness includes length and diameter. The same is true of Xanthantha when in deep water; in shallow water, the peduncles are stouter. These species are also peculiar in that the upper part of the flower-stalk is somewhat four-furrowed with shallow rounded grooves. In all other species the peduncles are 1 to 2.5 cm. in diameter, and stiff enough to raise the massive flowers 5 to 30 or 40 cm. above the water. The more slender peduncles of *N. amazonum* (Hydrocallis) are yet quite stiff and reach to or very little above the water surface. In exceptionally shallow water the same may be true for all of the Castalia group.

The epidermis presents nothing characteristic. It bears a large number of hair bases. Beneath it there is a single layer of thin-walled cells in *N. dentata, rubra rosea, devoniensis, arnoldiana*, and *zanzibariensis*. The inner wall of this layer is somewhat collenchymatous in *N. zanzibariensis* ×, *marliacea chromatella, alba candidissima*, and *gladstoniana*. Following this layer in the above-named forms, or including it in *N. rubra, lotus, sturtevantii, caerulea, odorata*, and *tuberosa*, there are 3 to 11 layers of collenchyma as in the petiole. The character of the remaining tissue is also like that of the petioles. In Apocarpiae the cells contain a good deal of starch, but not so in Lotos and Eu-castalia. Four main air-canals traverse the peduncles of Castalia, but six is the standard number for the remaining groups; these numbers are subject to an occasional variation of one more or less, but much oftener of one more. The canals are equal

and arranged symmetrically about the centre of the peduncle (Fig. 26). Outside of each of these are two rather prominent but much smaller canals, and in *N. zanzibariensis* each of these is followed by two more quite evident canals. Many smaller scattered ones are always present. Idioblasts are extremely scarce in the Lotos group, frequent in Apocarpiae, plentiful in Castalia; fibrous (bipolar) idioblasts occur throughout the peduncle in Eu-castalia and around the periphery of the upper part in Brachyceras. Thyll-like masses of soft cells are frequent on the sides of the larger air-canals in Apocarpiae, occasional in Lotos, and not found in Castalia.

Vascular bundles are distributed on the same principle as in the petiole (Fig. 26). In the centre is a large double or triple bundle. Opposite each of the 4 or 6 main partitions there is a large double bundle, often with two well-formed air-canals in Apocarpiae and Castalia, but with the second canal a mere fissure without definite wall in Lotos. Midway between these bundles are smaller ones, and so on in several series, according to the size of the peduncle. Examples are shown in detail in the diagrams. The constituents of the bundles are exactly as described for petioles.

Just beneath the flower the peduncle widens out to form a receptacle for the insertion of the floral organs. This widening extends over about 1.3 cm. in Lotos, making an inverted frustum of a cone with a slope of about 45° . In Apocarpiae, Hydrocallis, and Eu-castalia the transition is more sudden, almost like the limb of a salver-form corolla. The resulting receptacle is usually round, but in Chamaenymphaea its upper margin is square, with distinct and prominent angles. In Xanthantha there are four rounded prominences on the sides of the receptacle, with distinct grooves between; the grooves are continued down a short distance on the petiole, but they swell again quickly above, so that the receptacle is nearly round at the line of insertion of the sepals. The color of the receptacle is usually like the peduncle, but paler. Within the upper part of this region the vascular bundles of the peduncle unite into an extremely complex horizontal network, from which bundles are separated out for the floral organs. The complexity of this anastomosis is too great to admit of any definition or unraveling as yet.

The flower proper has four sepals, of which one is anterior and outer. The two lateral sepals are covered on one edge by the anterior one, and on their posterior sides they overlap the posterior sepal. At times three or five sepals may occur. I have seen the smaller number in *N. rubra*

and the larger in *N. elegans*, and Eichler (1878, 2: 183-186) records both numbers for *N. alba*. A trimerous flower of *N. ampla* was the type of Gaudichaud's *N. trisepala*. Hexamerous and heptamerous flowers are known. When five sepals occur, two stand in place of one in the posterior position; when only three are present, the posterior one is lacking (Payer, 1857; Eichler, l. c.).

The number of petals varies from 7 (*N. tetragona*) to 33 (*N. capensis*). The 4 outermost are largest and alternate with the sepals; over each interval between these, i. e., opposite each sepal, is a pair of smaller petals, making a whorl of 8. This seems to be followed in *Brachyceras* and *Lotos* by another alternating whorl of 8. Of this row usually only 4 or 5 are present in *N. caerulea*, while an additional row is found more or




FIG. 36.—Floral diagram for *Nymphaea*.

less complete in *N. capensis* and *zanzibariensis*. In *Hydrocallis* the petals are all regularly arranged in alternating whorls of 4. Here, also, the outermost stamens follow in one or two whorls of 4; then come one or two whorls of 8, the first of which has two members over each interspace between the preceding 4; within this it is impossible to make out any order. The stamens of the *Lotos* group follow on in more or less definite whorls of 8, and the same may frequently

be seen in *Brachyceras*. In old flowers of *N. caerulea*, long after inflorescence, when the organs are spread apart by the growth of the ripening ovary, I have several times found the stamens arranged in 16 vertical lines, with mostly 4 stamens in each line. The whorled arrangement is not distinct in *Castalia*, and Eichler (l. c.) states for *N. alba* that there are 4 petals alternate with the sepals, and 4 alternate with these, i. e., over the sepals. These 8 are the beginning points for oblique lines of successively smaller petals, rising right and left with equal inclination. Each series has, on the average, four members. The inclination of the spirals is such that each successive petal stands over the space between two neighbors, so that in all 16 vertical rows of a petals each are formed. The arrangement of the stamens was not made out. The inner petals and stamens are inserted at various levels up the sides of the ovary (receptacle). There is a narrow, naked zone between the petals and stamens in *Lotos* and *Anecphyra*, but in other genera the two sets of organs are in continuous series, except in some forms of *N. candida* and *tetragona*. The carpels are always in a circle in the middle of the flower, abutting against a central prolongation of the floral axis.

We will now take up some details relating to the individual floral organs. The line of insertion of the sepals is usually smooth and rounded; but in *N. candida* the bases of the sepals are slightly produced downward, and in *N. fennica* the sepals make a sharp, clean-cut angle with the receptacle. The general shape of the sepals is ovate. They are always greenish and chlorophyllous outside, and soft and petaloid inside; the margins which are covered in the bud are wholly petaloid. Specific details of shape, size, color, and texture are given in the taxonomic portion of this paper. The epidermis of the outside of the sepals has a very smooth surface, and consists of irregularly polygonal cells in surface view, nearly square in section. Bases of mucilage hairs are frequent in *N. tuberosa* and plentiful in *N. odorata*. In the latter species, also, stomata are present. They begin at or just below the middle of the sepal and are more plentiful toward the apex and are a little larger than those of the leaf (0.015 by 0.015 mm.). The cells of the inner epidermis are rounded and prominent on the exposed side, of approximately rectangular shape, and shallower than those of the back of the sepal. Here also rounded cells like the bases of mucilage hairs are frequent, but no stomata. The parenchyma of the sepal is traversed longitudinally by vascular bundles and in the lower parts by air-canals. Inside the outer epidermis there are in *N. zanzibariensis* \times about 8 tiers of close-fitting, nearly spherical cells containing chlorophyll; they become gradually larger from without inward. Then follow 1 or 2 flattened cells and a vascular bundle, or, between the bundles, 2 to 4 flattened cells and an air-canal. About 5 roundish cells intervene between the air-canals and the inner epidermis. At the apex of the sepals the structure differs from this only in the absence of air-canals. Just within the epidermis on each side two or three layers of cells are feebly collenchymatous, but most noticeably so on the inner side of the sepal. The air-canals in this hybrid are rather large, round or oval, and arranged in a single row between the middle of the parenchyma and the inner epidermis. The partitions between them are two or three to several cells thick. The vascular bundles have a well-developed protoxylem, and at some distance from this, in the larger ones, a small air-canal. There is a row of larger bundles about the middle of the parenchyma and a row of smaller ones between the air-canals and the inner epidermis, with still others between the canals. Many stellate idioblasts project into the air-canals, but none was found elsewhere in these sepals. Thyll-like ingrowths also occur. One of these consisted of but two dense clavate cells, another had a multicellular base surmounted

by a crown of ovate cells with dense granular contents. Intermediate forms were seen.

In *N. odorata* the sepal is quite thick at the base, but very thin above. In the basal region there are about 12 tiers of cells between the outer epidermis and the air-canals, of which the first 4 or 5 are slightly collenchymatous. They are all rounded in outline and become gradually larger from without inward. Among them are very many bipolar idioblasts lying lengthwise of the sepal. The air-canals are very numerous and irregular in shape and size. They are separated by partitions only one cell thick, and occupy a zone about as thick as the denser parenchyma just described. Great numbers of idioblasts of irregularly stellate forms occur here. Between this zone and the inner epidermis there is a zone of about 6 layers of parenchyma. A single irregular row of vascular bundles traverses the partitions between the air-canals. They have well-developed protoxylem and, in all the larger ones, an air-canal. The same structure is continued in the apex of the sepal, but with fewer tiers of cells and much smaller air-passages. Nearly all of the parenchyma cells contain chloroplasts, especially the two or three outer layers, where the cells are crowded together and polygonal in outline.

A section near the middle of the sepal of *N. tuberosa* shows a still more leaf-like arrangement. Within the outer epidermis are two to four layers of round cells with large intercellular spaces and containing many chloroplasts. Then comes a zone 3 to 5 times wider than the first, made up of branching lines of cells and large intercellular spaces. Through this zone the vascular bundles travel, accompanied by one or two layers of close-fitting parenchyma. Phloem and xylem are well represented, but no air-canal was seen. The orientation of the bundles is normal in all parts of the flower. Stellate idioblasts are plentiful in the air-chambers. The inner epidermis is backed by a single continuous layer of rounded cells. Near the apex of the sepal the air-chambers are quite small, the intervening partitions are multicellular, and idioblasts much fewer. The total thickness of the sepal, however, may be greater than at the middle.

Most of the general features of the petals have been already mentioned, and specific details are sufficiently covered in the chapter on taxonomy. The outer four petals are usually of about the size and shape of the sepals. They are thicker at base than elsewhere, and are traversed by a number of longitudinal veins which divide up into a fine network in the upper half or two-thirds of the petal. There may be some longitudinal air-canals in the basal parts. No distinction of blade and claw occurs, but

the oval to lanceolate lamina tapers gently to a comparatively broad insertion. Where the petals are brightly colored, the lower parts are usually paler, and often yellowish, even in blue flowers. The margins of the petals, as of the sepals, are always entire and are of softer texture than the sepals. The inner ones are shorter and narrower than the outer.

The structure of the basal and sepaloid portions of the outer petals of *N. odorata* is exactly like that of the sepals, even to the presence of large stomata on the back. The softer parts of these petals, and all of the inner ones, are much thinner. The epidermis of both surfaces is like the inner epidermis of the sepals, and has numerous hair-bases. Parallel and anastomosing veins traverse the parenchyma, accompanied in the middle line by idioblasts of varied shapes, but without air-canals.

The stamens are quite characteristic in the different groups of waterlilies. In *Castalia*, especially *N. alba*, all gradations are found, from inner petals with a callous yellow tip or with one or two tiny anther cells, to stamens with petaloid base and a small but perfect anther, and so on to the innermost stamens, where the anther is large and thick and broader than the filament. *N. amazonum* shows similar but more rapid gradations; the innermost filaments are filiform and the anthers narrowly linear. In *N. gigantea*, however, all of the filaments are slender, and anthers narrow. *Lotos* also shows no gradation from petal to stamen, but the outer filaments are as much as half an inch wide at base; their insertion is wide and somewhat decurrent at the sides. The anther is broad and ligulate, with blunt, round apex. The inner stamens are shorter and narrower, ligulate in shape, and not decurrent. In all of the foregoing groups the connective is not continued above the anther cells more than as a limiting border to the anther, with the exception of the outermost stamens of *N. gigantea*, which bear a tiny subulate tip. In *Brachyceras*, however, there is a prominent prolongation of the connective at the apex of a large number of the outer stamens. This is least in *N. elegans* (0.08 cm.), small in *N. flavo-virens*, but may reach nearly 1.3 cm. in length in *N. zanzibariensis*. In this group, also, transitional forms between petal and stamen are sometimes seen. The outer filaments are ovate, often shorter than the lanceolate or linear anthers; these grade by slow degrees into the innermost stamens, which are short and slender and without appendage. In all species the outer stamens are colored like the petals, excepting the yellow anther cells in *Castalia* and *Apocarpiae* and the reddish-brown anthers of some *Lotos* species. The innermost stamens are wholly yellow in all but *N. rubra*, where the reddish-brown color persists.

The structure of the filament resembles that of the inner petals. The epidermis bears hair-bases, the parenchyma is made of soft, rounded cells, and air-spaces are present. There are one to three or more longitudinal vascular bundles. The mature anther is covered by a single layer of square cells, a little deeper than wide, with thickened inner and lateral walls; the outer wall is unthickened. The anther cells are parallel and introrse, with longitudinal dehiscence (Fig. 37, *a, b*). In *Lotos* and *Brachyceras* the division between the two loculi of each cell is

quite evident after dehiscence, as the pollen dust remaining after most has been shed lies in two pairs of grooves on the inner face of the anther. Chiffot (1902) has recently made a minute study of sporophyll structure in *Nymphaeaceae*, including nine species of *Nymphaea*. He finds slight differences in the venation of the stamens. He sums up his work (which I have not had time to verify) in a classifica-




FIG. 37.—*a, b*, transverse sections of anther of *N. flava* near base and near apex, respectively; *c*, vertical section of stigma, showing papillae, *N. tuberosa*. All after Chiffot.

tion based on the distribution of idioblasts ("sclerites") and stomata in the stamen, and of idioblasts in the carpels (l. c., p. 280). We quote this in translation. The names are correct and mostly well chosen, unless in the case of "*N. blanda*." The material of this came from the Kew Herbarium, where *N. rudgeana* occurs under the name of *N. blanda*, and is much more plentiful.

SYNCARPIAE :

- Idioblasts rare in the filament, always present in the anther.....*a.*
 Idioblasts absent from filament, anther, and ovary (*Xanthantha*).....*N. flava.*
 Idioblasts present in the filament and outer part of ovary (*Castalia*).....*c.*
a. Stomata present on upper epidermis of filament (*Lotos*). Idioblasts absent from mesophyll of ovary, present in carpellary styles.....*N. thermatis.*
a. Stomata wholly absent from the stamen (*Hydrocallis*).....*b.*
b. Idioblasts of but one kind, present in filament and anther....."*N. blanda.*"
b. Idioblasts of two kinds, localized in the anther.....*N. oxypetala.*
c. Idioblasts absent from the anther, but numerous in the carpellary rays.....*d.*
c. Idioblasts present in anther, rare in carpellary ray.....*N. tuberosa.*
d. Stomata absent from whole stamen.....*N. alba.*
d. Stomata present at base of loculi on both faces of filament. *N. pygmaea* [= *N. tetragona*].

APOCARPIAE :

Idioblasts rare in the filament, always present in the anther. Stomata absent from all the surface of the filament (Brachyceras). Idioblasts absent from all parts of the mesophyll of the ovary and carpellary styles.....*N. caerulea*.
 Idioblasts absent from filament and anther (Anecphyia).....*N. gigantea*.

The dry microspores (pollen grains) of *N. alba* are oval and deeply folded in on one side (Kerner, 1895, fig. 218); in Brachyceras (Fig. 38, *b-e*) they are spheroid, with greatly flattened poles, or, in *N. capensis*, lenticular, and the edges may be folded under from three sides. Fischer (1890) speaks of them as folded in (*eingefaltet*) in *N. dentata*, *lotus*, *rubra*, and *alba*, the infolded half being separated from the other by an equatorial line. Along this line the exine separates in germination. The exine on the infolded half is thinner and smoother than on the other half, and has parallel to the equatorial line a ring of similar thickness and sculpture to the outer half (Fischer, l. c.). In water the grains become spherical in a




FIG. 38.—Pollen: a, young grain of *N. flavo-virens*; b—e, *N. caerulea*; b, just matured; c, nearly dry; d, e, as shed from the anther, seen from opposite sides.

few minutes, and along the equatorial line in *N. capensis*, *caerulea*, *zanzibariensis*, and hybrids the two halves of the exine separate slightly; they seem to be too small to cover the whole swollen grain. In pollen of *N. odorata* mounted in glycerine jelly, some grains have the exine caps still touching at one edge, but wide apart at the other, while some are equidistant all round, and some are unbroken. Fine rods, points, and granules cover the exine in *Eu-castalia*, and one-half of it in *N. tetragona* and *flava* (Caspary, 1865; 1888). It is smooth in Brachyceras, and, according to Caspary (ll. c.), in Anecphyia, Lotos, and Hydrocallis. Fischer (1890), however, found it granulate (*körnig-walzig*) in *N. rubra* and *dentata*, and smooth in *N. lotus*, and I have found it smooth in *N. mexicana*. In germination Caspary frequently refers to an operculum, and in one place (1888) to the "smaller half" of the exine; but the two parts which I have noticed in Brachyceras and *N. odorata* are practically equal, and Fischer speaks simply of two pieces (*zwei Stücke*) in *N. alba*, and elsewhere of the two "halves" of the exine. The term "operculum" is therefore misleading.

The pistil is composed of 5 to 35 carpels, the number being extremely variable for any one species. They are placed radially round a central

prolongation of the floral axis and are immersed in the excavated receptacle with about half of the ventral suture exposed above and the other half fused with the central axis. The back of each carpel is more or less prolonged above the receptacle (except in *N. gigantea*) into a stylar process. We shall speak of this as a carpellary style (Fig. 39, *c*). The exposed portions of the ventral sutures are connivent or united into a broad, round disc, cup, or funnel, the whole surface of which is stigmatic. At the center of this the floral axis projects as a process (Fig. 39, *a*) which is ovoid or nearly spherical in *Eu-castalia*, narrowly ovate in *N. tetragona*, linear and rounded in *Xanthantha*, linear and acute in *Hydrocallis*, broadly conical and obtuse in *Lotos* and *Apocarpiae*. It is of a dull white color.




FIG. 39.




FIG. 40.




FIG. 39.—Diagram of ovary (*Brachyceras*) in longitudinal section: *a*, axile process; *c*, carpellary style; *n*, air-canals; *r*, receptacle; *s*, stigmatic papillae; *t*, torus, with bases of floral leaves.

FIG. 40.—Diagram of ovary in transverse section: *a*, syncarpous; *b*, apocarpous.

The stigmatic surface (Fig. 39, *s*), is usually yellow and densely papillose. The papillae completely cover the upper surface of the small rounded dorsal projections of the carpels of *N. gigantea*, and in other species they extend for a short distance up on the inner face of the carpellary styles. The styles themselves are, as indicated, wanting in *N. gigantea*. In *Brachyceras* they are short, stiff, orange-colored bodies, grading from mere points in *N. elegans* to erect processes in *N. flavo-virens* or stout, incurved bodies 0.6 cm. long in *N. zanzibariensis*. In *Xanthantha* and *Chamaenymphaea* they are more or less ligulate, and stand out horizontally in the basal part. In *Eu-castalia* and *Lotos* they are 0.6 to 1.3 cm. long, ligulate and flexible, and in *Hydrocallis* of about the same length, slender and terete below, with a large clavate end.

In the structure of the ovary Caspary (1865) was first to recognize two fundamentally different types. In most of the old group *Cyanea* of De Candolle and Planchon he found the walls between the cells of the ovary

are composed of two distinct lamellae, which easily fall apart along their smooth surfaces of contact. In all other species there is no such division in the walls, but the tissues in each partition are perfectly continuous. The first group was called on this account *Lytopleura* (λύτος free, πλευρά, side), with the definition "carpella toto latere libera tantum externe ad dorsum et interne ad processum axilem coniunctum enata." The remaining group was called *Symphytopleura* (συμφύτος, connate), and defined "carpella toto latere coniunctum enata." It seems desirable, however, to get rid of names as far as possible, so we have adopted the simple descriptive terms "apocarpous" and "syncarpous" for the two groups. It is valuable to keep in mind that apocarpy occurs in a large group of Nymphaeas, as the Cabombeae and Nelumboneae are all apocarpous. The dehiscence of the fruit of *Nuphar*, *N. flava*, and the fossil *Anœctomeria* into separate carpels suggests a recent apocarpous ancestry.

The absence of any definite placenta in *Nymphaea* has long been a subject of remark. The ovules are attached in large numbers all over the walls of the ovary cells, both lateral and dorsal. They are anatropous, and, at the time of flowering, are suspended on the funiculi with the micropyle upward. The cells of the ovary are oval in side view, wedge-shaped in transverse section, and are filled with a stiff, colorless mucilage.

Externally the ovary (or receptacle) is densely covered with fibrous and mucilaginous hairs. Those of the first type are few and early deciduous in *N. zanzibariensis* ×, but plentiful in the other species examined; they are plainly visible in the *Lotos* group. The longest I noted in *N. odorata* was 0.34 mm., and in *N. o. minor* 0.66 mm., composed of two shaft-cells; the longest in *N. tuberosa* was 0.3 mm., with three shaft-cells; in *N. zanzibariensis* × 0.25 mm., five-sixths of its apical part being a single cell. The epidermis is about 0.15 mm. thick, composed mostly of cubical cells. Within this is a layer of dense tissue about 0.34 mm. thick, of small polyhedral cells with very minute intercellular spaces, followed by a loose, spongy tissue with very large air-spaces. In *N. zanzibariensis* × the air-space in the latter zone barely exceeds the cellular tissue in volume and there are no idioblasts. In *N. tuberosa* and *odorata* the air-space greatly preponderates, and in the latter stellate cells abound. The spongy layer is much narrower and idioblasts very scarce in *N. odorata minor*. The epidermis bounding the ovary cells is backed by a single continuous layer of soft parenchyma cells. In *Syncarpiae* this layer and the lacunar parenchyma are alone present between the epidermal layers in the partitions of the ovary. In *Apocarpiae* the condition is very different. The line of

division between the carpels lies in the middle of each partition and extends from a point in the wall of the ovary a little farther in than the back of the ovary cells to a point in the central axis distinctly farther in than the inner edge of the cells. On each side of this line is a smooth face of square or columnar epidermal cells; the two sides are in contact. This epidermis is backed by two layers of closely packed rectangular cells; then comes a line of open spongy tissue, then a single layer of parenchyma supporting the epidermis which lines the cells of the ovary.

This epidermis is composed of short columnar cells of highly glandular nature; each one bulges out into the cavity with a round, turgid end. They doubtless secrete the mucilage which fills the ovary. The axis of the ovary is composed of spherical cells with large intercellular spaces in *N. zanzibariensis* ×; in *Eu-castalia* (*N. alba candidissima*, *odorata*, *tuberosa*) the spaces are so large that the cells are drawn out into several broad arms. Many stellate idioblasts were present in *N. odorata*. In the upper parts the tissues of the axis become solid. The process in which it terminates is firm and composed of thin-walled parenchyma; the cells are often slightly elongated and arranged in rows bending from the center out to the periphery. A regular epidermis of small cubical cells covers the process.

The stigma is marked with a number of narrow radiating furrows, one between every two carpels and one along the ventral suture of each. Indeed, the ventral sutures are scarcely closed and are easily torn apart. The stigmatic papillae (Fig. 37, *c*) are crowded as close as they can stand and consist of rows of 2 to 8 short cylindrical cells. The terminal one is rounded and contains large, oily-looking bodies. In *Hydrocallis* the cells separate from one another and the stigma is covered with a moist, powdery mass of oily-looking cells, some of which remain attached to each other in strings.

The carpellary styles have numerous mucilage hairs on the epidermis and are made up internally of spherical cells loosely laid together. On the clavate apex of the styles of *N. amazonum*, the epidermis has a slightly corrugated cuticle, and the cells contain a pink-purple pigment.

The vascular system of the ovary presents certain regular features. From the complicated plexus in the base of the receptacle the immediate connections have not been worked out, but sooner or later there is separated a ring of bundles which ascend with numerous branchings and anastomoses in and just outside of the lacunar tissue of the ovary wall, and a ring which ascend in the central axis near the edges of the cells of the ovary. In *N. odorata* another bundle passes up the centre of the axis

to terminate in the axile process. From the bundles of the outer ring branches are given off to the petals and stamens on the one side and to the walls and partitions of the ovary and ultimately to the ovules on the other. Finally, a bundle extends into each carpellary style. In Syncarpiae the bundles of the inner ring, like those of the outer, are irregularly placed with regard to the carpels, and they seem to unite among themselves by oblique branches; but in Apocarpiae there are one or two bundles in the inner edge of each carpel, and these are separated from neighboring ones by the divisions between the carpels. The inner bundles branch copiously into the partitions between the cells of the ovary in order to connect with the ovules. The bundles are so oriented as to bring xylem next to the ovary cells and phloem away from these, that is, normally with regard to the carpel itself. Consequently the bundles of the outer ring have xylem on the axial side, but the inner ring has phloem toward the axis. In the partitions the bundles nearest one cell have their xylem next to that cell; since those on the other side of the partition are similarly arranged, the two sets have their phloem sides turned toward one another. The central axile bundle of *N. odorata* has one or two spiral tracheæ with phloem all round, but especially thick on two opposite sides. Some peculiar vascular bundles occur in the ovary wall. The largest bundles of this type have an outer mass of phloem, then a band of xylem; this is followed by a band of small-celled parenchyma, and this by another xylem band equal to the former. These are comparable with the smaller veins of the leaves where two bundles stand one above the other; in the ovary the phloem of the upper bundle is suppressed and the intervening parenchyma reduced.

The fruit of a waterlily is technically a berry. The outer wall of the ovary remains firm, but its inner tissues become soft and mealy, i. e., the cells easily separate from one another. The ovary-cells are filled with a greater or lesser number of hard spheroid or ovoid seeds embedded in mucilage, and each surrounded with an aril. Dehiscence is irregular; the fruit simply bursts open by the growth of the arils and swelling of the mucilage. In *N. flava*, however, there is a decided tendency for the carpels to separate, still containing the seeds. The ripening of the fruit takes place under water, during which time various changes occur in the floral leaves. In *Castalia* these completely rot away, leaving only small scars. In *Lotos* about half an inch of the bases of the outer stamens remains attached to the fruit. In *N. amazonum* the sepals persist and the other parts of the flower may be only partly decayed. In *Brachyceras*

the sepals and outer four petals remain and become stiff and turgid and develop a good deal of additional chlorophyll. The fruits of *N. tetragona* and *flava* are small (2 to 2.5 cm. long), and the persistent carpellary styles form only an insignificant crown around the top. In *Eu-castalia* the stigma grows very little if any after anthesis, but is about half as wide as the diameter of the spheroid fruit. But in *Brachyceras* and *Lotos*, where the fruits become 8 to 12 cm. across, the stigma keeps pace with the growth of the rest of the pistil, so that the fruit has much the same shape as the ovary of the flower.

The seeds of waterlilies offer marked characteristics which are often of great systematic value. They were made an object of special study by Weberbauer (1894), from whose valuable paper many of the following details, especially regarding *N. alba*, are taken. Some important species, however, e. g., *N. tetragona* and *flava*, did not come under his notice. The largest seeds are those of *Xanthantha* and *Anecphyra*, then *N. tetragona*, followed by *N. tuberosa*, *candida*, *alba*, and *odorata*; those of *Lotos* and *Brachyceras* are considerably smaller than the preceding; the smallest are found in *Hydrocallis*. They vary in number inversely as the size. *N. flava* may have only seven perfect seeds to a fruit, or one to three per carpel; *N. tuberosa* has sixty to seventy, while *N. lotus*, *rubra*, *caerulea*, *capensis*, *zanzibariensis*, and *amazonum* have thousands. They are nearly globular in *N. flava*, *flavo-virens*, *elegans*, and *amazonum*, and ellipsoid in the rest. The micropylar end is always slightly pointed, and in *Eu-castalia* and *Chamaenymphaea* the raphe forms a gentle swelling along one side. In *Castalia* the color of the seed is usually greenish black, but brown is the regular color in *N. tuberosa*. Dark brownish-olive tints are found in all others that I have seen, except *N. amazonum*, which is reddish brown, covered with silvery hairs.

The micropyle and hilum lie near together at one end of the seed. The character of the surface, whether smooth or ridged or hairy, can best be discussed in describing the microscopic details of structure.

The aril which is attached to the ripe seed is a bell-shaped outgrowth of the funiculus. It is whitish and translucent, mucilaginous, and holds between its two coats tiny air bubbles. It is much shorter than the seed in *N. tuberosa*, a little longer than the seed in *N. odorata* (Fig. 41, a), *lotus*, *caerulea*, *capensis*, *zanzibariensis*, and *amazonum*, but in these the seed is visible at the open end of the aril. In *N. alba* (Weberbauer) and *gladstoniana* the seed is completely inclosed and hidden by the aril, while the aril of *N. flava* is a large, wrinkled bag, big enough, if stretched out, to

cover two seeds with ease. Its cells (Fig. 41, *c-e*) are tubular and stretched out in the direction of its growth, thin-walled, and somewhat pointed. In *N. flava* they are about three times longer and wider than in *N. odorata* and *caerulea*. The inner layer of cells adheres closely to the seed, and its cells are much smaller than those of the outer layer. The walls are supplied with fine pores (Weberbauer). The aril serves, by its mucilage and inclosed air, to float the seed for a short time; it drops the seed in the course of a few hours (*N. tuberosa*) or a day or so (*N. caerulea*), partly by being bursted and torn through absorption of water, partly by decay (Fig. 41, *b*).

The seed proper is protected by a firm shell consisting of two parts, the outer a single layer of thick-walled, close-fitting cells, the inner a




FIG. 41.—The aril, *N. odorata*: *a*, diagrammatic section of aril and seed; *b*, portion of aril after the seed is dropped; *c*, cell of the aril where the outer wall bends in, in continuity with the inner wall of the aril; *d*, cell of inner wall; *e*, cell of outer wall.

few layers of thick-walled, but loosely placed cells. The latter layer is of the same thickness as the former; its cells are much flattened tangentially and contain large tangential air-spaces; the walls are lignified, with the exception of a thin layer next to the lumen. The cells of the outer layer are also strongly compressed tangentially (except in *N. flava*). On account of the great induration, which is thickest on the outer wall, they have but a small lumen (Fig. 42). The walls are penetrated by pore-canals. They are composed of lignin, excepting a thin layer of cellulose next to the lumen and an outer thin cuticula which projects inward along the boundaries of the cells. In the cells there are (in *N. alba*) bluish-green granules which give color to the seed. In surface view the outer cells are arranged in longitudinal rows, and, except at the micropylar end, they have very sinuous walls. Over the raphe the cells are elongated in the direction of the rows, but elsewhere at right angles to the rows. At the micropylar end of the seed the cells of the hard (outer) layer are nearly square and in rows, but interrupted over the hilum, which lies (in *N. alba*) about

three cells from the micropyle. At the hilum the thick-walled cells of the inner seed coat are rounder and more closely packed than elsewhere.

Based on the examination of the seeds of about twenty species of *Nymphaea*, Weberbauer distinguished four types of testa, as follows:

- (1) Surface bare, smooth, and shining: *N. alba*, *candida*, *tuberosa*, *odorata*.
- (2) Bare, with longitudinal ridges; adjacent edges of rows of cells are alternately raised up or level; the ridges may be interrupted at middle of seed (*N. rubra* (Fig. 42, *a*), *pubescens*).




FIG. 42.—Sections of outer cell layer of testa: *a*, *N. rubra* fb, *N. flavo-virens* (" *N. gracilis* " Weberb.); *c*, *N. stellata*. After Weberbauer.

- (3) The seed bears longitudinal rows of hairs in the position of the ridges of the second type; the rows may be similarly interrupted (*N. blanda*, *amazonum*, *gigantea*, *caerulea*, *stellata* (Fig. 42, *c*), *capensis*, *ampla*, *madagascariensis*); *N. lotus*, *thermalis*, and *dentata* are only slightly hairy and show transitions to the second type.
- (4) Both longitudinal and transverse cell walls have short papillar outgrowths (*N. flavo-virens*, Fig. 42, *b*).

Differences occur in the degree of flattening of the outer cells and thickening of the walls, as also in the number of hairs and character of the surface under them. In *N. thermalis* the amount of thickening is less than in other *Lotos* species, and in *N. gigantea* the outer walls of the cells are scarcely thicker than the lateral and inner walls. In *N. rubra* the cells are but little compressed. *N. amazonum* has a dull, roughened surface beneath the hairs, but in "*N. blanda* " (probably *N. rudgeana*) this is very smooth and shiny and the hairs are bent at the tip. *N. ampla*

and *madagascariensis* show an inclination to the formation of ridges as in the second type, with a reduction of the hairs.

The outer coat of *N. flava* is peculiar in several points. It is covered with long, slender, appressed hairs just visible to the naked eye, springing from all sides of the cells. It thus combines the characters of the third and fourth types of Weberbauer. The cells are extremely wavy superficially, and so irregular in shape as to render the longitudinal rows obscure. They differ from those of all other species investigated in being nearly twice as deep as wide. A great amount of induration of the outer walls leaves the lumen as a small pear-shaped space at the inner end of the cell. This is a striking approach toward the narrow columnar structure of the hard layer of *Victoria* and other genera of Nymphaeaceae. I find that *N. tetragona* belongs plainly to the first type of seed coat according to Weberbauer, and *N. elegans* to the fourth type.

The inner seed coat is pressed to a thin layer, except at the tip of the nucellus. The walls are thickened on the inner side, but as it approaches the micropyle the thickening extends up the side walls, until at the micropyle only the outer walls are unthickened. With this thickening there is an increase in the height and sinuosity of the side walls. The micropyle is closed by slightly thickened rounded cells and a layer of thinner cells overlying the inner coat (cf. Fig. 44). A vascular bundle passes along the raphe, and spreads in the seed coat irregularly (Fig. 43), as figured by Chiffot (1902).




FIG. 43.—Distribution of vascular bundles from the chalaza, in seed coat of *N. alba*. After Chiffot.

Nine-tenths of the space of the seed is occupied by perisperm (nucellar tissue). This consists of large, thin-walled polyhedral cells (Fig. 44, *p*), densely packed with starch. The outermost cells of the nucellus are shriveled and compressed together into a thin membrane, which is thickest between the embryo and the seed coat. The outer food-storing cells are small and somewhat flattened, but in most of the nucellar tissue they are elongated and disposed somewhat in lines (*Leitungsbahnen* of Weberbauer) running obliquely upward toward an air-space beneath the embryo. The central axis of the seed is filled with looser, thin, elongated starch-laden cells. The nuclei of the cells, where distinct, are pressed over against one wall. The starch is in simple or compound granules, and these, in *N. gladstoniana* and *odorata*, are aggregated into spherical masses. The grains are very small, and the spherical masses are not

larger than single grains of some plants. Each spherule is surrounded by a pellicle of protoplasm, and a network of the same substance ramifies among the constituent granules. This type of aggregation exists in a less perfect condition in *N. flava*, but was not seen elsewhere. In *N. odorata* stained sections of the perisperm show a network of thicker plasma strands between the starch spherules near the middle of each cell.




FIG. 44.—Longitudinal section of seed:
c, cotyledon; e, endosperm; g, tegmen;
m, micropyle; p, perisperm; t, testa.

In the micropylar end of the seed a small lenticular or globose space (Fig. 44) is occupied by the endosperm and embryo. The former is a single layer of cubical cells (*e*) inclosing the latter. The endosperm cells are thin-walled, but Weberbauer was able to find the walls covered with pits so that the thicker portions formed a fine network. They have moderate nuclei, and contain a rich supply of proteids and oil, but no starch. Over the radicle the endosperm is very thin and poor in contents. The embryo has two equal, fleshy, hemispherical cotyledons; excavated on the inner side to receive the plumule. Between their symmetrical bases is the tiny caulicle, and a slight prominence at the end of this is the radicle. Food-

storing tissue of isodiametric cells and elongated conducting cells are distinguishable; an axial strand of the latter is found in the caulicle, with a branch into each cotyledon. No starch is found in the embryo, but it is richly supplied in all its parts with oil and protein. In a crushed embryo of *N. flava* the oil globules run together in considerable drops which stain easily with alcannin. The plumule consists of two rounded papillæ, the leaf rudiments, placed transversely to the cotyledons. One of these is about four times as large in volume as the other.

CHAPTER III.

DEVELOPMENT.


ORGANOGENY AND EMBRYOLOGY.

If it were not for the long hairs which clothe the apex of the stem of *Nymphaea*, there could hardly be a more favorable object for the study of the development of the organs of a mature plant. We cut off the broad tip of a rhizome of *N. alba*, *odorata*, or *tuberosa* 1 cm. back and pin it down to the wax bottom of a dissecting pan. Then with the aid of a dissecting microscope the larger leaves and their stipules are cut away. The hairs may be pulled out with fine forceps. This is the most difficult part of the task. Finally one discovers that the stem apex is slightly basin-shaped. At the center is a very minute elevation, the growing point, and around it the rudiments of leaves and flowers are arranged in spiral order.

The figures of leaf development given by Payer (1857) for *N. alba* are equally applicable to *N. odorata*, and would need but little alteration for *N. rubra*. I have examined the last two by dissection, and have studied *N. caerulea*, *odorata*, and *flava* briefly in serial microtome section. The youngest rudiments at the stem apex are mere rounded papillæ, without indication of their future destiny. They gradually elongate and on reaching a length of 0.08 cm. the foliar or floral character becomes evident. The leaf rudiment (cf. Pl. II, 1-7) takes on a more and more conical form, while the floral rudiment remains broad and rounded and develops the anterior sepal. A leaf of *N. rubra* var., 0.16 cm. long, is about three-quarters as wide at base, and tapers to a rounded apex; on the inner face a broad triangular depression is sharply marked off by two lateral ridges which are continuous over the apex and curve inward a little below, ending about one-fifth of the length of the rudiment above its base. Below this is the petiole; the upper part is the lamina. The rudiment becomes longer and more acute, and the lateral ridges become slightly rolled inward until in a leaf 0.3 cm. long the former triangular depression has become a narrow groove, rounded above. At the base of the petiole there is now on either side a narrow rounded auricle, three times as long as

broad, placed so that one end touches the rhizome and the other is a very short distance above. These are the stipules. In a leaf 0.64 cm. long the lamina is still more than twice the length of the petiole; the inrolled sides now meet in the median line and the veins are prominent. The lobes of the leaf extend down along the front of the petiole and are slightly divaricate. The petiole is about as broad as long and somewhat contracted at each end. The stipules are slightly larger and more nearly vertical. The coating of hairs on petiole, stipules, and lamina is well developed, and the swollen collar at the base of the leaf is becoming evident. Subsequent development is, to outward appearances, chiefly a matter of size, except with regard to the stipules. On a leaf of *N. rubra* whose petiole is already more than 5 cm. long these form lunate auricles, with nearly vertical line of attachment to the petiole, and a lobe extending upward a short distance above the line of insertion. Such a stipule is about one-third as wide as the diameter of the petiole and twice as long as wide. After this it decreases in proportionate width, while greatly elongating to reach the mature form. In *N. odorata* (Pl. II) and *N. alba* the young leaf rudiment, less than 0.16 cm. in length, is more rounded and less acute than in *N. rubra* and the stipules are quite different. About the time the flattening of the inner side of the rudiment to form the lamina occurs, two elongated ridges appear, one on either side of the base of the leaf, extending along toward each other just in front of the rudimentary petiole. The adjacent ends soon meet in the median line and the beginning of the stipular plate of the *Castalia* group is evident. Being shorter in the median line than at the sides, its outline is obcordate. As the whole ridge grows higher, it overtops its leaf at the length of about 0.3 cm., and on either side of the middle line an S-shaped fold occurs, which throws the median part of the stipules away from the leaf, or, to state it otherwise, forms a groove into which the leaf fits. A great thickening along these folds makes two strong keels on the inner side of the stipule. Later this broad plate elongates to the typical adult form. A leaf rudiment of *N. odorata* 0.3 cm. long had downward pointing hairs covering the back of the lamina and the petiole, but on the next younger leaf these were present only on the lamina.

The formation of the principal air-canals takes place at an extremely early period. The first beginning of separation of the cells was seen in *N. caerulea* in a rudiment 0.5 mm. long. The canals were seen with the naked eye in a leaf rudiment of *N. flava* about 1 mm. long; the bounding walls were composed of columnar cells. At 1.6 mm. long all of the canals are indicated. In the smaller leaf the fusion of the three main bundles



A. KORONSKI DEL.

NYMPHAEA ODORATA.

1-7, development of leaf and stipules; 1, 2, front and back views of the same rudiment; 3, older; 4, 5, front and side views of one rudiment; 6, 7, front and back views; 8, rhizome with roots and leaves trimmed off, natural size; 9, transverse section of rhizome, natural size.

from the petiole to a single trace and the separation of this again into the central and two lateral traces was seen. The bundles were chiefly composed of procambial cells, though some spirals were present in the three branches within the inner fork. The lamina of the older leaf mentioned had elongated cells along the lines of the veins, but the parenchyma was almost totally undifferentiated and was without intercellular spaces. A leaf of *N. tuberosa richardsoni* whose lamina and petiole are each 1.3 cm. long has the air-canals well developed along the midrib. Between the veins the mesophyll consists of five layers of cubical cells arranged in vertical lines from the upper to the lower epidermis. The layer next to each epidermis is continuous, but between the vertical rows in the three middle layers long intercellular spaces are present. Idioblasts are already present near the midrib. A leaf of *N. odorata* with lamina 2.5 cm. long and petiole 3.2 cm. has the air-chambers of the mesophyll well marked off by plates of cells; the palisade consists of a single layer of dense cubical cells, underlaid by two or three layers of flat cells elongated parallel to the surface of the leaf; the mucilage hairs are large and functional. When the lamina is 8 cm. long the palisade still consists of a single cell-layer; the big idioblasts have not yet appeared. Stoma-mother-cells are present in full number and nearly mature size; some, indeed, have just divided to form the guard cells. They are round, granular, and highly refractive. The maturation of the stomata occurs only a day or two before the leaf finally expands. Caspary (1854; 1858), in announcing first the apical growth of leaves, showed that this apical growth continues longer in *Nymphaea* than in other plants, and that the margin of the leaf in all *Nymphaeaceae* is the latest part to complete its development.

The tissues of the stem begin to differentiate within 0.25 mm. of the point of apical growth. Noplerome is at any time distinguishable. The lacunar cortex acquires intercellular spaces while all of the tissues are still meristematic, and the early establishment of desmogen strands, adventitious roots, and external hairs has already been referred to.

Concerning the development of the flower, we are able to corroborate the work of Payer (1857) and Goebel (1886) on *N. alba* by observations on *N. caerulea* and *lotus*, and to add some details. The discussion of important morphological problems will be deferred whenever possible until the observed facts are set forth. The earliest rudiment of a flower that I have seen was a smooth, thimble-shaped upgrowth at the stem apex in *N. caerulea*. On such a papilla, according to Payer, there appears in *N. alba* the rudiment of the anterior sepal; then the two lateral sepals

arise on the sides, and later the posterior sepal. Hence comes their peculiar æstivation. Four papillæ next appear alternate with the sepals. They arise simultaneously, grow rapidly, and are always larger than the inner floral organs, which originate later. They are at the base of a hemispherical receptacle whose surface, naked hitherto, becomes covered little by little from base to summit with a number of new papillæ. These are arranged in ten vertical rows, one abutting on each petal, one on each lateral sepal, and two on the posterior and anterior sepals. The lowest ones soon flatten out and become petals; the uppermost become typical stamens; between these two sets one finds all gradations from stamen to petal. The stamen rudiments, however, do not cover the whole receptacle. A bare space remains at the summit, around the edges of which a row of papillæ appears. These (the carpels) become horse-shoe shaped, and their inner edges join, making a sinuous line. The sinuosities extend somewhat toward the center, and a thick process of the receptacle grows up to fill the central space, closing the ovary-cells. Now the sepals and the four outer petals remain stationary, as it were, while the rest of the receptacle elongates, carrying with it the carpels, stamens, and inner petals. Thus the ovary comes to be inferior with regard to the stamens and inner petals while the outer petals and the sepals have an inferior insertion. There is no fusion of the floral leaves outside the carpels with the ovary or receptacle, as Koehne (*vide* Goebel) believed.

According to this account from Payer, the ovary would bear the carpels at its summit, and its lower parts would be of axial origin. Goebel (l. c.) noted this difficulty and showed that before the carpels are mapped out there is a hollowing of the receptacle as is common in inferior ovaries. From the edge of the axial excavation, but reaching to the bottom of it, arise the carpel-rudiments. They are never free from the receptacle on the outer side. The whole wall of the ovary-cells, however, is of carpellary origin, and no part is formed from the vegetative apex of the flower stalk. Our own observations on *N. caerulea* and *lotus* support Goebel's view.

In *N. lotus* the time relations of the origin of the outer floral organs differ slightly from that given by Payer. In the apex of a large flowering plant we found three rudimentary flowers of successive ages and sizes, in all of which only the anterior and lateral sepal-rudiments were present (Fig. 45, *a*, *b*). This shows that these organs originate much earlier than those farther in. The anterior sepal was much larger than the others, and was inserted considerably farther down. In such a rudiment one could hardly speak of a peduncle, for this sepal seemed almost sessile on the

parent stem. The next older flower noted (Fig. 45, *c*) had a broad papilla representing the posterior sepal, a rounded one for the right-antero-lateral petal and a partly formed papilla for the left antero-lateral petal. The right petal was about half as large as the posterior sepal, and this was about half as large as a lateral sepal, and this again half as large as the anterior sepal. The next flower had the two anterior petals about equally developed. The remaining organs (except the carpels) originate *one by one*; two postero-lateral petals come next, then four petals opposite the sepals; then four opposite the first petals. The exact order of these was not determined (Fig. 45, *d*). In early stages the bud exceeds the peduncle in length, but after the total length of the two reaches 2.5 cm. the peduncle begins to exceed the bud. Previous to this stage the anterior and lateral



FIG. 45.—Development of flower, *N. lotus* var.; *a*, end view; *b*, side view of very early stage; *c*, with rudiments of sepals and two anterior petals; *d*, sepals, two whorls of petals, and one member of the next whorl laid down.

sepals alone cover the bud; later they are pushed apart and the posterior sepal is exposed. The carpels are rather late to develop. In a bud 1 cm. long they resemble little folded leaves, fused half way up the back with the hollowed receptacle, but open along the ventral suture, and, even in *N. lotus*, wholly free from each other.

The above facts throw light on several questions, and first upon the kind of inflorescence found in *Nymphaea*. It will be remembered that the flowers stand in place of leaves on the stem, but without any subtending bract. Payer says the case is very simple: Each flower arises in the axil of a leaf, but on account of crowding in the bud, the flower comes to be at some distance from its leaf, and it requires some experience ("il faut quelque habitude") to find the leaf to which a given flower belongs. Schumann (1894) maintains the same view and cites the case of *Victoria*, in which there are parallel spirals of leaves and flowers on the stem, and at the apex each leaf has a flower to its left as they originate. Raciborski (1894) opposes this with the theory that the bract is entirely suppressed in *Nymphaea* and *Victoria*. This better accords with the exact location of the flowers in the leaf spirals; and in *Nuphar* there is at times, if not always, a rudimentary bract subtending the young flowers. Eichler (1875), however,

on the authority of Caspary and Braun (in personal letters), reluctantly accepts the belief that the flowers are axillary, but the bract and bract-oles are carried up on the summit of the peduncle as anterior and lateral sepals. The argument for this has been based largely upon the uncertain ground of teratology. Planchon (1850, *e*) figured a flower of *N. caerulea* "whose peduncle showed accidentally [at the lower end] three spatulate bracts, with petioles wavy here and there on the margins as the sepals are at base."* Caspary (*vide* Eichler) found in the same species a flower with the anterior sepal at the base of the peduncle as a ribbon-shaped bract, the lateral sepals also pushed down, and the posterior sepal in its proper place. This was followed by four sepals in a whorl, placed diagonally like the second whorl of a normal flower. Caspary found similar cases in *N. alba*, *gigantea*, *rubra*, and hybrids of *N. caerulea* and *capensis*. My own observations on the development of the flower of *N. lotus* fully substantiate Caspary's view, and, I may say, completely turned me from an opponent to an adherent of his theory. The low insertion of the rudiment of the outer sepal and its very early appearance, followed at once by the two lateral sepals, are convincing. This also explains the peculiar relations of the sepals in the bud; on any other theory, except a blank displacement, the anterior sepal should be, like the posterior, covered by the lateral sepals.

It remains, however, to explain the presence of a single posterior sepal and the oblique position of the next four floral leaves. Caspary and Braun looked upon the single sepal as an "Ergänzungsblatt." But if the floral diagram of Nuphar as given by Baillon (3: 82) can be depended on, in which the outermost of the five sepals is posterior and the petals "are inserted along a spiral," we have the most perfect starting point for the development of the flower of Nymphaea. The outermost sepal of Nuphar homologizes with the posterior sepal of Nymphaea, and a very slight shifting of the remaining four sepals away from the median anterior line gives them the oblique position of the four outer petals of Nymphaea. The strongly sepaloid character of these petals, especially in Brachyceras, indicates such an origin. As to the inner petals, from the acycly of Nuphar, Nymphaea shows a continually increasing tendency to cyclic symmetry. In *N. lotus* the rudiments of all of the floral leaves (excepting the three outer sepals) arise in series, one after another, but Payer's account of *N. alba* places the four outer petals in a whorl, and the inner

* ——— dont le pédoncule offre accidentellement trois bractées spatulées, à pétiole ondulé ça-et-là sur les bords, comme les sépales le sont à leur base.

petals and the stamens in alternating whorls of five ; probably this plant should be worked over anew. In the mature flower the cyclic arrangement is least evident in *Castalia* and but little more so in *Lotos* ; but, as stated, in old flowers of *Brachyceras*, and open flowers of *Hydrocallis* it seems to prevail in all of the parts (cf. Fig. 36). Probably cyclic arrangement is always to be considered as derived from acyclic, and *Nymphaea* seems to be in the transition stage. For such flowers the term hemicyclic or spirocyclic (Engler, 1898) is best. It goes beyond the truth to place *Nymphaeaceae* among acyclic orders as Goebel did (1887, p. 412).

While still maintaining that the terms sepal and petal as commonly used for waterlilies are physiologically correct, the morphological value of the petals must be considered. We have shown that the anterior sepal represents the bract, the lateral sepals the bracteoles, and the inner sepal with the four outer petals the primitive sepals. For the last homology I am indebted to a suggestion from my instructor, Dr. John W. Harshberger. In development no distinction can be made between the rudiments of the remaining petals and the stamens, while in *N. alba* the four outer petals do have a distinct and simultaneous origin. Payer, therefore, pointed out, and rightly so, that the inner petals are really modified stamens, and the waterlilies are habitually double flowers in the same sense as roses, almonds, etc., are doubled in cultivation. This at once explains and is supported by the extremely variable number of petals and the occurrence of transitional forms between petal and stamen. It seems probable, however, that in last analysis all petals are modified stamens, and in *Lotos* and *Anecphyra*, where a naked space occurs between the insertion of stamens and petals, and intermediate forms rarely if ever occur, the distinction between the two classes of organs is being rapidly drawn, and the homology is more distant than in *Castalia*. The fixation of definitive petal and stamen characters upon the floral rudiments is taking place before our eyes in the genus *Nymphaea*. It is striking, but on second thought only natural, to find this kind of specialization going on alongside of the change from spiral to cyclic symmetry. The two phenomena are but manifestations of the same law of adaptation and differentiation in form and function.

After the stamen rudiment is established it grows considerably before the archesporium appears. It has been claimed that the anther cells are at first extrorse and are pushed around to the inner side by uneven growth of the connective. In *N. lotus*, at least, this is not the case. Two pairs of archesporial lines are differentiated in the substance of the anther,

each consisting of a single straight row of cells. They are removed four or five cells from the inner epidermis and seven to twelve cells from the outer epidermis, and between each pair of lines eight cells intervene. The cells immediately surrounding the archesporia take on a more or less concentric arrangement, and the development goes on in the usual way for flowering plants. In *N. caerulea* the outer stamens develop slightly in advance of the inner ones; where the former are 1.3 cm. long and the spore-mother-cells are already separate from one another and becoming rounded off, the mother-cells of the inner stamens form a continuous tissue.

The ovules originate after the ovary has attained a considerable size, say 0.5 cm. in diameter in *N. caerulea*. At first a tiny rounded column




FIG. 46.—Ovule of *N. odorata*, from a half-grown bud, showing archesporium. From a photomicrograph.




FIG. 47.—Embryo sac of *N. odorata*; longitudinal section of ovule at time of flowering. From a photomicrograph.

projects into the enlarging ovary cell. This swells at the end into a knob, an integument of two cell-layers grows up around the knob, and then a second integument outside the first. When the inner integument has reached the height of the nucellus, the outer one is about half as high (cf. Fig. 46). Meanwhile the knob has turned over at right angles to the supporting column in its change toward anatropy. A large archesporial cell is now visible at the apex of the nucellus, covered by a layer of cells. The archesporial cell presents five times as large a surface in longitudinal section as the surrounding cells; its nucleus is as large as an entire cell of the nucellus, is rather poor in contents, and has a single dense nucleolus. Its further development has been described for *N. odorata* by Cook (1902). According to his account, a tapetal cell is cut off at the outer end of the archesporial cell (cf. Fig. 46), and from the former several tapetal cells arise by a variable series of divisions. Three potential megaspores are next cut off from the mother-cell. These rapidly degenerate, leaving a

single large megaspore. This cell elongates to form the embryo-sac. Returning to the stage in which only the archesporial cell is found, we note an elongation of cells in the center of the funiculus which foreshadows the vascular bundle. This was seen in an ovary of *N. odorata* 0.6 cm. in diameter; the ovules were just visible to the naked eye. In an anther from the same flower the microspores are formed, but have not received the characteristic markings on the exine; the tapetum appears as a layer of disintegrated matter around the walls of the anther cell; the thickenings are not yet laid down in the anther wall. After this the ovule rapidly grows to its mature form. The outer integument becomes three cells thick and loses its protoplasm, while the inner integument consists of two layers, of which the inner alone remains richly protoplasmic. The nucellus consists of many cells arranged in radial rows; the outer ones are tangentially flattened, the central ones rounded. The raphe is prominent and is traversed by a slender vascular bundle with a spiral trachæa on the side next to the nucellus. The funiculus is covered at base with a glandular epidermis like that of the ovary, but the glandular cells end at a sharp line near the seed, beyond which the epidermis is plain and smooth. Between the epidermis and the vascular bundle the round parenchyma cells enclose large intercellular spaces. The embryo-sac (Fig. 47) is prominent as a clear area below the micropyle, and is shaped like a flask with the neck extending down into the axis of the seed. The ratio of the diameter of the body and neck of the flask is as 5 to 1 in *N. odorata* and *zanzibariensis*, but in *N. lotus* the whole ovule is longer and narrower, and the embryo-sac is lanceolate in longitudinal section, with rounded ends. A single layer of columnar nucellar cells covers its outer end.

A day or two before the flower opens the egg apparatus is complete. The embryo-sac is slightly narrowed at the micropylar end, where it is covered, as before, with one layer of columnar cells. In this upper part of the sac three similar cells are crowded, two above and one below. The rest of the sac is lined already by a few cells around the sides, visible only in my preparations as compressed nuclei. Hofmeister (1858) doubtless referred to the same thing in *Nuphar*, "whose embryo-sac," he says, "even before fecundation shows clearly a cellular wall" (Zellstoffhaut). A pair of nuclei indistinctly seen in the extreme end of the narrow inner part of the sac in *N. odorata* doubtless represent the antipodal cells; a single cell with very large nucleolus occupies the same position in *N. zanzibariensis*. The outer integument now consists of two (or near the raphe three) layers

of slightly flattened cells, poor in contents. The inner integument has both of its layers very thin, and the outer one nearly empty.

Dahmen (1892) critically examined the funiculus of the ovules of *Nymphaea*. Since the so-called aril originates as a swelling on the funiculus before fecundation occurs, he considers that it is not an aril in the usual sense, restricting the use of the term to outgrowths which occur when the seed is ripening. The distinction, however, is extremely unimportant, especially as the aril of *Nymphaea* does not reach maturity until the seed is ripe, and most of its growth occurs after the seed has attained its full size. In *N. lotus* Dahmen noted two swollen zones on the funiculus near the ovule, but only one in *N. rosea* (*quid?*) and *zanzibariensis*. The epidermis of the funiculus has slightly thickened walls; within it is a thin-walled parenchyma and a vascular bundle with phloem and a little xylem. The bundle has no connection with the aril. Small round starch grains are found temporarily in the parenchyma, epidermis, and phloem. Intercellular spaces occur only in the arillar swellings according to Dahmen, but I find them plentifully elsewhere in *N. odorata*. The tissues are all filled with mucilage, which is only precipitated by strong alcohol. The protoplasm is dull yellowish. Asparagin occurs in the funiculi, but no sugar was found.

Unfortunately we cannot accurately trace all of these tissues to their mature state, but the changes are not important in any part except the embryo-sac. The early stages were worked out by Hofmeister (1858) in *Nuphar luteum* and *advena*, which differ from *Nymphaea* in that the narrow inner part of the embryo-sac is much longer, and extends after fecundation to the chalaza; an axial tube remains open even in the mature seed (Weberbauer, 1894). In *Nuphar* there are three cells at the top of the embryo-sac, two upper synergidæ and an ovum below. About the time of fecundation a transverse wall divides the narrow part of the embryo sac from the upper wide part, and the latter is soon filled by two or three endosperm cells. The fertilized ovum now divides transversely, and a suspensor of one to five cells is formed above the embryo. The observations of Mr. Cook (1902) on *N. odorata* seem to be corroborated up to the first cell-wall laid down in the embryo-sac. His views on the development of the embryo, however, which he considers to be monocotyledonous and without suspensor, are totally at variance with my own preparations. I cannot imagine that his interpretations are correct. This portion of Mr. Cook's paper is based chiefly on *Nuphar advena*, in which Caspary's drawings (in Hb. Berlin) seem also to indicate the absence of a suspensor.

The earliest fertilized ovule of *Nymphaea* that I have seen is of *N. lotus*, and has already reached nearly its mature size. The integuments are considerably hardened, and the perisperm is loaded with starch. A broad space at the micropylar end of the seed is occupied by the endosperm, the cells of which are very thin and watery (Fig. 48, *a*). A distinct layer of perisperm still bounds the endosperm on the side next to the seed coat. From a point near the micropyle a row of three cells projects into the endosperm, representing the embryo. An older seed of the same species shows the endosperm occupying an approximately spherical space, somewhat pointed above and flattened below; its cells are large and




FIG. 48.—Embryology: (*a*), (*b*) successive stages, *N. lotus*; (*c*) spherical embryo with suspensor, *N. odorata*; (*d*) early differentiation of cotyledons and plumule, *N. caerulea*.

distinctly nucleate, but very thin walled and poor in contents. The embryo (Fig. 48, *b*) consists of a line of three suspensor cells and a terminal knob of probably eight cells (four in longitudinal section). The uppermost suspensor cell is hexagonal, the others square (in section). After this the endosperm enlarges very little. As the embryo encroaches upon it, the outer cells become denser and more regular until they reach the mature condition, and the inner ones are crushed to a thin layer of remnants between the permanent outer layer and the cotyledons. The embryo proper (cf. Conard, 1902) becomes accurately spherical as it enlarges, until it consists of some hundreds of cells (Fig. 48, *c*). Then the lower end becomes flattened by reason of the outgrowth of cells on each side of the lower pole. In section the embryo now appears triangular and almost equilateral. The two lobes increase symmetrically and form the two equal cotyledons. At first these spread out nearly horizontally (Fig. 48, *d*), while in the middle between them a slight cone-like papilla

represents the plumule, and a similar prominence opposite (next to the suspensor) is the radicle. Subsequently the cotyledons spread round the walls of the endosperm and fill up all of the limited space available, while between them the two leaf-rudiments of the plumule are differentiated.

GERMINATION AND EARLY GROWTH.

Corresponding with the habits of life of the various species of *Nymphaea* are certain requirements for the proper growth of seedlings. Seeds of the *Eu-castalia* group quickly lose the power of germination if dried ; in nature only those which are, by chance freshets, stranded hopelessly above the normal water level ever become dry. *N. tetragona* can withstand drought fairly well. Seeds from Kashmir communicated by Mr. Wm. Gollan, of Saharanpur, India, germinated quite well, but of several sendings received in the early spring of successive years from Japan, only one seed has ever sprouted. The former were sent to us directly after they were gathered, while the latter have doubtless been kept in a seed-house since the previous summer. Seeds of the *Lotos* and *Brachyceras* group can withstand a great deal of drought ; they are accustomed to it ; but they are kept much more successfully, as Caspary (1877) recommended, packed in clay and air dried. Under these conditions a considerable amount of moisture is retained, even when the mass appears to be perfectly dry. *N. zanzibariensis* was introduced into Europe from Zanzibar by seeds packed in chalk ; and of a box of seeds of *N. dentata*, mingled with soil, received last summer (1901) from Jamaica, nearly every one sown germinated. In all of the *Castalia* group the seeds should be kept in bottles of water. It was thus, also, that *Victoria regia* was successfully carried to England after a long series of costly failures.

For germination the seeds of waterlilies need to be submerged in 5 to 30 cm. of water. Those of the *Castalia* group prefer a temperature of 15° to 18° R., but the tropical species do best at 23° R. (Siber, 1883). A very irregular length of time is required. Of a quantity of *N. elegans* × *zanzibariensis* seeds sown as soon as collected, a large number came up in two weeks ; after more than a year some earth from this pot chanced to be placed in a warmer tank, and numerous new and vigorous seedlings appeared. In the Dreer Gardens at Riverton, N. J., I have seen flowering plants of *N. caerulea* which came up spontaneously out of doors where two years previously that species had been grown ; the seeds had lain dormant over all one summer. In this case Mr. Tricker informed me that the bottom of the pond had been dug over each spring. Probably the

seeds were buried in the first digging and brought to the surface in the second. In midsummer *N. zanzibariensis* seeds will germinate quickly after maturing, and the bags of seed must be gathered as soon as the fruit bursts; but in the summer of 1900 numerous seedlings of this plant sprang up in the pond of the Botanic Garden (University of Pennsylvania) and blossomed before frost; they must have come from seed ripened in the previous autumn. Mr. Waters (1886) gives an interesting account of the germination of *N. odorata*. Seeds gathered in the fall of 1883 were sown at once in an aquarium kept in a living room with north light. In March, 1884, many were germinating. In June, 1885, the vessel was placed where it received direct skylight with sun for an hour at noon; a half dozen new plants appeared in August. In the fall they were returned to the living room, and about Christmas another seed had germinated. From February to April, 1886, four others sprouted; these had therefore lain dormant for about two and a half years, although they were constantly in conditions which would permit germination.

The general features of a seedling *Nymphaea* were noted by Tittmann in 1821. Treviranus, Caspary, Klebs, Goebel, and others have since remarked upon or figured such seedlings. The first visible evidence of life in the seed is the loosening of an operculum at the apex (Fig. 49, 8, o). This is a conical body bearing the micropyle and hilum; its edge is ragged by reason of the sinuous margins of the cells of the testa. The operculum is pushed aside by the protruding embryo and its wrappings, and lies on these at one side near the edge of the opening from which it was torn. The seed coat is also rent with short longitudinal fissures, dividing the lip of the aperture first formed into numerous acute teeth (Fig. 49, 8). As the embryo emerges it is covered by a white sheath produced by the swelling and straightening out of the overlying "rumpled up" portion of the inner seed coat; this protects it from the sharp and ragged edges of the testa. The cotyledons remain permanently within the seed and show no changes in the inner parts except in the emptying of the cells. It is by the elongation of the bases of the cotyledons into a kind of petioles that the radicle and plumule are passively carried out of the seed. These cotyledonary petioles also curve geotropically downward until the caulicle is in a vertical position, and then they cease to grow (Fig. 49, 3, 4).

Through all this time the plumule and radicle have remained dormant, but now both start into activity, the former very rapidly. The hypocotyl does not elongate at all. The epicotyl and first leaf shoot upward as a slender subulate body (Fig. 49, 3, 4). The elongation of the epicotyl




FIG. 49.—Seedlings of a hybrid *Nymphaea* of the *Lotos* group. 1, tuber formation at summit of epicotyl well advanced. 2, the first broad leaf expanded, the primary root, with root hairs, mature. 3, the first (filiform) leaf nearly mature, and rhizoids springing from cotyledon. 4, a slightly older plant, from a seed which was buried more deeply in earth; the epicotyl is much elongated. 5, first secondary root. 6, small ripening tuber; epicotyl rotted off. 7, beginning of second secondary root and third broad leaf (4th leaf). 8, soon after germination; the tegmen (dotted) extends beyond the hard seed coat, bearing the detached operculum. 9, plantlet of same age as 8, with cotyledons broken off from their petioles. *a*, first (filiform) leaf; *o*, operculum.

depends upon the depth to which the seeds are buried ; it reaches up just to the surface of the soil. If they are uncovered at the bottom of the water, the epicotyl is scarcely visible (Fig. 49, 3) ; it is about as long as the width of the cotyledonary petioles. In other circumstances this internode may be 2.5 cm. long (2, 4, 5). The stimulus which effects this difference is light. Seeds of *N. gladstoniana* and *flava* grown in glass bottles of water in the dark sent out very long epicotyls reaching far above the layer of seeds in the bottom of the bottle. The first leaf produced by the seedling is a slender awl-shaped object, like a spear of grass (Tricker, 1897) ; it looks like a prolongation of the epicotyl (Fig. 49, (a) ; the boundary between the two is marked by a tiny rudiment of the next leaf. While these changes are going on in the plumule, a large tuft of root-hairs is formed on a broad prominence at the base of each cotyledonary petiole. These hairs serve to anchor the plantlet to the substratum and doubtless to absorb some food during the inactivity of the radicle (Goebel, 1893). After the subulate leaf has nearly reached maturity, and the second leaf-rudiment is swelling, the radicle begins to elongate (Fig. 49, 4). Hitherto it has been a tiny papilla between the bases of the cotyledons, but it soon grows out into a primary root 5 or 8 centimeters long (5).

The second leaf of the plantlet arises opposite the first and develops a petiole and an ovate to linear lamina (2, 5). At its base a single adventitious root comes out and descends into the earth ; it only becomes evident after the leaf is nearly mature (5). Subsequent leaves are broader and broader in the lamina, becoming deltoid in *Lotos* and cordate to nearly orbicular in *Brachyceras* (cf. Fig. 50). Several of them remain on short petioles and are typically aquatic, but finally small floating leaves are sent up. Each one bears one or more adventitious roots at the base. The petioles of all the earlier leaves are winged and clasping at the base ; no stipules are developed until later.

The plantlet being thus pretty well established, the primary root ceases to function and soon dies away. As the nutriment is baled out from the seed, the central portions of the cotyledons are first emptied, then their outer parts, and then the endosperm. Finally the solution of the perisperm begins at the end next to the embryo and works steadily back until the supply is exhausted. The nutriment furnished to the young plant, therefore, is at first highly proteinaceous, and at the last wholly carbohydrate. The cotyledons remain of the same size as before germination, or very nearly so. When the seed has been emptied of its food, the epicotyl shrivels and dies as the primary root did before it (Fig. 49, 1, 6).

The internodes above the epicotyl are not developed, but the stem gradually thickens and enlarges into a miniature tuber. In nearly all of the genus the plant is now essentially mature; it needs only to enlarge. But in *Eu-castalia* a marked change takes place. The internodes after a time




FIG. 50.—Seedling leaves: (a), *N. amazonum*; a, first leaf; b, second (first broad) leaf; c, third leaf; e, epicotyl; p, primary root; sl, first secondary root; (b), *N. caerulea*; 1, 2, 3, 4, first and following broad leaves; (c), first floating leaf, *N. odorata gigantea*; (d), *N. lotus* var., 1, 2, 3, 4, first and following leaves, the last very young; (e), *N. zanzibaricensis*; 1, 2, 3, first and following broad leaves; (f), *N. tetragona*, 1, 2, 3, first and following broad submerged leaves; 1 A, first floating leaf. Twice natural size.

regularly, but slightly, elongate, and the stem suddenly becomes plagiotropic; thus a tiny horizontal rhizome is produced. From this point onward maturity is simply a matter of size.

In structure the characteristic features of the order are evident at a very tender age. While the primary root is still a mere papilla, the root-cap consists of a single layer of cells, and behind it are three to four close

layers of meristem cells ; immediately back of these, large intercellular spaces abound. The epidermis of the primary and early adventitious roots differs from all mature rootage in having a copious supply of root-hairs (Fig. 49, 2, 5). It will be recalled that root-hairs are generally said to be wholly lacking in *Nymphaea*, *Nuphar*, *Euryale*, and *Victoria*. As we have observed them in *N. dentata*, *lotus*, *caerulea*, *zanzibariensis*, *amazonum*, *elegans*, *odorata*, *capensis*, and hybrids, they are doubtless universal in the genus. On one occasion also they were found on early roots of a plant springing from a tuber of *N. caerulea*. *Victoria* lacks them even on the primary root. The epidermal cells of the early roots (in *N. dentata*) are long and rectangular in surface view, and about as deep as wide ; where root-hairs occur, however, they spring from cubical cells. No shedding of epidermis occurs in these roots. The root-cap is long and thimble-shaped.

Inside the epidermis there are in the primary root about six layers of thin-walled cortex cells and a small (diarch?) vascular bundle. The adventitious roots are like this, but successively larger. In the earliest of these the diarch bundle is quite plain and is surrounded by a distinct endodermis ; the two xylem patches are continuous across the middle of the bundle. The appearance of the central vascular strand of the hypocotyl and lower part of the epicotyl is exactly the same as this, but it is described here as "two opposite bundles with their xylems confluent" (cf. Gwynne-Vaughan, 1897). A short process of procambial cells extends toward the base of each cotyledon, but no vascular tissue extends into them. They are composed of elongated thin-walled cells, and have a rather narrow insertion. The bundles of the stem are turned with their sides toward the cotyledons, i. e., a line connecting the bases of the cotyledons would pass through the confluent xylem and between the phloem masses. Higher up in the epicotyl the two bundles become more distinct, and each, instead of being semicircular in section, is nearly round ; the xylems are still in contact, though torn asunder to leave an irregular air-canal in the middle. The first two leaves are placed opposite the phloems of the two bundles and at their point of insertion the vascular system spreads out toward them on each side. In close succession the bundles of the first adventitious root, the acicular leaf, the first broad leaf, and the second root and broad leaf join the widened portion of the system, with anastomoses across from bundle to bundle. Each of the above-named organs has a single bundle. No central strands exist above this, but the bundles spread out through the now fleshy stem on their way to the various organs. The communication from vessel to vessel which easily

occurs in ordinary plants by reason of their proximity is made possible in these thick stems with widely separated bundles by the profusion of cross-branches. Gwynne-Vaughan (1897) noticed in the center of the young stem of *N. zanzibariensis* a cylinder of meristem tissue suggesting a stele, in which later desmogen strands were differentiated. He evidently considered this as furnishing a kind of transition from the "monostelic" epicotyl to the "astelic" stem.

The epidermis of all parts of the plant above the cotyledons, excepting the upper surface of the leaves, is supplied with mucilage hairs. In *N. flava* these are so numerous on the acicular leaf as to make a plainly visible coating of jelly all over it, as is seen on petioles of *Brasenia*. The




FIG. 51.—First broad (submerged) leaf of *N. lotus* seedling: a, stoma in upper epidermis; b, portion of tip of leaf, showing distribution of stomata by dots.

hair-bases remain on the full-grown parts as in mature plants. The inner tissues are very loose throughout. In the epicotyl the intercellular spaces are often as large as the rounded cortex cells. The acicular leaf is similarly constructed. The first broad leaf of *N. dentata* has four well-developed air-canals in the petiole; the second has six canals, which are at first of almost equal size. The lamina of these leaves is extremely thin and fragile. Stomata are found scattered over the upper surface in *N. lotus* (Fig. 51), *caerulea*, *elegans*, *amazonum*, *zanzibariensis*, and *capensis*, but I failed to discover any in *N. odorata* or *rubra*; probably the observation is at fault, for they are at best rather difficult to see. The best success was had with material fixed in chrom-acetic acid and mounted in balsam; probably Wächter's (1897) chloral hydrate method would prove equally effective. The palisade-layer of these leaves is reduced to a single layer of hemispherical cells against the upper epidermis. Between these and the lower epidermis there are branching partitions two cells high, enclosing large air-spaces (Constantin, 1886). The venation is very simple.

Between the bases of the second and third leaves a few long protective hairs appear as on the adult stem-apex. The young stem is at first devoid of lacunar tissue; its fundamental parenchyma consists of rounded cells in which starch is rapidly deposited. From this time on the plant is in a position to go into a state of rest on any emergency.

CHAPTER IV.

PHYSIOLOGY.

Special observations on the physiology of waterlilies are not numerous. That such plants have the usual "senses of direction"—geotropism and heliotropism—goes without saying. The primary and adventitious roots are all alike highly sensitive to gravitation at first, but the latter soon become more or less passive and run obliquely downward, while the secondary and tertiary roots ramify throughout the soil from its surface to a depth of 30 cm. or more. The peculiar type of root spoken of on a previous page as "contractile" exhibits a striking physiological adaptation. Such roots have been found only on young plants of the *Lotos* and apocarpous groups, excepting *N. flavo-virens*, in which adults also have contractile roots. In all of the plants mentioned, however, resting tubers are produced at the close of the season. The object evidently is to draw these tubers well down into the earth for protection against drought and herbivorous animals. For the adult plants, with the one exception named, perish when the flowering season is over, and consequently are not supplied with any special contractile organs. *N. flavo-virens* × *zanzibariensis* bears a few contractile roots on the lower part of the tuber of adult plants. This hybrid usually has persistent tubers as in *N. flavo-virens*; its contractile roots, however, show none of the peculiar structure which characterizes those of *N. flavo-virens*. As a rule it is the lowest (oldest) root from each of the older leaf-bases which is contractile; in *N. lotus* one or two upper roots occasionally contract. This lowest root is strongly geotropic, while the others are rather feebly so. It also persists in a living condition after all of its companion roots have completely rotted away. After contraction it becomes fusiform in shape. The greater density of the cortex in contractile roots indicates that this is the layer where contraction takes place, probably, as Rimbach (1902) has shown for liliaceous plants, by shortening and widening of the cells. Thus we see a strong differentiation, apparently greatest in *N. flavo-virens*, into nutritive and mechanical roots.

In stems the great density of tissue in all but the *Castalia* group, and especially in resting tubers, has already been shown. This is distinctly related to the storage of starch which takes place so largely in such plants.

I know of no experiments upon the geotropism of stems outside of the *Eu-castalia* group. Among these plagiotropism is very pronounced. A stem of *N. odorata* 3 cm. in diameter and 10 cm. long planted upright in a pot in early spring had turned its apex to a horizontal position by mid-summer.

Young petioles and peduncles of different species turn through 90° in the course of twenty-four hours if placed in a horizontal position. This tendency is, of course, well developed in all species. The leaf-stalks and flower-stalks, however, are often so slender that their positions are mostly passive, except at the ends. The buds in *Castalia*, and the leaves in all species, by their buoyancy make their way to the surface of the water unless opposed by other forces. We have already noted that the leaf in coming up through the water has its midrib in a straight line with the petiole, and on reaching the air the petiole bends over at the top nearly at right angles to the lamina (Frank, 1872). That this is not a purely passive condition is shown by the stiffness and turgidity of the organs. Also, when plants are moved close together or placed in small tanks, where the upper parts of the petioles are thrown out of their former directions, they bend the lamina down until it is more or less submerged. In the course of twenty-four hours, however, the leaf is again lying flat upon the water surface. A corresponding bending has taken place in the upper part of the petiole. This bending may be due simply to readjustments of a mechanical kind in the elastic collenchyma of the petiole, or it may be the result of a distinctly vital action. In the latter case it is related to the phenomena next to be described.

It has been noted that the "length of the petioles and peduncles depends upon the depth of the water in which the plant is growing." Not only is this true for plants in different localities, but a given plant, if moved from shallow into deeper water, where all of its leaves are submerged a few centimeters, will be found on the following day with all its leaves floating in the normal manner. Plants moved from deep to shallow water need no adjustment except in the angle between the petiole and lamina; but leaves produced afterward have petioles only long enough for the new conditions. Now, it is certain that throughout the life of a leaf its petiole is continually growing longer, even though the water level remains constant. This is necessary in order to make room for the new leaves which are rising in succession from the center of the plant. One need only look at a large plant of any tropical *Nymphaea* as grown in gardens to be convinced of this. We see an area ten or twelve feet in

diameter covered with the foliage from a single well-grown specimen. If the gardeners have not been too careful we see that the outer border of this ring is occupied by yellow and decaying leaves on very long petioles. Within these comes a zone of large green and shining healthy leaves, then smaller tender ones, and, at the center, one or two are only partly unrolled from the bud. The rate of elongation of a petiole of *N. rubra* detached from the parent plant was 2.5 cm. per day. This, with perhaps a certain amount of stretching of the collenchyma and softer tissues, may account for the rise of leaves on plants moved from shallow to deeper water, but it does not reach the case of adjustment from deep to shallow water. Frank (1872) investigated the causes of this phenomenon, giving especial attention to *Hydrocharis morsus-ranae*, and concluded that gravitation (as expressed by water pressure) and light, though not the causes, are used by the plant as signs by which to measure how much it has yet to accomplish before a growing organ has reached its most advantageous position ("Gravitation und Licht sind nicht die Erreger jener Wachstumsformen, sondern die Pflanze bedient sich ihrer nur als Merkmale, an denen sie abmisst, wieviel sie noch zu leisten hat, bis das durch Wachstum zu richtende Glied seine vortheilhafteste Lage erreicht hat." p. 85). The expression is an excellent one, even if the "signs" are insufficient. For is it not so with all stimuli and all organisms? No external stimulus is in itself a final cause of any physiological action; that is, the irritability of protoplasm is the indispensable condition of all vital functions. Karsten (1888), experimenting on *Hydrocharis* and *Ranunculus sceleratus*, showed the insufficiency of Frank's explanation, and proved that it is the oxygen of the air which inhibits the growth of the petioles as soon as the leaf-blade reaches the surface of the water ("—dass es der Sauerstoff der Atmosphäre ist, welche bei den Schwimmblättern jene constatirte Hemmung im Wachstum ihrer Stiele bewirkt, sobald sie die Wasseroberfläche erreichen." p. 577). In *Nymphaea*, however, the inhibiting influence of the air still permits the slow elongation of the petioles by which the older leaves are moved farther and farther away from the center of growth.

Once spread out upon the water surface, the leaves are subjected to the stress of currents in air and water. Jahn (1896) pointed out four requirements for such foliage: (1) lightness and firmness of lamina; (2) the greatest possible amount of surface; (3) insertion of petiole at center of leaf; (4) the petiole must make a large angle with the lamina. The first is attained by the great amount of air space, and in *Lotos* and *Apo-carpiae* by the girder-like veins. But in strong winds the leaves are often

raised up at one edge or blown completely wrong side up. The toughness of the lamina prevents its tearing. Breadth of leaf surface is carried to its ultimate extent in the circular leaves. The larger the leaves the less easily they will be overturned, and a further need will be appreciated when it is noted that waterlilies must have all of their foliage in one plane; a distribution in space of three dimensions is not available to them. That the rounded outline has been acquired by a backward extension of the basal lobes of the leaf is due to the third condition. A round lamina with marginal attachment of the petiole is quite a possible thing. But if such a leaf were to exert any tension upon its anchorage, the effect would be to submerge the basal portion. The central attachment obviates this difficulty; and peltation is a further advance toward the same end. Various other adaptations of the plant in irritable response to its peculiar environment have been referred to in previous pages. A number of interesting activities of the floral parts will be described shortly.

The nutritive relations of waterlilies have not been specially worked out. They require a large amount of nitrogenous food, as every cultivator can testify, but prefer it in the form of nitrates rather than ammonia. Excess of calcium, as in limestone waters, is not beneficial. Doubtless these substances are absorbed with water by the roots directly, since no root-hairs are present. And the importance of the roots is shown by the great reduction in vigor of plants when moved from one pot to another, though they soon regain their strength. Wächter (1897) has shown, however, that complete removal of the roots is less injurious than removal of the leaves. Water is also absorbed elsewhere than at the roots. A leaf of *N. rubra* 35 cm. across, severed from the parent plant and left floating in the water, with the end of the petiole tied to a stick above the water level, not only remained apparently healthy for three days, but grew 1.3 cm. in diameter, and its petiole elongated 6.3 cm. Whether or not this leaf was transpiring moisture through the stomata I cannot say; but that a large amount of transpiration occurs from waterlily leaves was shown by a small tank in my father's garden. This was a water-tight iron vessel four feet square, and the surface was almost completely covered with leaves so that very little free evaporation could occur. After every clear summer day it was necessary to add one to three buckets of water to keep the level constant. So reduced is the xylem in the petioles that one questions how and where any sap can ascend. Some have thought the small air-canals in the vascular bundles are filled with liquid, but we find no evidence of this. But, in a leaf placed with the end of the petiole in

watery eosin, the phloem portions of the bundles were stained as though the coloring matter had traveled up in them. The whole subject of the course of water in aquatic plants needs investigation.

Respiration is to be looked upon as causing some of the most characteristic structures of water plants, namely the air-canals. In August, 1867, Lechartier experimented on *N. alba* as it grew naturally in the rivers. He found that on cutting off a leaf just below the water surface a flow of gas takes place from the air-canals of the petiole. This flow continues throughout the day, ceases at dark (7 p. m.), and begins again the next morning (8.30 a. m.). It may continue even against a pressure of 26 cm. of water, and after all of the leaves have been cut off the plant. In one instance 220 cc. was collected from a single petiole in an afternoon, and in another 262 cc. The total amount of gas from a single plant was 1,028 cc. in fifty-three hours. In these plants all of the leaves were submerged during the experiments. A plant with several floating leaves was next used. A petiole was cut off near the leaf, and when held 1 cm. below the water surface no gas came out; when raised in a closed inverted tube of water 10 cm. above the surface of the river, the flow amounted to 600 cc. in fifteen minutes. This gas was tested in portions of 60 cc. collected successively, and at three times of day, as follows:

The first, fifth, and tenth portions of air contained—

	AT 6.30 A. M.			AT 11.30 A. M.			AT 2.30 P. M.	
	I.	V.	X.	I.	V.	X.	I.	V.
CO ₂	1	3	2.5	0.5	2.5	2.4	0.5	2
O.	7.7	8.1	8.2	9	9.7	9.7	16.8	10.7
N.	91.3	88.9	89.3	90.5	87.8	87.9	82.7	87.3
	100	100	100	100	100	100	100	100

From these figures it appears that the air drawn out last at each period (V, X), and therefore probably from the stem and roots of the plant, contains more carbon dioxide than that in the petiole, and that the oxygen content of the inclosed air increases greatly while the plant is exposed to sunlight. At best, though, the proportion of oxygen present is much less than in atmospheric air. It appears also from the first experiments that the gases are not necessarily, if at all, derived directly from the air. Barthélemy (1874) attempted to repeat Lechartier's work, but found that the flow of gas diminished rapidly after the first gush; he

therefore believed the flow to be due to a higher pressure in the plant than outside. He agreed with Lechartier in believing that there is a movement of gases in the air-canals of Nymphaeaceae toward the leaf, to make exit through the stomata, and concluded that stomata in general are for the exit rather than for the entrance of gases. Goebel's (1893) experiment seems to differ from these. On a dull autumn day petioles of *N. rubra* and *stellata* (?) were cut off under mercury near the water surface and held as nearly as possible erect. The smaller intercellular spaces became in every case injected with mercury up to the lamina, even in pieces 60 cm. long. This would indicate a considerable negative pressure. Recognizing the positive pressure as noticed by Sachs (though without mention of Lechartier or Barthélemy), Goebel concludes that when the amount of assimilation is slight there is a rarefaction of air in the canals caused by the continuance of respiration; but when assimilation is active, part of the oxygen is given off into the intercellular spaces, and reaches the air-canals and finally extends to the rhizome and root. This view at once harmonizes the observed phenomena and explains the presence of the air-canals. It is the more plausible when we consider the peaty soil in which our waterlilies grow and the general absence of free oxygen in submerged muddy material.

Since the behavior of the flowers has for its object the successful reproduction of the species, and since there is in this connection a very distinct series of movements and activities, the whole relation of these parts has been reserved to this point, although there would be good reason to take them up under the head of irritability. The rise of the flower bud from the rhizome to the surface of the water takes place in the same manner as that of the leaf, and the peduncle must be regulated in length by the same stimuli that regulate the petiole; it is even capable, in *Castalia*, of a slight elongation if the water level rises after the flower first comes into bloom. A peculiar adaptation occurs, on the other hand, in plants of any species, when grown in very shallow water, say 10 to 15 cm. This often occurs in our gardens, where we have the tropical kinds as near to the surface as possible in order to keep them warm. Now, the flower bud is first pushed out from the apex of the plant in a very immature state, and it is to finish its development as it is rising through the water. In very shallow water, therefore, it reaches the surface when it is by no means ready to be exposed to the air. The situation is recognized at once by the plant, and the peduncle bends to one side and becomes S-shaped

(Fig. 52); thus the bud maintains its erect position and is kept submerged. Then in due time, the bud having matured and the peduncle having reached a suitable length, the latter straightens up and lifts the former into the proper position for opening. In *N. flavo-virens*, where I have noticed this most plainly, the flower stands about a foot above the water.

The opening of the flower occurs at a particular time of day for each species of *Nymphaea*. Indeed, we have attempted in the accompanying




FIG. 52.—A strong-growing waterlily in shallow water.

list* to imitate Linnaeus's floral clock in this genus alone. After remaining open a few minutes (*N. amazonum*) or hours, the flower closes at a certain time, and this is repeated on two (*N. flava*) or three (*N. odorata*, *caerulea*, etc.) to six or seven (*N. gigantea*) successive days. This is the foundation on which was based the statement of Pliny and others that the flowers retreat under water at night. The process of opening and closing usually occupies nearly an hour. On its first day the flower always opens

*Floral clock for the latitude of Philadelphia (40° N.).

3-4 a. m.	<i>N. amazonum</i> (new flower) opens.	12-1 p. m.	<i>N. odorata</i> , <i>tuberosa</i> , <i>caerulea</i> , and <i>elegans</i> close.
4-5	<i>N. amazonum</i> (old flower) opens wide.	1-2	<i>N. alba candidissima</i> closes.
5-6	<i>N. amazonum</i> closes; <i>N. marliacea carnea</i> opens.	2-3	<i>N. elegans</i> × <i>zanzibariensis</i> and <i>marliacea chromatella</i> close.
6-7	<i>N. alba candidissima</i> and <i>odorata</i> minor open.	3-4	<i>N. mexicana</i> closes, <i>N. capensis</i> × <i>zanzibariensis</i> closes.
	<i>N. gracilis</i> and <i>elegans</i> × <i>zanzibariensis</i> open.	4-5	
7-8	<i>N. elegans</i> , <i>capensis</i> , and <i>caerulea</i> × <i>zanzibariensis</i> open.		<i>N. tetragona</i> , <i>gracilis</i> , and <i>Pennsylvania</i> close.
	<i>N. caerulea</i> , <i>marliacea chromatella</i> , and <i>tuberosa</i> open.	5-6	<i>N. capensis</i> , <i>zanzibariensis</i> , and <i>zanzibariensis</i> × close.
8-9	<i>N. marliacea chromatella</i> (new flower) opens.	6-7	
	<i>N. capensis</i> × <i>zanzibariensis</i> opens.	7-8	<i>N. dentata</i> and <i>omarana</i> open.
9-10	<i>N. zanzibariensis</i> × opens.		<i>N. amazonum</i> (old flower) opens sepals.
10-11	<i>N. mexicana</i> opens.		<i>N. rubra</i> , <i>rubra rosea</i> , and <i>devoniensis</i> open.
	<i>N. rubra</i> and <i>rubra rosea</i> close.	8-9	
11-12 m.	<i>N. tetragona</i> and <i>zanzibariensis</i> open.	9-10	<i>N. rudgeana</i> opens and closes (Casp.).
	<i>N. omarana</i> closes.	10-11	
		11-12	

about an hour later than on subsequent days, closes earlier, and spreads but half as wide. An exception to this must be made for *N. amazonum*, whose very peculiar habits are detailed in the description of the species. *N. rudgeana* has also shown a very short nocturnal period of opening. Observations on other *Hydrocallis* species would undoubtedly yield interesting results. The characteristics of each species, so far as known, are given in the taxonomic chapter.

The stimulus to these actions is to be attributed, in diurnal species at least, wholly to light. If plucked and taken into a room they rapidly close, even though the normal time has not come. On the following morning, however, they reopen even in a very dimly lighted room. Subsequent movements of the cut flower soon become irregular, and it finally ceases to move. This is probably due to the death of the protoplasm in the sensitive or motor centers, though the flower may remain open without wilting for some days. That light is the normal stimulus is also shown by the earlier opening of the flowers in more northern latitudes. Thus Kerner (1895) gives 7 a. m. as the time for opening of *N. alba* at Upsala, and 8 to 9 a. m. at Innsbruck, 13° farther south. Heat seems to have no effect upon the *Eu-castalia* group in ordinary atmospheric quantities; for the time of opening and closing remains the same on days and nights when the mercury is continually above 80° F. and on cool, cloudy days when the temperature does not rise above 65° F. In tropical species as grown out of doors in our climate heat does have a marked effect. One evening in 1900, when the mercury registered about 95° F., *N. zanzibariensis* remained open nearly an hour later than usual; and in autumn, when the night temperature reaches 40° F. and the plants are looking the worse for wear, the diurnal tropical species become very irregular and open but a little way. The conclusion to be drawn is that the plant itself must be in a certain condition of health or tonicity to enable its parts to perform their functions. The effect of heat is essentially systemic rather than local. In *Lotos* it seems likely that heat may have a more distinct influence upon the flowers, but it is still obscure. They do not close until the heat of the sun is making itself felt, but on exceedingly hot nights they open to perfection, and on much cooler days they close at the usual time. But when the cold of autumn injures the plants, they sometimes remain open two or three days and nights continuously. On one occasion at Riverton, N. J., I saw about sixty large flowers of this type cut in the morning and placed in jars of water in a shaded glass house; they closed very slowly and incompletely. We must conclude, therefore, that light is again the

principal stimulus, causing in these closure, in other species opening, of the flower. The difference in effect is paralleled in positive and negative heliotropism and positive and negative geotropism. The influence of different colors of light has never been tried. Chemical stimuli were used by Tassi (1884). He found that flowers of *N. alba* and other plants were unable to perform their movements under the influence of anæsthetics, and in some plants the color changed.

The large and showy flowers of waterlilies are in many ways designed for the visits of insects. The colors are mostly conspicuous and attractive. *N. caerulea* is comparatively insignificant; and *N. rubra* makes very little showing at night, but in the early morning it is magnificent. *N. rudgeana*, according to Caspary (1878), is often cleistogamous. The possibility of such a thing is suggested by its regular occurrence in Euryale; and *N. amazonum*, with its odd habits, may well be considered as approaching the same condition. Certain it is that close pollination occurs regularly in this species. In cold weather, too, the flowers of *N. amazonum* seem to be fertilized without ever rising to the water surface. The occurrence of similar irregular cleistogamy in *N. rudgeana* may have been due to unnatural conditions. Observations are totally lacking on *Hydrocallis* species in their native haunts.

In *Castalia* and *Apocarpiae* the flowers have a sweet ethereal odor. This is richest and most delicious in *N. odorata*, faint in *N. tetragona*, scarcely perceptible and only present on the first day of opening in *N. alba*. The *Lotos* and *Hydrocallis* groups have very little odor; in the latter it is pleasant and ethereal, but in the former it is dull and rather offensive. The flowers are always pistillate on the first day of opening, and the stigmatic cup is filled nearly to overflowing with a large quantity of slightly sweetened water. This is excreted by the stigma itself and by the axile process. The stamens at this time stand erect around the stigma, leaving a narrow vertical pit in the center of the flower, bounded all over the sides by the still closed anthers of stamens of different lengths. All the stamens are stiff in *Lotos*, but in *Castalia* the innermost filaments are very slender and flexible, scarcely able to hold up the heavy anthers. The carpellary styles also stand erect. In flowers of the second and later days the stigma is quite dry and the papillae shriveled (in *N. odorata* and *tuberosa*; Robertson, 1889), though in *N. alba*, according to Schulz (1890) still receptive. The carpellary styles, when long enough, have bent inward over the stigma until they lie horizontally or point downward, and the inner stamens meet in the middle so as more or less to hide the pistil. The

stamens now dehisce. Where the flower is open only for two days, as in *Xanthantha*, all of the stamens dehisce on the second day, but the outer ones precede the inner by a few hours. In the rest of *Castalia* the inner stamens dehisce on the second day of opening; they do not completely cover the entrance to the stigma from above, but they hang over far enough to drop their pollen upon it, and sometimes close fertilization occurs. In *Brachyceras*, as a rule, the entrance to the pistil is totally obstructed on the second day by the inner stamens, and the outer ones are dehiscing; subsequently the inner stamens bend outward and dehisce until, on the last day, the passage to the stigma is wide open again. In spite of this, *N. caerulea* and *stellata* are said by Caspary (1877) to be capable of self-pollination, the latter while still in the bud. The stiff stamens of the *Lotos* group dehisce simultaneously on the second day, and undergo no considerable change of position.

The exact manner of effecting cross-pollination and the insects concerned are unknown for the *Lotos* group, but the white and light-pink varieties are extremely fertile when grown out of doors in the vicinity of Philadelphia. The agency of insects in *Hydrocallis* is likewise undetermined. *N. alba* is, in the opinion of Delpino, fertilized by scarabaeid beetles (*Cetoniae* and *Glaphyridae*); he regards *Nymphaea* and *Victoria* as especially adapted for beetles. Kirchner, in his "Flora von Stuttgart," page 275, mentions "flower-beetles" as visitors (*vide* Müller, 1883, p. 93; Schulz, 1890), and Picciola found *Donacia* (a chrysomelid beetle) abundantly. But Schulz found *N. alba* perfectly fertile with its own pollen, and considered that the flies and beetles which visit it always cause close fertilization. *N. tuberosa* is visited by small mining bees (*Andrenidae*), flower-flies, and beetles (Robertson, 1889), and *N. odorata* by *Halictus* and others. In our own experience, mining bees and flower-flies are the only insects found. They are drowned in large numbers in the stigmatic fluid, and are found in the closed flowers after anthesis. In a single bloom of *N. capensis* \times *zanzi-bariensis* I once counted thirty-two little bees! Bacon (1874) noticed dead insects in *N. odorata* and supposed that they were caught by the closing of the flower; Delpino attributed their death to the heavy odor of the flower, and Planchon to the accumulation of carbon dioxide in the floral cup (*vide* Robertson). But Robertson is undoubtedly correct in considering it simply a case of drowning. The course of events is about thus: The insects which visit the flowers are in search of the copious pollen; no true nectar is secreted. The earliest flowers to open each day are the older ones, in which pollen is plentiful and the stigma is dry. The insects fly

from flower to flower in safety gathering their loads. When an hour later the new flowers open with their receptive stigmas, the insects are well dusted over. Coming to the narrow opening of the new flower, they rush in with confident haste; but reaching the slender inner stamens, these bend down under the weight, and the visitor is dropped into the pool of liquid in the stigmatic basin. As he struggles to get out by crawling up the styles, he must again lay hold of the treacherous inner stamens, and be again let down into the water. Thus pollen is washed off the bee into the fluid, and the need of the plant is met; it is a matter of strength and endurance on the part of the visitor whether or not he gets out alive. When the stigmatic fluid is absorbed, the pollen grains settle down among the papillæ and are in a position to germinate. In some species a considerable amount of heat is evolved in the newly opened flower, but never in anything like the quantity found in *Victoria regia*.

On the last day of opening the flower begins to sink back into the water again. In *Hydrocallis* it takes but 2 to 5 hours for the closed flower to become totally submerged; in *N. odorata* it requires 6 to 12 hours, and the flower remains nearly wide open. In *Lotos* and *Brachyceras* also the flower often sinks while still open, but on its last day it has already moved down near to the water surface, and is not totally submerged until 12 to 20 hours later. The submergence of the flower is due to active, even powerful, movements of the peduncle, and occurs most pronouncedly in fertilized flowers. Infertile flowers scarcely get below the surface of the water, and then quickly disintegrate; sometimes the peduncle decays before the floral parts, showing how great is the transmitted effect of fertilization. Under the most favorable circumstances only about half of the ovules proceed with development to form mature seeds, but the presence of 10 or 12 fertile ovules in each cell of such fecund species as *N. lotus* or *caerulea* is sufficient to stimulate the movements of the peduncle. In *Lotos* the peduncle simply bends over and carries the flower down, and the ripening fruit lies on its side. In *N. amazonum* there is a double curve, so that the ripening fruit is upright. But in other species more or less of spiral coiling accompanies the bending. The stout peduncles of *Brachyceras* descend in the same manner as *N. amazonum*, but there is in addition a strong curving of the lower half of the peduncle to the right or left. The result is that we find the fruits near the bottom of the water, 15 to 35 cm. away from the crown of the plant and on the opposite side from the point of insertion of the fruit-stalk. *N. flava* in shallow water (15 cm.) makes the same kind of a bend; as the stalk is more slender, the bends are sharper and the

fruit is pressed close against the mud. *N. tetragona* resembles *N. flava* in these respects. In deep water (1 to 5 meters) *N. flava*, *odorata*, *alba*, and *tuberosa* carry the spiral turning to its highest development. From a few centimeters above the rhizome to within a few centimeters of the flower, the peduncle is coiled into a close helix from 2 to 8 centimeters in diameter, and with 2 to 8 or 10 turns; thus the fruit is drawn down within about half a meter of the bottom of the water, and often quite into the mass of algæ and other vegetation overlying the mud. Just such an adaptation has given the specific name to *Vallisneria spiralis*. Besides removing the fruit from the drying influence of the air, the purpose of these movements is doubtless twofold: First, to hide the fruit from the many aerial, aquatic, and amphibious animals which might feed upon it, for the majority of such creatures get their food at the surface rather than in the depths of the water; secondly, to reduce the danger of the fruits being broken off, as would easily occur with the long, slender peduncles of *Castalia*.

CHAPTER V.

TAXONOMY.¹

Genus **NYMPHAEA** (Linn.) J. E. Smith.

GENERIC DIAGNOSIS—Sepals 4 (rarely 3 or 5), inferior. Petals many (12 to 40), multiseriate, the lowest alternate with the sepals. Stamens many (20 to 700), multiseriate, inserted above the petals on the upraised torus which surrounds the carpels; outer filaments broader, often petaloid; innermost slender or filiform; anthers introrse, bilocular. Carpels many (8 to 35), sunk in the cup-shaped, fleshy receptacle, fused dorsally with it, and produced above it into shorter or longer processes, the carpellary styles (except in *Sec. Anecphyta*); margins of carpels fused centrally with the floral axis, which extends above them as a short axile process. Stigma broad, concave, radiate. Ovules very many, anatropous, pendulous from the sides of the ovary cells. Fruit a spongy berry, ripening under water and bursting irregularly. Seeds with a floating sac-like aril, open at the apex; endosperm very small; perisperm copious. Embryo small, straight.

Aquatic herbs with perennial elongated or tuberous rhizome, rooting in mud at the bottom of ponds, streams, etc.; leaves floating, ovate to orbicular, fissi-cordate, 5 to 60 cm. in diameter; flowers solitary, showy, floating or raised above the water on stiff scapes, 2.5 to 30 cm. in diameter, white, blue, red, or yellow, in all shades.

Founded by Smith on *N. alba* L.

Nymphaea, Tournefort 1700, in part. Linnaeus 1753, in part.

Nymphaea, J. E. Smith 1809. DeCandolle 1821 *b*, 1824. Planchon 1853 *b*. Lehmann 1853 *a*. Caspary 1855, 1865, etc. Bentham & Hooker 1862. Gray, etc. *Not* Salisbury 1806 *a*.

Castalia, Salisbury 1806 *a*. Greene 1887 *a* and *b*, 1888. Britten 1888 *a*. Lawson 1889. Britton & Brown 1897.

Leuconymphaea, Ludwig 1737. Kuntze 1891. MacMillan 1892.

Nymphea, Rafinesque 1830.

¹ This chapter, together with most of the bibliography at the end of Chapter VIII, was submitted to the University of Pennsylvania in partial fulfillment of the requirements for the degree of Doctor of Philosophy, May 1, 1901. At that time I had placed the members of the *Lotos* group in a single species, *N. lotus*. The separation of these into three distinct species, the fusion of *N. flava* and *N. mexicana*, the addition of some African species, and the substitution of "*N. flavovirens*" for "*N. gracilis*" are the only material changes made since that time. A few citations and measurements have been added in several species.

In order to present a tabular view of species and subgenera the following synopsis and key are inserted. The genus *Nymphaea* divides readily into two main divisions, which are subdivided into five subgenera.

Group I. *Nymphaeae apocarpiae*. Subgenus (1) *Anecphyta*. (2) *Brachyceras*.

Group II. *Nymphaeae syncarpiae*. Subgenus (3) *Castalia*. (4) *Lotos*. (5) *Hydrocallis*.

Analytic Key.

- Carpels free at sides, i. e., walls between ovary cells double (Fig. 40) (*Nymphaeae apocarpiae*)..... 1
- Carpels fused at sides, i. e., walls between ovary cells single (Fig. 40) (*Nymphaeae syncarpiae*)..... 13
1. Carpellary styles wanting; stamens unappendaged (*Anecphyta*)..... *N. gigantea*
 1. Carpellary styles present, thick and fleshy; stamens appendaged (*Brachyceras*)..... 2
 2. Flowers yellow..... 3
 2. Flowers never yellow..... 4
 3. Leaves 4 to 6 cm. across; veins inconspicuous..... *N. sulfurea*
 3. Leaves 20 to 25 cm. across; veins very prominent..... *N. stuhlmannii*
 4. Leaves entire or nearly so..... 5
 4. Leaves dentate or crenate..... 10
 5. Leaves narrowly elliptic (twice as long as broad), blotched..... *N. ovalifolia*
 5. Leaves ovate or orbicular..... 6
 6. American species; flowers pale violet..... *N. elegans*
 6. African species..... 7
 7. Mature leaves bulbilliferous..... *N. micrantha*
 7. Not bulbilliferous..... 8
 8. Leaves deep purple beneath..... *N. calliantha*
 8. Leaves green or purplish-green beneath, spotted with black..... 9
 9. Petals 5 to 10; stamens 11 to 16..... *N. heudelotii*
 9. Petals 14 to 20; stamens 50 to 75..... *N. caerulea*
 10. Flowers white..... 11
 10. Flowers blue or pink..... 12
 11. Petals narrow, acute; leaves pure green beneath..... *N. flavo-virens*
 11. Petals elliptic, obtuse; leaves black-spotted beneath..... *N. ampla*
 12. Petals 20 to 30; stamens 150 to 275..... *N. capensis*
 12. Petals 11 to 14; stamens 33 to 55..... *N. stellata*
 13. Sepals prominently veined; styles linear; leaves spinose-dentate (*Lotos*)..... 14
 13. Sepals obscurely veined; outer filaments petaloid..... 17
 14. Leaves 10 to 15 cm. long, thin and membranous..... *N. zenkeri*
 14. Leaves 20 to 25 cm. in diameter, stiff; venation very prominent..... 15
 15. Flowers red; leaves bronzy..... *N. rubra*
 15. Flowers white..... 16
 16. Leaf orbicular, smooth or finely puberulent beneath..... *N. lotus*
 16. Leaf ovate, densely pubescent beneath..... *N. pubescens*
 17. Styles clavate; flowers nocturnal (*Hydrocallis*)..... 18
 17. Styles ligulate; flowers diurnal (*Castalia*)..... 26
 18. Sepals and petals long acuminate..... *N. oxypetala*
 18. Sepals and petals acute or obtuse..... 19
 19. Leaves sinuate..... *N. rudgeana*
 19. Leaves entire..... 20
 20. Petiole bearing a ring of long hairs at top..... *N. amazonum*
 20. No ring of hairs at top of petiole..... 21

- 21. Styles 12 to 16 mm. long.....*N. gardneriana*
- 21. Styles 4 to 10 mm. long.....22
 - 22. Sepals with black markings.....23
 - 22. Sepals marked with dark crimson lines.....24
 - 22. Sepals marked with fuscous striae.....25
 - 23. Spots few, large; leaves large, broadly peltate.....*N. lasiophylla*
 - 23. Spots few, linear; leaves small, narrowly peltate.....*N. tenerinervia*
 - 24. Leaves green above and below.....*N. blanda*
 - 24. Leaves marked beneath with dark purple forked and branching lines....*N. jamesoniana*
- 25. Leaves very narrowly peltate, small.....*N. stenaspidota*
- 25. Leaves larger and more peltate.....*N. gibertii*
- 26. Rhizome erect.....27
- 26. Rhizome horizontal; flowers white or pink.....29
 - 27. Flowers yellow (*Xanthantha*).....*N. mexicana*
 - 27. Flowers white, small (*Chamaenymphaea*).....28
- 28. Leaves plain green above.....*N. fennica*
- 28. Leaves more or less blotched with brown.....*N. tetragona*
- 29. Leaves crowded on the rhizome; European or Asiatic.....30
- 29. Leaves scattered on the rhizome; American.....31
 - 30. Line of attachment of sepals to receptacle sharply angular.....*N. candida*
 - 30. Line of attachment of sepals rounded.....*N. alba*
 - 31. Petals spatulate; rhizome tuberiferous.....*N. tuberosa*
 - 31. Petals elliptic; rhizome not tuberiferous.....*N. odorata*

Group I. NYMPHAEAE APOCARPIAE (= LYTOPLEURA Casp. 1865, 1878, 1888).

Carpels free from one another at the sides, fused along part of the suture with the axis of the flower, and dorsally with the perigynous torus. Tropical species with diurnal flowers ranging in color from blue through pink to white, raised 7 to 30 cm. above the water, on stiff peduncles. Venation of sepals inconspicuous. Outermost stamens first to dehisce, innermost last. Principal air-canals in the peduncle 6 (5 to 7), in the petiole 2; idioblasts very few; multicellular ingrowths rather frequent in the air-canals. Rhizomes erect, tuberous, drying off in the resting season. Plants glabrous throughout, except on the apical portion of the tuber and the base of the petioles and peduncles.

Subgenus 1. ANECPHYA Casp. 1865, 1888.

Carpellary styles absent. Stamens, very many, with narrow filaments and short, curved anthers, without appendage, or simply mucronate, inserted very densely at the summit of the torus around the stigmatic disc, the outermost being at some distance from the insertion of the innermost petals. Seeds larger than in the next section. Flowers appearing subtended each by two leaves, i. e., there are on the rhizome oblique series of flower bases alternating with two series of leaves. One species, in Australia and New Guinea.

Sec. Cyanea, Planchon 1852 b, 1853 b (in part).

Sec. Appendiculatae, trib. *Cyananthos*, Lehmann 1853 a (in part).

Sec. Inappendiculatae, trib. *Castalia*, Lehm. 1853 a (in part).

Nymphaea gigantea Hook. (Plate III.)

DIAGNOSIS.—See under subgenus *Anecphya*.


Nymphaea gigantea, W. J. Hooker 1852 *a*, *fid.* original specimen in hb. Kew. Planchon 1851 *b*, 1852 *d*, 1853 *b*. Rev. Hort. 1852 *b*. Lehmann 1853 *a*. Paxton 1853 *d*. F. Müller 1861, 1862. Bentham & Müller 1863. Caspary 1865. Garden 1883 *b*. G. & F. 1893 *a*, with good half-tone. Tricker 1897. Moenkemyer 1897. G. C. 1900. Conard 1901 *a*. Not seen: Lemaire 1853; Duchartre 1858; A. G. 1894, 1897.

Castalia stellaris, Salisbury 1806 *b* (in note to tab. 14, referring to specimen collected by Banks at Endeavor River).

Castalia gigantea, Britten 1888 *a*. Lawson 1889.

Victoria Fitzroyana, Hort. (*vide* Hooker, l. c.).

DESCRIPTION.—*Flower* 6 to 30 cm. in diameter (12.5 to 19 cm. as cultivated about Philadelphia; 30 cm. in the type specimen, dried), opening for 7 days from 9 a. m. to 7 p. m. (Casp. 1865), *inodorous*.—*Bud* ovoid, rounded at apex.—*Peduncle* terete, rather slender (1 to 2.5 cm. in diameter), tapering upward, smooth, light green, rising 10 to 35 cm. (18 inches, Robinson 1865) above the water; air-canals as in group Apocarpiae (figured by Hooker 1852 *a*, as petiole).—*Receptacle* short, small, dark green.—*Sepals* 4, oval or elliptic, rounded at the apex, breadth: length = 1:2.5 to 3 (average); persistent in fruit. Anterior (outermost) sepal pure green without, with a few blackish lines and dots; margins blue-purple above, shading to carmine-purple at point of attachment. Posterior (innermost) sepal with a broad green area in middle of back; a wide border (3 to 5 mm.) around apex and sides, narrowing to the base of the sepal, covered by the lateral sepals in the bud, of a dark royal-purple color in apical part, shading to sky blue at sides and carmine-purple at base. Lateral sepals with one side covered, and similar in coloring to posterior sepal. Five strong veins and several smaller ones visible at base of each sepal. Inside of sepals sky blue, shading to royal purple at apex, dark blue on lateral margins, and carmine purple below.—*Petals* 18 to 51, longer than the sepals and not entirely covered by these after the first day of opening; outermost petals obovate, obtuse, narrowed at base, deeply concave, not at all sepaloid, outside sky blue, shading to royal purple at apex and base, similar in color, but paler, within. Intermediate petal obovate to spatulate, rounded at apex, tapering at base, colored like outer petals, but paler throughout; innermost petal oblanceolate, rounded at apex, tapering to the base, pale whitish blue, tinged pure blue at apex and base. All of the petals thin and fragile, finely 1 to 7 nerved, satiny and crumpled like chiffon, fading in color on later days of opening.—*Stamens* 367 to 745, incurved at summit through an arc of 45° to 90°, half as long as the petals, separated from these by a wide interval and inserted densely on the upper part of the ovary. Anthers bright yellow, about 75 outer ones bearing a short, thin, acute apical appendage (or all unappendaged, Casp. 1865). Filaments paler yellow; 10 or 12 outermost ones broader than their anthers; all the rest are nearly or quite thread-like and longer than their anthers. "Outermost anthers first to open, innermost last. Pollen smooth" (Casp. 1865).—*Carpels* 12 to 20, quite distinct from one another and rather easily separated from the receptacle, stigmatic over all their upper free surfaces; carpellary styles wanting. Ovules large, few in number.—*Seed* "large,



NYMPHÆA GIGANTEA.

1. Anterior sepal. 2. Outermost stamen. 3. Inner stamens. 4. Median petal. 5. Vertical section of ovary. 6. Outermost petal.

dark colored, ellipsoid, apiculate, usually covered with interrupted longitudinal lines of hairs" (Casp. 1865). (See table of measurements of flowers, below.)

Submerged leaves from sprouting tuber (Fig. 34) 2 or 3, entire, green above, reddish beneath. First leaf triangular-hastate, with rounded apex and angles, and nearly straight sides; sinus very broad and shallow. Second leaf ovate-sagittate, broadly rounded at apex; sinus broadly triangular, lobes narrowly rounded. First floating leaf ovate, with deep open sinus and rounded apex and lobes; margin slightly irregular-wavy. Second and third leaves similar, with narrower sinus and margins distinctly sinuate-dentate on outer side of lobes; first two dull green beneath, third suffused with purplish blue, and with a few blackish spots.

Leaf of mature plant very narrowly peltate, orbicular-ovate or elliptic, 60 cm. or less in diameter, breadth: length = 1:1.4; margin flat or slightly wavy, sharply dentate; teeth short, acute (or obtuse, Casp. 1865 and Mrs. Rowan's paintings), 2.5 cm. apart and 0.6 cm. long; upper surface green and veiny, minutely elevate-punctate; under surface glabrous, brownish pink when young, becoming Tyrian purple when full grown. Veins prominently reticulated on under side of leaf; primary nerves 9 or 10 on each side; length of principal area: length of radius of leaf = 1:1.33. Depth of sinus = 0.37 of length of leaf; margins entire, touching or slightly overlapping within, then curving out, becoming 7.5 to 15 cm. apart at periphery of leaf; angles produced into a fine subulate tooth.—*Petiole* smooth, terete, 60 to 150 cm. long, with 2 large air-canals, 2 smaller ones before and behind these, and a surrounding ring of 10 still smaller ones; 2 double bundles anteriorly and posteriorly, with a peripheral ring of 11 bundles.—*Stipules* absent, but petiole winged at base, the wings gradually vanishing above.

Rhizome (tuber) ovoid; small ones (Fig. 14) nearly spherical, 1.6 to 1.75 cm. in diameter, contracted above, the vegetative bud springing abruptly from the rounded summit; larger tubers with prominent leaf-bases. Each flower subtended by two leaves, the peduncular scars on the rhizome forming an oblique series alternating with two series of leaf-scars (Casp. 1865).

MEASUREMENTS OF FLOWER FROM UNIVERSITY OF PENNSYLVANIA BOTANIC GARDEN, 1900 (IN CM).

SEPALS.		PETALS.		STAMENS.				
Length.	Breadth.	Length.	Breadth.	Length of Filament.	Length of Anther.	Width of Filament.	Width of Anther.	Length of Appendage.
7 (outer.)	2.2	8 (outer.)	2.6	2.55	1.15	0.25	0.16	0.16
7 (inner.)	2.4	7.3 (median.)	2.2	1.9	0.95	0.075	0.08	0.075
		6.7 (inner.)	1.6	1.45	0.65	0.04	0.08	0
				0.33	0.3	0.025	0.04	0

MEASUREMENTS OF LEAVES (IN CM.).

	Length of Midrib.	Length from Apex to Angle.	Depth of Sinus.	Width of Leaf.	Width of Sinus.
First submerged*	2.4	2.87	0.5	1.9	1.9
Second submerged*	2.23	3.2	0.8	2.8	1.9
First floating*	2.55	4	1.6	2.5	1.12
Second floating*	2.87	5.1	1.9	3.2	1.42
Third floating*	3.2	4.8	2.23	3.5	1.3
Mature.....	38.2	30.6
Mature.....	46	40

* From a small tuber.

GEOGRAPHIC DISTRIBUTION.—Australia and New Guinea. "Lakes and marshes throughout tropical Australia" (Benth. & Müll. 1863). "At river mouths in S. Australia," Schomburgk 1875. "Moreton Bay, Queensland; Clarence River, N. S. W.," Benth & Müll., l. c. Papua, Müll. 1875. "New Guinea, coll. Zippel; Endeavor River, coll. Banks," Casp. 1865. Rockhampton, E. Australia, coll. A. Dietrich, in hb. Berlin. King's Creek, Queensland, coll. Müller, in hb. Munich.

Type collected by Bidwill, No. 39, at Wide Bay, Queensland, in hbb. Kew, Berlin.

Forma *alba*—with white flowers. Benth. & Müll., l. c.

Forma *rosea*—with pink flowers. Benth. & Müll., l. c.

NOTES.—Introduced into England in 1852, and fruited by Van Houtte (Ghent) in 1855. Flowered in open air, in heated water, at Glasnevin (Dublin) in 1865. Frequent in cultivation in America, flowering freely out of doors all summer. Tubers are said to germinate better in deep water, i. e., about 60 cm.; but this is not necessary if good bottom heat is furnished.

Var. *violacea* (Lehm.) new comb. (Plate I, Frontispiece.)

Smaller than the type. Flower 12 to 15 cm. in diameter. Bud conical-ovoid, acute. Sepals coriaceous, ovate to oblong, tapering above with nearly straight sides to the obtuse apex; outer surface dark green more or less densely *marked with* interrupted heavier and lighter *black lines*; inner surface pale. Petals many, rich violet, slightly shorter than the sepals; outer ones larger, obovate oblong, tapering above. Stamens very many, much shorter than the corolla; appendage obsolete. Carpels about 10.

Leaves subovate, *repand*, light green above, deep purple beneath; petiole to apex 9 to 11 cm.; width 11.5 to 12.7 cm.; lobes 6.4 cm. long, obtuse; primary nerves 10 to 12; veins numerous, reticulate, prominent beneath, green. Sinus margins curved, open at periphery.

Rhizome cylindrical, the size of one's little finger. (Details mostly from Lehmann.)

Nymphaea violacea, Lehmann 1853 a, *fid.* original specimens coll. John Macgillivray, Oct. 10, 1848, Cape York, Voyage of the Rattlesnake, Botany, 410, in hb. Kew.

N. Banksii, Cunn., *fid.* original specimen, coll. A. Cunningham, June, 1819, Endeavor River, N. E. Australia, in hb. Kew.

- N. serrata*, Müller, *fid.* original specimen, coll. F. Müller, July 15, 1855, Arnheim's Land, Australia, in hb. Kew.
- N. repanda*, Müller, *fid.* original specimen, coll. F. Müller, July 16, 1856, Arnheim's Land; also Head of Sturt's Creek, Australia; both in hb. Kew.
- N. versicolor*, Müller, *fid.* original specimen, coll. F. Müller, July 15, 1856, Arnheim's Land, Australia, in hb. Kew. *Not* Roxb. 1809.
- N. stellata*, Müller 1861, *fid.* original specimen, sent by F. Müller from Rockingham Bay, Queensland, in hb. Munich; from Escape Cliffs, N. Australia, coll. W. Halls, in hb. Kew; from Barron River, Queensland, coll. W. Sayer, in hb. Paris; also in hb. British Museum. *Not* Willd. 1797.
- N. Brownii*, F. M. Bailey, 1899, *fid.* original specimen in hb. British Museum.

GEOGRAPHIC DISTRIBUTION.—Queensland, Arnheim's Land, Australia.

NOTES.—Caspary considered this merely a small form of *N. gigantea*; but the paintings of both types made by Mrs. Rowan in the native habitat, which I saw at the Philadelphia Museum, April 16, 1901, show the marked peculiarities cited above, which certainly entitle the plant to varietal rank. Mrs. Rowan considers it a very distinct type, and says it is restricted to the Cape York Peninsula, a region practically uninhabited by white people. We are especially fortunate in having opportunity to reproduce Mrs. Rowan's painting from the original, which is now the property of the University of Pennsylvania. Examination of the European collections gave fully conclusive evidence on the rank of this form. (Cf. also its synonymy.)

Subgenus 2. BRACHYCERAS Casp. 1865, 1878, 1888.

Carpellary styles present, short, stiff, and fleshy. Stamens numerous, following the petals in order on the torus directly or without much interval; exterior anthers long, more or less strongly appendaged with a process of the connective, the corresponding filaments being flat and more or less expanded. Seed smaller. Twelve species of world-wide distribution in the tropics.

Cyanea and part of *Lotos* DC. 1821 *b*.

Cyanea (mostly) Planchon 1852 *b*, 1853 *b*.

Section I. *Appendiculatae* Lehmann 1853 *a* (in part).

***Nymphaea elegans* Hook. (Plate IV; Fig. 53.)**

Leaves *entire* or slightly wavy at base, narrowly peltate, broadly *ovate* to ovate-orbicular; under surface dark purple; about 18 cm. long. Flower 7 to 13 cm. in diameter, pale violet, open from 8 a. m. to 1 p. m. Buds ovate. Sepals marked with black lines and dots. Petals 12 to 20, ovate, obtuse. Stamens about 100, stout, yellow; *appendage minute*; filaments narrow.

Nymphaea elegans, Hooker 1851, *fid.* original specimen, cultivated at Kew, from Texas, in hb.

Kew. *Revue Horticole* 1851 *b*. Paxton 1853 *b*. Sterns 1888. Tricker 1897. Conard 1901 *a*.

Castalia elegans, Greene 1888. Lawson 1889. Rose 1895.

Nymphaea Mexicana, Gray 1850. *Not* Zucc. 1832.

DESCRIPTION.—*Flower* 7 to 13 cm. in diameter, open widely on three successive days from 8 a. m. to 1 p. m.; odor sweet, moderately strong.—*Bud* ovate, obtuse or rounded at apex.—*Peduncle* terete, slender, stiff, rising 12 to 18 cm. above the water,

reddish brown, with 5 or 6 main air-canals, each with two very small canals outside.—*Receptacle* very narrow, sloping.—*Sepals* 4 (or sometimes 5) lanceolate, breadth: length = 1:3.4 to 3.6, obtuse or sub-acute; outer surface dark green, marked with fine brownish-black lines and dots, especially near the margins; 9 longitudinal veins visible by looking through the sepal at a light; inner surface dull greenish-white.—*Petals* 13 to 24, lanceolate, tapering to base and apex, breadth: length = 1:3.7 in outermost petals, crowded on lower part of torus. Outer surface of outermost petal sepaloid





FIG. 53.—*Nymphaea elegans*: a, sepal; b, petal of outermost whorl; c, petal of second whorl; d, petal of innermost whorl; e, outer stamen; f, successively smaller stamens; g, vertical section of ovary. Natural size.

FLORAL ORGANS.

	No.	No.	No.	No.*
Sepals ...	4	5	5	4
Petals ...	21	20	24	13
Stamens .	145	118	139
Carpels ..	22	22	25	15
Total	192	165	193

* Small flower, early in season.

in midline, green, with blackish lines and dots, with 5 strong veins visible on looking through; edges and inner surface pale violet, nearly white, fading to dull whitish on lower third of petal. Second row of petals a little shorter than first, pale violet above, nearly white in lower half, 5-veined. Innermost petal narrowly lanceolate, colored like second series, but very pale.—*Stamens* 80 to 145, stout, yellow, about one-half the length of the petals, inserted around the top of the ovary, leaving a bare space above the petal insertions; appendages very small, only present on the outer stamens. Outermost filament narrowly elliptic, slightly broader than anther; innermost tapering



NYMPHÆA ELEGANS.

from the width of the anther at top of filament to about one-half as wide at base. All of the anthers longer than the filaments. (See measurements at end of description.)—*Ovary* nearly hemispherical, with a naked ring on the sides between petals and stamens.—*Carpels* 15 to 25; styles yellow, erect, minute, 0.8 mm. long, a little broader than high, acute, the tip projecting as a very small point beyond and above the broadly rounded and centrally grooved stigmatic ray. Stigma more or less curved funnel-shape, with large central depression, in which the slender, conical, acute axile process stands free. Diameter of stigma 0.8 cm.; depth of depression 0.3 cm.; height of axile process 0.2 cm.—*Fruit* rounded, much depressed, cheese-shaped, 3.2 cm. in diameter by 2.2 cm. high, to 3.5 cm. in diameter by 1.9 cm. high, of a pale greenish color, subtended by the persistent sepals, contracted above to the low crown of hard, inwardly-directed styles; stigma basin-shaped, about 1.6 cm. in diameter, black, radially striate-sulcate; axile process broadly conical and obtuse.—*Seeds* nearly globose, about 0.13 cm. in diameter, mucronate at hilum by persistence of a portion of the funiculus, dull olive green, smooth, with rather strong raphe. Aril about as long as the seed, and closely investing it.

Germination may occur immediately on ripening of seed, or after a period of drought. First leaf of seedling filiform, 1.6 to 2.8 cm. long. Second leaf ovate, narrowed above, obtuse, 1.12 cm. long by 0.48 cm. wide, rounded at base; petiole 0.8 cm. long. Third leaf like second, but with slightly cordate base. Fourth leaf broader and more cordate at base. Fifth leaf broadly ovate, cordate, with rounded apex and basal lobes.

First submerged leaf from small tuber (Fig. 34) narrowly triangular, acute at apex; base truncate with rounded angles. Second leaf typically cordate, acute. First three floating leaves entire, ovate, broadest about midway of length, with rather wide sinus; apex broadly rounded, angles rounded; first two leaves green on both sides, third green above, purplish beneath. Fourth floating leaf speckled above with small brownish blotches, under surface brownish red with a number of fine darker specks; margin wavy on outside of lobes.

MEASUREMENTS OF LEAVES FROM SMALL TUBER (IN CM.).

	Length of Midrib.	Length from Apex to Angle.	Depth of Sinus.	Width of Leaf.	Width of Sinus.
First submerged	1.6	1.55	0	0.5
Second submerged	2.5	2.9	0.45	1.9	1.0
Second floating	2.6	4.5	1.9	3.0	1.2
Fourth floating	5.7	2.55	4.15

Leaf of mature plant broadly oval, or at times nearly orbicular; breadth: length = 1:1.3; usual length 15 to 18 cm., peltate by 0.6 to 2.0 cm., of rather thin texture, entire in upper half; very gently sinuate-dentate in basal half; apex rounded. Upper surface dark green, with small blackish-purple markings when young; under surface bright purplish-red with frequent blue-purple spots, greenish along the midline. Veins prominent out to the sixth grade; principal nerves 6 to 8 on each side; length of principal area: radius of leaf = 1:1.76.—*Sinus* open, depth: length of leaf = 1:3

(approx.), margins straight or slightly concave, converging toward the periphery; angles about 3.2 cm. apart, tapering, acute.—*Petiole* slender, light brown, attached to the lamina by a slender "collar"; principal air-canals 4, two larger and two smaller; stellate cells numerous on walls of larger canals.

Rhizome (tuber) erect, ovoid, black, thickly covered with leaf scars, about 7.5 cm. long by 3.5 cm. thick, ripening early in the fall. No stolons formed in vegetative period. Small tubers (Fig. 14), 1.2 to 1.35 cm. in diameter, spherical-ovoid, smooth in lower half, tapering above to the scaly-woolly vegetative end.

MEASUREMENTS IN CENTIMETERS.

STAMENS OF FLOWER A.*					SEPALs.		PETALS.		
Total Length.	Width of Filament.	Length of Anther and Appendage.	Width of Anther.	Length of Appendage.	Length.	Width.	Length.	Width.	Remarks.
1.75	0.2	0.9	0.16	0.08	3.8	1.1	3.5	0.9	Outer. <i>a</i>
1.42	0.16	0.8	0.13	0.04	<i>a</i> 3.8	<i>ao</i> .96	3.3	0.9	Median. <i>a</i>
1.13	0.13	0.47	0.13	0	3.65	1.1	3.2	0.8	Inner. <i>a</i>
0.95	0.1	0.64	0.13	0	3.8	0.96			
0.64	0.06	0.48	0.13	0	2.9	0.8			

* Measurements in this table and those marked *a* in adjoining tables are from the same flower.

GEOGRAPHIC DISTRIBUTION.—Texas, Mexico to Guatemala, chiefly in warm lowlands. "Near head of Leona River" (Gray 1850); Waco, Texas (Sterns 1888); Rio Grande, El Paso, Texas (Coulter 1890); Guatemala (Smith 1893); Tamaulipas, Vera Cruz, and Mazatlan, Mexico; Brownsville, Texas (coll. Pringle, Flora of Texas, 1888, No. 1955). Also coll. Berlandier, No. 2402, June, 1834, at Palo Alto, Rio de las Mines, Mexico, in hb. Kew, Paris, and No. 972 in hb. Berlin; coll. Hartweg, Mexico, No. 1972 in hb. Paris and 1592 in hb. Delessert.

NOTES.—Types collected by Dr. C. Wright on Leona River in June, 1849, and sent to A. Gray, and thence with seeds to Hooker, who raised plants and described the species from them. It was rediscovered in 1887 by Misses Trimble and Wright at the Waco locality in eastern-central Texas.


The flower is beautiful and delicately colored; the plant grows easily and blooms and fruits profusely.

Nymphaea ampla (Salisb.) DC. (Plate V.)

Leaves 15 to 40 cm. in diameter, sub-orbicular, narrowly peltate, *sinuate* or nearly entire, with small black spots above and below, at least when young; under surface red-purple; lobes acute. Flowers white, 7 to 13 cm. in diameter; sepals ovate-lanceolate, obtuse or somewhat acute, marked with blackish lines; petals 7 to 21, lance-ovate, *obtuse*; stamens 30 to 190, yellow, outermost ones much longer than innermost.

Castalia ampla, Salisbury 1806 *a*, 1806 *b*.

Nymphaea ampla, DC. 1821 *b*, 1824 (*fid.* leaf of original specimen, in hb. British Museum). Sprengel 1825. Don 1831. Macfadyen 1837. Schomburgk 1848. Gray 1850. Planchon 1853 *b*. Grisebach 1864. Caspary 1878. Garden 1883 *b*. Watson 1883. Hemsley 1888. Pringle 1890. Gray, etc., 1895. Conard, 1901 *a*.



NYMPHÆA AMPLA.

Flower. 2, Leaf. 3, Flower seen from side. 4, Rays of stigma and carpellary styles. 5, Stamens.
6, Rays of stigma from another flower.

- N. Lotus*, Linn. 176a (the American plant). Aublet 1775.⁵ Willdenow 1797. Loudon 1855.
N. Candolleana, Lehmann 1853 a, as to the leaf (*fid.* original specimen from hb. Lehmann now in hb. Berlin). Flower is of *N. rudgeana*.
N. foliis circinnatis maximis, Burmann 1759.
N. ampla var. *Plumieri*, Planchon 1853 b. Grisebach 1857. Caspary 1878.
N. trisejala Gaudich. ? *fid.* Eichler 1878.

DESCRIPTION.—*Flowers* white, 9 to 13 cm. across.—*Sepals* 4, coriaceous, narrowly oblong, breadth: length = 1:2.3 to 5.8 (average of 51 sepals from 43 flowers = 1:3.6, Casp. 1878), obtuse, acute or acuminate, outer surface green, marked with short blackish lines.—*Petals* 7 to 21, the outermost tinged yellowish-green.—*Stamens* 30 to 190, outermost much longer than innermost; anthers appendiculate.—*Carpels* 14 to 23; styles short-conical, gradually narrowed or abruptly apiculate-acuminate, acute, sub-acute, or obtuse, breadth: length = 1:1.5 on the average, = 1:1 to 2.5 in extremes; axile process rounded, breadth: length = 1:0.09 on the average, = 1:0.3 to 2.0 in extremes; stigma extending out on styles in short, rounded or rarely acute rays.—*Seed* sub-globose-elliptic, about 1 mm. long, with longitudinal rows of hairs.—*Leaves* large, narrowly peltate (3 to 31 mm.; average 10 mm.), sub-orbicular, 15 to 40 cm. in diameter, sinuate or nearly entire, green above, with small black spots; under surface red-purple; veins prominent, principal nerves 5 to 14 (average 10) on each side of leaf; length of principal area: radius of leaf = 1:2.

GEOGRAPHIC DISTRIBUTION.—Tropical and sub-tropical America, from 26° N. in Texas, through the Antilles, to 8° S. in Brazil; Fort Clark and Spofford, Texas (Plank 1896). Lampasas, Mexico. Nuevo Leon; Lakes between Ocuilzapotlan and Famulte de las Sabanas; Lagunas de Macultepec (very large specimen, coll. J. N. Rovirosa, 1889, in hb. Acad. Nat. Sci. Phila., with petals 9.5 cm. long and leaf 56 cm. long by 48 cm. wide). Mexico, coll. Houston, No. 1731, in hb. British Museum.

SEPAL DIMENSIONS.	
Breadth.	Length.
cm.	cm.
0.9	2.6
2.9	9.2
2.4	9.4

Springs and streams near Monterey, Mexico (Pringle, Plant. Mex., 1889, No. 2581). La Paila, New Granada. St. Domingo island. Vera Cruz, Hazienda de Mamulique, Hazienda de Tamatoc, Laguna Verde, Mexico (Casp. 1878). Aguada del Labach, Yucatan, coll. Schottmüller, No. 528, in hb. British Museum; also Gaumer, No. 428, in hb. Boissier. Cuba; St. Miragoane; Alligator Pond, Jamaica; Rio Ulna, Honduras; Belize, Honduras, coll. J. Robertson, Dec. 27, 1889, No. 20, in hb. British Museum. Hog Island, Bahamas, coll. Eggers, No. 4081. Martinique, coll. Plee, in hb. Paris. Guatemala (Smith 1891, 1893) *fid.* original specimen in hb. Kew. Encruzilhada, near Pernambuco, Brazil, coll. H. Schenck, Herb. Brazil, No. 4152, in hb. Berlin, and coll. Gardner, No. 915, near Alinda, in hb. Kew. Demarara, British Guiana, coll. Parker, in hb. Kew. Trinidad, coll. Fendler, No. 207, in hb. Kew. St. Vincent, south end, coll. Smith, No. 1708, in hb. Kew. Prov. Quito, Peru, coll. Hartweg, No. 1592, in hb. Boissier.

NOTES.—In the arrangement of this species we have followed Caspary as closely as possible; he examined the type material in nearly all of the European collections. DeCandolle's type specimen consists of a leaf of this species with a flower of *N. rudgeana* Mey.

The true species (var. *Plumieri* Planch., etc.) is of powerful growth, but has not yet been introduced into cultivation. We have discarded the varietal name in this and in other species, allowing the specific name alone to stand for the form originally described.

Var. *speciosa* (Mart. & Zucc.) Casp.

Of medium size; stamens 42 to 129; leaves less coriaceous, margins more or less repand-sinuate or dentate, with obtuse teeth; nerves slightly prominent beneath; lobes divergent, overlapping or approximate. Tuber sub-globose.

N. speciosa Martius & Zuccarini 1832, *fid.* original specimen, coll. Martius, in aquis S. Christoph., Prov. Rio de Janeiro, Brazil, in hb. Munich, in sched. No. 28.

N. ampla, Hooker 1849.

N. ampla β *Hookeri*, Planchon 1853 *b*.

N. ampla γ *Salzmanni*, Planchon 1853 *b* (flower).

N. tropaeolifolia, Lehmann 1853 *a* (flower), *fid.* original specimen in hb. Berlin. Leaf is of *N. rudgeana*.

N. nervosa, Lehmann 1853 *a*, from hb. Steudel, *fid.* Casp. and original specimen in hb. Berlin.

N. ampla var. *speciosa*, Caspary 1878.

N. Leiboldiana, Lehmann 1853 *a*, as to the American plant in hb. Vienna, *fid.* Caspary 1878. Specimens "ex herb. Lehm." in hbb. Kew and Berlin are from Africa, and appear to be *N. capensis*.

N. gracilis, Zuccarini 1832 *a, b*, *fid.* original specimens (2 sheets) coll. Karwinski, Aug. 1827, "ex lacu Mexicano," in hb. Munich. Coll. Pringle, Plant. Mex. 1891, State of Jalisco, No. 3891.

N. undulata, Lehmann 1853 *a*, *fid.* original specimens, coll. Galeotti, No. 4846 (4840 in Kew), Nov., 1840, "lacs près Oaxaca, Mexico," ex hb. Lehmann in hbb. Berlin, Kew. Hemsley 1888.

GEOGRAPHIC DISTRIBUTION.—Tropical America from 19° N. to 23° S. Valley of Mexico (Karwinski); Oaxaca, Mexico (Galeotti); Guadalajara (Pringle). Caguas, Porto Rico, coll. P. Sintenis, No. 2577, Sept. 5, 1885. St. Domingo, coll. Poiteau, 1802, in hb. Delessert. Jamaica; Nevis; St. Croix; Lebanon in Antigua; Maracaibo; La Paila in New Granada; Merida; Demerara in British Guiana; Kaw River in French Guiana; Pernambuco, Santa Cruz, St. Christophe, Para, Rio de Janeiro, Cabo Frio, Capocabana, and Bahia in Brazil (Caspary 1878).

NOTES.—This is the form cultivated in Europe as *N. ampla*, sent to Kew from Jamaica by Macfadyen in 1847 or 1848, and to Caspary from Caracas by Dr. Ernst in 1869.

Specimens from St. Christophe and Maracaibo have the lobes of the leaf widely divergent; those cultivated in Europe from Jamaica stock have the lobes touching; nearly all the others in collections have an open but very narrow sinus.

The type specimens of *N. ampla* γ *Salzmanni* Planch. and *N. tropaeolifolia* Lehm. consist each of a flower of this variety with a leaf of *N. rudgeana* Mey. (Casp. 1878).

Var. *pulchella* (DC.) Casp.

Flowers of medium to small size; stamens 30 to 50; margin of leaves sub-entire or slightly repand-sinuate; veins slender, scarcely prominent.

N. pulchella, DC. 1821 *b*, *fid.* original specimens, without data, in hb. DeCandolle, but marked coll. Pavon, at Guayaquil (DC. ms.) in hbb. Paris and British Museum. Planchon 1853 *b*. Lehmann 1853 *a*.

N. lineata, St. Hilaire 1833, *fid.* Caspary 1878, and original specimen in hb. Paris.

N. ampla var. *pulchella*, Caspary 1878.

GEOGRAPHIC DISTRIBUTION.—South America, from 2° to 23° S. Guaniva, Porto Rico, coll. Sintenis, No. 3662, det. Caspary, in hbb. Berlin, Kew, Munich. Guayaquil, Peru; Province of Rio de Janeiro (between Sitio de Paulista and Sitio do Porier), Brazil (Caspary 1878).

Nymphaea flavo-virens Lehmann. (Plate VI; Fig. 54.)

Leaves sub-orbicular, 30 to 45 cm. in diameter, narrowly peltate, deeply and irregularly *sinate* or nearly entire, plain *green on both sides*; angle of lobes rounded. Flowers white, 10 to 15 cm. in diameter; sepals pure green, or with 2 or 3 scattered short black lines near the margins; petals 16 to 20, narrow, *acuminate*; stamens about 60, deep yellow; outermost filaments short, broad, petaloid; anthers with a yellowish-white appendage.

Nymphaea flavo-virens, Lehmann 1852 b, 1854, *fid.* specimens from the Hamburg Botanic Garden, 1864, in hb. Kew, and from hb. Lehmann in hb. Berlin. Hooker 1901, *fid.* original specimen in hb. Kew, cult. in Kew Garden.

N. gracilis Hort. Watson 1887? G. & F. 1894 b. Tricker 1897. Conard 1901 a. *Not* Zuccarini 1832 a. *N. mexicana* Hort, *not* Zuccarini 1832, *fid.* Hooker, l. c.

DESCRIPTION.—*Flowers* 10 to 15 cm. in diameter, open from early morning to 5 or 6 p. m., sweet scented, resembling *Convallaria majalis*.—*Peduncle* terete, slender, glabrous, tapering upward, rising 20 to 30 cm. above water, with 6 small main air-canals and 12 secondary ones, all with thick partitions between.—*Sepals* 4, lanceolate, tapering to an acute apex, 8.3 cm. long by 2 to 2.4 cm. wide, green and obscurely nerved outside, sometimes with a few scattered short black lines; inner surface white.—*Petals* 18 or 19, of firm texture, outermost opening nearly horizontally, about as long as the sepals, narrowly lanceolate, acute, breadth: length = 1:5.6 to 6.1 (= 1.27 cm.: 7.8 cm.; and 1.4 cm.: 8.3 cm.). Outermost petal greenish-white outside, with 2 or 3 reddish lineolæ. Inner petals smaller, pure white.—*Stamens* about 60 (56 to 61), yellow; outer ones longer, with short, broad, petaloid filaments, and appendages of medium length, stout, light yellow in color.—*Carpels* 12 to 15; styles short, stout, fleshy, orange-yellow, becoming elongated and incurved in fruit.—*Fruit* nearly globose, 2.2 cm. in diameter by 2.87 cm. high, crowned by the small circle of styles (1.9 cm. in diameter at base, outside measurement), and slightly depressed, basin-like stigmatic disc; axile process broadly conical with rounded apex, about twice as wide as high. Cells of berry oval, about 1.9 cm. high by 0.95 cm. wide radially.—*Seed* nearly spherical, with insignificant raphe, about 0.2 cm. in diameter.

FLORAL ORGANS.			MATURE LEAVES.	
Organs.	No.	No.	Length.	Breadth.
Sepals.....	4	4	cm.	cm.
Petals.....	18	19	43.3	38.9
Stamens.....	60	56	46.0	40.0
Carpels.....	15	15	46.3	42.7

Submerged *leaves* from small tuber 2 or 3; first one ovate, acute, or oftener triangular-hastate with acute apex and angles; second leaf much larger, angles slightly rounded, lobes long and narrow, widely diverging, thin and crisped or even twisted. First floating leaf ovate, abruptly acuminate, broadest opposite the insertion of the petiole, slightly crenulate; sinus deep, margins straight or slightly curved, slightly divergent or touching or overlapping, angles narrowly rounded; upper surface green with a few brown blotches, especially near the margin; under surface green, blotched with brown.

Leaf of mature plant narrowly peltate (1.2 to 1.9 cm.), orbicular-ovate, 30 to 45 cm. in diameter, deeply and irregularly sinuate-dentate, with obtuse or rounded teeth




FIG. 84.—*Nymphaea flavo-virens*: a, sepal; b, petal of outermost whorl; c, petal of second whorl; d, petal of third whorl; e, outer stamen; f, inner stamens; g, vertical section of ovary. Natural size.

1.2 cm. long and 2 cm. apart, rarely nearly entire; pea-green above, paler below; veins prominent beneath, primary nerves 7 to 9 on each side; length of principal area: radius of leaf = 1:1.6 to 1.75.—*Sinus*, depth: length of leaf = 1:2.5 to 2.8; margins more or less convex, divergent or overlapping; angles rounded.—*Petiole* terete, 1.2 cm. in diameter, 60 to 150 cm. long.

Rhizome (tuber) erect, stout, 3.8 cm. long by 2.9 cm. thick to 21 cm. long by 10 cm. thick (!), brownish-black, very rough with projecting leaf cushions, each capped by the dried base of the petiole and marked on the under side with root scars; upper



NYMPHÆA FLAVOVIRENS.

quarter of tuber clothed with long light brown hairs, above which the stout soft leaf-rudiments may project visibly even in the dried state. Phyllotaxy of a high order, but the leaf scars are 1.2 to 1.9 cm. apart, and by their dry projecting habit give the tuber somewhat the appearance of a rough pine-cone.

MEASUREMENTS OF LEAVES FROM SMALL TUBER, IN CENTIMETERS.

Leaf.	Length of Midrib.	Length from Apex to Angle of Lobes.	Diameter of Leaf.	Width of Sinus.	Depth of Sinus.
First submerged	1.6	2.2	1.6	1.6	0.5
Second submerged	2.5	4.0	4.0	4.0	1.25
First floating	3.0	5.6	3.35	0.6	2.55
First floating	5.6	3.0	1.0	2.2
First floating	7.3	4.8	0.8	3.35
First floating	5.4	3.5	0.6	2.2
First floating	3.0	2.9	0.8	2.2
First floating	3.0	3.5	1.9	2.2

GEOGRAPHIC DISTRIBUTION.—Uncertain.

NOTES.—This species has been known for ten years in American gardens as *N. gracilis*. An examination of Zuccarini's types shows this name to be mistaken, while the plants agree well with the types of *N. flavo-virens* both of Lehmann and Hooker. Concerning its original home there is some doubt. Lehmann's type in hb. Kew is marked "Hort. Bot. Hamburg 1864, ex hb. Reichenbach fil." The plant figured in the Botanical Magazine was grown at Kew from stock received in 1892 from W. N. Pike, Floral Park, N. Y., under the name of *N. mexicana*. The present stock in American gardens was collected by Mr. C. G. Pringle and introduced by Mr. E. D. Sturtevant, then of Bordentown, N. J., previous to 1894 (G. & F. 1894 b). Of Mr. Pringle's *Plantae Mexicanae*, No. 3891 is labeled "*Nymphaea gracilis* Zucc.," and agrees well with the types. Concerning the herbarium specimens and the living plants, however, Mr. Pringle writes as follows under date of September 18, 1904 (received while the present chapter was in press): "No. 3891 of my *Plantae Mexicanae* was collected in an artificial pond near the station of El Castillo some fifteen miles east of Guadalajara; and from the same station I gathered, at the end of the season, when they were lying dry on the surface of the soil and resembling pine cones (the water of the pond had then been drawn off) the tubers which I suppose were supplied to Dr. Sturtevant through my associate, Mr. F. H. Horsford, of Charlotte, Vermont. I am sure of these facts." In G. & F. 3:415 (1890) Mr. Pringle writes: "*Nymphaea gracilis* I only know in the region drained by the Lerma, yet this is a wide region, extending from Aguas Calientes and San Luis Potosi on the north to near the City of Mexico on the east and south and to beyond Guadalajara on the west." Is *N. flavo-virens* Lehm. merely a cultivated form of *N. gracilis* Zucc. (= *N. ampla* DC.)?

This is a robust species, and very resistant in the resting state. It hybridizes very readily with pollen of *N. sansibariensis*, from which cross beautiful garden varieties have arisen and been named in several places, e. g. *N. Astraea*, *N. Greyae*, *N. maurii*, *N. Wm. Stone*, *N. Mrs. C. W. Ward*, *N. gracilis asurea*, *N. g. purpurea*, *N. g. rosea perfecta*, *N. g. rubra*.

Nymphaea stellata Willdenow.

Leaves elliptic-orbicular, rather broadly peltate; margin irregularly *sinuate*; lobes obtuse; upper surface green; pink or *blue-violet beneath*. Flower 5 to 12 cm. across, pale blue (varying to pink or white), open from 8 a. m. to 2 p. m. Buds ovate; sepals with minute blackish dots. Petals 11 to 14, dull white at base; stamens 33 to 54; appendage blue, anthers and filaments pale yellowish.

Nymphaea stellata, Willdenow 1797. Andrews tab. 330. Aiton 1811. DeCandolle 1821 *b*, 1824. Wight & Arnott 1834. Planchon 1853 *b*. Rev. Hort., 1854 *a*, 1855 *b*, col. plate. Caspary 1865 in part; 1877. Conard 1901 *a*.

Castalia stellaris, Salisbury 1806 *a*.

N. malabarica, Poiret, in Lamarck 1802, *fid.* original specimen coll. Sonnerat, Isle de France, from hb. Lamarck, in hb. Paris.

N. stellata var. *parviflora*, Hooker & Thomson, 1855.

DESCRIPTION.—*Flowers* small, 5 to 13 cm. across, open on three successive days from 8 a. m. to 2 p. m., nearly odorless.—*Bud* oblong, ovate, rounded at apex.—*Peduncle* terete, slender, rising well above the water-surface.—*Sepals* 4, oblong, subovate-triangular, breadth: length = 1:2.8 to 3.5, margins nearly straight toward the apex; outer surface light green, uniform or marked with minute dark purplish lines; inner surface bluish-white.—*Petals* 10 to 16, lanceolate, acute, shorter than the sepals, pale blue above, yellowish-white at base.—*Stamens* 33 to 54, with small blue appendage; anthers and filaments pale yellow.—*Carpels* 10 to 17; styles short-triangular, usually apiculate, obtuse; breadth: length = 1:1 to 1.5; stigmatic ray terminating on the style in a short obtuse triangle, breadth: length = 1:0.5 to 0.7. Stigma slightly concave.—*Seed* elliptic globose, diameter: length = 0.8:0.9 mm.; = 0.8:1.0 mm., gray.

Leaf of adult plant rather broadly peltate; breadth of pelta: depth of sinus = 1:6 to 10; outline sub-orbicular-elliptic, 12 to 15 cm. in diameter, irregularly sinuate-repand, or subentire, rounded or slightly retuse at apex; upper surface bright green, sometimes faintly brownish blotched; under surface purplish to deep blue-violet, with green veins. Primary veins 9 to 11 on each side of leaf; length of principal area: radius of leaf = 1:1.4 to 1.6.—*Sinus* deep, usually open; margins nearly straight; angles slightly produced, acute or obtuse.—*Rhizome* ovoid.

GEOGRAPHIC DISTRIBUTION.—Southern and southeastern Asia and neighboring islands, Java, Borneo, and the Philippines. Malabar, Tanjore in India (Hainan, coll. C. M. & A. Henry, No. 8382).

Var. *cyanea* (Roxburgh) Hooker & Thomson.

Flowers of medium size, blue, with faint odor of none.

Nymphaea cyanea, Roxburgh 1824. Wight & Arnott 1834.


N. stellata β , Sims 1819. Planchon 1853 *b*.

Var. *versicolor* (Roxburgh) Hooker & Thomson. (Plate VII.)

Flowers of medium size, pink; stamens numerous. Leaves sinuate, pink beneath, marked above and below with pustules 1 to 2 mm. in diameter.

Nymphaea versicolor, Roxburgh, in Sims 1809. Roxburgh 1814, 1824. Planchon 1853 *b*.

N. punctata, Edgeworth 1845 = *N. Edgeworthii* Lehmann 1852 *b*, *fid.* original specimen, coll. M. P. Edgeworth, 1844, Sadhaura, India, in hb. Kew. Not *N. punctata* Kar. & Kir. 1841?



NYMPHAEA STELLATA VERSICOLOR.

a. Sepal. *b-c.* Petals of successive whorls. *f.* Stamens of closed flower. *g.* Closed flower.

- N. rhodantha*, Lehmann 1853 *a*, *fid.* specimen coll. Cumming, No. 702, "in insulis Philippin.," from hb. Lehm. marked in the handwriting of Lehmann, in hb. Berlin.
N. Hookeriana, Lehmann 1853 *a*, *fid.* original specimen marked in handwriting of Lehmann, coll. Hooker & Thomson, Dec. 19, 1850, at Noapolly, Bengal, from hb. Lehm. in hbb. Berlin, Kew.
N. bella, Lehmann 1853 *a*, as to the flower; leaf is of *N. pubescens*, *fid.* original specimen from hb. Lehm. in hb. Berlin.

NOTES.—Hooker & Thomson record, and the herbaria bear them out, that no sharp line could be drawn between the varieties of this species as it occurs in India, but they were certainly wrong in including the African plants. The three extreme Indian forms are themselves fairly recognizable. The margin of the leaf may be almost entire. The pustules so evident on the leaf of our *N. versicolor* cultivated from seeds sent by Mr. Gollan of Saharanpur, India, may be present at times in the other varieties. Our plant also had a great number of bulbils on the caudex, as shown in several herbarium specimens both of blue and pink forms.

Willdenow's description was based solely on the figure and text of Van Rheede's *Flora Malabarica* 11: 53, tab. 27, and was very brief: "*N. foliis integerrimis, lobis divaricatis, acutis, calyce tetraphyllo petalis acutis longiore.*" Andrews figured the plant in color and later Sims gave a rather larger form than that of Andrews. Planchon figures a plant evidently identical with that of Andrews and Van Rheede, and Caspary (1877) places its description clearly in parallel columns with the allied forms *N. caerulea*, *capensis*, and *sansibariensis*. Of these it comes much nearest to *N. caerulea*, but is plainly distinct. I have been unable to find it in American gardens.

The flowers of this species, according to Caspary (1877), are regularly self-pollinated, often while still in the bud; it refused to cross with *N. caerulea* under Caspary's management.

Rose-colored and white varieties of *N. stellata* sent from Canara to Caspary by the missionary Zeigler in 1869 were long cultivated in the botanic garden at Königsberg.

Nymphaea caerulea Savigny. (Plate VIII; Fig. 55.)

Leaves *entire* or slightly wavy at base, orbicular or ovate-orbicular, narrowly peltate, becoming 30 to 40 cm. in diameter; green above; under surface *green* with small dark purple *spots*, purplish all round near margin. Flowers 7 to 15 cm. across, open from 7.30 a. m. to 12 m. Buds conical. Sepals thickly *marked with black lines and dots*. Petals 14 to 20, lanceolate, light blue above, lower half dull white. Stamens 50 to 73; appendage long (0.5 cm. on outermost stamens), slender, pale blue.

Nymphaea caerulea, Savigny 1802, *fid.* original specimens coll. Delile, 1798, near Cairo. Ventenat 1803. Delile 1813. DeCandolle 1821 *b*. Planchon 1851 *a*, 1853 *b*. Caspary 1877. Wildeman & Dur. 1900. Conard 1901 *a*.

N. stellata, Caspary 1865 in part, 1873. Boissier 1867, 1888. Oliver 1868; and of many authors and collectors. *Not* Willdenow 1797.

N. maculata, Schum. & Thonn. 1829, *fid.* original specimens from Copenhagen, kindly loaned by the curator of the herbarium. Welwitsch ms. in hb. Paris.

N. poecila, Lehmann 1853 *a*, *fid.* original specimens from hb. Lehmann seen in hb. Berlin.

N. scutifolia, Tricker 1897. *Not Castalia scutifolia*, Salisbury 1806 *a*.

N. discolor, Lehmann 1853 *a* = *N. caerulea*, Kotschy MS. (see note).

Castalia stellaris, Salisbury 1806 *b* (in part).

C. caerulea, Tratinick 1822.

DESCRIPTION.—*Flowers* 7 to 17 cm. across, light blue, with a faint and characteristic sweet odor, open on 3 days from 7.30 a. m. to 12 m. (4 days, 8 a. m. to 2 p. m. Casp. 1877).—*Bud* distinctly conical, with straight sides, obtuse, abruptly contracted below to the receptacle, 7 cm. long by 2.5 cm. in diameter at base.—*Receptacle* nearly three times as wide as peduncle, spreading out at about 45° from the vertical, pale purplish green.—*Peduncle* terete, 0.6 to 0.8 cm. in diameter, 18 to 38 cm. long, most slender about 1.25 cm. below flower, smooth, dull brownish-green; main air-canals 6, surrounded by a circle of 12 smaller ones.—*Sepals* 4, broadly lanceolate, breadth: length = 1:2.8 to 4.7, the sides nearly straight in upper two-thirds, somewhat converging below to the broad base; apex rounded. Outer surface dark green, thickly flecked with purplish-black dots and lines most dense near margins of sepal and midway of length; the green ground-color assumes a yellowish tint near base of sepal. Seven




FIG. 55.—*Nymphaea caerulea*: a, closed flower; b, sepal; c, d, e, outer, median, and inner petals; f, h, stamens; g, carpellary style viewed en face; i, vertical section of ovary; k, vertical section of fruit. Reduced about one-half.

longitudinal veins can be seen by looking through the sepal at the light. Inner surface dull white, tinged blue on midline near apex, greenish and veiny and semi-translucent in lowest three-quarters of length.—*Petals* 12 to 20, of moderately firm texture, opening about 30° above horizontal, about as long as the sepals. They stand in 3 series: first, a whorl of 4, alternate with the sepals; second, a whorl of 8, one on each side of each outer petal; third, a whorl of 8 alternate with the second, but usually imperfect, consisting of only 2 to 5 petals on one side of the flower, rendering it so far unsymmetrical. Outermost petal narrowly elliptic-lanceolate, obtuse, with rather broad insertion (0.8 cm. in Flower No. 3, see table of measurements), not at all concave; outer surface colored on lower half and on the midline dark green with black spots exactly like the sepals; one-third of width at margin on each side, above, colored pale blue; inner surface white on lower half, becoming translucent and 7-veined at base, shading above to a pale sky-blue at apex and on upper margins. Petals of second whorl shorter than those of the first, rhombic-lanceolate, narrowed at apex and base, 5-veined



NYMPHÆA CŒRULEA.

below, white on the lower third, pale blue above, pure sky-blue at apex, the blue and white shading together insensibly, the latter predominating in two-thirds of length on inner surface of petal. Petal of third (innermost) whorl linear-lanceolate, obtuse, blue at apex; outer surface with white margins in lower three-fourths of length, the blue continuing half way down the midline; on inner surface, white prevails on lower five-sevenths of length.—*Stamens* 50 to 73, sometimes appearing inserted without order, sometimes indistinctly spiral, often in about 16 vertical ranks of 3 to 5 stamens each. Outermost stamens with short and rather broad filaments and long acuminate anther with two long, nearly parallel anther cells and proportionately long, acute, 3-angled appendage, one angle pointing inward; blue at tip and half-way down, yellowish-white below. Median stamen has short, broadly elliptic filament, very long parallel anther cells, and short appendage; anther and filament bright yellow, only the appendage blue. Innermost stamen bright yellow all over, short, stout; anther broader and longer than filament; no appendage.—*Ovary* nearly hemispherical (e. g., 1.9 cm. in diameter by 0.95 cm. high; 0.4 cm. by 0.24 cm.).—*Carpels* 14 to 21; styles short (0.3 cm. long by 0.08 cm. in diameter), fleshy, nearly erect, subacute, concave inward, all alike, pure yellow, papillose up to about 0.08 cm. from apex, the papillose area ending roundly. Stigma nearly flat, bending upward on the styles, yellow. Axile process rising abruptly from the stigma, broader than high (height : breadth = 1 : 1.5; = 0.24 cm. : 0.38 cm.) and somewhat conical in shape, with obtuse tip, of a whitish color.—*Fruit* large, round (4.5 to 6.4 cm. in diameter by 2.5 to 3.8 cm. high), truncate above, with deep radiating fissures between the carpels, flattened or even excavated beneath around the peduncle, of a pale green color, becoming translucent and brownish, crowned with the hard, slightly enlarged styles, and surrounded by the sepals and outer 4 petals, all of which are dark green and spotted as in the flower. The peduncle makes a large, rude spiral turn, holding the fruit still erect but with its base nearly or quite resting on the earth.—*Seed* ellipsoidal, acuminate at the hilum, 0.17 cm. long by 0.12 cm. in diameter, dull olive brown; surface marked with about 14 interrupted longitudinal lines of minute hairs; raphe evident, not prominent. Aril longer than the seed.

Germination may take place immediately on ripening, or the seeds will withstand drying over winter. *First leaf of seedling* filiform, 1.6 to 1.9 cm. long. *Second leaf* broadly elliptic on a petiole about 2.5 cm. long; blade about 1.27 cm. long by 0.6 cm. wide. *Third leaf* broader and shorter. *Fourth leaf* deltoid-ovate with rounded angles and apex, and truncate base; lamina 1.6 cm. long by 1.27 cm. wide at base; later leaves finally deltoid-cordate, with rounded apex and angles, and rather deep sinus. *First floating leaves* nearly orbicular, 2.5 to 3.8 cm. in diameter, entire; sinus deep with straight and touching margins; under surface marked with irregular blackish spots.

First leaves from tuber submerged, 2 or 3 on each shoot; the first one may have a minutely denticulate margin, 1 cm. long by 0.3 cm. wide; or, more commonly, the lamina is entire, broadly deltoid, 3.2 cm. long by 3.2 cm. wide at base, with rounded angles, and petiole 2.5 to 3.8 cm. long. A third one may be produced, of oval shape, finally cordate, with deep open sinus and rounded apex, 3.8 cm. long by 2.9 cm. wide. *First floating leaves from tuber* like those of seedling, but larger; perfectly entire.

Leaf of mature plant very narrowly peltate (1:14 to 16, Casp. 1877), ovate-orbicular to orbicular, 30 to 40 cm. in diameter (33 cm. long by 30.6 cm. wide), soft,

thin and quickly withering, slightly wavy or sinuate in the basal half, apex slightly emarginate, dark green and obscurely veiny above, color darker over insertion of petiole. Under surface paler green, with numerous small dark purple blotches, which are larger near the midrib than at the periphery; margins purplish, shading from dark red-purple at the extreme edge to green, the transition taking place in the course of about 1 cm. near sinus angles, in about 2.5 cm. at apex of leaf. Veins prominent out to the fifth grade; primary nerves 6 to 10 on each side of leaf. Petiole attached by quite a strong "collar." Length of principal area: radius of leaf = 1:1.3 to 1.7.—*Sinus* usually closed; depth: length of leaf = 1:2.7 (= 13.5 cm.: 35.7 cm.); margins doubly curved, convex and overlapping above, separating about 2.5 cm. from periphery of leaf and becoming parallel; angles subacute, slightly produced, about 0.6 cm. apart.—*Petiole* terete, or flattened near the leaf, about 0.6 cm. in diameter, dull brownish-green; with 2 larger upper air-canals, and 2 smaller ones below, and a ring of 12 still smaller ones outside.—*Stipules* smooth, fused at base, short, distant above, acuminate, very acute; 1.9 to 2.2 cm. long, 1.3 cm. wide at base; free portion 1.1 to 1.6 cm. long, 0.5 cm. wide; tips 0.9 to 1.2 cm. apart.

Rhizome (tuber) erect, thick, ovoid, 2.5 to 7.5 cm. long by 2 to 6.4 cm. in diameter, blackish, apex protected by leaf-bases and long fine hairs. Phyllotaxy of a very high order, the leaf-bases completely covering the larger rhizomes, leaving only about 0.3 cm. around each one. Roots springing from the bases of the petioles. Offsets formed only when the tuber breaks out from the dried state; 2 or 3 shoots may come from one tuber; the stolon is terminal, very short, the point of origin of new leaves remaining within the coating of long hairs.

	Number of Floral Organs.							Ideal.	Average.
Sepals.....	4	4	4	4	4	4	4	4	4
Petals.....	17	14	16	20	16	16	14	20	16+
Stamens.....	61	50	58	57	69	73	52	64	60
Carpels.....	17	15	16	20	17	21	15	16	17+
Totals.....	99	83	94	101	104	114	85	104	97+

MEASUREMENTS OF SEFALS.

Flower.	Length.	Breadth.
	cm.	cm.
Flower 1.....	6.8	1.9
Flower 2.....	6.2	1.75
Flower 3.....	7.0	1.9
Flower 4.....	8.6	2.6
	8.8	2.9
	8.8	2.7

MEASUREMENTS OF PETALS (IN CENTIMETERS).

Flower 1.		Flower 2.		Flower 4.						Flower 5.	
				Outermost Whorl.		Second Whorl.		Innermost (Imperfect) Whorl.			
Length.	Breadth.	Length.	Breadth.	Length.	Breadth.	Length.	Breadth.	Length.	Breadth.	Length.	Breadth.
6.7	1.4	6.5	<i>o</i> 1.4	8.45	2.0	7.8	2.9	7.3	1.75	5.9	<i>o</i> 1.4
6.4	1.35	6.3	<i>m</i> 1.3	8.45	1.8	8.0	2.8	7.3	1.5	5.6	<i>m</i> 1.4
6.2	1.2			8.3	<i>i</i> 2.0	8.0	2.8	7.2	1.75	5.4	<i>m</i> 1.1
5.7	0.8			8.45	1.9	7.8	2.8	7.0	1.3	5.26	<i>i</i> 0.8
5.6	0.7					7.65	2.0			4.95	<i>i</i> 0.7
						7.65	2.0				
						7.65	2.0				
						7.65	1.9				

i = inner. *m* = median. *o* = outer.

MEASUREMENTS OF STAMENS (IN CENTIMETERS).

Flower.	Total Length.	Breadth of Filament.	Length of Anther Cells.	Breadth of Anther.	Length of Appendage.
Flower 1.	3.75	0.56	1.6	0.32	0.5
	2.7	0.4	1.6	0.24	0.3
	1.4	0.16	0.8	0.16	0.08
	0.88	0.13	0.48	0.16	0
Flower 3.	3.7	0.56	1.6	0.32	0.56
	2.7	0.48	1.6	0.24	0.24
	0.88	0.13	0.48	0.16	0
	3.5	0.48	1.6	0.32	0.48
Flower 5. ...	2.1	0.32	1.42	0.24	0.16
	1.12	0.16	0.72	0.21	0.04

GEOGRAPHIC DISTRIBUTION.—Northern and Central Africa. Cairo, Savigny 1802. Damietta and Rosetta, coll. Schweinfurth. Guinea, Schum. & Thonn. Nubia, Kotschy (see note). Sona Gungu (Distr. of Cataracts), Congo, Wild. & Dur., 1900. Angola, Welwitsch. Omkenen, Kordofan, coll. Dr. Hendur, No. 890, in hb. Berlin. Cyrenaica, coll. M. Pacho, 1826, in hb. Paris.

Var. *albiflora*, Caspary.

Flowers white; sepals without black spots.

Nymphaea caerulea var. *albiflora*, Caspary 1877.

N. abbreviata, Guill. & Perr. 1830.

N. ampla, Kotschy MS. = *N. nubica*, Lehmann (see Note). Not *N. ampla*, DC. 1821 b.

GEOGRAPHIC DISTRIBUTION.—With the type. Rare. Damietta, Egypt, coll. Sieber, *fid.* Caspary 1877. Egypt, coll. Schweinfurth, 1885, in hb. British Museum. Central Africa, coll. Schweinfurth, No. 2329, in hb. Berlin. Kounoun, Cape Verde, coll. Perrottet, 1831, in hb. Delessert.

NOTE.—The name of this species has had a varied application, as is shown by the synonymy of this and the preceding and following plants. The cause lies partly in

the close resemblance of *N. caerulea* and *N. stellata*, and partly in the fact that these and *N. capensis* were introduced into cultivation near the same time, and the descriptive character of the name *caerulea* made it equally applicable to all. The geographical proximity of this and *N. capensis* may have added to the confusion. Indeed, examination of herbarium material shows that *N. caerulea* is connected by intermediate forms with *N. micrantha* on the west and *N. capensis* on the south. We have not been able to secure living material of *N. micrantha*, but the *capensis* type is very easily distinguished from the present species. Their hybrid (*N. pulcherrima* Tricker) is entirely sterile. Other related forms are discussed in their proper places. Many botanists have included all the blue waterlilies of Africa and Asia under the name of *N. stellata*, as did Hooker & Thoms. (1855); Caspary, ten years later, separated off *N. capensis*, and in 1877 gave exact descriptions of four species in parallel columns; he stated that his old arrangement (1865) needed complete revision, but unfortunately this work was left undone.

The Kotschy collection from Nubia has long been a stumbling block to students of Nymphaea. They are marked No. 166 *N. caerulea* Sav. and No. 167 *N. ampla* DC.—“Kotschyi Iter Nubicum. In stagnibus pluvialibus ad radices eurentas montis Cordofani, Arasch Cool, Jan. 5, 1841, d. Oct. 12, 1839.” The first is represented in hbb. Kew, Paris, Boiss., Deless., and Berlin. It was marked by Caspary “*N. capensis* Thunb.” The Boissier specimen has narrower petals and fewer stamens than the type of *capensis*; the Berlin specimens differ between themselves—one flower has spotted sepals, and the leaf gently sinuate; another has leaves typical of *N. caerulea* but no spots on the sepal. No. 167 was marked “*N. caerulea* Sav.” by Caspary in hb. Boiss., with the addition of “var. *albida*” in hb. Paris. The leaf is gently sinuate in the Kew, Delessert, and one Paris specimen. It is also represented in hbb. Berlin and Boissier. The leaf may or may not have black spots and some purple coloration beneath. The flower resembles that of *N. caerulea*, but was evidently white, and in the Kew specimen, at least, the outer stamen is provided with an unusually long, lanceolate appendage. The two plants seem strikingly intermediate between *N. capensis* and *N. caerulea*. No. 167 is the type of Lehmann’s *N. nubica*.

Self-fertilization occurs regularly in this species.

Reference to the importance of *N. caerulea* as the Blue Lotus, the lotus *par excellence* of Egypt, has been made in Chapter I.

Nymphaea micrantha Guillemain & Perrottet. (Plate IX.)

Leaves small, round-cordate, peltate, entire, petiolate; petioles very long, slender; lobes divaricate, acuminate; under surface reddish, marked with violet-black dots; upper surface glabrous, pale green, in mature plants bulbiferous at the summit of the petiole; stigmatic rays 15.

N. micrantha, Guillemain & Perrottet 1830. Hooker 1850. Paxton 1853 a.

N. caerulea, Guillemain & Perrottet 1830. Not Savigny 1802.

N. caerulea var. *albida*, Guillemain & Perrottet 1830 = *N. micrantha*, Hook.

N. rufescens, Guillemain & Perrottet 1830.

N. stellata var. *bulbillifera*, Planchon 1852 c. Not *N. stellata*, Willdenow 1797.

N. vivipara, Lehmann 1852 a, b, 1853 a, 1854.

N. guineensis, Schumacher & Thonning 1829, *fid.* Chifflet 1902.



NYMPHAEA MICRANTHA.

Under side of leaf; 2, Upper side with young plant developing; 3, Caudex, with a branch, surface of a caudex, enlarged; 5, Cross section of a caudex; 6, Longitudinal section of a caudex; 7, Superficial tangential section through leaf cushions of fig. 4; *h*, base of a petiole; *f*, base of a peduncle; 8, Section a little deeper than 7, 9, same as 8, a little deeper.

DESCRIPTION.—*Sepals* 5, narrow, lanceolate, acuminate, with violet dots.—*Petals* 10, 1.3 to 5 cm. long, a little shorter than the sepals, lanceolate, narrow, blue to white.—*Stamens* numerous; filaments whitish, narrow at base; anthers of various lengths, twice as long as the filaments; appendage short, conic-terete.—*Ovary* round. Seeds very numerous, very small, blackish.—*Leaves* 7.6 cm. long, 5.1 cm. wide (in the type).—*Rhizomes* clustered, with soft tawny wool around the bases of the petioles; roots very long.

GEOGRAPHIC DISTRIBUTION.—West Coast of Africa. In swamps of the peninsula of Cape Verde, near n'Batal; in the Galam region; in the kingdom of Cayor, etc. Flowers almost all the year.

TYPES.—Coll. Perrottet, 1830, in hbb. Delessert, Kew, DeCandolle. Also coll. E. Holub, Eastern Bamangwato territory, Bechuanaland.

NOTES.—The most striking difference between this and *N. caerulea* Sav. lies in the viviparous habit. Chiffot (1902) states, and Planchon's description indicates, that this character does not appear until the second year of the plant's growth. The first year it has nearly white flowers, and corresponds to *N. guineensis* Sch. & Th.; the second year bulbils appear, but the flowers are small and pale, and the plant corresponds to *N. micrantha* Guill. & Perr. Only in the third year, according to Chiffot, does the plant acquire its definite morphological characters.

We do not find either in the specimens or descriptions of Guillemin & Perrottet any important differences between the several viviparous forms they enumerate. *N. rufescens* is a larger plant; sepal 7.6 cm. long, petals 18 to 20, stamens very numerous with petaloid filament; carpels 18 to 20; leaves 12 to 25 cm. in diameter, more or less spotted beneath, primary veins 12 to 20, prominent; coll. Perrottet, 1830, Senegal, seen in hbb. Delessert, Boissier, DeCandolle; also coll. Roger, Dec., 1823, Senegambia, in hb. Kew (with the note "Les graines servent de nourriture aux nègres"); also coll. Buchholz, Eliva Sonanga, Cape Lopez, West Africa, in hb. Berlin. *N. caerulea* Guill. & Perr. has "leaves strongly peltate, impunctate, red beneath, lobes long, free, acute"; types coll. Perrottet, 1831, Senegal, in hbb. Delessert, Kew; also coll. Leprieur, Sept., 1821, "in paludosis prope Ngalete, regio Cago, Senegambia," in hb. Delessert; also coll. C. Barter, Baikie's Niger Expedition, No. 7064, 1858, at Nupe, in hb. Paris. *N. caerulea* var. *albida* Guill. & Perr. has larger flowers than the type, with narrow lanceolate petals, nearly white; types coll. Perrottet, Walo, Senegambia, in hb. Delessert; also coll. Leprieur, in same district in hb. Delessert. This is apparently identical with *N. micrantha* Hook. Caspary's "*N. micrantha* Hook." (notes and herbarium, now in hb. Berlin) has an orbicular leaf with wide sinus and obtuse lobes, with or without black spots beneath; petals ovate, white, 3.8 to 4.5 cm. long. This plant was much used by Caspary in hybridization, giving well-marked intermediates with the closely allied *N. caerulea* Sav. (seen in hbb. Kew, British Museum, Berlin).

Nymphaea heudelotii Planchon. (Fig. 56.)

Flowers small, 2.8 to 5.1 cm. in diameter. Sepals lance-ovate, with black spots outside. Petals 5 to 10, lanceolate, acute, bluish-white. Stamens 11 to 16; anthers much longer than the filaments. Carpels 4 to 10. Leaves almost or quite entire, ovate

or orbicular, cleft nearly to the petiole, 2.5 to 8.2 cm. long, reddish beneath, with black specks. Seed smooth.

N. Heudelotii, Planchon 1853 *b*, according to the original specimen.

N. pseudo-pygmaea, Lehmann 1853 *a*, according to the original specimen in hb. Kew, which consists of a submerged leaf, with flower and fruit, much dilapidated, coll. Heudelot and communicated by hb. Paris.

DESCRIPTION.—Planchon gives the following: Dwarf, glabrous; floating leaves cordate-suborbiculate, very narrowly peltate, with the sinus narrow and nearly closed




FIG. 56.—*Nymphaea heudelotii*: (a), (b), leaves; (c), flower; 1, 2, 3, 4, sepals. From a drawing of the types in the notes of R. Caspary, now in hb. Berlin, by kind permission of the Directors. Natural size.

(in the membranous submerged leaves wide open); margin slightly repand; under surface purplish, violet spotted. Flowers small; sepals ovate at base, becoming rather long attenuate, with violet lines outside; petals 5 to 8, bluish, appendiculate, anthers five to six times longer than the rather broader filaments; rays of the stigma 8 to 10, short, triangular, acute. Fruit globose, shorter than the calyx; seed elliptic-globose, smooth (not costate).

GEOGRAPHIC DISTRIBUTION.—Senegambia, in shallow flowing streams; Fouta Dhiallon.

TYPES.—Coll. Heudelot, No. 844, in 1837, seen in hbb. Delessert, Berlin, and Kew. In hb. Kew I saw another specimen consisting of a half-closed flower and two frag-

mentary leaves, coll. Sierra Leone Boundary Commission, Dec. 22, 1891, in "small streams, Luseniga, Samu." In hb. Berlin is a specimen, coll. Alex. V. Mechow's Exped., No. 480, Jan., 1880, at Malange, West Africa, marked *N. stellata*; also coll. Pogge, No. 559, Jan. 2, "auf der Ueberschwemmung ausgesetzten Stellen am Lulua," and No. 558, Nov. 21, 1881, "Wassertümpel in der Campine am Lulua"; also. coll. Schweinfurth, No. 2329, Oct. 30, 1869, "Land der Djue: Gr. Scriba Ghattes in der Sumpfsteppe im Wasser; Bl. reinweiss."

Var. *nana* new var. (Fig. 57.)

Sepals 4, lanceolate, obtuse, 1.2 to 2 cm. long by about 0.32 cm. wide, green outside, with small and distinct or large and diffuse black spots; nearly white within. Petals 7 to 10, lanceolate, acute, shorter than the sepals, 1.5 to 1.7 cm. long, 4 mm. wide, white. Stamens 11 to 14, yellow, with very short appendage, all nearly alike and about half as long as the petals, apparently in two series. Stigma of 5 to 6 broad carpels, with short, broad styles. Fruit nearly globose, surrounded by all of the floral parts. Seed gray-green, ellipsoid, 1.3 mm. long, 0.88 mm. in diameter.




FIG. 57.—*Nymphaea heudelotii nana*: a, open flower, 1, 2, 3, 4, sepals; b, under side of leaf; c, flower pressed on one side showing outside of sepals; d, stamen: twice natural size. Drawn by J. Pohl from specimens of Baum's No. 655 in hb. Berlin, by kind permission of the directors.

Leaves orbicular, 2 to 3.1 cm. in diameter; pelta 1 mm.; entire, green above, red beneath, with black specks, somewhat coriaceous; primary veins 5 to 6, depressed; length of principal area: length of radius = 3:4; sinus margins straight, diverging, lobes rounded.

Plant glabrous throughout; petioles and peduncles very slender, 15 to 36 cm. long. Caudex an ovoid or globose tuber.

N. Guineensis, Gilg 1903. Baum 1902. Not Sch. & Th. 1829.

DISTRIBUTION AND TYPES.—Coll. H. Baum, No. 655, Jan. 17, 1900, Kunene-Zambesi Expedition, "am linken Longa-Ufer bei Minnesera, 1250 m. ü. M., in flachen sumpfigen Gräben, selten." "Eine Miniatur-Nymphaea mit weissen wohlriechenden, höchstens die Grösse eines Markstückes erreichenden Blüten." Seen in hbb. Berlin, Delessert, British Museum, Kew, Munich.

NOTES.—On comparing Mr. Baum's specimens with the originals of *N. guineensis* Schumacher & Thonning, kindly sent to me at Berlin by the directors of the Museum of Copenhagen, Professor Gilg fully agreed that his former identification of the two was mistaken. Whether the Baum specimens should have specific rank must remain at present a matter of opinion; they are the most divergent forms yet known of a series of African waterlilies leading by slight gradations up to *N. caerulea* Sav. No

one could doubt that the two extremes are specifically distinct. The Mechow specimen, No. 480 cited above, differs from Baum's No. 655 in having larger flowers (5 cm. in diameter), sepals 1.7 to 2.8 cm. long, stamens two-thirds as long as the petals, leaves 3.8 to 4.5 cm. across, with big blotches of brown above; length of principal area: length of radius = 2:3. Pogge's No. 559 has the flower like Baum's 655, the leaf 2 cm. across, blotched brown above, dull dark green beneath. Schweinfurth's No. 2329 has blotched leaves 5 cm. across, flower 5 cm. in diameter, stamens 25, a little more than half as long as the petals. Pogge's 558 has leaves 5.7 to 7.6 cm. across, and sepal 3.2 cm. long (poor specimen). Next to this come Planchon's types of *N. heudelotii*. On the other hand, *N. micrantha* Guill. & Perr. seems to differ from *N. heudelotii* Planch. chiefly in being viviparous.




FIG. 58.—*Nymphaea ovalifolia*: leaf and flower. Under side of leaf on right, showing veins. Upper side of leaf on left, with blotches shaded in on lower half; folded over at margin. One-half natural size. From a tracing of the original specimen of Böhm, in hb. Berlin.

Nymphaea ovalifolia new sp. (Fig. 58.)

Leaf narrowly elliptic, 25 cm. long by 14.7 cm. wide, with large irregular brown blotches above; sinus 10 cm. deep, sides nearly parallel, lobes acute, pelta 0.3 cm. wide. Primary veins about 6; principal area 2.5 cm. wide by 5.7 cm. long. Under surface plain green.

Flowers deep blue ("himmelblau"), closed in dull weather. Sepals and petals acuminate, without dark spots; sepal 4 cm. long by 1.3 cm. wide.

DISTRIBUTION AND TYPES.—Coll. C. Böhm, No. 92, March, 1882, Deutsche Expedition nach Ost-Afrika, in the Wala River, Ugally, in hb. Berlin. With this may be classed a specimen, coll. F. Stuhlmann, No. 481, July 27, 1890, Expedition Emin Pasha, at Palla Bay, marked "*N. stellata* var. *alba*," in hb. Berlin.

NOTE.—Although a single imperfect specimen affords but a feeble foundation for a species, the peculiarities of this one require us to give it separate consideration. A name therefore seems necessary.




FIG. 59.—*Nymphaea calliantha*: Flower and under side of leaf, reduced three-sevenths. Outer stamen, enlarged one-seventh. Drawn by J. Pohl, from Baum's No. 806 in hb. Berlin.

Nymphaea calliantha Conard. (Fig. 59.)

Flowers 10 to 15 cm. in diameter, pink, violet purple, or light blue; sepals green outside, with black spots near the margin, lanceolate. Leaf entire, ovate-orbicular, cleft nearly to the petiole, purplish to deep royal purple beneath.

N. caerulea, Gilg 1903. *Not* Savigny 1802.

N. calliantha, Conard 1903.

DESCRIPTION.—*Sepals* 4, lanceolate, 7 cm. long by 1.7 cm. wide, acute, outer surface dull green with a few black spots near the margin, covered margins tinted red; inner surface bright rose pink on upper 1.5 to 2 cm., shading to white below.—*Petals*

17, lanceolate; outer one 1.7 cm. wide, sepaloid on back, its margins petaloid; whitish below, shading pink in upper two-thirds, to decided rose pink in uppermost 1 cm.; inner surface white in lower three-fourths, becoming rose pink at apex, and on margins for 1 to 2 cm. below apex; inner petals white.—*Stamens* about 100, yellow; outermost stamen has filament 4 mm. wide, 8 mm. long, anther 2.5 mm. wide at base, 19 mm. long, appendage 6 mm. long, 1 mm. wide at base, subacute.—*Stigma?*—*Fruit?*—*Leaf* ovate-orbicular, entire, 13 to 28 cm. long by 9 to 23 cm. wide, pelta 0.5 cm., green above. Under surface purplish on margin, shading to green in the space of 3 to 4 cm., spotless. Primary veins 8 on each side, length of principal area: radius = 7.7 cm.: 10.2 cm.

GEOGRAPHIC DISTRIBUTION.—Central and Southwest Africa.

TYPES.—Coll. H. Baum, Reise nach Süd-West Afrika, Kunene-Zambesi Expedition, No. 395, Nov. 9, 1899, "am Kubango unterh. der Kueio, 1120 m. ü. M." Native name "Amavu." In hbb. Delessert, Berlin, British Museum. Gilg (1903) adds, evidently quoting Baum, "Blüthen weissblau. * * * Blätter sehr dünn." The pink color seen in the herbaria may therefore be due to changes in drying, as some other specimens in this collection had undergone the same change. Professor Gilg also considers Höpfner's No. 36 from Mossamedes (in hb. Berlin) to be identical with Baum's 395. A specimen in hb. Kew, coll. F. D. & E. J. Lugard, Sept., 1896, Botletle River, Ngamiland, Tropical Africa, appears to be the same, as also one, coll. W. P. Johnson, Lake Nyassa, in hb. Kew. Baum's No. 208, Oct. 4, 1899, "an ruhigen Stellen im Okachitanda bei Kassinga, 1290 m. ü. M., am Ufer und in Einbuchtungen des Flusses, auch in der Mundung und in Pfannen hinter Kassinga" (Gilg 1903), has smaller leaf and flower, but more numerous floral organs. Leaf 16 cm. long by 13.5 cm. wide; under surface deep red-purple. Petals 20 to 26, stamens 115 or more. In hbb. Berlin, Delessert, British Museum. No. 396 of Baum, from the same locality as 395, is smaller than the latter, but doubtless of the same species. Flowers rose color; petals 11 to 14, 4 to 4.5 cm. long; stamens more than 50. Leaves very dark purple beneath. In hbb. Delessert, Berlin. Professor Gilg (1903) considers Fischer's No. 4 (in hb. Berlin) from the African lake region between Magu and Kagehi to be identical with the foregoing. We place here also a specimen in hb. Kew, coll. A. Carson, 1891, at Karonga, Nyassa, having flowers 10 cm. across, deep blue; petals elliptic-lanceolate, stamens stout; leaf oval, 14 cm. long by 10 cm. wide, lobes acute, overlapping, margins wavy in lower half, under surface dark red-purple.

Var. *tenuis* Conard.

Leaves nearly orbicular, 7.5 to 10 cm. long by 7 to 8.6 cm. wide, green above, dull dark purple beneath; primary veins 6; length of principal area: radius = 3.2 cm.: 3.8 cm.; sinus lobes slightly diverging or overlapping, obtuse, margins nearly straight.

Flower 9 to 13 cm. across; petals and sepals very narrow (e. g., sepal 5.75 cm. by 1 cm.; petals 5.4 cm. by 0.8 cm., 5.1 cm. by 0.85 cm.). Sepals 4, green outside, with numerous black spots; margin red-purple; inside white. Petals 14 to 17, 3.5 to 5.4 cm. long, white or pale blue, rounded at apex. Stamens 33 or more, slender, yellow, the outermost with filament 3 mm. wide and 1 cm. long, anther 7 mm. long, appendage 7 mm. long; innermost stamen with filament 3 mm. long and 0.8 mm. wide, anther 3 mm. long and 1.3 mm. wide, appendage 1.25 mm. long. Carpels 10.

N. caerulea, Gilg 1903. *Not* Savigny 1802.

N. calliantha var. *tenuis*, Conard 1903.

DISTRIBUTION AND TYPES.—Coll. H. Baum, No. 771, March 10, 1900, "an ruhigen Stellen in der Kuito-Niederung zwischen Kutue und Sobi, 1200 m. ü. M." in hbb. Delessert, Berlin. Professor Gilg unites with this form Pogge's No. 560 from the "Baschilangebiet" and Buchner's No. 88 from the "Malangebiet"; I prefer to class No. 88 with *N. heudelotii*, but I have no notes on Pogge's No. 560. Both are in hb. Berlin.

NOTES.—This species is distinct enough, we believe, from the nearest relative, *N. caerulea*. The color of the under side of the leaf, and the peculiar long narrow area between the two primary veins nearest the sinus, are easily noted characteristics. It should prove a valuable acquisition for the water-garden.

Nymphaea capensis Thunberg. (Plate X; Fig. 60.)

Leaves large, nearly orbicular, deeply *sinuate*; angles produced, acuminate; *green on both sides*. Flowers bright blue, large, open from 7 a. m. to 4 p. m. Buds ovate. Sepals pure green, spotless. Petals 20 to 30, elliptic. Stamens about 150, appendaged.

Nymphaea capensis, Thunberg 1800, *fid.* original specimens, coll. Burmann, No. 491, from hb. Thunb. in hbb. Delessert, DeCandolle. Harvey 1838. Lehmann 1853 *a*. Caspary 1865, 1877. Conard 1901 *a*.

N. caerulea, Andrews, tab. 197. Kerner 1795. Dryander 1801, *fid.* original specimens in hb. British Museum. Aiton 1811. Spach 1846. Tricker 1897, and others. *Not* Savigny 1802.

Castalia scutifolia, Salisbury 1806 *a* and *b*.

N. scutifolia, DeCandolle 1821 *b*, 1824, *fid.* original specimen from hb. Thunb. in hb. DeCandolle. Planchon 1850 *c*, 1853 *b*. Paxton 1853 *c*.

N. cyanea Hort. *fid.* Paxton, l. c.

N. Berneriana, Planchon 1852 *b*; 1853 *a, b*; *fid.* original specimens, coll. Bernier, No. 158, 1835, "Nord de Madagascar," in hbb. Delessert, Paris.

N. Emirnensis, Planchon 1852 *b*; 1853 *a, b*; *fid.* original specimens coll. Bojer, "in ubisque paludosis in provinc. Emirna, insula Madagascar," in hbb. Paris, DeCandolle.

N. Leiboldiana, Lehmann 1853 *a*, as to the African plant, *fid.* specimens from hb. Lehmann in hbb. Kew, Berlin.

N. Petersiana, Klotzsch 1862, *fid.* original specimen, coll. Peters, Feb. 8, 1848, Mozambique, in hb. Berlin.

N. stellata var. *macrantha*, Gilg MS., *fid.* specimens coll. F. Wilms, Flora Africae Australis, No. 10, Dec., 1883, Distr. Middelberg, Transvaal, in hb. Berlin, and No. 13, July, 1884, Distr. Lydenburg, "zwischen Spitzkop und dem Komatiflusse," in hbb. Kew, British Museum, Berlin. *Not* *N. stellata*, Willdenow 1797.

N. stellata of Cape collectors and (in part) of many botanists. *Not* Willdenow 1797.

DESCRIPTION.—*Flower* 15 to 20 cm. across, opening on 4 successive days from 7 a. m. to 4 p. m. (5 days, 7 a. m. to 1 p. m.; 5 a. m. to 3 p. m. Caspary 1877), sweet scented.—*Bud* narrowly ovate, pure green.—*Peduncle* terete, 60 cm. long, rising 22 cm. above water; green; 0.8 to 1.3 cm. in diameter, main air canals 6, surrounded by 12 smaller ones, and these by 24 very small ones.—*Receptacle* yellowish.—*Sepals* 4, narrowly wedge-ovate, breadth: length = 1:2.4 to 4.3, tapering above to a rounded apex, opening to about 30° above horizontal; thick and fleshy in texture; outer surface deep

green toward apex, paler and yellowish in lower third, and on margins; that part of margin which is covered in the bud is white with a bluish tinge; inner surface greenish-white, tinged with blue above, pale green in lower quarter; obscurely many nerved (18 to 19) at base. Persistent in fruit.—*Petals* 21 to 38 (15 to 27, Casp. 1877) of rather thin texture, shorter than the sepals, all plane (i. e., not concave). Outermost petal elliptic-lanceolate, tapering at base, obtuse at apex; outer surface rich sky-blue above, lower third greenish in midline, with nearly white margins; 5-veined; inner surface rich sky-blue above, shading to nearly white in lower third, and then to yellowish at the base. Inner petals successively shorter and narrower, colored like the outermost except-





FIG. 60.—*Nymphaea capensis*: a, sepal; b, outermost petal, hooded at apex; c, median petal; d, innermost petal; e, f, outer and inner stamens; g, vertical section of ovary. Natural size.

ing the green color on the back. Inner 3 series of petals acute; innermost sometimes narrowly long-acuminate, simulating a stamen.—*Stamens* 120 to 225 (82 to 243, Casp. 1877), the outermost about half as long as the petals. Anthers all longer than the filaments; appendages obtusely triangular, long on outer stamens, becoming obsolete only on the innermost. Outer filaments broadly elliptic, much wider (3 times) than anther; inner-median filaments about as wide as the anthers; innermost filaments narrower than the anthers. Appendages always blue, like the petals; filaments yellow throughout; backs of the outer anthers (connectives) shading from blue above through deep blue-purple to yellow at base. Inner stamens yellow throughout. Just outside of the ring of carpellary styles there often appear short filiform yellow processes, which evidently represent stamens reduced by crowding and lack of nourishment.—*Ovary* about 2 cm. in diameter.—*Carpels* 24 to 31 (12 to 47, Casp. 1877); styles stout, oblong to linear-lanceolate (breadth: length = 1:2 to 5.5), fleshy, pure

CARNEGIE INSTITUTION OF WASHINGTON



NYMPHÆA CAPENSIS.

yellow, rounded at apex, 0.64 cm. long on back, 0.16 cm. wide at base. Stigmatic rays extending up two-thirds of the length of the styles, and ending at an acute angle but with rounded apex. Axile process conical, white, translucent.—*Fruit* depressed spheroidal, 5.7 cm. in diameter by 3.6 cm. high, crowned with the comparatively long (0.64 cm.) obtuse incurved styles; stigma concave.—*Seed* ellipsoidal to nearly globose, 0.16 cm. by 0.1 cm. (average) (0.15 by 0.11; 0.16 by 0.09; 0.17 by 0.11), acuminate at hilum, dull dark olive-brown, with about 18 interrupted longitudinal lines of rather long hairs, giving the seeds a rough appearance to the naked eye, and making them roll about irregularly.

Germination immediate or after drying off. First leaf of seedling filiform, 1.75 to 2 cm. long. Second leaf elliptic, 1.1 cm. long by 0.46 cm. wide, rounded at both ends. Third leaf broadly elliptic, 1.1 cm. long by 0.64 cm. wide, rounded at apex, abruptly rounded at base. Late submerged leaf nearly orbicular, entire, deeply cordate, broadly rounded at apex, lobes rounded, diverging 30° to 40° ; length of leaf 2.4 cm., width 2.2 cm., depth of sinus 1 cm., petiole stout, about 1.3 cm. long by 0.08 cm. thick.

Germinating tuber produces 3 or 4 submerged leaves. First leaf broadly triangular with rounded angles and truncate base; second leaf ovate-cordate, apex abruptly short-acuminate, sides parallel in lower half, sinus about 80° open, with straight margins and rounded angles; third leaf cordate-ovate, with rounded apex and lobes, sinus deep and wide, open about 45° ; fourth leaf similar to third, but with acute angles and margin a little wavy on outside of lobes. First floating leaf coriaceous, orbicular-ovate, narrowly peltate (0.25 cm.), margin slightly wavy in lower half, excavated on outer side of angles of lobes; apex rounded; sinus deep, narrow, margins convex, touching above, angles obtuse or subacute.

Leaf of mature plant narrowly peltate (1.3 to 1.6 cm.), orbicular or orbicular-ovate, 25 to 40 cm. in diameter, thin and soft in texture, doubly or trebly sinuate dentate, somewhat crisped, teeth mostly rounded, sometimes angular and obtuse, depressions between teeth 0.3 to 1.3 cm. deep; apex of leaf rounded. Upper surface bright green, depressed-veiny, somewhat brown-spotted when young; astomatic area large, paler in color, umbonate over the insertion of the petiole. Stomata very many and small on most of the lamina, larger and scattered at margins of astomatic area. Under surface pea-green, veins all prominent, 10 to 12 on each side; length of principal area: radius of leaf = 1:1.1 to 2.0.—*Sinus*, depth: length of leaf = 1:1 to 1.16, margins overlapping above, diverging toward periphery, angles produced, acuminate, awn-tipped.—*Petiole* terete, dark green, about 1 cm. in diameter, 60 to 150 cm. long, with 4 main air-canals, 2 larger and 2 smaller, and 10 small ones surrounding these; transverse section near the leaf shows several large thickened fibers in the parenchyma and around the periphery; stellate cells very few, with short, thick rays. Both of these types of cell diminish in prominence further down the petiole. Base of petiole finely puberulent.—*Stipules* partly adnate.

Rhizome (tuber) ovoid; small ones distinctly egg-shaped, smooth in lower two-thirds of length, tapering above to the bud, 2.5 cm. long by 1.5 to 1.6 in diameter; older ones clothed with long, dark silky hairs and thickly beset with leaf-bases; producing no offsets during active growth. Roots spring from the bases of the petioles.

GEOGRAPHIC DISTRIBUTION.—South and East Africa; Madagascar; Comorro Islands. Zeekoevley, Promontory of the Cape of Good Hope, and Zwartkops river at Uitenhage, Thunberg 1800. Port Natal, Pretoria, L'oldstrom; Hopefield, Delagoa Bay, Albany, Semliki Valley; Zanzibar, Island of Nossi-bé; Island of Johanna, Comorro. Tananarivo; Province of Emirna, Madagascar.

Flower.	SEPALA.		PETALA.		NUMBER OF FLORAL ORGANS.				
	Length.	Breadth.	Length.	Breadth.	Organ.	I.	II.	III.	IV.
	cm.	cm.	cm.	cm.					
Flower 1, U. of P.	7.5	2.4	7.0	1.35	Sepals ...	4	4	4	4
	7.6	2.3	6.5	1.1	Petals....	24	21	38	33
	7.5	2.2	6.0	0.8	Stamens ..	120?	130?	225	167
	7.6	2.2	5.9	0.7	Carpels ..	25?	24?	31	25
Flower 2 } River-	5.4	1.75	5.4	1.1-1.3	Total	173	179	298	229
Flower 3 } ton. }	6.7	2.2	6.7	1.1-1.3					

t = inner.

MATURE LEAF MEASUREMENTS.

Breadth.	Length.
cm.	cm.
32.5	38.9
31.2	35.7
30.6	35.7

STAMEN MEASUREMENTS (IN CENTIMETERS).

Total Length.	Width of Filament.	Length of Anther Cells.	Width of Anther.	Length of Appendage.
3.35	0.4
2.2	0.16
1.1	0.15
3.7	0.6	1.6	0.2	0.5
3.2	0.3	1.75	0.2	0.35
2.5	0.3	1.6	0.16	0.24
2.2	0.2	1.4	0.16	0.16
1.6	0.16	1.0	0.16	0.16

LEAVES FROM SMALL TUBER (CENTIMETERS).

Leaf.	Length of Midrib.	Length, Apex to Angle.	Width.	Sinus Depth.	Sinus Width.
First submerged.....	1.3	1.4	1.3	0	0
Second submerged.....	1.6	2.8	1.8	0.8	1.5
Third submerged.....	2.5	3.9	2.9	1.4	1.9
Fourth submerged.....	3.1	5.5	4.4	2.3	2.1
First floating.....	3.4	6.1	5.0	2.4	1.1

NOTES.—The description of Thunberg is so brief that it is no wonder his name was long neglected. It reads as follows: "N. foliis subpeltatis cordatis orbiculatis integris, petalis lanceolatis calyce aequalibus." "Foliis integris" is only true of young leaves. The synonymy given above will show how far this species has been confused with the Egyptian *N. caerulea*. It is generally known in gardens at present as *N. scutifolia*, sometimes as *N. caerulea*.

Planchon says of *N. berneriana* that the filaments are much broader and appendage longer than in *N. capensis*, and *N. emirnensis* had the filaments shorter than in

capensis; after examining the types, beside much other material from South Africa and Madagascar in the European herbaria, we can see no basis for a separation of these forms.

N. capensis grows easily and flowers and fruits freely. Caspary (1877) considered it incapable of self-pollination, but it produced much seed in the Botanic Garden of the University of Pennsylvania (1900), though it had usually but one flower open at a time.

Introduced at Kew by F. Masson about 1792, carried from the Cape in H. M. S. "Gorgon," Captain Parker.

Var. *madagascariensis* (DC.) new comb.

"Leaves narrowly peltate, 5.1 to 6.3 cm. in diameter, obtusely sinuate, impunctate, glabrous, lobes divaricate. Flowers blue. Sepals 4, green outside, oblong, subobtusate, 2.1 cm. long. Petals 8, oblong, subacute, 4 inner ones smaller. Stamens 8 to 12, shorter than the petals. Carpels 8 to 12. Rhizome small, sub-spherical." (DeCandolle, 1821 b, 1824). A small form of *N. capensis*.

Nymphaea madagascariensis, DeCandolle 1821 b, 1824. Planchon 1853 b. Not Caspary 1880.

GEOGRAPHIC DISTRIBUTION.—Madagascar.

TYPES.—Coll. Brugière, Madagascar, 1801, in hb. DeCandolle. Other specimens coll. Bernier, No. 159, "étangs à Ling-raton," in hb. Paris; coll. Pervillé, No. 677, Feb., 1841, Ambongo, Madagascar, in hb. Paris; coll. Perrottet, 1820, Madagascar, in hb. Paris; coll. Chapelin, Madagascar, in hb. Paris; coll. Boivin, 1847-52, Madagascar, in hb. Paris.

NOTES.—Caspary (1880) regarded DeCandolle's type as a dwarf, of which the larger specimens of Perrottet, Goudot, and Rutenberg were more perfect forms. We recognize, with Caspary, that our knowledge of Mascarene Nymphaeas is extremely deficient, but it has seemed best to include all the larger ones in *N. capensis*, and to recognize these smaller ones simply as dwarfs of that species. This view is supported by the known capacity of the species, and especially of the var. *sansibariensis*, to develop small flowers when in limited quarters. A study of living plants can alone settle the question.

Var. *sansibariensis* (Casp.) new comb.¹ (Plate XI; Fig. 61.)

Leaves large, somewhat peltate, nearly orbicular, closely and irregularly *sinuate-dentate*; sinus closed, angles not produced; under surface more or less suffused *violet*. Flower large, open from 11 a. m. to 5 p. m. Sepals green, spotless, margins purple, inner surface deep purplish-blue. Petals 18 to 24, oblong, obtuse, deep blue (light blue or rosy in varieties). Stamens *very many* (136 to 242), appendages and back of outer anthers deep blue, shading to carmine-purple (in the type).

Nymphaea sansibariensis, Caspary 1877, *fid.* original specimens from hb. Casp. in hbb. Berlin, Kew, Munich; 1882. André 1882. Moenkemyer 1897. Tricker 1897. Conard 1901 a.
N. stellata var. *sansibariensis*, Hooker 1885. Rev. Hort. 1897. Not *N. stellata*, Willdenow 1797.

¹ Referred to in the text; for the sake of brevity, as "*N. sansibariensis*."

DESCRIPTION.—*Flowers* 15 to 25 cm. across (25 to 250 mm., Casp. 1877), opening on 3 to 5 successive days from 11 a. m. to 5 p. m.; highly fragrant; number of floral organs 175 to 300, average about 220.—*Bud* rather broad, oblong-ovate, obtuse or rounded at apex.—*Peduncle* stout, rising 10 to 20 cm. above the water, with 6 main air-canals.—*Receptacle* rather long, swollen, with sloping sides.—*Sepals* 4, oblong-ovate, breadth: length = 1 : 2.3 to 3.0, obtuse, opening about 15° above horizontal; margins gently curved toward the apex; outer surface dark green, often shaded with reddish-brown in upper three-quarters; uncovered margins deep carmine-brown, covered margins shading from carmine-brown to deep violet; inner surface deep purplish-blue above, shading to yellowish-green at base. Innermost sepal narrowest, with broad (12 mm.) covered margins. Outer surface of sepals with 7 principal veins (5 in small




FIG. 61.—*Nymphaea capensis zanzibaricensis*: Sepals, petals, and stamens of successive series, slightly reduced.

flowers); alternate with these are 8 more slender nerves. Inner surface shows the veins as darker lines, there being 32 or more at base of each sepal.—*Petals* 16 to 24, long obovate, the outer obtuse, innermost acute, all rich deep blue above, with obscure darker veins, shading through carmine-purple to whitish at the point of attachment to the torus. The outer 4 stand in a whorl alternate with the sepals; all, or only the outer 2, carmine-brown on the back just above the base. Second whorl consists of 8 smaller petals, alternate by twos with the sepals. A third whorl of 8 still smaller petals follows, alternating with the second, but often only the anterior and lateral ones are developed. A few petals of a fourth whorl, alternate with the third, may be present, even when the third is not fully developed. All of the petals, except those of the fourth whorl, have 5 principal nerves, visible on the outer side.—*Stamens* 126 to 242 according to size of flower, slightly shorter than the petals; appendage and inner side of outer anthers deep blue, back of anthers deep carmine-purple, giving way to light yellow on the long-elliptic filament. Inner filaments inverted wedge-shape. In very large



NYMPHÆA CAPENSIS ZANZIBARIENSIS.

flowers the carmine-purple on the back of the outermost anthers extends down to the middle of the filament; the inner side of the filament is also suffused with blue above. Pollen yellow to the naked eye, colorless under the microscope with transmitted light; grains flattened-spherical, smooth, with large nucleus. Appendage of outermost stamens lanceolate, about 7 times as long as broad, with a swelling on inner side which grows to a keel on median stamens, and on innermost stamens the appendage is thicker than wide. Anthers bent inward, making an angle with the filament.—*Carpels* 15 to 31; styles triangular, breadth: length = 1:2.5 to 2.8, tapering above, acute, straight and erect on first day of opening, afterward bending gradually inward until in fruit they are hook-shaped. Stigma yellow, its rays short, triangular.—*Fruit* yellowish, depressed-spherical, 56 mm. high by 67 mm. in diameter, covered by the enlarged, thick and leathery sepals, containing several thousand seeds.—*Seed* dull brown, elliptic, rather long, with papillæ at one end; diameter: length = 0.75 mm.: 1.2 mm.; = 0.8 mm.: 1.45 mm., with 15 to 24 interrupted rows of short hairs, the rows at one end often alternate with those at the other.

Germination immediate, or after drying. First leaf of seedling filiform. Second leaf broadly ovate, sub-acute, rather abrupt at base, 1.3 cm. long by 0.8 cm. wide. Third leaf orbicular-ovate, truncate near its junction with the petiole, 1.1 cm. long by 1.0 cm. wide. Fourth leaf round-reniform, with shallow, rounded sinus and rounded lobes, 1.6 cm. long by 1.4 cm. wide. Late submerged leaf orbicular, fissi-cordate, 3.8 cm. long by 3.5 cm. wide, entire, rounded at apex; sinus 1.9 cm. deep, margins convex, divergent, angles rounded. First floating leaves orbicular, 2 to 2.5 cm. in diameter, entire; sinus deep, closed, its margins straight and touching, angles meeting and completing the circular outline of the leaf; upper surface more or less thickly blotched with irregular reddish-brown spots; under surface pale green, with a distinct violet tinge all around near the margins. The later leaves have less and less of brown spotting above, and gradually acquire the characteristic margin and color beneath as the plant approaches maturity.

MEASUREMENTS.

SEPALs.		
Source of Data.	Length.	Width.
	cm.	cm.
Caspary, 1882... {	8.2	3.7
	8.4	3.8
	8.4	3.7
	8.4	3.0
Riverton flowers { 1	6.0	2.5
	6.85	2.4
PETALS.		
Riverton flowers { 1	5.7	1.3
	6.5	1.3

Submerged leaves from sprouting tuber 2 or 3. First leaf deltoid, with straight sides and curved base; apex acute. Second leaf broadly orbicular-cordate, with broad, open, rounded sinus and narrowly rounded angles. Third leaf similar to second, larger, with narrower, more acute sinus. First floating leaf orbicular to orbicular-ovate, entire, blotched more or less densely with red-brown above, under surface red on a green ground. (This paragraph describes the growth from a small tuber of the *rosea* form.)

Leaf of mature plant 15 to 60 cm. in diameter, circular or slightly elliptic, narrowly peltate, length of pelta: depth of sinus = 1:9 to 17; texture rather firm and

leathery; margin coarsely and irregularly sinuate-dentate, the teeth mostly angular and obtuse, the larger sinuses as much as 1.3 cm. deep. Upper surface green, faintly brown-blotched when young; under surface suffused violet or even dark purple; veins prominent, primary nerves 10 to 12 on each side; length of principal area: radius of leaf = 1:1.1 to 1.7.—*Sinus*, depth:length of leaf = 1:2 to 2.9, margins convex, more or less widely overlapping, or oftener touching and both curled upward, forming a raised keel 1.3 to 2.5 cm. high in place of the sinus; angles forming an acute tooth in series with the marginal serration of the leaf, but lying within the circle described by the leaf-margin.—*Stipules* fused at base, long-lanceolate, tapering, acuminate.

Rhizome ovate or cylindric-ovate, rather stout, protected by long hairs at summit, smooth below when dry; producing no offsets during vegetative season.

MEASUREMENTS OF LEAVES.


Leaf.	Length.	Breadth.	Length of Lobes.	Length of Pelta.	Length of Principal Area.	Number of Veins.
	cm.	cm.	cm.	cm.	cm.	
Mature.....	36.3	33	15.3	1.6	9.6	10
Mature.....	31.2	33	14.7	1.6	11.1	11
Mature.....	37.3	34.4	12.7	1.3	11.1	10
Caspary, 1882.....	60	60
Mature.....	34.4	1.9

Leaf (small tuber of var. <i>rosea</i>).	Length of Midrib.	Length from Apex to Angle.	Width.	<i>Sinus</i> .	
				Depth.	Width.
	cm.	cm.	cm.	cm.	cm.
First submerged	1.15	1.0	0.75	0	0
Second submerged	1.5	2.45	2.2	0.8	1.5
Third submerged	1.75	3.25	2.9	1.4	1.8
First floating	2.0	2.0	2.7	1.7	0.5
First floating	1.65	3.0	2.5	1.4	1.0

GEOGRAPHIC DISTRIBUTION.—The island and town of Zanzibar, in permanent rain-pools (Caspary 1877).

NOTES.—Seeds of this species were received by Caspary from J. M. Hildebrandt in the middle of April, 1874, packed in chalk. Planted in water at 22° R., they germinated freely in about two months, and in 1875 seven strong plants came into flower; these were the types on which the species was established. In herbaria, however, it is almost indistinguishable from *N. capensis*, and they form fertile crosses; we have therefore reduced this one to varietal rank. It hybridizes readily with all the members of the *Brachyceras* group.

Seeds developed late in the season will withstand the winters of Philadelphia and vicinity, germinate spontaneously, and form blooming plants the following summer; but the flowers are produced too late to ripen seed for the succeeding season. The same is true of *N. caerulea*, whose seeds have lain two years before developing plants. Planted in small pots, *N. zanzibariensis* will produce perfect flowers of any desired size down to 2.5 to 3 cm. in diameter.



NYMPHÆA SULFUREA.

When raised from seed, it sports freely into the two following forms, with numerous intermediates: Form *azurea* Hort., with light blue flowers, sepals lacking the purple shadings; form *rosea*, with pink or reddish flowers, sepals green, under side of leaves shaded reddish. This form appeared first with Herr L. Graebener (1887) in 1884 in the Botanic Garden of Carlsruhe, although the first published description was by W. Siber in 1887. Graebener claims to have obtained it at will by crossing *N. zanzibariensis* with *N. dentata*, though many of the hybrid seedlings came blue. Caspary did not, nor do we, accept this theory of its origin. The experiment needs to be successfully repeated, but we have not had opportunity to try it. [Cf. also Revue Horticole, 1890 a, and Rev. de l'hortic. belge et étrangère, 1890, May 1 (not seen).]

Nymphaea sulfurea Gilg. (Plate XII.)

"Rhizome stout, conical. Petioles long [38 to 46 cm.] and slender; leaves deeply cordate, i. e. narrowly triangular excised; outline broadly ovate or suborbicular, entire; subcoriaceous, glabrous, reddish above, [deep] red beneath; primary veins 6, slightly prominent, outer veins sub-inconspicuous or invisible. Flowers 4.5 to 7 cm. in diameter, deep sulphur color, sweet scented; sepals lanceolate, acute, purple or purplish on both sides, with many slightly prominent parallel nerves; petals equaling the sepals, but often a little narrower, shorter and more acute; stamens 40 to 50, linear; anthers elongate, connective evidently elongate and dilated; carpels 12 to 14. •

"Leaves 4.5 to 5.5 cm. long and about as wide, the sinus being usually about 1 to 1.5 cm. deep. Sepals 2 to 3 cm. long, 1 to 1.5 cm. wide. The deep sulphur yellow petals are 2 to 2.8 cm. long, 0.7 to 1.2 cm. wide. Anthers bright yellow." (Gilg, 1903.)

Rhizome 6.4 to 12 or 15 cm. long, about 2.5 cm. across, only one-third of which is flesh, the rest being a dense layer of black hairs; leaf bases many, prominent; the rhizome was evidently erect but not tuberous. In the specimen at Kew the sepals are copper-red outside, greenish-yellow inside. Petals 13, cadmium-yellow.

N. sulfurea, Gilg 1903.

DISTRIBUTION AND TYPES.—Coll. H. Baum, No. 657, Jan. 17, 1900, Kunene-Sambesi-Expedition, "am linken Longa Ufer bei der Imbala, Minnesera, in flachen sumpfigen Gräben," altitude 1,250 m., in hbb. Berlin, Kew, Delessert, Munich, British Museum. Also No. 325, October, 1899, "in der Nähe des Kuebe, in einem Bache, welche in einem Sumpfe entspringt und in den Kuebe mündet, nicht im Kuebe selbst," altitude 1,150 m., in hbb. Delessert, Berlin; this number has larger leaves and flowers and broader petals than the former, with the leaves plain reddish-brown above; in No. 657 the leaves are blotched all over the upper surface with large reddish-brown blotches. No. 325 is mentioned first in Gilg's text, and appears, from the color of the leaves, to be especially designated in the description (our first two paragraphs are a nearly literal translation); in case of separation of the forms, No. 325 would have to stand as the type.

Nymphaea stuhlmannii (Schw.) Gilg. (Fig. 62.)

Sepals yellowish green, petals bright sulphur yellow, stamens orange yellow, with sulphur yellow anther. Stigma orange. Receptacle brown.

N. lotus var. *stuhlmannii*, Schweinfurth in Engler 1895.

N. stuhlmannii, Gilg 1903.

DESCRIPTION.—Flowers 10 to 15 cm. across, sweet scented ("duftet sehr aromatisch"). Sepals 4, obovate, broadly rounded above, with numerous longitudinal veins, 8.3 cm. long by 2.5 cm. wide. Petals about 22, broadly obovate, with one to several longitudinal veins. Stamens about 125, stout and thick, all appendaged, the innermost very shortly so. Carpels about 23; stigma shallow, flat. Leaf orbicular-ovate, entire, 21 cm. wide by 25.5 cm. long; sinus margins nearly straight, lobes diverging, obtuse; green on both sides; veins prominent; primary veins 7; principal area 7 cm. long.




FIG. 82.—*Nymphaea stuhlmannii*: Flower, under side of leaf, and outer stamen. Drawn by J. Pohl, from the type in hb. Berlin, by kind permission of the Directors. Reduced one-half; stamen natural size.

DISTRIBUTION AND TYPE.—Coll. Stuhlmann, No. 410, July 16, 1890, at "Uniamweni, Gunda mkali, bei Bibisande," Africa, altitude 1,200 m., in hb. Berlin.

NOTES.—A single sheet of this plant exists in the Berlin collection; it has one leaf, two separate open halves of a large flower, and one small wrinkled flower—enough to show that a splendid garden plant is yet to be introduced.

Group II. NYMPHAEAE SYNCARPIAE (SYMPHYTOPLEURA, Casp. 1865, 1878, 1888).

Carpels completely fused with one another at the sides; attached also to the axis of the flower and to the torus as in Group I. Stamens not appendiculate. Flowers white, rose, purple or yellow, never blue; nocturnal or diurnal.

Subgenus 3. CASTALIA DC. 1821.

Flowers diurnal, usually floating. Sepals not evidently veined. Stamens inserted in series with the petals and grading into them in size and shape; innermost stamens with narrow filaments. Styles linear, more or less ligulate. Leaves entire or sinuate or crenulate, never sharply dentate. Rhizomes not protected against drought, but lying dormant in cold weather. Plant glabrous except on the rhizome and bases of petioles and peduncles. Seed smooth. Seven species, found in all of the North Temperate Zone, except the Pacific Slope of North America.

Castalia and part of *Lotos*, Planchon 1852 *b*, 1853 *b*.

Sec. II. *Inappendiculatae*, trib. III. *Castalia* (in part), Lehmann 1853 *a*.

Castalia and *Xanthantha*, Caspary 1888.

A. XANTHANTHA CASPARY 1888.

Flowers yellow, opening near noon and closing in the late afternoon. Outermost stamens first to dehisce. Pollen smooth. Seed very large. Floating leaves sinuate, more or less blotched with reddish brown. Principal air-canals in peduncle 4, in petiole 2; idioblasts in course of petioles and peduncles stellate only. Rhizomes erect, short, giving rise to numerous long stolons or runners which propagate the plant very widely during summer, but produce in autumn on geotropic stolons characteristic brood-bodies, consisting of a row of buds and a cluster of short fleshy roots (resembling those of *Limnanthemum*). One species, native in Florida, Southern Texas, and Mexico.

***Nymphaea mexicana* Zuccarini. (Plate XIII; Figs. 63, 64.)**

Flowers 6 to 13 cm. in diameter, bright yellow; sepals and petals elliptic, ovate to lanceolate, acute or rather obtuse. Receptacle with four swollen ridges. Leaves floating or aerial, orbicular to ovate, narrowly peltate, nearly entire or denticulate-wavy, 10 to 18 cm. in diameter, with the petiole inserted much nearer the lobes than the apex; upper surface blotched with brown, at least when young; lower surface deep purple or purplish-green (green in aerial leaves), with small blackish spots.¹

Nymphaea mexicana, Zuccarini 1832 *a* and *b*, *fid.* original specimens, coll. Karwinski, Sept., 1827, "aus dem See bei Mexico," in hb. Munich. Planchon 1853 *b*. Hemsley 1888. Pringle 1890. Gerard 1890 *b*; 1891. Plank 1896? Tricker 1897. Conard 1901 *a*. Not Gray 1850.

N. flava, Leitner 1838. Gray 1876, *fid.* original specimens. Treat 1877. Meehan 1880. Chapman 1883. Carrière 1884. Hooker 1887, *fid.* original specimen in hb. Kew. Gray, etc., 1895. Tricker 1897. Conard 1901 *a*.

N. lutea, Treat 1877. Not Linn. 1753.

Castalia flava, Greene 1888.

¹ Referred to in the text as "*N. flava*" wherever the material used was from Florida plants directly or in cultivation.

N. planchonii, Caspary MS. (flower) in hb. Berlin. This specimen bears several marks: (1) coll. "Poepfig, No. 3033, 1832, Colufer Amazon, *Nymphaea hepatica*"; (2) "No. 10 *Nymphaea* [*obtusiloba* stricken out] *tussilagifolia* Lehm." in Lehmann's handwriting; (3) "*Nymphaea* (flore partim rubro, partim flavo). In lacu chalcensi prope Yotla (sit. Mexico), 14 Mayi, G. Andrieux, Plant. Mex. exsicc. No. 541." The leaf is of *N. rudgeana*, the flower is of *N. mexicana*. No. 541 of Andrieux in hb. Paris is *N. mexicana*.

DESCRIPTION.—*Flowers* floating, or raised 5 to 12 cm. above the water when in shallow places, 7 to 10 cm. in diameter, open from 11 a. m. to 4 p. m., with faint odor of a tea-rose or odorless.—*Peduncle* terete, 3 to 6 mm. in diameter, 16 to 150 cm. long.—*Receptacle* four-sided, the corners broadly rounded and prominent, the sides slightly grooved; two of the corner-ridges are larger than the alternate two.—*Sepals* 4, elliptic to lance-ovate, obtuse, length: width = 4.5 cm.: 1.3 cm.; outer surface green with pale brownish margins; seven longitudinal veins visible by looking through the sepal at a





FIG. 68.—*Nymphaea mexicana*: a, sepal; b-e, successive petals; f, g, stamens; h, section of ovary; k, section of fruit. a-h from Mexican (?) plants, cult. at Riverton, N. J.; k, from Florida plant, in the Botanic Garden, University of Pennsylvania. Six-sevenths natural size.

strong light; inner surface yellow; opening to about 15° above horizontal.—*Petals* 12 to 23, outermost of the size and shape of the sepals or somewhat narrower, obtuse or acute, slightly purplish without. Inner ones narrowly obovate, rounded at apex.—*Stamens* about 50, stout, golden yellow, grading inward from petaloid to typical stamens. Innermost stamens short, anther about as long as or shorter than its filament and of the same width. Back of anthers convex, face deeply grooved between the anther cells. Pollen smooth.—*Carpels* 7 to 10; styles short, fleshy, with a deep furrow on the inner face. Stigma deeply curved-funnel-shape, the papillose rays ending roundly on the base of the styles; each ray with a short longitudinal median fissure (the suture). Axile process small, rounded, in the bottom of the narrow central pit of the stigma.—*Fruit* spherical in Texan specimens, ovoid in those from Florida, 2.5 cm. in diameter, crowned with the small stigma 0.6 cm. in diameter.—*Seeds* globose, very large, 0.48 cm. in diameter, very finely appressed-hairy, dull greenish-black.

Submerged leaves from brood-body 1 to 3, narrowly hastate, acuminate. First floating leaves ovate to orbicular-ovate, much blotched above with reddish-brown; sinus slightly open, or overlapping; margin entire in apical portion, sinuate below, especially at angles; under surface green, tinged with reddish-brown, with a few blackish specks.



NYMPHÆA MEXICANA.

Leaves of mature plant floating, or aerial and 7 to 12 cm. above the water, broadly ovate to orbicular, evidently peltate, entire, or more commonly sinuate or crenulate-wavy at base, becoming entire or slightly emarginate at apex; green above, with brown mottlings, at least on the floating leaves; under surface deep purplish-red, often becoming greenish, marked with small blackish dots. Primary veins scarcely visible, 5 to 10 on each side, depressed from the second fork outward.—*Sinus* short, depth: length of leaf = 1:2.6 to 2.8; margins nearly straight, slightly separated or overlapping; angles slightly or evidently produced, obtuse or somewhat acute, made prominent by a deep concavity of the margin of the leaf on outer side of lobe. The aerial leaves may become concave above by the overlapping of the sinus margins.—*Petiole* with two main air-canals placed transversely, and two smaller ones placed anteriorly and posteriorly; stellate cells small, numerous, short armed.—*Stipules* fused into a single entire lanceolate organ, thin, membranaceous and translucent; apex rounded; 3.3 cm. long by 0.8 cm. wide, standing erect and clasping the younger leaves; smooth, and uniform in thickness.

Rhizome erect (1.9 cm. long by 1.4 cm. thick), becoming as much as 30 cm. long and 5 to 6 cm. thick (Treat 1877), densely covered between the leaf bases with long, light-colored hairs, and on the sides marked with large, projecting, spirally arranged leaf cushions, which are about 0.64 cm. apart from center to center. From the upper part of the rhizome naked stolons 0.5 to 1.0 cm. in diameter are




FIG. 64.—*Nymphaea mexicana*: a, first broad leaf, b, acicular leaf of seedling; c, d, e, submerged leaves of seedlings; f, first floating leaf of seedling. Florida stock. Natural size.

given off; these pass along under the mud in which the plant grows for a distance of 15 or 20 cm. to 1 meter, when the terminal bud turns upward and forms a new plant; in a few weeks the new plant again sends out runners, and the connection with the parent stem dies away. In autumn the stolons become geotropic and bury their tips 20 cm. or more in the mud, and there form brood-bodies. A brood-body consists of an axis 2.5 cm. long, with a row of 3 to 6 or 7 upward pointing buds on one side, and a cluster of about a dozen or more fleshy roots 1.3 to 3.8 cm. long and 0.4 to 0.48 cm. in diameter hanging down like a "hand" of bananas on the other side. In spring, the uppermost bud sends up a naked stolon at whose summit leaves spring up as noted above; roots spring from the bases of these leaves, and soon an independent plant is formed. If the first bud is broken off, the second sprouts, and so on; probably the second and lower buds would sprout sooner or later in any case, so long as the food supply in the fleshy roots was not used up.

MEASUREMENTS OF FLORAL PARTS IN CENTIMETERS.

SEPALA.		PETALA.		STAMENS.						Remark.
Length.	Breadth.	Length.	Breadth.	Total Length.	Length of Filament.	Breadth of Filament.	Length of Anther.	Breadth of Anther.	Length of Appendage.	
<i>i</i> 5	1.9	<i>o</i> 4.5	1.5	2.55	0.64	(<i>a</i>)	(<i>a</i>)	(<i>a</i>)	} One flower.
<i>l</i> 4.8	1.75	4.5	1.4	1.5	0.3	(<i>a</i>)	(<i>a</i>)	(<i>a</i>)	
<i>r</i> 4.8	1.75	3.7	1.3	1.6	0.8	0.16	0.8	0.23	0	
....	<i>i</i> 3.2	0.95	1.12	0.48	0.10	0.6	0.16	0	
....	0.86	0.4	0.16	0.48	0.24	0	
4.8	1.6	
4.5	<i>R.</i> 1.6	
3.0	1.3	
5.4	<i>H.</i> 1.9	

R. = Riverton plant. H. = Harshberger's plant. *i* = innermost. *l* = left. *r* = right. *o* = outermost.
(*a*) = withered.

NUMBER OF FLORAL PARTS.

Floral Parts.	I.	II.
Sepals.....	4	4+8+8+7= 27
Petals.....	26	
Stamens.....	60	
Carpels.....	9	
Total.....	99	89

LEAF MEASUREMENTS.

Source of Data.	Diameter of Petiole.	Length of Lamina.	Breadth.	Depth of Sinus.	Length of Midrib.	Length of Principal Area.	Length of Radius.	Pelta.	Number of Veins.
Mexican specimens at Riverton.....	cm.	cm.	cm.	cm.	cm.	cm.	cm.	cm.	
	0.47	15.6	14.3	5.6	9.4	5.1	7.0	0.3	8
	1.06	17.1	16	5.7	11.0	6.4	7.8	0.32	8
	1.06	17	15.3	5.75	10.4	5.4	7.65	0.32	8
	0.48	14.8	12.8	5.1	9.0	5.4	6.4	0.3	8
Harshberger coll ..	0.4	12.6	10.8	4.5	7.6	4.5	5.6	0.3	7
	16.25	13	5.1	0.48
	7.0	5.4	3.5	0
Pringle coll	12.75	11.48	4.15	0.64	10
	13.35	12.75	4.5	0.8	8
First floating leaves from brood-bodies.	5.20	4.6	2.07
	4.6	3.8	1.9
	3.35	2.55	1.3
Riverton, 1901.....	4.3	3.5	1.6
	2.0	1.2	0
Submerged leaf of same	11.15	9.9
	11.5	10.2
	11.8	10.2
	12.1	11.6
Aerial leaves, Riverton, 1900.....	8.9	7.65

GEOGRAPHIC DISTRIBUTION.—Florida, Texas, and Mexico. "Lagoons of the lower Rio Grande southward to the Valley of Mexico, and westward to the valley of the Lerma, State of Jalisco" (Pringle 1890). Lake Xochimilcho, Valley of Mexico, coll. J. W. Harshberger. Brownsville, Texas, coll. Pringle, *Flora of Texas*, 1888, No. 1956. In Florida: St. Johns River, from Jacksonville southward for 40 miles (Treat, 1877, *fid.* original specimens); Curtis, *North American Plants*, No. 101 *a* and Second Distribution No. 4815. Miami River; Prairie Creek (both in hb. Acad. Nat. Sci. Phila.). Little River, coll. Dr. J. M. Macfarlane, cult. in Botanic Garden, Univ. of Pennsylvania. Reservoir Pond, Palm Beach, coll. Mr. Thomas. Also coll. Rugel, "ad fl. Alachua, Florida or." July, 1848, in hb. British Museum.

NOTES.—Zuccarini's description of *N. mexicana* ascribes white flowers to it, whereas the leaf agrees with that given above. Examination of the types leaves no doubt as to the identity of the plants now so familiar in cultivation; the white color must have been purely a guess, as Professor Radlkofer suggested to me. The dried specimens are brown like the average herbarium specimens of the European waterlily.

Our conclusion to unite the Florida and the Mexican plants comes only after prolonged consideration and comparison, and it is to be regretted that the very suggestive name *N. flava* has to be abandoned. It has seemed to us that the leaves of the Mexican plant are thicker and rounder, with less of purple coloration beneath. The floral leaves also are a little broader than those of the Florida plants. A fruit on Pringle's No. 1956 in hb. Acad. Nat. Sci. Phila. seems to have been nearly spherical, while the fruits of the Florida plants in our garden were ovoid. We have not been able to secure living plants direct from any Mexican locality. The Prairie Creek specimens, collected by Garber in 1878, have leaves more nearly orbicular than those from other Florida localities; this is probably because they grew in shallow water. We see in cultivation like variations from this cause.

The name *N. flava* Leitner rested on the floral decorations and name on Audubon's plate of the great white swan; the leaves accompanying the yellow flowers are evidently those of a Nuphar. Excepting Rugel's unrecognized specimen, the species was known only by that plate until Dr. Edw. Palmer in 1874 sent a dried specimen to Harvard, with a statement of its yellow color. Mrs. Treat, however, in 1876, again discovered the plant, and made it known by sending ample material both fresh and dried to Harvard; from there it was sent to Kew, where it flowered first in July, 1882.

B. CHAMAENYMPHAEA PLANCHON 1853 b.

Flowers white or rosy, opening near noon and closing in the late afternoon. Innermost stamens first to dehisce. Pollen aculeate or tuberculate. Seed of medium size. Leaves entire, obovate to oval. Principal air-canals in peduncle 4, in petiole 2; idioblasts stellate only. Rhizome erect, short, entirely without offsets (at least in *N. tetragona*). Native of the North Temperate Zone, especially in China and Japan.

Nymphaea tetragona Georgi. (Plate XIV; Fig. 65.)

Flower small, 2.5 to 5 cm. across, white, with a small number of floral parts; receptacle distinctly tetragonal. Leaves ovate, small (2.5 to 12 cm. long), green above with brown blotches when young, under surface dull red; sinus open, lobes acute. Petiole with 2 main air-canals. Rhizome erect, covered with projecting leaf-scars.

- Nymphaea tetragona*, Georgi 1775, *fid.* original specimen from hb. Pallas, in hb. British Museum; 1800. Caspary 1865. Robinson 1896. Conard 1901 a.
N. tetragonanthos, Pallas MS., in Sims 1813, *fid.* specimen cited above.
N. pygmaea, Aiton 1811. Sims 1813. Smith 1819. DeCandolle 1821 b, 1824. Sprengel 1825. Don 1831. Ledebour 1842. Turczaninow 1842. Planchon 1852 b; 1853 a and b. Lehmann 1853 a. Hooker & Thomson 1855. Loudon 1855. Hooker 1872. Garden 1883 b. Tricker 1897. Moenkemyer 1897.
N. foliis cordatis integerrimis and *N. alba minor*, Gmelin 1769.
N. pygmaea alba, Hort., Gerard 1890 a?
Castalia pygmaea, Salisbury 1806 b.
C. Leibergi, Morong 1888, *fid.* original specimens. G. & F. 1888.
C. odorata var. *minor*, Macoun 1891 (in part) *fid.* specimen coll. J. M. Macoun, July 17, 1886, No. 94 from hb. Geol. and Nat. Hist. Survey, Canada, in hb. British Museum. *Not N. odorata* var. *minor* Sims 1814.
C. tetragona, Lawson 1889. Britton & Brown 1897.




FIG. 65.—*Nymphaea tetragona*: a, section of ovary; b, section of receptacle; c, outer, d, inner sepal; e, outer, f, median, g, innermost petal; h, stamens. Natural size.

DESCRIPTION.—*Flower* floating, 3.3 to 7.6 cm. across, open on 3 or 4 days from noon until 5 p. m., sweet-scented (or odorless, Britton & Brown 1897).—*Peduncle* slender, 0.3 to 0.4 cm. in diameter, terete, 10 to 30 cm. long, with 4 main air-canals.—*Receptacle* enlarging abruptly from the scape, distinctly tetragonal, with rounded angles, green.—*Sepals* 4, ovate to oblong-ovate or broadly lanceolate, breadth : length = 1 : 1.16 to 3.61, obtuse or slightly acute; opening horizontally or less, putrescent in fruit; green and veinless outside, white within; when dry, marked outside with short elevated lines.—*Petals* 8 to 17, rather thin, pure white (or faintly striped with purple lines, Morong 1888), about as long as the sepals, oblong, obovate or broadly lanceolate, or oblong-elliptic, apex obtuse or somewhat acute, narrowed toward the base, grading into the stamens.—*Stamens* about 40, with golden yellow anthers, shorter than the petals (stamens 12 to 16 in the American plant, in 3 or 4 rows, running up the ovary about half way, Morong 1888); outer stamens shorter than median ones; outermost filaments elliptic or obovate to lanceolate-oblong, very broad, narrowed toward the base (inserted up to the summit of the ovary, Casp. 1865; Turcz. 1842); outermost anthers shorter than median and inner, cells diverging below, sometimes only one cell developed. Median stamen with filament as in outer, but narrower; cells of anther parallel. Innermost stamens very short, filaments slender, cells



NYMPHÆA TETRAGONA.

of anthers as in median stamens.—*Pollen* yellow, finely tuberculate, operculum smooth; diameter 0.03 to 0.04 mm., average 0.034 mm.—*Carpels* 6 to 8 (4 to 12, as hitherto described); styles thin, subcoriaceous, ovate or oblong-elliptic, short and blunt, breadth: length $\doteq 1:1.25$ to 3, concave; stigmatic area extending on their bases as an upraised cushion, ending obtusely. Stigma little or not at all depressed.—*Fruit* spherical, naked, green, crowned with the small stigma.—*Seed* large, 0.3 to 0.2 cm. long by 0.16 to 0.17 cm. in diameter, dark brown, smooth.

Seeds which germinate in late summer form small plants, and at approach of winter, lose their leaves and retire into a small tuber. These germinate, producing first a series of submerged leaves, then small floating leaves as follows: Submerged leaves broadly obovate, rounded at apex, thin, pale green; sinus deep, margins nearly straight near the petiole and parallel or diverging or slightly overlapping, curved outward below to the broadly rounded lobes. First floating leaf obovate-oblong, rounded at apex; sinus overlapping, lobes narrow, rounded at angles, suggesting rabbit-ears; green above with a brown line around margin; under surface greenish-red, densely marked with fine bright red marblings.

Leaf of mature plant cleft to the petiole, more or less coriaceous, broadly oblong, ovate or elliptic, 5 to 10 cm. long by 3.3 to 7.6 cm. wide, entire, rounded at apex (rarely emarginate, Casp. 1865), dark green above, more or less mottled (at least when young) with reddish-brown; under surface green to dull red; primary veins 5 or 6 on each side of leaf, sunk in the tissues; length of principal area: radius of leaf $= 1:1.5$ to 1.9 (average 1:1.3).—*Sinus* depth: length of leaf $= 1:1.8$ to 2.2 (average 1:2), lobes unequal, margins nearly straight or slightly convex, touching, or diverging and 1.9 to 3.8 cm. apart at periphery, angles more or less produced, rounded to sub-acute or rarely acuminate. Astomatic area very small; stomata larger and not so crowded as in *Eu-castalia*, scattered toward the point of insertion of the petiole; cells of upper epidermis large.—*Petiole* smooth, terete, very slender, 0.24 to 0.4 cm. in diameter, 10 to 30 cm. long, with 4 main air-canals, 2 larger and 2 smaller, with 4 still smaller ones anteriorly and posteriorly, and one on each side; 2 double bundles are present (1 anterior and 1 posterior) with 3 or 4 smaller ones on either side; stellate cells projecting into the 6 larger air-canals, rays very slender, long, densely covered with small crystals, quite brittle.—*Stipules* oblong-ovate or elongate-triangular, acute, not at all keeled.

MEASUREMENTS OF SEPALS
(AFTER CASPARY, 1865).

Breadth.	Length.
cm.	cm.
0.6	1.8
1.3	3.3
0.85	1.9
0.8	3.1

Rhizome erect, 7 to 15 cm. long, blackish, covered with long hairs (1.3 cm. long); apex covered with leaf-bases and stipules. Entirely without branches or offsets.

LEAVES FROM SMALL SEEDLING-TUBER (IN CENTIMETERS).

Leaf.	Length.	Breadth.	Depth of Sinus.	Width of Sinus.	
				Half-way up.	At Angles.
Submerged	4.8	3.35	2.55	0.16	1.1
Submerged	1.4	1.1	0.8	0.08	0.3
Submerged	3.2	2.1	1.6	0	0.6
Submerged	3.5	2.4	1.75	(a)	0.3
First floating	3.7	2.4	1.9	(a)	0.6

a Overlapping.

GEOGRAPHIC DISTRIBUTION.—Eastern Europe, Asia and North America, south to Australia. Russia (Baikal region), Georgi 1775. Khasia Hills, and marshes at Nonkreem, alt. 5,600 ft., India, Hook. & Thom. 1855, *fid.* specimens coll. Hooker, Duthie, Stewart, etc. N. Queensland, Australia, Müller 1887? Siberia, Gmelin 1769. Common in China and Japan, *fid.* numerous specimens. Granite Station, Kootenai County, Idaho, U. S. A., coll. Leiberg, Heller and the writer. Misinaibi River and along Severn River, Canada (Ontario), Macoun 1891.

NOTES.—Caspary (1865), from whom the measurements in the text were mostly taken, divides the species thus:

I. *Lata*: Sepals and petals shorter and broader, outermost petals slightly exceeding the sepals; depth of sinus less than half the length of the leaf. Leaves not spotted. Pollen smaller. Found in eastern and northern Asia.

II. *Angusta*: Sepals and petals longer and narrower; depth of sinus equal to or exceeding half the length of the leaf; pollen larger. This varies into (1) *orientalis*, outermost petals a little shorter than the sepals; lobes of leaves long-produced, rarely acuminate; leaves not spotted. China and Japan. (2) *indica*, outermost petals slightly exceeding the sepals; lobes of leaves long-produced, tapering and acuminate; leaves usually brown-spotted above. Northern India (Nonkreem). Georgi's specimens are of the broader sepaled type. Those with narrower petals and sepals may deserve varietal rank as var. *angusta* Casp.

The American plant, from its small number of stamens and their insertion below the summit of the torus, may deserve the rank of a variety.

N. tetragona was introduced into England from China in 1805 by the East India Company, in the ship "Winchelsea," Capt. Campbell. It is hardy in our climate. Being of small size it is suitable for aquaria.

The seeds are used for food in Japan, and the leaf buds are also eaten, dressed with vinegar (Rein 1886).

Nymphaea acutiloba, DC. 1821, is of uncertain identity, but as it came from China it is probably *N. tetragona* Georgi.

Nymphaea fennica Mela.

Flower cup-shaped, small, 3.8 to 6.9 cm. across, white or rosy; receptacle large, square, sloping upward, with a keel running from the peduncle to each corner; sepals forming a sharp angle at their line of insertion. Petiole with 2 main air-canals.

Nymphaea fennica, Mela 1897, *fid.* specimens coll. A. J. Mela, in hb. Univ. of Penna. G. C. 1899.

DESCRIPTION (taken from Mela's paper).—*Flower* cup-shaped, small.—*Bud* short ovate, square at base, constricted just above the base, then rounded and rapidly drawn in to the acute apex.—*Receptacle* characteristic, very broad; breadth of receptacle: length of sepals = 6 mm.: 14 mm. (small flower); = 9 mm.: 19 mm. (medium); = 12 mm.: 25 mm. (large flower). Looking at the receptacle with the apex of the bud turned away, the surface slopes gently, roof-like, from the top of the peduncle, with a low, narrow keel running to each angle. Edges of receptacle not projecting downward as in *N. candida*, but plane beneath, making a sharp angle on the side. In fruit the receptacle is a little wider than the berry and calyx, these being completely hidden

when the fruit is viewed from beneath.—*Sepals* elliptic-ovate, a little contracted below the apex, often very broad; length: breadth = 3:2 (18 to 19 mm.: 12 to 13 mm.); calyx somewhat contracted just above its origin, so that the edges of the receptacle, which are sharp-angled outwardly, appear to project.—*Petals* 10 to 15, very concave, and crowded, with apex directed upward so that the corolla is cup-shaped; lanceolate or narrowly-lanceolate.—*Stamens* about 50. *Anthers* very short and broad (3 mm. long by 1 mm. wide); filaments petaloid, with broad, elliptic, deep yellow blade and strongly contracted, whitish claw; blade often with 1 to 3 longitudinal folds, with 1 or 2 transverse folds between blade and claw.—*Stigma* 5 to 9 rayed, with yellow, often violet-tipped, styles. Stigmatic surface usually (not always) deep violet, with generally 3-pointed rays.—*Fruit* broad conical-ovate, broadest at base, but not so broad as the receptacle which forms a square disc, whose edges (and especially the corners) extend noticeably beyond the circumference of the fruit; the calyx persists as a 4-sided pyramid surrounding the fruit.

Leaf small, 7 to 12 cm. long by 5 to 9 cm. wide, elliptic-cordate; lobes acute or obtuse, margins overlapping or approaching or more or less wide apart (3 cm.). Primary veins of the lobes usually divergent, even when the lobes overlap, though they are sometimes parallel or even converging.—*Petiole* slightly flattened, with 2 large air-canals.

Rhizome erect, 5 to 10 cm. long, about 2.5 cm. in diameter, conical at apex, covered with long black hairs. One of our specimens has two equal branches.

GEOGRAPHIC DISTRIBUTION.—Middle and East Finland, mostly in small forest ponds, sometimes in running water, from the shallows to a depth of 1 or 2 meters, often accompanied by large and small forms of *N. candida*. Found also in Southern Finland. (Cf. specimens coll. Lönnbohm, Aug., 1898, No. 3601, "locus classicus," in several herbaria.)

NOTES.—The receptacle and air-canals of petiole place this species in near relation to *N. tetragona*; in several other respects it approaches *N. candida semiaperta*. One is inclined to suggest that *N. tetragona* of China shades off through the Siberian forms into *N. fennica*, this then runs into *N. candida*, and it again into *N. alba* of Germany and England. A careful review of these forms, in the living state by cultivation and hybridization, as also in histological details, is highly desirable.

The seeds of *N. fennica* have not as yet been described.

Numerous stations for this species throughout Finland are given in Mela's paper. Red-flowered specimens occur "im See Keskimmainen im Kirchspiel Lapinlahti," and in Pieni Musto and Jäläjärvi.

Through the kindness of Mr. Mela, we have a fine series of specimens of *N. fennica*; of several rhizomes sent to us alive, only one survives, and it has never bloomed.

C. *EUCASTALIA* PLANCHON 1853 b.

Flowers white or rosy to deep carmine, opening in early morning, closing from noon to mid-afternoon. Innermost stamens first to dehisce. Pollen aculeate or tuberculate. Seed of medium size. Leaves entire, nearly orbicular, of solid color above. Principal air-canals in peduncle 4, in petiole 4; thickened bipolar idioblasts more or less numerous in the tissues of leaf and flower stalks, this type of cell being absent

from other syncarpous members of the genus. Rhizome horizontal, long and creeping, more or less branched. North temperate zone, south to Algeria, Cashmir, and British Guiana.

Nymphaea candida Presl. (Plate XV; Fig. 66.)

Leaves floating, crowded on the rhizome, phyllotaxy about 13 on 34; *lowest pair of veins* on under side of leaf (veins of the lobes) *curved toward one another*. Flower odorless, white, 6.4 to 7.6 cm. across. *Line of insertion of the sepals angular*, projecting downward. All of the filaments broader than the anthers. Ovary much contracted and destitute of stamens immediately below the stigmas. Fruit ovoid, seed large.

- Nymphaea candida*, Presl 1822, *fid.* specimens coll. Topitz, Flora exsiccata austro-hungarica, No. 1282, "in stagno Egersee ad pagum Sonnberg prope urbem Gratzen (locus classicus)." Reichenbach 1845. Planchon 1853 *b*. Schuchardt 1853. Celakovsky 1867. Caspary 1879. Grisebach 1882. Gerard 1892. Tricker 1897. Moenkemyer 1897. Conard 1901 *a*.
- N. alba*, Linnaeus 1753; 1762 (in part), and other European authors.
- N. alba oocarpa*, Caspary 1855 = *N. alba oligostigma* Casp. 1863; 1865.
- N. biradiata*, Sommerauer 1833, *fid.* specimens coll. Sommerauer, in Triebnersee in Styria in hbb. Paris, Boissier, and coll. Wettstein, Flora exsiccata austro-hungarica, No. 1281. Coll. Statzer in I. Dörfner's Herb. Norm., No. 3502; coll. Keller in Magnier, Fl. select. exsicc. No. 3453; coll. F. G. Strobil, "in aquis stagnantibus: Triebner—vel Gaishornsee vallis Paltinae (locus classicus)." Reichenbach 1845. Fries 1846. Planchon 1853 *b*. Schuchardt 1853.
- N. semiaperta*, Klinggraeff 1848, *fid.* F. Schulz, Herb. Norm. nov. ser. Cent. 3, No. 207, and specimen coll. Caspary, Aug. 9, 1859, near Königsberg, in hb. Boissier. Schuchardt 1853.
- N. neglecta*, Hausleutner 1850, *fid.* specimen coll. R. Fritz, July, 1870, in a pond near Rybnick, Ober-Schlesien, in hb. Berlin.
- N. Kosteletzkyi*, Palliardi MS., *fid.* Lehmann 1852 *b*, and specimens sent by Palliardi to Lehmann, from hb. Lehmann in hbb. Kew, Berlin. Schuchardt 1853.
- N. pauciradiata*, Bunge, in Meyer & Bunge 1829 = *N. alba* Patr. *fid.* Meyer & Bunge, l. c.; *fid.* specimens coll. Ledebour, 1845, in the Altai region, in hbb. Paris, Munich.
- N. intermedia*, Weiker, in Reichenbach 1842.
- N. Basniniana*, Turczaninow 1842, *fid.* specimens sent by Turczaninow from hb. St. Petersburg, in hbb. Kew, Boissier, DeCandolle = *N. bashiniana*, Steudel 1841.
- N. Cachimiriana*, Cambessedes in Jacquemont 1844, *fid.* original specimens in hb. Paris = *N. alba* var. *Kashmiriana*, Hook. & Thoms. 1855. Hooker 1872.
- N. punctata*, Kar. & Kir. 1842, *fid.* Casp. 1879, from Semenow 1854, and specimens coll. Kar. & Kir. "in Songoriae lacubus prope fluvium Lapsa," in hbb. Berlin, Paris, DeCandolle.
- N. alba*, L. var. *minor* DC., *fid.* specimen coll. Fischer, 1819, in hb. DeCandolle. Besler 1613, cf. Flora 1833. Schuchardt 1853. = *N. minor* Reichenbach 1842; 1845. = *N. permixta*, Boreau 1859.
- N. Milletii*, Boreau 1859, *fid.* specimen coll. Ed. Longeron, June 12, 1861, Maine et Loire (locus classicus?) in hb. British Museum.
- N. Wenzelii*, Maack in litt., *fid.* plate from Ruprecht 1859, in hb. British Museum.

DESCRIPTION.—*Flower* floating, 6 to 13 cm. in diameter.—*Sepals* 4 (or 5) oblong or ovate-oblong (3.8 cm. long by 1.3 cm. wide), narrowed at apex, acute or obtuse, about 7-veined, green outside, white within.—*Petals* 12 to 20, white, oblong to oblong-lanceolate, obtuse or somewhat acute, 7-nerved, outer ones nearly as long as the sepals.—*Stamens* 32 to 70, shorter than in *N. alba*, grading inward from the petals, orange-yellow; filaments lanceolate (outer) to linear-lanceolate (inner), long acuminate, never narrower than the anthers, usually inserted only on the sides, not on the summit, of

the ovary. Pollen granulate with smooth operculum, larger than in *N. alba*.—*Ovary* ovate or roundish, usually contracted and destitute of stamen insertions below the stigma.—*Carpels* 5 to 14; styles linear, flattened, breadth: length = 1: 1.5 to 2.5; apex rounded or somewhat acute. Stigma concave, yellow, red or violet, the rays terminating usually in 3 teeth (a central and two lateral) on the base of each style. Axile process slender.—*Fruit* ovoid or spherical; in the former case, narrowed below the stigma, which stands as it were on a short thick column surmounting the berry; greenish or reddish; subtended by the persistent sepals; diameter 1.9 to 4.4 cm.—*Seed* larger than in *N. alba*, ellipsoid, brownish, 0.3 cm. long; aril longer than the seed.

Leaf cleft at base to the petiole, sub-orbicular to oval, 10 or 12 to 30 cm. long and 25 cm. wide, entire.—*Sinus*, depth: length of leaf = 1: 2.5; lobes nearly equal, inner margins curved, overlapping a little above, and spreading out toward periphery of leaf (or straight, and parallel or touching); angles more or less acute. Veins on under surface of leaf prominent, the lowest pair (i. e., those running into the lobes) curved, and, if produced, would cross, inclosing an oval area.—*Petiole* terete, smooth.

Rhizome stout, 5 cm. or more in diameter, horizontal, with strong lateral roots, but often without side-branches; apex surrounded by petioles, peduncles and stipules. Phyllotaxy about 13 on 34 with very short internodes; the surface of the rhizome may almost be said to consist of large leaf-cushions.

GEOGRAPHIC DISTRIBUTION.—

Northern and arctic Europe and Asia, south to the mountains of Germany and the Himalayas. Krumme-See, near Grubno, in West Prussia (Caspary 1884). Canton St. Gallen, in Switzerland (Gremli 1882). Lojo in Poland (Lindberg 1881). Herjedalen in Sweden (Behm 1887). Far north in Finland (Saelan 1879). Egersee, near Gratzen, in Austria (Kerner 1886). Königgrätz, in Bohemia (Hansgirk 1880). Vésztő, in Hungary (Borbás 1881). Ascends 500 meters in southern Bavaria (Schenck 1885). East slopes of Urals (Cler 1873). Triebnersee, Palatinathal, Austria (Kerner 1886). Bohemia, in ponds and ditches (Presl 1822). Austro-Hungary (Leopoldskron, coll. Stohl), *Flora exsiccata austro-hungarica*,




FIG. 66.—*Nymphaea candida*: Under side of leaf of specimen in hb. British Museum, from the classic locality (*Flora exsiccata austro-hungarica*, No. 1282), by courtesy of the Directors. P. Highley, del. Reduced one-quarter.

No. 1283. Franzensbrunn: 3 Nomenteiche, coll. Caspary, Aug. 25, 1855, in hb. Kew. Lakes of the Vosges near Sembach, Bavaria, coll. Koch, July 20, 1859. Hammerteich near Falkenberg, Ober-Schlesien, *fid.* specimen in hb. Kew. Teplitz in Bohemia, coll. Winkler, 1853, in hbb. Boissier, DeCandolle. Near Stockholm, Sweden, coll. Ljogruen, 1845, in hbb. Munich, DeCandolle. Lithuania, coll. E. Rudominówna, in hb. Kew. Neusattel near Ellnbogen, coll. Caspary & Ortman, 1855, in hb. Kew. Schwarzersee near Kitzbühel, Tyrol, coll. Traunsteiner, No. 1608, marked "*N. alba*," in hbb. Boissier, Paris. Lakes of the Baikal region, Siberia, coll. Fischer, 1836, in hb. Paris. Cashmere Lake, coll. J. E. Winterbottom, May 13, 1847, and coll. Falconer, both marked "*N. alba*" in hb. Kew.

NOTES.—The species varies widely as indicated above in the description, and as may be inferred from the lengthy synonymy. Presl's distinctions were not widely known, or were lost sight of by most botanists. He separated *N. candida* from *N. alba* largely on account of the absence of stamens from the summit of the ovary. The same name had been used for a European white waterlily by Tragus, Fuchs, Caesalpinus and others. *N. pauciradiata* was characterized by its small flowers and few carpels (8 to 9). *N. biradiata* was noticed on account of the blood-red star on the stigma. *N. basniniana* was separated from *N. alba* on account of having oval leaves instead of round, and its small number (9) of carpels. *N. cachemiriana* has also only 7 to 8 carpels; the original description is quite complete. *N. semiaperta* has as its outstanding trait the fact that even at noonday the flowers remain only half open. *N. neglecta* was marked off from *alba* by its small oval fruit, few rayed stigma, and the converging course of the lowest pair of veins of the leaf; from *candida* in having petals longer than the calyx, and ovary only one-third bare, instead of two-thirds as in Presl's *candida*; from *semiaperta* by smallness of ovary and color of stigma. It is interesting to notice how various observers have been impressed with different features of the plant as they appear more or less exaggerated in certain localities.

Probably the best disposition of the case is that of Caspary in 1879, when he first granted specific recognition to this group of forms. His paper of 1855 placed these plants in variety *oocarpa* of *N. alba*, with the following divisions:

N. alba var. *oocarpa*.

E. *angustata*—styles longer and narrower; Königswarth in Bohemia.

F. *semiaperta*—styles shorter; flower opening one half.

a. *erythrocarpa*—fruit reddish (= *N. semiaperta* and *biradiata*)

b. *chlorocarpa*—fruit greenish (= *N. neglecta*)

G. *aperta*:

a. *erythrocarpa* (= *N. kosteletskyi* and *cubogermen*, from Franzensbrunn)
(= *N. candida* Presl from Pardubitz in Bohemia)

b. *chlorocarpa* (= *N. candida* Ortman from Ellnbogen, Bohemia)
(= *N. candida* Presl from Pardubitz, Bohemia)

The name *oocarpa* was changed by the author to *oligostigma* in 1863, and finally, on discovering that crosses between *N. alba oocarpa* and *N. alba sphaerocarpa* were true hybrids, with imperfect sexual apparatus, the two were made distinct species, and the following disposition of the one in hand was given, with a few, mostly Swedish, localities.

N. candida Presl.

Var. I. *oocarpa*; fruit ovoid, higher than broad.

1. *aperta*; sepals and petals opening to form an obtuse angle.

A. *xanthostigma*; stigma yellow. Nerike; Fagertärn; E. Prussia; Königsberg; a few lakes in West Prussia.

B. *erythro stigma*; stigma more or less dark crimson, especially near apices of stigmatic rays. Södermanland and Norbotten.

a. *erythrocarpa*. Norbotten.

b. *chlorocarpa*. Norbotten.

2. *semiaperta*; sepals and petals forming an acute angle when open; fl. campanulate. Prussia, east of the Weichsel, and Bohemia.

Erythrocarpa and *chlorocarpa*, *N. biradiata* and *N. semiaperta*.

Var. II. *sphaeroides*; fruit spheroidal, broader than tall.

1. *aperta*; sepals and petals opening to form an obtuse angle.

A. *erythrocarpa*. Norbotten.

B. *chlorocarpa*. Norbotten.

2. *semiaperta*; sepals and petals forming an acute angle when open; fl. campanulate.

A. *erythrocarpa*. Norbotten; Prussia.

B. *chlorocarpa*. Prussia.

N. alba × *candida* occurs in East Prussia at Neuhausen near Königsberg, near Goldap, and elsewhere (Caspary 1879). Sernander (1894) claims to have found a red variety of *N. candida* in Fagertärn, Sweden.

Nymphaea nitida, Sims 1811 *a*, with entire, suborbicular leaves, with obtuse lobes; flowers white, cup-shaped, may belong here. Its habitat is unknown, and it has not recently been positively identified anywhere. The figure of the Botanical Magazine was "drawn at Mr. Vere's garden" in Kensington-Gore, Mr. Anderson, gardener. A specimen exists in hb. Caspary (now Berlin), which was presented by Prof. M. T. Masters in 1854 from the botanic garden of Oxford. Here it was received in 1840 from Kent, whither it came directly from Anderson. This specimen appears to belong to *N. candida* as here defined.

Nymphaea alba (L.) Presl.

Leaves nearly orbicular, floating, red when very young, 10 to 30 cm. in diameter, crowded on the rhizome, phyllotaxy about 13 on 34; *lowest pair of veins straight and diverging*. Flower odorless, pure white (in the type), 10 to 12 cm. across, opening fully. *Line of insertion of sepals rounded*, not prominent. Stamens covering the ovary to the summit. Filaments of inmost stamens not wider than the anthers. Axile process spherical. Fruit more or less spherical, seed small.

Nymphaea alba, Linnaeus 1753, *fid.* original specimen in hb. Linnaeus, without data; 1762 (in part). Willdenow 1797 (in part). Aiton 1789; 1811 (in part). Smith 1800; 1809 (in part), and all writers previous to 1822, and many since.

N. alba, Presl 1822. Reichenbach 1845. Hentze 1848 *a*; 1852 *a, b*. Schuchardt 1853. Caspary 1879. De Halácsy 1900. Conard 1901 *a*.

N. alba melocarpa, Caspary 1855 = *N. alba polystigma* Casp. 1863.

N. Aescopi, Orphanides MS. in Boissier 1883; *fid.* specimens coll. T. G. Orphanides, *Flora Graeca exsiccata*, No. 1051 (hb. Orphanid., No. 264) Feb., 1862, "ad lacu Baldovo supra Vodena Macedoniae," in hbb. Paris, Boissier.

N. Dioscoridis, Heldr. MS., in Boissier 1883; *fid.* specimens coll. Heldreich, Herbar. Flor. Hellenic., May 23, 1878, at "Aetolia: in lacu Lysimachion," in hb. Boissier.

- N. venusta*, Hentze 1848 *b*; 1852 *a*, *fid.* specimens coll. Hentze from hb. Lehmann, in hbb. Kew, Berlin.
- N. rotundifolia*, Hentze 1848 *b*; 1852 *a*, *fid.* specimens coll. Hentze, from hbb. Lehmann and Caspary, in hbb. Kew, Berlin.
- N. erythrocarpa*, Hentze 1852 *b* = *N. alba* Hentze 1848 *a*; 1852 *a*, *fid.* specimen coll. Hentze, from hb. Lehmann, in hb. Berlin.
- N. parviflora*, Hentze 1848 *b*; 1852 *a*, *fid.* specimens coll. Hentze, from hb. Lehmann, in hbb. Kew, Berlin.
- N. splendens*, Hentze 1848 *a*; 1852 *a*, *fid.* specimens coll. Hentze, from hb. Lehmann, in hbb. Kew, Berlin.
- N. urceolata*, Hentze 1848 *b*; 1852 *a*, *fid.* specimen from hb. Lehmann, in hb. Berlin.
- N. alba* var. *intermedia* Gave 1892; *fid.* original specimen coll. P. Gave, June 30, 1891, St. André, Haute Savoie.
- Castalia speciosa*, Salisbury, 1806 *a*. Britten 1888 *a*.
- C. alba*, Woodville & Wood 1806. Link 1831. Greene 1888. Lawson 1889.

DESCRIPTION.—*Flower* floating, 7 to 15 cm. in diameter, open on 4 days from 7 a. m. to 4 p. m. (7 a. m. Upsala; 8 a. m. Innsbruck, Kerner 1895), (5 p. m. Schulz 1890), faintly sweet-scented on first day of opening, odorless afterward.—*Peduncle* terete.—*Receptacle* rounded along the line of insertion of the sepals.—*Sepals* 4 (rarely 3 or 5, Eichler 1875) oblong or ovate, obtuse or somewhat acute, smooth, opening out horizontally or more, putrescent in fruit, green mostly shaded with reddish-brown outside, whitish or pale reddish within, stiff, obscurely 7-nerved.—*Petals* 12 to 24, of rather firm texture, outermost opening horizontally, grading inward in size, shape and position to the stamens. Outermost petals about as long as the calyx, lanceolate to oblong, or ovate, obtuse, white, often striped with green, gray, or reddish on the back.—*Stamens* 64 to 100 or more, covering the torus to its summit, innermost first to ripen. Outer ones 15 to 17 mm. long, innermost 4 to 5 mm. long. Anthers sulphur-yellow to orange-yellow, sickle shaped with the convexity inward, inserted at an angle with the filament, the angle being slight in the outer stamens, reaching 90° in the innermost; lines of dehiscence facing inward and downward; outermost anthers 10 to 12 mm. long, innermost about 3 mm. Filaments curved, convex side outward, bringing the anthers over the middle of the flower; outer filaments white, petaloid; innermost filament filiform, yellow, narrower than the anther. Pollen aculeate, operculum smooth; 0.038 mm. in diameter.—*Ovary* slightly contracted below the stigma, covered with stamens to the summit.—*Carpels* 8 to 24 (mean = 12 to 20); styles fleshy, triangular-ovate, rounded at apex, more or less concave and 1 to 5 sulcate on inner side, sulphur yellow, often tinted orange. Stigmatic area scarcely produced above to the bases of the styles, ending acutely. Stigma more or less deeply depressed, basin or funnel shape, sulphur-yellow. Axile process conical, acute, yellowish-white.—*Fruit* globose or depressed-globose, crowned with the styles, which are bent sharply inward. Inner wall of fruit cells whitish, spongy; tissues green or blood-red. Ripe fruit yellowish-green outside, devoid of floral leaves.—*Seed* 3 mm. long by 2 mm. in diameter, ellipsoidal or ovoid, dark olive green, smooth; raphe evident. Aril inclosing the seed, open at end opposite hilum, and with irregular margin.

Submerged leaves of adult plant 2 or 3, broadly deltoid; lamina about 10 cm. across, with stomata on upper epidermis; petiole 10 cm. long; leaves produced in fall, or in unfavorable conditions. (Cf. Arcangeli 1890 *b*.)

Mature floating leaf circular or round-ovate, entire or slightly emarginate at apex, somewhat leathery, usually dark green above, paler in astomatic area and over primary veins; yellowish-green or reddish beneath; reddish or even dark red when very young; marginal line brownish-red.—*Sinus* reaching to the petiole, open or closed, margins curved, or rarely nearly straight, separated, touching or overlapping; angles obtuse. Veins of the lobes, if produced, diverging.—*Stipulæ* large, lanceolate, narrowly emarginate, bicarinate, entirely free, far overreaching the apex of the rhizome.

Rhizome horizontal, often very thick (5 to 8 cm.), becoming 90 to 120 cm. long, black, with prominent leaf cushions. Apex protected by the long stipules and the usual long fine hairs. Phyllotaxy of a high order, about 13 on 34. Branches few, stout, strongly attached.

GEOGRAPHIC DISTRIBUTION. — Europe and Northern Africa. Great Britain (Smith 1800, etc.). Denmark, France, Germany, Italy, Spain, Greece. Algeria (Planchon 1853 *b*). Sweden. E. g. Heldreich, Herbar. Graecum Norm., No. 1106, coll. in "Euboea Septentrionalis: in stagnis Suvala ad cumen Tympanon in Telethrii." Steinitz, Flora exsiccata Austro-Hungar., No. 2056, "Hungaria: in aquis stagnantibus prope Rakos in ditioe Pestinensi." C. Scholz, No. 775 of A. Callier: Flora Silesiaca exsiccata, Editio 1895, "Guhrau: Wald bei Gabel." Lignier, No. 3452 in Magnier, Fl. select. exsicc., 1893-4, "Loir-et-cher: Villeherviers, étang au Glandier."

NOTES.—This is the *Nymphaea par excellence* of the classic botanists. It has a wide distribution and varies much in size of leaf and flower, as well as in the color of all the parts, and the shape of the fruit. Hentze (1848-52) distinguished several varieties which so fully retained their characteristics in cultivation and in propagation from seed that he regarded them as practically of specific rank. *N. splendens* was so named for its orange-yellow instead of sulphur-yellow stamens, and was collected in ponds in "Reinhardswalde in Niederhessen" and between Beberbeck and Hombressen. *N. urceolata* was characterized by the deeply urceolate stigma; collected between Rödelheim and Bockenheim, and at Bergen near Frankfurt a. M.; also at Darmstadt ("grossen Wog"), Buchrainweiher near Heissenstamm, and Bulau near Hanau. *N. venusta*, with many (24) petals and (90) stamens, and a cup-shaped flower, seemed especially showy; collected in the so-called "Grosse Judenteiche" at Gosslar in the Harz. *N. rotundifolia* was named for the shape of its leaves; collected near Heringen, "Kleinensee im Werra-Thal." Hentze's typical *N. alba* came from Sweden (Upsala). *N. erythrocarpa* was characterized by the blood-red tissues of the interior of the fruit, and came from "Bremerhafen, aus dem Lande Hadeln." *N. parviflora* was distinguished by its small flowers (7 to 10 cm. across, the others being 10 to 15 cm.), accom-

SIZE OF LEAVES.

Length.	Width.
cm.	cm.
27	24.0
27 1	25.5
35.1	30.6
37	34.4
36.4	31.2
34.4	29.3
9.5-23	9.5-23

SIZE OF FRUIT.

Height.	Diameter.
cm.	cm.
3.8	4.0
3.2	3.5

panied by leaves of the usual size; it was collected at two stations near Lich. All of these were supported by numbers of specimens in all stages of flower and fruit.

In Greece, *N. aesopii* of Macedonia was separated off by Orphanides on account of its huge size, and *N. dioscoridis* from Lake Lysimachia in Actolia for its smallness.

Caspary began his work on waterlilies by reviewing this species. He rightly maintained that the smallness or largeness of the plant is not a safe guide to classification, but, that there were other characteristics of a more profound and constant nature on which divisions could be founded. Accordingly in 1855 he gave the following arrangement:

N. alba.

I. *melocarpa*.

A. *depressa*.

a. *chlorocarpa* = *N. venusta* Htze.

= *N. rotundifolia* Htze.

b. *erythrocarpa* = *N. erythrocarpa* Htze.

B. *circumvallata*.

C. *sphaerocarpa*.

a. *chlorocarpa*.

a. *flava* = *N. parviflora* Htze.

= *N. alba* Htze.

β. *splendens* = *N. splendens* Htze.

b. *erythrocarpa*.

D. *urceolata* = *N. urceolata* Htze.

II. *Oocarpa* (see under *N. candida* Presl).

In 1863 Caspary changed the main headings, substituting I. *Polystigma* and II. *Oligostigma* in the above table. Finally in 1879, as referred to under *N. candida*, he raised the two varieties to specific rank under the names of *N. alba* (L.) Presl and *N. candida* Presl, dividing the former species and giving a few localities, thus:

N. alba.

I. *sphaerocarpa*. Fruit subglobose.

1. *platystigma*. Stigma more than half the diameter of the fruit (commonest form).

A. *chlorocarpa*. Fruit green (widely distributed).

a. *flava*. Stamens sulphur color.

b. *splendens*. Stamens orange.

B. *erythrocarpa*. Fruit more or less suffused crimson.

a. *vulgaris*. Petals white, or outer ones pale rosy.

b. *rosea*. Petals and stamens deep crimson = *N. alba* and *rosea* Hartm. Handb. Skand. Fl., 1864, p. 76.

2. *engystigma*. Stigma, measured from the backs of the processes, equal to or less than half the diameter of the fruit (rare); West Prussia, near Danzig.


II. *depressa*. Fruit depressed-globose; alt.: lat. = 2:3 to 5:6.

1. *chlorocarpa*—here and there in Germany.

2. *erythrocarpa*—here and there in Germany.

III. *urceolata*. Stigma deeply infundibuliform in fruit, sunk in to middle of fruit—in Germany, very rare. *Chlorocarpa* and *erythrocarpa*.

IV. *oviformis*. Fruit ovoid; upper one-fourth to one-third of height destitute of filaments—in some lakes of West Prussia.



NYMPHÆA ALBA RUBRA, 1-19; *N. CANDIDA*, 20-22.

Nymphaea alba rubra. 1, Partly opened flower. 2, Fully opened flower on its last day. 3, Sepal. 4-8, Petals. 9-12, Stamens of successive whorls from outside inward, viewed from front side and back. 13, Ovary stripped of sepals, petals and stamens, from the side. 14, Stigma and styles from above. 15, Section of ovary. 16, Pollen, from pole and from side. 17-19, Fruits. 20, Petal. 21, Stigma and styles. 22, Flower cut in half.

In all of these varieties, both larger and smaller forms occur. This division has been adopted by some botanists, but is decidedly too cumbrous for practical use. We have therefore inserted the most important variety and the only one requiring special notice; namely, the pink Swedish waterlily, under its usual name, *Nymphaea alba* var. *rubra*.

Var. *rubra*, Lönneroth. (Plate XV.)

Outermost petals rosy, intermediate intensely rosy, innermost deep carmine-red; anthers and stigma yellow; filaments and styles orange to deep red-brown. Variable in depth and purity of color, deepening on second and third days of flowering.

Nymphaea alba var. *rubra*, Lönneroth 1856. Liebman & Lange 1874. Garden 1879. Hooker 1884. *fid.* original specimen from Kew Garden, in hb. Kew. André 1884.

N. alba var. *rosea*, Hartman. Trimen 1872. Masters 1878. Hemsley 1879. Tricker 1897. Conard 1901 a.

N. alba sphaerocarpa platystigma erythrocarpa rosea, Caspary 1879.

N. alba sphaerocarpa rubra, Caspary 1871.

N. alba var., Fries, 1858.

N. alba var. *purpurea*, Fries MS. in Herb. Norm., *fid.* specimen, coll. T. G. Gjöbel, "Nerica, in lacu Fagertärn, par. Hammar," in hb. Kew.

N. sphaerocarpa, Carrière 1878. Tricker 1897.

N. sphaerocarpa var. *rubra*, Duchartre 1877.

N. Caspary, Carrière 1879 b (*N. Casparyi* Carrière 1880; *N. Casparyi* Carrière 1888).

DESCRIPTION.—Flowers 7 to 15 cm. in diameter, opening pale pink, changing to rose-pink or even deep red, often with a bluish cast; the color appears as linings on a white or pink ground.—*Petals* narrower than in the type, obtuse or rounded.—*Rhizomes* strong, branching as in the type.

GEOGRAPHIC DISTRIBUTION.—Lake Fayer (Fagertärn) in the Parish of Hammar, Nerike, Sweden, collected by B. E. Kjellmark in July, 1856.

NOTES.—Introduced by Caspary in 1871 and later by Froebel of Zurich, and sold in England in 1878 at £5 per root. Requires cool weather and water, and is difficult of cultivation, at least in this country. Flowered first in America by Mr. Hovey of Boston, and later by Wm. Tricker at Dongan Hills, N. J. It was received by Caspary in 1863, and in the Botanic Garden of Königsberg was found to produce highly fertile crosses with the type (*N. alba sphaerocarpa*); a close relationship was thus proven.

E. Fries, in a letter to the "Botanische Zeitung," published in 1858 (p. 73), refers to this as a *Nymphaea* with rosy-purple flowers, giving to its native pond in Nerike, the name of "Fagersjö," "the beautiful lake." He considered it only a form of *N. alba*.

Carrière writes in 1888 of a *N. casparyi alba*, as a new seedling from *N. casparyi*; the description is peculiar; but if it refers to a white form, it can be no less than a return to the typical color.

Nymphaea odorata Ait. (Fig. 67.)

Rhizome horizontal, with few stout persistent branches. Phyllotaxy about 2 on 5, with long internodes (2 to 5 cm.). Petioles *even* greenish-purple. Leaves orbicular, usually *purplish beneath*, coriaceous; sinus open or closed. Flower very sweet

scented, opening early (6 a. m.); sepals usually purplish-green or purple (pure green in var. *gigantea*). Seed of medium size.

Nymphaea odorata, Aiton 1789, *fid.* original specimen in hb. British Museum, from Kew Garden (excluding Siberian plant); 1811. Willdenow 1797; 1816. Sims 1805 *b.* Andre's tab. 297. Pursh 1814. Nuttall 1818. Smith 1819. DeCandolle 1821 *b.*; 1824. Rafinesque 1830. Planchon 1853 *b.* London 1855. Caspary 1855; 1865. Meehan 1880. Wood 1880. Gray 1889. Gray, etc., 1895. Tricker 1897. Conard 1901 *a.*

N. alba, Linnaeus 1753 (the North American plant). Walter 1788. Michaux 1803, *fid.* specimen from hb. Michx., in hb. Paris.

N. alba canadensis, Graham in Jameson Edinb. rev. str. l. journ., vol. 8, p. 386, 1826 (not seen).

N. alba flore pleno odorata, Gronovius 1762.

Castalia pudica, Salisbury 1806 *a.* Britten 1888 *a.*

C. odorata, Woodville & Wood 1806. Greene 1888. Branner & Coville 1888. Lawson 1889. Britton 1889 *a.* Britton, etc., 1894. Britton & Brown 1897.

DESCRIPTION.—*Flowers* usually floating, 7 to 12 or 15 cm. across, opening on 3 or 4 successive days from 6 a. m. to 12 m., with a strong, sweet, characteristic odor. —*Buds* of two forms, the one slender, conical, rounded at apex, the other ovoid. —*Peduncle* terete, greenish-purple, usually slender and weak (0.3 to 0.5 cm. in diameter); in the case of strong crowded plants in shallow water (30 cm. or less), the peduncles may be rigid and bear the flowers 15 cm. above the water (Sugar Hollow Pond, Danbury, Conn.). In fruit the peduncle coils into a close spiral (or loose if peduncle is very stout), bent to right or left, or both ways in one peduncle; coils 5 to 9, about 2.5 cm. in diameter. Air-canals as in *Sec. Castalia*. —*Receptacle* short, round, scarcely evident, horizontal. —*Sepals* 4, ovate to lance-ovate, rounded at apex, narrowed at base, putrescent after flowering. Outside green, more or less shaded with reddish-brown or red, covered margins nearly white; veinless; inside greenish-white. —*Petals* 23 to 32 (average 27), smaller than the sepals; outer ones ovate to elliptic-lanceolate, slightly concave, apex obtuse or rounded, narrowed at base, pure white, spreading out as much as 15° below the horizontal. Median petal slightly obovate, obtuse at apex, wedge-shaped at base. Inner petal broadly ob-lanceolate, obtuse, sides curved and tapering at base. Outermost staminode ob-lanceolate, acute, with one short anther cell. —*Stamens* 55 to 106 (average 79) inserted in direct series with the petals; innermost ripen first, outermost last. Filaments of all dimensions from staminodes to filiform threads, the innermost being more slender than their anthers, which are bent inward at right angles. Anthers curved, concave outward, placed obliquely so that the apex stands over the point of attachment or nearer the center of the flower; anthers largest in intermediate stamens. Pollen grains spherical, thickly beset with longer and shorter rods and lumps, alike from all the stamens, rupturing in germination by a large circular cap which is rough like the other parts of the grain. —*Carpels* 13 to 25 (average 17), with short linear styles, 0.64 cm. long by 0.16 cm. wide, which are erect on the first day of opening, later strongly incurved over the stigmatic disc. The latter is basin-shaped, shallow, but of varying depth. Stigmatic surface continued out on the styles one-half of their length or less, then narrowed suddenly and finally ending acuminate. Axile process nearly spherical, pointed at top, much narrowed at point of attachment. —*Ovules* many, small. —*Seed* ovoid, of medium size, 0.23 cm. long by 0.16 cm. in diameter, dark olive color, smooth, shining; aril one-fourth longer than the seed.

The seeds of *N. odorata* may germinate immediately after escaping from the fruit, or may remain dormant in cold water until the following spring; the first is probably the case with fruits ripened before September 1, the second with those




FIG. 67.—*Nymphaea odorata*: Under side of leaf on left; upper surface on right; a, sepal; b-d, outer, median, and inner petals; e, staminode; f, outer, median, and inner stamens; g, section of ovary at close of flowering period; s, stomatal area. Natural size of leaf 20.9 cm. \times 22.5 cm.; all reduced proportionately.

ripened later. In both cases probably the first floating leaves are thrown up in the summer after the seed was formed. I found great numbers of seedlings (var. *minor*) in a pond south of Marlton, N. J., August 30, 1900, with only submerged leaves. The first leaf is filiform, about 1.6 cm. long. The second is elliptic-oblong. Intermediate

leaves are ovate, cordate, rounded at apex, with rounded basal lobes and sinus. Late submerged leaves are sagittate-cordate, with deep narrow sinus; are stiff in texture, bright emerald green, and stand erect or semi-erect, 1.12 to 1.42 cm. long by 0.8 to 1.0 cm. wide.

Leaf of mature plant nearly orbicular, fissi-cordate, never peltate, entire or slightly emarginate at apex, 12 to 25 cm. in diameter, smooth and dark green above, veins not evident; under side pustulate or spongy in appearance, smooth or slightly pubescent (?), varying in color from dark dull purplish-red to green tinged with red in the lateral regions. Veins evident but not prominent beneath, the whole lamina being thickened about them. Primary veins 8 to 9 on each side of leaf. Length of principal area: length of radius of leaf = 1:1.12 to 1.2 (= 7.6 cm.: 8.6 cm.; = 6.4:7.6 cm.). Depth of sinus less than one-half the length of the leaf (1:2.5, average); margins straight or gently curved, touching, or spreading as much as 30°; angles obtuse, not at all produced.—*Petiole* terete, slender, smooth or slightly pubescent (always pubescent or hirsute when young, and at base in maturity), 30 to 180 cm. long, reddish-green to dark purplish-red, with 4 main air-canals and 2 to 4 smaller ones. Idioblasts very numerous, about 150 to 200 in central quadrangle one centimeter below leaf; many bipolar idioblasts in the smaller intercellular spaces, and a ring of thickened fibers around periphery.—*Stipules* fused into a broadly wedge-shaped, thin, white and semi-transparent scale, closely appressed to the rhizome, with two-cleft apex and slightly decurrent, oblique base; outer surface pubescent, smooth next to the rhizome; length 1.3 to 2 cm., width 1.2 to 1.4 cm.; bearing a shallow rounded furrow next to the petiole, with 2 longitudinal sub-median keels, 0.3 cm. apart beneath.

Rhizome stout, 2.25 to 3.2 cm. thick and 30 to 100 cm. long, pale in color, covered with a dense, short, black pubescence. Hairs of two types, one larger and stouter, of comparatively short, iso-diametric cells, the others much more numerous, slender, composed of few elongated cells; all with 2 or 3 discoid basal cells. Interior dull white with a pinkish tinge. Apex rounded, clothed with stipules and long fine hairs. Branches stout, few in number, their attachment 1.3 to 2 cm. in diameter.

GEOGRAPHIC DISTRIBUTION.—Common in the Eastern United States; north to Nova Scotia and Manitoba, south to Virginia and Arkansas.

NOTES.—Introduced into Europe (England) in 1786, by Wm. Hamilton. In 1801 it was "far less common" there than *N. caerulea*, and was considered a tender plant; was well known in Europe in 1850; was cultivated in McMahon's garden in Philadelphia in 1830 (Harshberger 1899), and appears in American trade-lists in 1883 and probably earlier.

Flower from June to October; fruit July to October. The roots were found to be uninjured by drying away of the water in the fall at State College, Pa. (Buckhout 1891); the plant was also seen blooming well in the absence of water at Baur's Lay, Buzzards Bay, R. I. (Sturtevant 1889). The plants which I have regarded as types grow at Bristol, Pa., in a mill-pond.

NUMBER OF FLORAL ORGANS.

ORGANS.	I.	II.	III.	IV.	V.	VI.	VII.	VIII.	IX.	X.	XI.	XII.	XIII.	XIV.	XV.	Average.
Sepals.....	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Petals.....	32	25	27	29	27	30	30	32	26	24	24	24	25	23	31	27+
Staminodes.	1	1	2	0	7	..	4	4	5	..	3	..	1	..
Stamens....	87	..	96	75	106	76	70	100	72	69	69	55	70	66	71	79+
Carpels	19	14	16	16	23	19	24	25	14	13	15	13	18	14	17	17+
Total.....	143	..	145	124	167	129	132	165	116	110	117	96	120	107	124	127+

MEASUREMENTS (IN CENTIMETERS).

SEPALA.		STAMENS.			
Length.	Breadth.	Length.	Width of Filament.	Length of Anther.	Width of Anther.
5.9	2.5	4.15	1.3	0.95	st 0.95
7.5	2.1	3.8	0.9	1.42	0.6
PETALS.		3.5	0.6	1.42	0.24
		3.5	0.5	1.42	0.2
5.9	o 2.2	2.55	0.16	0.95	0.16
6.3	o 1.8	1.9	0.13	0.8	0.08
5.4	m 1.9	0.95	0.03	0.48	0.04
5.1	i 1.75				

o = outer.

i = inner.

m = median.

st = staminode.

Var. minor Sims. (Fig. 68.)

Whole plant one-quarter to one-half the size of the type, with more of red coloration on sepals and under side of leaves.

Nymphaea odorata var. *minor*, Sims 1814. Britton 1889 a. Gray 1889. A. G. 1893. Tricker 1897. Conard 1901 a.

N. minor, DeCandolle 1821 b. Donn 1831. Not Reichenbach 1842; 1845.

N. odorata var. *parviflora*, Rafinesque 1830.

N. odorata var. *rubella*, Rafinesque 1830.

DESCRIPTION.—*Flowers* 5 to 9 cm. across (1.3 cm., G. & F. 1894 a).—*Buds* broadly or narrowly ovate, 3.3 cm. long by 2.07 cm. in diameter to 2.9 cm. long by 1.3 cm. in diameter.—*Peduncle* dark reddish-brown, 0.24 to 0.32 cm. in diameter, 10 to 50 cm. long, only half supporting the flower even when the plant has no water around it, as sometimes happens in summer.—*Receptacle* green, rounded-quadrilateral, diameter 0.64 cm.—*Sepals* dark brownish-green or pure green, red or whitish on the margins, nearly white at base, greenish-white within, obscurely 7-nerved, especially visible within; breadth: length = 1:2.8 to 2.5.—*Petals* 17 to 24, sometimes marked with pink when old.—*Stamens* 37 to 68.—*Carpels* 10 to 16; papillose area more or less continued out on the styles, which vary greatly in length and width, even in the same flower.—*Ovary* nearly spherical, 0.8 to 1.12 cm. in diameter by 0.5 to 0.63 cm. high.—*Axile process* round, translucent, whitish, its top rising above the level of the bases of the styles, i. e., in a very shallow stigmatic basin.

Leaves deep red beneath (or green when aerial), lobes usually diverging; diameter 5 to 13 cm. (4 cm., G. & F. 1894 a).—*Petioles* like the peduncles.—*Stipules* 1.3 cm.

long by 1.3 cm. wide, bifid, otherwise like those of the type.—*Rhizome* 1.3 to 1.9 cm. in diameter, densely covered with long black hairs; yellowish in cross-section.

MEASUREMENTS.

Diameter of flowers 8.9 cm.; 8.3 cm.; 7.9 cm.; 6.7 cm.; 5.7 cm.
Carpellary styles 0.4 cm. long, 0.08 cm. wide, continuation of stigma 0.13 cm. long.

GEOGRAPHIC DISTRIBUTION.—Shallow water in cold bogs and sandy soil, occurring with the type, but chiefly on the Atlantic Slope. The commonest form in New Jersey.





FIG. 68.—*Nymphaea odorata minor*: Upper row of figures from one flower of the narrow form; s, sepal; p 1, 2, 3, 4, successive petals; st 1-7, successive stamens; c, carpellary style, with stigmatic surface dotted; s 2, b 2, sepal and bud of the broader form; s 1, b 1, sepal and bud of the narrow form. st 2, staminode; 2 st 2, outer stamen; c 2, carpellary style, all of the broader form. Natural size, except carpellary styles, which are enlarged.

NUMBER OF FLORAL ORGANS.

ORGAN.	MARLTON, N. J.			RAQUETTE LAKE, N. Y.												
	I.	II.	III.	I.	II.	III.	IV.	V.	VI.	VII.	VIII.	IX.	X.	XI.	XII.	XIII.
Sepals	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Petals	24	22	17	27	27	27	24	30	25	25	24	27	27	28	25	19
Stamens	68	51	37	64	65	..	67	69	60	67	st 4	st 1	66	77	68	69
Carpels	16	12	10	14	18	..	14	15	14	14	14	14	13	17
Total	112	89	68	109	114	..	109	118	103	110	111	123	110	109

st = Staminode.

NOTES.—Specimens of this variety were found at Atco, N. J., in 1900, growing in sphagnum and peat where no water was visible; the leaves in this case were aerial,



NYPHÆA LOTUS.
collected by Schweinfurth at Damietta, Egypt.

and had stomata on the back near the apical region. Such leaves were 5 to 10 cm. in diameter, mostly or entirely green beneath. The petioles were green or purplish-green and had two large upper air-canals and two smaller lower ones, with no others visible to the unaided eye. The thickened idioblasts were very numerous, probably giving the necessary stiffness to the petiole.

MEASUREMENTS OF FLOWER I, MARLTON, N. J.

SEPALs.		PETALs.		STAMENs.		
Length.	Width.	Length.	Width.	Length.	Width.	Length of Anther.
cm.	cm.	cm.	cm.	cm.	cm.	cm.
3.5	1.35	3.35	1.12	1.75	0.4	0.64
3.5	1.35	3.0	1.15	1.75	0.24	0.7
....	3.0	0.8	1.75	0.21	0.8
....	2.3	0.55	1.6	0.10	0.64
....	1.42	0.08	0.48
....	1.12	0.08	0.48
....	0.48	0.04	0.16

FLOWER II, MARLTON, N. J.

cm.	cm.	cm.	cm.	cm.	cm.	cm.
3.7	1.75	3.35	1.42	1.92	0.48	0.48
3.5	1.75	3.2	1.6	1.9	0.5
3.5	1.75	3.2	1.42	1.75	0.4
3.5	1.75	3.0	1.42	1.6	0.21	0.64
....	2.86	1.42	1.6	0.16
....	2.4	1.12	1.12	0.08	0.48
....	st 2.07	0.8	0.8	0.04	0.32

FLOWER III, MARLTON, N. J.

cm.	cm.	cm.	cm.	cm.	cm.	cm.
2.87	1.04	2.87	1.04	1.75	0.32	0.48
2.87	1.12	2.8	1.12	0.64	0.04	0.3
....	2.8	0.95
....	2.55	0.8
....	2.4	0.4

t = Inner.

st = Staminode.

MEASUREMENTS OF SPECIMENS FROM RAQUETTE LAKE, N. Y.

SEPALs.		STAMENs.				LEAVES.				
Length.	Width.	Length.	Width.	Length of Anther.	Width of Anther.	Length.	Width.	Number of Veins.	Principal Area.	Depth of Sinus.
cm.	cm.	cm.	cm.	cm.	cm.	cm.	cm.		cm.	cm.
4.5	1.9	2.55	0.64	0.95	0.4	11.8	11.	6	4.15	5.9
4.5	1.6	2.55	0.5	0.95	0.5	15.3	13.7	7	5.4	6.0
4.15	1.6	2.23	0.16	0.64	0.08	13.1	12.4	7	5.2	5.1
3.7	1.6	1.3	0.05	0.50	0.05	14.3	13.1	6	4.8	5.4

Plants from Raquette Lake, N. Y., differ a little from the New Jersey form; the leaves tend more to an ovate shape, with overlapping sinus and slightly produced lobes; in 30 to 180 cm. of water. The flowers have a slightly larger number of organs.

Introduced into England by Pursh as *N. odorata rosea* in 1812.

Var. *rosea* Pursh.

Flowers of medium size, 8 to 10 cm. across, deep pink, or red; when closed, after once blooming, the sepals remain spread out horizontal on the water. Leaves 12 cm. in diameter, deep crimson beneath, dark purplish-green above; primary veins about 7 on each side; length of principal area:radius of leaf = 1:1.2 to 1.26; sinus open, angles somewhat produced.

Nymphaea odorata var. *rosea*, Pursh 1814, *fid.* specimen coll. Pursh 1808, in Bass and Wading Rivers, in hb. Kew. Garden 1883 *b.* Tricker 1897. Conard 1901 *a.*

N. odorata minor floribus roseis, Hooker 1883, marked *N. odorata* var. *rubra* on the type in hb. Kew; raised in Kew Garden from plants sent by A. Gray.

N. rosea, Rafinesque 1830. Donn 1831.

N. sanguinea, Donn 1831?

Castalia odorata forma *rosea*, Britton 1889 *a.*; 1890. Millspaugh 1893.

C. odorata rosen, Britton, etc., 1894. Britton & Brown 1897.

N. odorata rubra, Rev. Hortie. 1881 *b.* Wittmack Ill. Gartenztg., 1882, p. 367.

GEOGRAPHIC DISTRIBUTION.—Cape Cod; Barnstable, Mass. (Gray 1889); Lancaster, Mass. Cape May County, N. J.; Woodstown, Salem County, N. J.; Manchester, Ocean County, N. J. (Britton 1889 *a.*). Buffalo, Putnam County, W. Va. (Millspaugh 1893). Rare and local.

NOTES.—Millspaugh gives the following remarkable account of the Buffalo station: "On a plat of low bottom land near Buffalo, Putnam County, W. Va., the plough turns up a large number of small tubers each season that the soil is cultivated. These planted in tubs produce, much to the astonishment of the neighborhood, beautiful deep-pink waterlilies. How long this bottom has been drained is not known, but the evidence adduced by the fact above stated of the existence of a pond here, certainly over a century ago, is very interesting, as is also the light thrown upon the distribution of this pretty form of waterlily."

The plants in cultivation are said to have sprung from a single original specimen.

Var. *gigantea* Tricker. (Fig. 69.)

Distinguished by large size in all its parts. Flowers less odorous than in the type; sepals mostly green. Leaves turned up around apical part of margin.

N. odorata var. *gigantea*, Tricker 1897. Conard 1901 *a.*

N. reniformis, Walter 1788? DeCandolle 1821 *b.* Donn 1831. Not Gray 1889.

Castalia reniformis, Nash 1895, *fid.* original specimens.

C. tuberosa, Lloyd & Tracy 1901? MacCarthy 1885?

N. odorata var. *chlorhiza*, Rafinesque 1830?

N. spiralis, Rafinesque 1830 (excluding synonyms).

N. Maximiliani, Lehmann 1853 *a.*, as to the flower; leaf is of *N. tenerinervia*; *fid.* specimen from hb. Lehmann in hb. Berlin.

N. Parkeriana, Lehmann 1853 *a.*; 1854. Watson 1894. Conard 1901 *a.* *Fid.* specimens coll. Parker in British Guiana, from hb. Lehmann in hbb. Kew, Berlin.

N. Pringlei, Rose M.S., coll. Pringle, Plantæ Mexicanæ 1896, No. 6464, from Lake Xochimilco = *N. tussilagifolia*, Pringle 1897?

DESCRIPTION.—*Flowers* floating, 10 to 15 cm. in diameter, closed before 2 p. m.; odor dull or absent.—*Peduncles* terete, rather stout, 8 to 10 mm. in diameter, in fruit showing about 3 spiral turns 3.9 to 5 cm. in diameter.—*Sepals* narrowly ovate, rounded at apex, breadth: length = 1:2.4; outer surface green.—*Petals* 24 to 31 (average of 13 flowers, 27.6), ovate or obovate, broadly rounded at apex, tapering at base, all alike in shape, pure white, outermost petals very faintly tinged with purple on the back near the base; shorter than the sepals; breadth: length = 1:2.9.—*Stamens* 69 to 120 (average of 9 flowers, 90.5).—*Carpels* 15 to 23 (average of 9 flowers, 17.7); styles long, flat, thin, bending strongly inward after anthesis; papillose ray ending bluntly far below the tip of the style.—*Fruit* depressed globose, reddish around the bases of the styles when nearly ripe.—*Seeds* as in the type, dark olive brown, smooth, 0.224 cm. long by 0.155 cm. in diameter, inclosed in the aril.

Mature leaves 40 cm. in diameter (15 to 60 cm., Nash 1895), apical margin and part of sides turned up for 2 to 5 cm., somewhat as in *Victoria*; upper surface dark green; green beneath, with only a very faint tinge of purplish near the margin of some leaves (bright red, Tricker 1897).—*Veins*, especially the midrib, prominent, 9 on each side; principal area: radius of leaf = 1:1.2.—*Sinus* open, margins curved; angles obtuse, very little or not at all produced.—*Petioles* stout, plain green.




FIG. 99.—*Nymphaea odorata gigantea*: s, sepel; p1, p2, outer and median petals; st 1, 2, 3, outer, median, and inner stamens. Natural size.

Rhizomes stout, clothed with short dark hairs; yellowish-white inside; leaves scattered, about 2.5 cm. apart. Branches few and stoutly attached.

GEOGRAPHIC DISTRIBUTION.—Southeastern United States; Delaware to Florida and Louisiana; Cuba; Mexico; British Guiana. E. g. C. Wright, *Plantæ Cubenses*, No. 1856, coll. at Nueva Felipina, Cuba. R. M. Harper, No. 1212, Cane Water Pond, Decatur County, Ga. Nash, Pl. Cent Penins. Florida, No. 1153, vicinity of Eustis. Curtiss, No. 6672, Lake Como, Fla.

NOTES.—The plants which I have taken as types of this variety came from the Delaware and Chesapeake Canal at the railroad bridge, 2 miles west of St. George's City, Del. Here it grows in water from 60 to 120 cm. deep; in Lake Ella, Florida, it grows from the shallows of the shore out to a depth of 3 to 5 meters (Nash 1895).

If Walter's *N. reniformis* can be identified with any known plant, this must be the one; but there is nothing but its geographical range by which to verify it, as no type exists in the Walter herbarium in hb. British Museum. His description is as follows: "*N. reniformis*, foliis reniformibus, corollis polypetalis, loculis mono-

spermis." If we accept the last two words as binding, the name cannot apply to any species of the present genus *Nymphaea*, but rather to *Nelumbo*, as was understood by Rafinesque (1830). It seems best, therefore, as Caspary already advised (1865), to discard the name entirely. Gray was certainly wrong in applying it to *N. tuberosa*, a species which does not exist in the region covered by Walter's Flora. In choosing a name, therefore, we have discarded the suggestion of Mr. Nash, and accepted the established and expressive name which the plant bears in gardens. Britton & Brown (1897) are certainly right in pronouncing this plant distinct from *N. tuberosa* Paine, as is shown by the absence of tubers and the small size of the seeds. In these respects, however, as well as in the great number of idioblasts in the petioles, and the behavior in germination and thereafter, it is in agreement with *N. odorata*. An interesting parallelism exists in the European *N. alba*, of which gigantic varieties occur in the warm and sunny climate of Greece.

NUMBER OF FLORAL ORGANS.

Sepals...	4	4	4	4	4	4	4	4	4	4	4	4	4
Petals...	27	28	24	29	28	28	28	27	26	28	26	24	31
Stamens...	80	108	..	108	69	89	79	..	73	89	120
Carpels...	16	18	..	19	16	19	17	..	17	15	23
Total....	127	158	..	160	117	140	128	..	120	136	176

MEASUREMENTS.

SEPALs.		OUTER PETALS.		STAMENS OF A LARGE FLOWER.				LEAVES.	
Length.	Width.	Length.	Width.	Length.	Width of Filament.	Length of Anther.	Width of Anther.	Length of Principal Area.	Length of Radius.
cm.	cm.	cm.	cm.	cm.	cm.	cm.	cm.	cm.	cm.
6.2	2.8	6.2	2.0	4.8	0.8	2.7	0.48	13.75	16.7
6.6	2.6	6.15	2.15	4.8	0.75	1.9	0.45	14.25	18.0
6.6	2.9	6.65	2.4	4.5	0.48	1.9	0.24	7.6	a 10.3
7.25	3.05	6.2	2.5	3.2	0.16	1.42	0.13	12.1	13.8
7.2	2.5	6.8	2.2	1.75	0.05	0.64	0.08	13	16
6.7	2.4	6.0	2.2					7.1	11.1
7.0	2.85	7.9	2.3					10.7	13
7.45	3.3	7.0	2.6					12.2	14.35
6.3	2.7	8.35	2.8					7.65	11.4
8.5	3.6	5.8	2.0					10.6	15.8

a = Young leaf.

The flowers of this variety are visited by *Halictus pectoralis* ♀, in Florida (Robertson 1889).

Caspary makes varieties of *Nymphaea odorata* based on the character of the petiole, "I *Glabra*," "II *Villosa*," and "villosissima"; the first was based on the collections of Pursh, probably our type and var. *minor*; the second rested on specimens from Texas in several European herbaria, and may be nearly our var. *gigantea*; the third was collected by Paine in Hidden Lake, Herkimer county, N. Y. The classification is of a very doubtful character, since the hairiness depends wholly upon the age of the petiole, the hairs being always present in the young state, but always shed sooner or later.



NYMPHÆA PUBESCENS.

Nymphaea tuberosa Paine. (Figs. 70, 71, 72.)

Rhizome horizontal, *with many*, often compound, slenderly attached *tuber-like* branches. Phyllotaxy 2 on 5, with long internodes. Petioles green, with longitudinal brown stripes above. Leaves orbicular, *pure green beneath*; sinus usually narrow, angles slightly produced. Flowers scentless or nearly so, opening about 8 a. m.; sepals pure green; petals obovate to oblanceolate, pure dazzling white, often deflexed. Seed large.

Nymphaea tuberosa, Paine 1865, *fid.* specimen coll. Paine on S. shore of Lake Ontario, from hb. A. Gray, in hb. Kew. Hooker 1881. Garden 1882; 1897. Gray, Manual ed. 5. Caspary 1888. Sargent 1888. Tricker 1897. Conard 1901 a.

N. reniformis, Gray 1889. Not Walter 1788, etc.

N. maculata, Rafinesque 1830.

N. alba, Nuttall 1818. Not Linn., etc.

N. blanda, Hort. (in some American gardens). Tricker 1897. Not Meyer 1818.

N. tuberosa maxima, Hort. Conard 1901 a.

N. tuberosa var. *parva*, Abbott 1888.

Leuconymphaea reniformis, MacMillan 1892.

Castalia reniformis, Branner & Coville 1888.

C. tuberosa, Greene 1888. Britton 1889 a. Lawson 1889. Hitchcock 1890. Britton & Brown 1897.




FIG. 70.—*Nymphaea tuberosa*: s, sepal; p1, p2, p3, successive petals; st 1-4, successive stamens. Natural size.

DESCRIPTION.—*Flower* 10 to 23 cm. across, floating, or when crowded and in shallow water raised 10 to 15 cm. above the surface. Open 3 or 4 days (2 or 3, Sargent 1888) from 8 a. m. to 1 p. m. (2 or 3 p. m., Sargent, l. c.); odorless (or with a faint odor of apples, Gray 1889).—*Peduncle* terete, stout, 0.5 to 0.9 cm. in diameter, green, forming in fruit, in the lower portion, about 3 close spirals 6 cm. in diameter, the upper portion only slightly bent; 30 cm. to 2 meters long; air-canals as in *N. odorata*.—*Sepals* 4, often becoming reflexed to the peduncle in flower, putrescent; pure green outside, rounded at apex.—*Petals* all pure white, obovate or almost spatulate, concave, rounded at apex, wedge-shaped at base, outer ones reflexed in flower, gradually smaller inward but retaining the spatulate or obovate shape.—*Stamens* as in *N. odorata*.—*Carpels* about 14; axile process globular.—*Fruit* depressed globose, bare of all floral parts, 3.2 cm. in diameter by 2.2 cm. high.—*Seeds* few (157 in a fruit), large, dark olive-brown, smooth, with very prominent raphe; 0.44 cm. long by 0.28 cm. in diameter. Aril about as long as the seed, or shorter, not stipitate.

The germinating tuber produces at first 3 or 4 thin and fragile submerged leaves. The first is broadly deltoid, rounded or emarginate at apex, truncate at base, 2.9 to 3.8 cm. wide at base by 1.6 to 1.9 cm. long on a slender petiole 7 to 12 cm. long. The second is similar to the first or may be much larger, somewhat drawn in at the petiole, approaching a hastate shape, 6.4 cm. wide by 3.8 cm. long. Third and fourth leaves hastate, rounded at apex, 5.4 cm. wide at base by 6.4 cm. long, the sinus 1.9 cm. deep. The first floating leaf is orbicular-ovate, entire, with rounded apex, open, straight narrow sinus with lobes produced and acuminate, 5.7 to 7.6 cm. in diameter. By degrees the mature foliage is attained.

Leaf of mature plant floating, or sometimes borne 2 to 7 cm. above the water, cleft to the petiole, less leathery in texture than in *N. odorata*, orbicular, 12 to 38 cm.




FIG. 71.—*Nymphaea tuberosa*: (a) group of tubers; 1, 2, 3, first, second, and third submerged leaves from sprouting tuber. Natural size.

across, entire, or slightly curved outward at apex, smooth, bright green and somewhat veiny above (purplish and shiny when very young), darker in color over the point of insertion of the petiole. Under surface mostly smooth, pitted toward the center (sometimes pubescent, Britton & Brown, l. c.), always green at maturity, slightly purplish toward margins when young; veins rather prominent, 7 to 13 on each side; length of principal area:radius of leaf = 1:1.6.—*Sinus* depth:length of leaf = 1:2.3, open or closed, margins gently curved, touching at proximal end, 3.2 to 6.4 cm. wide at periphery of leaf, angles short-acuminate, abrupt on outer side, obtuse at point.—*Petiole* pubescent when very young, smooth at maturity, terete or a little flattened ventrally, with 1 or 2 longitudinal ridges, 30 cm. to 2 m. long, 0.6 to 0.9 cm. in diameter; 4 main air-canals surrounded by 12 smaller ones; idioblasts in very small number, about 40 in central quadrangle 1 cm. below leaf. Color green, with 12 to 24 longitudinal brown stripes due to pigment dissolved in subepidermal tissue, running from near the leaf downward 1 or 2 dm. or even the whole length of the petiole; about one-half of the stripes are broader and more prominent than the rest.—

Stipules fused, whitish, appressed, broadly triangular, slightly emarginate, with a swelling near the base, 1.4 cm. long by 1.4 cm. wide.

Rhizome horizontal, stout, 2.5 to 5 cm. in diameter, 10 cm. to 90 cm. long; color pale, almost obscured by fine dark hairs; apex protected by stipules and long fine hairs. Phyllotaxy 2 on 5, becoming less evident on older parts; leaves 2 to 2.5 cm. apart. Roots 8 or more from one leaf-base. Branches numerous, 2.5 to 7 or 10 cm. apart; originating with strong connection (1.12 cm. in diameter) with parent rhizome, but the attachment later becomes very slender (0.3 to 0.8 cm.) so that the pieces easily break off, forming the so-called tubers. Mature tubers 2.2 to 6 or 8 cm. long by 1.3 to 1.9 cm. thick, occurring singly or in groups of 2 to 5 from an originally single shoot. They are loaded with starch, and show the usual rhizome structure; they spring from any point without any visible order on the parent stem; the connecting isthmus shows (in transverse section) 3 vascular bundles with central xylem, embedded in a mass of large-celled, loose, starch-laden parenchyma.

GEOGRAPHIC DISTRIBUTION.

—North and west of the Appalachian Mountains in North America: Lake Champlain, west through the Great Lakes to Minnesota, south to Arkansas. Very rare on the Atlantic Slope. Lake Hopatcong, New Jersey, *fid.* specimens cultivated at Riverton. Poquatquissing Creek, Mercer County, N. J. (Abbott 1888, and our own collections). Meadville, Pa. (Britton & Brown 1897). Raquette River, New York (Prentiss in Bull. Torr. Bot. Cl., 10: 43-45). Ontario, Canada (Britton 1889 *b*). Grosse Isle, mouth of Detroit River (Campbell, Bull. Torr. Bot. Cl., 13: 93-94, 1886). Southeastern Minnesota (Wheeler 1900). Ames, Iowa (Hitchcock 1890). Swamps near Little Rock, Ark. (Branner & Coville 1888).

NOTES.—A smaller variety from Lake Hopatcong, N. J., is known in gardens




FIG. 72.—*Nymphaea tuberosa*. Under side of leaf on right, upper side on left; s, stomatal area; a, petiole, showing stripes; b, stipule. Natural size of leaf 24.5 cm. long; stipule reduced proportionately. Petiole enlarged.

as *N. odorata maxima* (*N. tuberosa maxima* (Hort.) Conard 1901 a); it has leaves 7 to 15 cm. in diameter; margin of leaf a little drawn in at the sinus; lobes overlapping; angles acuminate. Petiole pubescent, with a few faint longitudinal stripes. Rhizome somewhat tuberiferous. Flower medium to large, cup-shaped, with the fragrance of *N. odorata*; sepals pure green outside, petals pure white like the type; rarely produces seed. This may be a natural hybrid with *N. odorata*, since that species is common in New Jersey, and Dr. Abbott has reported a diminutive but otherwise typical form of *N. tuberosa* under the name of *N. t.* var. *parva* from near Trenton, N. J.

A pink odorless waterlily found at Painesville, Ohio, may be a variety of this (Beardslee 1877).

Nymphaea tuberosa is a very strong grower; when one wades among the plants, great numbers of the tubers are detached, and float to the surface of the water; thus the plants are distributed and will in short time take complete possession of a small pond. Gray (1889) speaks of the tubers as "spontaneously detaching"; we have seen no way for this to occur; it seems more likely that they are naturally broken off by wading animals (deer, etc.) which feed on the leaves of *Nymphaeas*, as also by frogs, turtles, and even by fish.

At the margin of the astomatic area on the leaves, the stomata are large, oval or round, and scattered, immersed in shallow pits; those of the rest of the lamina are small, round and crowded. Stomata are absent from a narrow margin all round the leaf and along the sinus.

Flower, June to September. Fruit, July to October.


According to Robertson (1889) the flowers are visited by Hymenoptera: Andrenidae: (1) *Agapostemon radiatus* Say ♀; (2) *A. nigricans* F. ♀; (3, 4) *Halictus* spp. ♀; (5) *H. pectoralis* Sm. ♀; (6) *H. occidentalis* Cress. ♀; (7) *H. coriaceus* Sm. ♀; (8) *Prosopis* sp. ♀. Diptera: Syrphidae: (9) *Helophilus divisus* Lw. (10) *H. latifrons* Lw. Bombyliidae: (11) *Spartopolius fulvus* Wied. Coleoptera: Rhipiphoridae: (12) *Rhipiphorus limbatus* F.

Subgenus 4. LOTOS, DECANDOLLE 1821 (in part).

Flowers nocturnal, raised on stout peduncles 10 to 30 cm. above the water. Sepals with 7 to 13 conspicuous and prominent veins. Stamens inserted at some distance above the petals, all flat and more or less ligulate, rounded at apex, dehiscing simultaneously. Pollen smooth. Styles linear, ligulate. Leaves sinuate-dentate with acute sub-spinous teeth. Petioles, peduncles, and under side of leaves more or less pubescent. Main air-canals in peduncles 6 (5 to 7), in petioles 2; idioblasts and multicellular ingrowths absent. Rhizome tuberous, erect, ovoid, drying off in the resting season. Seed rather small, with interrupted longitudinal lines of short hairs. Four species native to the tropics of the Old World, from Senegambia to the Philippine Islands, extending north to Hungary (two isolated localities) and south to Madagascar.

Lotos, Planchon 1853 b. Caspary 1865; 1888.

Sec. II. *Inappendiculatae* trib. I *Lotos* (in part) and trib. II *Chamaelotos* (in part), Lehmann 1853 a.



NYMPHÆA RUBRA.

1-4, Vertical sections of flowers in different phases of inflorescence. 5, Sepals. 6-7 Petals. 8-10, Outer median and inner stamens from front and back. 11, 12, 15, 16, 17, 18, 19, 20, aspects of mature pollen. 13, 14, 21, phases of germination of pollen. 22, Transverse section of style. 23-26, Hairs on ovary. 27, Stigma spread out and seen from above. 28, Ovary and carpellary styles seen from the side. 29, Ovary and stamens.

NOTES.—The following species differ chiefly in color of leaf and flower, in shape of leaf, and in production of seed. It is stated in Hooker & Thomson (1855) that all gradations in color occur in India from the white to the deep-red forms; they therefore united them into one species, *N. lotus* L., with three varieties: *a. Lotus*; leaves orbicular or reniform, densely pubescent beneath; lobes divergent or approximate; flowers ample, red, rosy or white. *β. cordifolia*; leaves cordate-ovate, densely pubescent beneath; lobes divergent; flowers of medium size, white or carneous. *γ. pubescens*; leaves puberulent or pubescent beneath; flowers smaller, white, rosy or red. These characters are wholly unreliable in cultivation, whereas the color relations come pretty true to seed, and are usually reproduced precisely from the tuber. Caspary's (1865) division of the species into var. *lata* with sepals ovate to ovate-oblong, petals white or rosy, filaments yellow; var. *angusta*, with sepals mostly oblong-lanceolate, petals white, inner filaments with a purple spot; var. *oblonga*, with sepals mostly oblong, rarely oblong-lanceolate, petals white, rosy or purple, is also unsatisfactory. There seems to be no constant morphological difference on which to base a classification. In 1888, however, Caspary speaks of *N. lotus*, *pubescens*, and *rubra* as distinct species. This opinion may have been founded on the relations of hybrids, of which many are in cultivation. But the evidence from this source is not conclusive. For example, the hybrid *N. omarrana* has bronzy green leaves and large flowers with petals pinkish-red with a nearly white streak up the middle, and the floral leaves open out horizontally; it shows plainly the blending of its *N. lotus* and *N. rubra* parentage; it bears seed, however, much more freely than *N. rubra*, but less freely than *N. lotus*. Its exact parentage is stated to be *N. lotus* × *N. sturtevantii*; the latter is a seedling from *N. devoniensis*, raised without crossing, according to Mr. Sturtevant, but it gives evidence of *N. lotus* parentage. *N. devoniensis* was at first considered to be a hybrid of *N. lotus* and *N. rubra*, but it shows no evidence of white parentage, and is probably not of hybrid origin, and Hooker & Thomson claim to have found it common in India; it very rarely produces seed, however, a character which it seems to have inherited in exaggerated form from its red parent. Whatever else may be inferred from these facts, certain it is that crossing of these forms does not induce sterility, but rather that fertility increases the nearer the mixed progeny approaches to the highly fertile *N. lotus*. From what we have seen, however, there seems sufficient reason to consider *N. lotus*, *pubescens*, and *rubra* quite distinct.




FIG. 73.—Floral organs of the *Lotos* group. Outer, median and inner stamens; carpellary style; vertical section of ovary. Natural size. From a white flowered garden form.

Nymphaea lotus (Linnaeus) Willdenow. (Plate XVI.)

Flowers usually large, white or tinged pink on backs of outer petals; stamens yellow. Fruits numerous, depressed-spherical, truncate above, yellowish-green. Seeds brown, shining, with very fine meridional ridges.

Nymphaea lotus, Linnaeus 1753 (excluding Indian and American plants), *fid.* original specimen in hb. Linnaeus, now at Linn. Soc. London. Hooker & Thomson 1855 (in part). Miquel 1859 (in part). Caspary 1865 (in part). Boissier 1867 (in part).

N. lotus, Willdenow 1797. Savigny 1802. Waldstein & Kitaibel 1802. Andrews tab. 391. Sims 1805 *a.* Aiton 1811. Delile 1813. Sprengel 1817. DeCandolle 1821 *b*; 1824. Guillemain & Perrottet 1830. Planchon 1852 *b.* Lehmann 1853 *a.* Simkovics 1883. Caspary 1888. Tricker 1897. Moenkemeyer 1897. Conard 1901 *a.*

N. lotus a Aegyptia, Planchon 1853 *b.*

N. aegyptiaca, Opiz Naturalientausch (*fid.* Steudel 1841; Casp. 1865.)

N. thermalis, DeCandolle 1821 *b*; 1824, *fid.* specimen coll. Kitaibel at Grosswardein, 1815, in hb. DeCandolle. Reichenbach 1845. Lehmann 1853 *a.* Planchon 1851 *c*; 1853 *b.*

N. dentata, Schumacher, & Thonning 1829, *fid.* specimens "ded. Schum." from hb. Lehmann in hb. Berlin; no types of this exist at Copenhagen, *fid.* Prof. E. Warming. Walpers 1842. Hooker 1846. Planchon 1850 *a.* Rev. Horticole 1851 *a.* Loudon 1855. Tricker 1897.

N. Ortgiesiana, Planchon 1852 *e.*, *fid.* specimen sent by J. E. Planchon Feb. 4, 1853, in hb. Kew.

Castalia mystica, Salisbury 1806 *b.*

C. lotus, Woodville & Wood 1806. Tratinnick 1822.

DESCRIPTION.—*Flowers* 15 to 25 cm. across, open on 4 successive nights from 7.30 p. m. to 11 a. m., the sepals and petals all standing out horizontally, and stamens all erect; nearly odorless.—*Buds* ovate, obtuse.—*Peduncle* stout, pubescent, 0.6 to 2.0 cm. in diameter, with usually 6 main air-canals, surrounded by 12 smaller ones; no spiral bending in fruit.—*Receptacle* conical, about twice as wide as upper part of peduncle.—*Sepals* 4, broadly ovate (10.8 cm. long by 5.1 cm. wide), rounded at apex, pure green on back, white at base, with 10 to 16 creamy white, prominent veins; covered margins and inside white.—*Petals* 19 or 20, oval, broadly rounded at apex, tapering slightly at base, longer than the sepals; texture rather thick and firm; 4 outermost petals green along middle of back, otherwise white, or tinged with pink or purplish; inner petals shorter and narrower, never stamenodial.—*Stamens* about half as long as the petals, yellow; outer ones with broad, persistent filament having a lunate, semi-decurrent insertion on the torus; inner filaments slightly wider than the anthers, with or without a dark purplish-brown spot on upper part; outer anthers shorter than their filaments; inner anthers as long as, or slightly longer than the filaments.—*Ovary* finely pubescent.—*Carpels* about 30; styles yellow, tinged purplish-brown on the back, becoming incurved over the stigma in fruit; stigma funnel-shaped; axile process short, cylindric, rounded.—*Fruit* large, 6 to 9 cm. in diameter, with copious seeds; stigma funnel-shaped; calyx and enlarged outer filaments persistent. Seed 1.36 mm. by 1.07 mm. to 1.44 mm. by 1.09 mm., with interrupted longitudinal lines of hairs; aril inclosing the seed.

Germination may occur immediately after ripening of the seed, or better after a period of drought. First leaf filiform, 1.6 to 1.9 cm. long. Second leaf linear to linear-ovate, rounded at apex, tapering at base, 1.9 to 2.2 cm. long by 0.48 cm. wide; petiole slender, about 1.3 cm. long. Third leaf narrowly ovate with abruptly tapering



NYMPHÆA AMAZONUM.

1, Bud. 2, Fully open flower. 3, Half open flower on surface of water. 4, Sepal. 5-9, Petals. 10-13, Stamens. 14-17, Views of ovary and carpellary styles. 18, 19, Pollen. 20, Epidermis of ovary.

base, 1.6 cm. long by 0.64 cm. wide. Fourth leaf ovate, 1.6 cm. long by 0.95 cm. wide, broadest and nearly truncate at base, the sides nearly parallel below, curving in above the middle to the rounded apex. Fifth leaf cordate-ovate, with rounded apex and lobes, 1.68 cm. long by 1.04 cm. wide, sinus 0.16 cm. deep (cf. Lubbock 1892).

The germinating tuber gives rise, all over its apical region, to a large number of slender stolons about 2.5 cm. long and 0.08 to 0.16 cm. in diameter, with a lanceolate, acute, translucent bract 0.6 to 1.2 cm. long on the basal portion, and an apical center of vegetation, from which about three submerged leaves are first formed, varying greatly in size according to the supply of nourishment. The first leaf may have a petiole 3.8 cm. long, bearing a filiform midrib 1.3 cm. long with a minute protuberance on either side at base representing the lamina; or the lamina may be expanded as a linear terminal lobe with a shorter linear lobe on either side of the rounded




FIG. 74.—Early leaves of the *Lotos* group, from germinating tuber of *N. devontensis* Hort.: 1a, lamina and stipules of first submerged leaf; 2a, lamina, 1, stipules, of second submerged leaf; 2f, 3f, second and third floating leaves. Laminae natural size. Stipules enlarged.

base. The second submerged leaf is deltoid, with rounded angles and broad, shallow, rounded sinus. The third leaf is broadly deltoid, with deeper sinus. All three appear at first of a reddish color, later becoming green; their texture is very soft and thin, and margins entire. The first floating leaves vary much in size according to food-supply, but are entire, oval, deeply cordate, with rounded apex and lobes; length: breadth = 1.5:1 (about); gradually leaves of a more circular outline are produced, and when practically round the dentation appears, at first very faintly, slowly reaching the adult form in the older leaves.

Leaf of mature plant distinctly peltate (2 to 5 cm.), orbicular, 20 to 50 cm. in diameter, subspinose-dentate and more or less wavy at margin, the teeth being sharp and brown-tipped, situated on the crests of the vertical undulations of the margin, 1.3 to 5.0 cm. apart, with curved sinuses. Texture very firm and stiff by reason of the large prominent veins of the under surface; primary veins about 9 on either side

of the leaf, ramifying and anastomosing into a close reticulum, terminating in the teeth of the leaf-margin; the midrib may project as a narrow ridge, 1.3 cm. high near the petiole, becoming only 0.16 cm. high at apex, with sides perpendicular to the surface of the leaf. Upper surface of leaf dark green and shining; under surface greenish or dull purplish-brown, puberulent or rarely glabrous.—*Sinus* open or with margins slightly overlapping, rather shallow on account of the width of the peltation; angles formed by one of the dentations of the leaf.—*Petiole* 60 to 160 cm. long, 0.6 to 1.3 cm. in diameter, terete, usually pubescent, with a very strong "collar" at point of insertion of the leaf, with two main air-canals placed transversely, two smaller canals anteriorly and posteriorly and a ring of 14 smaller ones surrounding the 6 just mentioned. Stellate cells absent.—*Stipules* present as a narrow transparent wing on either side of the petiole at base.

Tuber from seedling plant ovoid, roughened with small scattered leaf-scars below, tapering to a point at the vegetative end, which is surrounded by long hairs. During the growing season, stolons in every way similar to those of the germinating tuber in shape and foliage as produced, along with short lateral buds on the caudex. At the approach of the succeeding resting season, the old caudex dies, and the stolons and buds ripen into rounded irregular tubers, smooth beneath and rough-hairy above, from which the plant is easily propagated. During active vegetation the caudex is covered closely by leaf-bases, is ovoid, 7 to 10 cm. long by 5 to 6 cm. thick.

GEOGRAPHIC DISTRIBUTION.—Egypt; central and west Africa. Senegambia, Guinea, Madagascar. Grosswardein, Hungary. E. g. coll. Schweinfurth, Nov. 6, 1887, Damietta, Egypt. Coll. Haynald, Fl. exsicc. austro-hungar., No. 72, at Grosswardein.

NOTES.—The following species were set up, apparently on insufficient grounds: *N. dentata*, white flowered, with narrow petals (width:length = 1:3.4), a purple spot on upper part of inner filaments (and leaves glabrous beneath. Schum. & Thonn.); the flower remains open until 1 p. m. Since the plant bearing this name in our gardens has the leaves densely pubescent beneath, its identity with the type form collected in Sierra Leone may be doubted. *N. thermalis* was separated from *N. lotus* chiefly for geographical reasons, and named on account of its habitat, namely, the hot springs of Grosswardein and Kaiserbade in Hungary. It has petals approaching in shape those of *N. dentata*, and is figured by Reichenbach (1845) as of a white color tinged with purplish.

The type form of the species was introduced into England from Egypt in 1802; the *dentata* form was brought from Sierra Leone by one Mr. Whitfield in 1846, and flowered first in that year (Hooker).

The resting tubers and seeds are important articles of food in Egypt and West Africa; the former are boiled, or roasted in the ashes of a fire, and are said to be quite palatable; the latter are washed clean from the decaying carpels and arils, dried, and ground into flour, from which a kind of bread is made. Both parts are very rich in starch.

In a plant of this species from Lake Nyassa, cultivated at Kew in 1886-88, some, or later all, of the flowers were transformed into tubers, which dropped off into the mud on the decay of the peduncle (Barber 1889).

The Linnaean specimen bears no data but the name, and the center of the leaf has been destroyed by insects. To this sheet is pinned a second, without mark of any kind, but bearing a flower of *N. odorata*. Reference is also made under *N. lotus* in the Species Plantarum to a specimen noted in Flora Zeylanica. This plant is in hb. Hermann,* now British Museum, and belongs to our *N. pubescens*.

Specimens of *N. thermalis* from the "locus classicus" seen in London show a




FIG. 75.—*Nymphaea zenkeri*. Flower and under side of leaf natural size. Stamen $\times 2$. From the specimen of Zenker in hb. Berlin, drawn by J. Pohl, by kind permission of the Directors.

peculiar venation of the leaf. In the *Lotos* group generally there is no plain demarcation of the primary areas of the network of veins; but in the plants referred to these areas were sharply marked off by short transverse veins about half way between the center and margin of the leaf. We would not care to separate the two forms, even as varieties, without further acquaintance with living plants direct from the classic localities.

Nymphaea zenkeri Gilg, n. sp. (Fig. 75.)

"Rhizome small, conical; leaves long petiolate, deeply cordate, i. e., deeply and very narrowly triangular-excised; the outline suborbicular or ovate-orbicular, repand-

sinuate-dentate; thin and membranaceous; younger ones glabrous, adult or sub-adult leaves glabrous above, densely pilose beneath with very short hairs; veins slightly prominent above, manifestly so beneath; venation loose, conspicuous; flowers 5 to 7 cm. in diameter, 'white'; sepals 4, ovate-lanceolate, acute, whitish within, light green outside; petals 7 to 8, smaller than the sepals, and becoming decidedly smaller and narrower inward; stamens 35 to 45, broadly linear; anthers rather short, connective scarcely produced; carpels several.

"Leaf 10 to 15 cm. long, 9 to 13 cm. wide; the sinus is about 2 to 4 cm. wide at base of lobes. The sepals are 2.5 to 3 cm. long, 7 to 10 mm. wide; the petals decrease in size inward down to 2 cm. long and 4 mm. wide. The outermost stamens are about 2 cm. long and 3 mm. wide at base, anthers 7 mm. long by 2 mm. wide." (E. Gilg.)

N. Zenkeri, Gilg, in herbaria.

GEOGRAPHIC DISTRIBUTION.—"Cameroon: Bipindi, in slowly flowing brooks and in streams of the Lokundje at Bequanohe. Coll. Zenker, No. 2130. Flower in July." (E. Gilg.)

NOTES.—Finding this species labeled by Professor Gilg in several European herbaria, but there being as yet no published description, we were favored by the Berlin professor with the above description from his own pen, based on the specimens in the Royal Herbarium. We have gladly inserted it therefore, translated *verbatim* from the Latin and German in which it was communicated.

Nymphaea pubescens Willdenow. (Plate XVII.)

Flowers small, white; stamens yellow. Leaves small, *ovate*, dark green. Fruits numerous, nearly spherical, contracted above, dark green. Seed spherical-ovoid, brownish-olive, shining, nearly smooth.

Nymphaea pubescens, Willdenow 1797. Aiton 1811. Smith 1819. Wight & Arnott 1834. Planchon 1853 *b*. Lehmann 1853 *a*. Caspary 1888.

N. lotus, Linnaeus 1753 (in part), *fid.* specimen in hb. Hermann, now British Museum. Roxburgh 1814; 1824. Hooker & Thomson 1855 (in part). Miquel 1859 (in part). Caspary 1865 (in part). Kurz Veg. cil. Bangk. (*fid.* Caspary 1865). Boissier 1867 (in part). Blanco 1878?

N. Coteka, Roxburgh 1806 = *Castalia edulis*, Salisbury 1806 *b*.

N. esculenta, Roxburgh 1814; 1824.

N. edulis, DeCandolle 1821 *b*.

N. sagittata, Edgeworth 1845, *fid.* specimen coll. M. P. Edgeworth, 1844, in N. W. India, in hb. Kew.


N. semisterilis, Lehmann 1853 *a* (*fid.* Hooker & Thomson 1855, and specimen in hb. Kew).

N. bella, Lehmann 1853 *a* as to the leaf, *fid.* specimen from hb. Lehmann in hb. Berlin. Flower is of *N. stellata* Willd.

N. Nouchali, Burman 1768, *fid.* specimen coll. Burman in India, in hb. Delessert = *N. Naccheli* J. F. Gmel. Syst. 1591, *fid.* Hooker & Jackson 1893.

Castalia sacra, Salisbury 1806 *b*.

DESCRIPTION.—*Flowers* small to medium size.—*Sepals* 7 to 9 cm. long, obtuse; green outside, with white veins.—*Petals* pure white; outer ones broadly obovate, width: length = 1:2.6.—*Outer stamens* not lunate-decurrent at insertion, separated from the petals by a wide gap.—*Fruit* about 4 cm. in diameter. Seed 1.9 mm. long by 1.52 mm. in diameter.



NYMPHÆA RUDGEANA.

1, 2, Views of the flower. 3, 4, Fruits. 5, Bud. 6, Same as 5, with outer floral organs removed. 7-10, Petals. 11-15, Stamens. 16-19, Views and details of gynoecium. 20-22, Pollen. 23, Fruit. 24, Cross section of ovary. 25-27, Sections of style. 28, Vertical section of stigma, showing papillae.

Leaves 25 cm. long or less; breadth length = 1:1.28.—*Sinus* open or closed; margin mostly curved. Upper surface of leaf dark green, under surface dull purplish-green, more or less pubescent. Length of petal: length of leaf = 1:12.

Tuber large, ovoid. (Other details as in *N. lotus*.)

GEOGRAPHIC DISTRIBUTION.—British India to the Philippine Islands; south to Java and Australia.

NOTES.—Of most of the plants classed above as synonyms descriptions are not available. *N. sagittata* was separated on account of its open sinus and entire, sagittate leaves; these were doubtless from a young plant. It was collected at Ambala, province of Sirhind, India. *N. semisterilis* is said to have the leaves obtusely dentate or crenate. No one except the founders of these two species has ever considered them distinct. The names *edulis* and *esculenta* were given in reference to the use of the tubers and seeds in India as food, as is the case with *N. lotus* in Africa.

N. pubescens is said to have been introduced into England from India in 1803. Willdenow took as his type the plate entitled "Ambel" in Van Rheede's Flora Malabarica.

The description and diagnosis given above are based on a plant grown by Mr. Tricker in the Dreer gardens at Riverton, N. J., in 1902, from seed sent by Mr. Gollan of Saharanpur, India, corroborated by comparison with herbarium material.

Nymphaea rubra Roxburgh. (Plate XVIII.)

Flowers deep purplish-red; stamens cinnabar-red, becoming brownish. Leaves large, dark bronzy red, becoming greenish in age. Fruits rare. Seed nearly spherical, dull brown, with fine, prominent, meridional ridges.

Nymphaea rubra, Roxburgh 1806; 1814; 1824; *fid.* color drawings in hb. Kew. Andrews tab. 503. Sims 1810. Aiton 1811. Smith 1819. DeCandolle 1821 b; 1824. Wight & Arnott 1834. Wight 1850. Planchon 1850 b and d; 1852 a. Lehmann 1853 a. Lindley 1853 a.

N. lotus, Hooker & Thomson 1855 (in part). Miquel 1859 (in part). Caspary 1865 (in part). Boissier 1867 (in part). *Not* Linn. 1753.

N. rubra var. *rosea*, Sims 1811 b.

N. rosea, Sweet 1827.

N. Devonensis, Hooker 1852 b, and Lindley 1853 b, *fid.* Hooker & Thoms. 1855. Garden 1883 a.

Castalia magnifica, Salisbury 1806 b.

C. lotus flore rubro, Tratinick 1822.

DESCRIPTION.—*Flowers* 15 to 25 cm. across, deep purplish-red, open from 8 p. m. to 11 a. m.—*Sepals* dull purplish-red, about 7 nerved, never opening more than 10° above horizontal.—*Petals* 12 to 20, narrowly oval, breadth: length = 1:3.15, rounded at apex, standing at various angles in the open flower from 45° to the level of the sepals.—*Stamens* about 55, cinnabar-red, becoming brownish.—*Fruits* very few, small.—*Seeds* 1.85 mm. long by 1.6 mm. in diameter.

Leaves large, 25 to 45 cm. across, dark reddish-brown, bronzy, becoming greenish in age; under surface pubescent. (Other details as in *N. lotus*.)

GEOGRAPHIC DISTRIBUTION.—British India; Bengal.

NOTES.—In gardens is distinguished *N. rubra rosea*, with leaves bronzy green blotched with brown; flowers large, magenta to dull red, open until 10.30 a. m.; petals narrow, pointed; stamen tips orange-brown.

We are doubtful if the true *N. rubra* exists in this country. Seed communicated by Mr. Chandradatta of Calcutta has germinated but produced no flowering plants as yet. It was introduced into England in 1803.

N. devoniensis at Lyon House, England, in 1885 produced a flower whose peduncle arose from the axil of a stamen of a previous flower (Barber 1889), and Dr. Kirk, according to Masters (1869), observed a similar abnormality in *N. lotus* in East Africa. The sepals, petals, stamens and even carpels of these species may become leaf-like (Masters 1869).

We have to admit that our arrangement of the *Lotos* group is far from being satisfactory or final. Important results would certainly follow a study of the plants of various parts of Africa, Asia and the outlying islands. This can only be done effectively on living plants, either in cultivation or in their native haunts. The several forms in gardens have proven useless on account of uncertainty of origin and probable admixture of other stocks by crossing.

Subgenus 5. HYDROCALLIS, PLANCHON 1852 b; 1853 a.

Flowers nocturnal, floating. Sepals not evidently veined. Petals in whorls of 4, alternate with the sepals and with each other. Stamens inserted in series with the petals, the outermost 4 or 8 more or less petaloid and in whorls like the petals; anthers dehiscing about simultaneously. Styles slender, cylindric, with enlarged club-shaped tips. Seeds small or minute, with numerous long hairs. Leaves entire, or dentate-sinuate with obtuse teeth. Rhizome erect, tuberous, drying off in the resting season. Ten known species, natives of the tropics of the Western Hemisphere.

Hydrocallis, Caspary 1878; 1888.

Castalia (in part), DC. 1821 b.

Tribe *I. eucanthos* (in part), *Chamaelotos* (in part), *Lotos* (in part) and *Castalia* (in part), Lehmann 1853 a.

***Nymphaea amazonum*, Martius & Zuccarini. (Plate XIX.)**

Number of floral parts 132 to 376. Sepals ovate-oblong, more or less acuminate. Petals 16 to 20, rows all about equidistant. Stamens 93 to 297. Pollen 0.0142 to 0.0174 mm. in diameter. Carpels 19 to 40. Fruit with funnel-shaped stigmatic disc, the funnel surface curved; sepals and outermost row of petals persistent. Seeds 10,000 to 27,000, very small, 0.386 mm. wide by 0.706 mm. long to 0.566 mm. by 0.973 mm., dull gray. Mature leaf entire, lobes subacuminate or rounded. Top of petiole bearing a ring of long hairs. Tuber producing stolons throughout its vegetative period. Flowers imperfectly opening two nights, becoming fully open suddenly the second night between 4 and 5 o'clock a. m. Bud ovate-oblong, acuminate.


Nymphaea amazonum, Martius & Zuccarini 1832, *fid.* specimens coll. Martius, No. 3313, near Para, Brazil, in hbb. Munich, Berlin. Planchon 1853 b. Lehmann 1853 a. Hooker 1854. Caspary 1878. Sagot 1881. Conard 1901 a.

N. albo-viridis, St. Hilaire 1833, *fid.* specimen coll. St. Hilaire, Prov. Rio de Janeiro, Brazil, in hb. Paris.

N. blanda, Macfadyen 1837. Hort. Glasnevin (*fid.* Hooker, l. c.). Not Meyer 1818.

N. blanda β *Amazonum*, Planchon 1856.

N. Rudgeana β *Amazonum*, Grisebach 1864. Not *N. rudgeana* Mey. 1818.



NYPHÆA BLANDA, N. BLANDA FENZLIANA, N. TENERINERVIA, N. STENASPIDOTA.

N. tenerinervia. 1, Flower. 2, Lower surface of leaf. 3, Apex of outer stamen. 4, Apex of innermost stamen. 5, Carpellary style. 6, Upper surface of leaf. 7, Outer surface of sepal.

N. stenaspidata. 8, Outer surface of sepal.

N. blanda fenzliana. 9, Young fruit. 10, 11, Outer and median stamens. 12, Leaf.

N. blanda. 13, Flower viewed from side. 14, Leaf. 15, Part of upper surface of same leaf. 16, Flower.

N. integrifolia, Salzmann MS., *fid.* specimen coll. Salzmann, 1830, at Bahia.

N. foetida, Gardner MS., *fid.* specimen coll. Gardner, No. 2477, Aug., 1839, in the Lake of Parana-gua, in hb. Berlin.

N. nocturna, March MS. (*fid.* Hooker, l. c.),

DESCRIPTION.—*Flower* floating, 10 to 12 cm. across, opening two nights. The first night, the bud stands with its base about 1 cm. or more immersed in the water, and begins to open about 3 o'clock a. m.; it spreads gradually until 4.15 a. m., when the sepals stand out at about 45° and the petals are loosened, leaving an aperture 1.3 cm. wide into the center of the flower. At 4.45 a. m. it begins to close, being completely closed about 6 a. m. The second night the bud has risen till its base is just out of the water, and begins to loosen at the apex at 6.30 p. m.; the sepals spread out rapidly to a horizontal position, followed by the outermost series of petals, which reach nearly the horizontal position; the second series also open slightly from the tip of the bud (about 1 cm.); this phase is completed by 8 p. m., a tight creamy-white acute bud being left in the center of the flower. The flower remains thus until about 3.30 a. m., when the parts begin to open out more fully, the process being completed about 4.45 a. m. At this time the sepals and outermost petals are horizontal in position, the inner petals standing at all angles up to about 40° above the horizontal; the outermost stamens lie against the innermost petals; from this position the stamens stand at all angles up to the innermost which bend over the stigma. All of the stamens have now dehisced, the flower is warmer than the surrounding air, and has a very faint sweetish odor with a suggestion of peaches. Closure of the flower begins about 5 a. m., and is led by the stamens and petals; these, with exception of 1 or 2 outermost petals, are united into a tight bud at 5.30 a. m., while the sepals are only 10° to 15° above the horizontal. By 6 o'clock complete closure is effected, and the flower is retreating below the water, where it becomes completely covered before the middle of the succeeding afternoon, i. e., in eight hours or less. From 7 to 7.30 p. m. and from 4 to 4.30 a. m. the movements of the petals and sepals on the second night is very rapid and may easily be seen; the apex of the organ rotates about its base, moving about 1.3 cm. in three minutes; the aperture at the apex of the bud therefore enlarges at twice this rate. In one observation the innermost petals were closed over the stamens at 4 a. m.; at 4.06 their apices stood 5 cm. apart! The closure of the flower after its full maturity is almost as rapid.—*Bud* 5.4 to 7.3 cm. long by 2.7 to 3.8 cm. in diameter, conical-ovate, broad at base, acuminate above, more or less obtuse, abruptly contracted below to the petiole.—*Peduncle* 40 to 50 cm. long, 0.6 to 0.8 cm. in diameter, terete, brownish-green, lighter at base, smooth, with 3 minute central air-canals, 6 to 7 main canals and 12 to 14 outer canals, separated by extremely thin partitions.—*Receptacle* round, pure dark brown, nearly horizontal, distinctly bounded from the sepals at the margins.—*Sepals* 4, fleshy, ovate, rounded at apex, carinate on back in upper part, the ridge vanishing about two-thirds of the length from the tip. Outer surface dark green above, paler below, the lower quarter being greenish-white; whole surface marked with strong purplish-black lines and dots, the lines becoming bright red on the lower quarter of the sepal. Inner surface apple green above, shading to greenish-white at base, with a few dull brownish spots and streaks on margins in upper half. Innermost (posterior) sepal deeply hooded at apex, i. e., the fleshy tip is

excavated, forming a scoop-like depression about 0.3 cm. deep, which receives the tip of the bud and covers it above and on three sides; outermost (anterior) and right sepal slightly hooded, left sepal very slightly hooded. Margins of innermost sepal covered in the bud, about 0.16 cm. wide, whitish and semi-transparent. All veinless, persistent in fruit.—*Petals* 16 to 20, of a yellowish-white color, rather thick and leathery, a little shorter than the sepals, deeply concave and slightly hooded at apex; when cut off from the receptacle (of a closed flower), the basal portion curls inward strongly, showing the tension to which it has been subjected in closure. Outer petal broadly elliptic, obtuse, obscurely 11-nerved; second and third series similar; fourth series similar but broader in proportion at middle and base, and more rounded at apex; fifth series becoming acute at apex.—*Stamens* 136 to 188, yellowish-white, with dirty yellow anthers, unappendaged. The lowest series of 8 have broad filaments with a fleshy midrib and parallel anther cells; filaments of second series about one-third as wide as the first, the inner ones becoming more slender and placed without visible order; innermost filaments narrower than their anthers.—*Carpels* 25 to 35, styles clavate, about 1.3 cm. long, the enlarged tip 0.5 cm. long by nearly 0.3 cm. in diameter, pure red around the end, the extreme tip whitish; they stand alternately in two positions—one is bent directly inward so that the tip touches the stigmatic disc two-thirds of the way to its center; the one on either side of this is coiled spirally so that the apex lies beside and against its base, there being but one turn of the coil. Stigmatic disc curved, scarcely depressed at center; papillose area continued 0.3 cm. out on the styles, where it ends obtusely. The stigmatic papillæ break up at the flowering time into a moist powdery mass of cells lying singly or in chains, of a golden yellow color. Axile process 0.25 cm. high by 0.08 cm. in diameter, appearing as a slender acute rod projecting half of its length from a narrow pit at the center of the flower.—*Ovary* spheroidal, 1.6 to 2.4 cm. in diameter, 1.12 to 1.42 cm. high. Ovules very numerous, very small.—*Fruit* sub-spherical, with sepals and outer petals standing loosely round it, about 3.9 cm. in diameter.—*Seeds* very small and very numerous, 0.1 cm. long by 0.074 cm. in diameter, reddish-brown in color, with a silvery appearance due to many scattered long white hairs; raphe scarcely evident.

Germination takes place as soon as seeds are shed. First leaf filiform, short (0.95 cm. long). Second leaf spatulate, rounded at apex, tapering at base, 0.8 cm. long by 0.32 cm. wide. Third leaf elliptic ovate.

Leaf of mature plant orbicular-ovate, breadth: length = 1: 1.2 to 1.18 (17.2 cm. by 14.3 cm), rounded at apex, peltate by about 0.3 cm., thin and soft in texture; margin entire, somewhat wavy up and down; upper surface green, yellowish toward the center, with faint brownish spots. Under surface glabrous, brownish-red, with numerous small spots of a blackish color. Veins all prominent, 7 to 9 on each side. Length of principal area: radius of leaf = 1: 1.4 to 1.47 (2.4 cm.: 3.5 cm.).—*Sinus* open or closed, depth: length of leaf = 1: 2.3 to 2.6 (7 cm.: 17.2 cm.), margins approaching or overlapping, nearly straight above, becoming strongly curved outward toward periphery, forming two broad, round, more or less widely separated lobes.—Astomatic area small; stomata becoming larger and scattered near it, but stopping rather suddenly.—*Petiole* glabrous, except a ring of long simple hairs at its junction with the leaf; 45' to 60 cm. long, 0.9 cm. in diameter; with two transversely placed

main air-canals, two smaller ones anteriorly and posteriorly, and two still smaller ones beyond these; one lateral canal on either side of main pair, and numerous smaller ones about; main partitions 2 cells thick; one double bundle anteriorly and one posteriorly and two equidistant from these and from each other on either side; numerous smaller bundles. Idioblasts numerous, all stellate, rather short armed.

Rhizome (tuber) erect or semi-erect, thick, about 7 cm. long by 3.8 cm. in diameter, brownish-black, apex protected by leaf-bases and long hairs. Phyllotaxy of a high order, the leaf-bases being very close together. Branches several (3 to 5 or 6), 7 to 10 cm. long on short stolon-like stalks, produced throughout the season of vegetation, and sending up leaves and flowers among those of the parent plant.

GEOGRAPHIC DISTRIBUTION.—In still water; lakes, ponds and ditches. Tropical America between 18° N., 23° S., 38° W., and 78° W., in Jamaica, Guiana, Surinam, Brazil (Para, Bahia, Rio Janeiro). New Granada. Laguna del Corcho, near Ocuiltzapotlan, Mexico.

MEASUREMENTS OF STAMENS (IN CENTIMETERS).

FLOWER 1.				FLOWER 2.				FLOWER 3.	
Length.	Width of Filament.	Length of Anther.	Width of Anther.	Length.	Width of Filament.	Length of Anther.	Width of Anther.	Length.	Width of Filament.
o 3.75	0.95	1.1	0.3	st 3.7	1.4	0.47	o 4.0	1.12
o 3.5	0.7	1.1	0.24	st 3.2	1.1	0.64	o 4.0	0.8
3.2	0.32	1.3	0.16	st 3.35	1.1	0.64	3.5	0.48
2.9	0.3	1.1	0.16	3.0	0.56	0.9	0.24
2.8	0.16	1.1	0.16	2.6	0.24	1.0	0.16
1.4	0.08	0.85	0.15	2.5	0.16	1.12	0.16
....	2.23	0.08	0.95	0.15
....	1.75	0.08	0.8	0.11
....	1.42	0.08	0.64	0.11

o = outer whorl. st = staminode. s = second whorl.

NUMBER OF FLORAL ORGANS.

Organs.	I.	II.	III.	IV.	V.	VI.	VII.	VIII.	Average.
Sepals.....	4	4	4	4	4	4	4	4	4
Petals.....	20	16	16	20	20	16	20	17	18+
Stamens.....	172	162	165	178	163	188	139	168
Carpels.....	30	30	30	33	32	35	25	30+
Total.....	226	212	215	235	219	247	185	219+

MEASUREMENTS OF SEPALS (IN CENTIMETERS).

Sepal.	FLOWER 1.		FLOWER 2.		FLOWER 3.	
	Length.	Breadth.	Length.	Breadth.	Length.	Breadth.
Outermost.....	7.3	2.9	7.0	2.7	5.6	2
Right.....	7.5	2.9	7.0	2.6	5.6	2
Left.....	7.3	2.8	7.0	2.55	5.6	2
Innermost.....	7.3	3.0	7.0	2.7	5.7	2.4

MEASUREMENTS OF PETALS (IN CENTIMETERS).

Series.	FLOWER 1.		FLOWER 2.		FLOWER 3.	
	Length.	Width.	Length.	Width.	Length.	Width.
Outermost.....	6	2.4	6.5	<i>o</i> 2.7	5	2
	6.4	<i>r</i> 2.7	4.95	2
	6.5	<i>l</i> 2.7
	6.4	<i>i</i> 2.7
Second.....	5.8	2.4	6.2	2.7	<i>o</i> 4.5	1.9
	6	2.7	<i>i</i> 4.5	1.9
Third.....	5.3	2.2	<i>o</i> 4.3	1.9
	5.1	2.1	<i>i</i> 4.15	1.75
	5.3	2.2
	5.2	2.1
Fourth.....	4.95	2.4	<i>o</i> 4.0	1.9
	4.95	2.1	<i>i</i> 3.7	1.4
	4.8	2.2
	4.7	1.9
Fifth.....	4.3	1.6	<i>o</i> 3.5	1.4
	4.6	1.9
	4.5	1.9
	4.3	1.6

o=outermost. *r*=right. *l*=left. *i*=innermost.

NOTES.—A very interesting species. The tubers may be dried off, but keep better in continuous vegetation, which may be arrested by small pots during the winter. In its native haunts it probably flowers all the year.

The outermost staminodes sometimes have two apices, and resemble a fusion of two such organs. The inner stamens also may be found with two or three anthers, either on the same or on separate connectives.

Var. *goudotiana* (Planchon) Caspary.

Peduncle bearing a ring of long hairs at top.

Nymphaea Goudotiana, Planchon 1853 *a* and *b*, *fid.* original specimen in hb. Paris.

N. amazonum forma *a Goudotiana*, Caspary 1878.

GEOGRAPHIC DISTRIBUTION.—New Granada (Llanos D'Illbog), coll. Holton, No. 689 in hb. Boissier. Province of Piahy, Brazil.

NOTES.—Sagot (1881) records a "*forma submersa*," with submerged leaves, but without further description, from a specimen coll. Karouany, 1855, No. 25 of hb. Sagot, in French Guiana; now in hb. Kew.

Nymphaea rudgeana, G. F. W. Meyer. (Plate XX.)

Number of floral parts 80 to 127. Sepals ovate-oblong. Petals of the third whorl separated from the lower ones by a wide interval. Stamens 43 to 83. Pollen 0.0324 to 0.0362 mm. in diameter. Carpels 11 to 24. Fruit bearing the deeply funnel-shaped stigma, surrounded by the sepals, petals and stamens, all of which are per-



NYMPHÆA LASIOPHYLLA AND *N. RUDGÉANA*

- N. lasiophylla*. 1, 2, Flower from face and back. 3, Leaf, showing lower side. 4, Part of larger leaf from above, lobes touching. 5, 6, Outermost and innermost stamens. 7, Part of lower surface of leaf.
- N. rudgeana*. 8, Leaf of a plant from Jamaica. 9, 10, 11, Stipules of three leaves of the Jamaica plant. 12, Fruit, raised at Königsberg. 13, Another fruit raised at Königsberg with sepals and petals removed. 14, Königsberg fruit in median section. 15, Small flower, island of Colares. 16, Sepal of a flower from Brazil. 17, 18, Stamens of same flower. 19, Apices of median and innermost stamens.

sistent. Seeds 1,000 to 8,000, short-elliptic, 1.15 mm. in diameter by 1.6 mm. long, to 1.3 mm. by 2.2 mm., shining, greenish-gray. Mature leaf sinuate-dentate. Petiole naked at point of insertion. Tuber producing stolons only when first germinating from the dry state. Flowers imperfectly open two or three nights, rarely entirely open before midnight. Buds ovate-oblong.

Nymphaea Rudgeana, G. F. W. Meyer 1818. Grisebach 1864. Caspary 1878. Garden 1883 b. Conard 1901 a.

N. ampla β *rudgeana*, Planchon 1853 b. Not *N. ampla*, DeCandolle 1821 b.

N. blanda, Planchon 1853 b; 1856. Caspary MS. in several herbaria, written about 1865 and before. Not Meyer 1818.

N. blanda β *amazonum*, Planchon 1856.

N. amazonum, Hort. Glasnevin; Planchon 1856. Not Mart. & Zucc. 1832.

N. tropaeolifolia, Lehmann 1853 a.

N. sinuata, Salzm. MS. as to the leaf, *fid.* specimens coll. Salzm. No. 389, Bahia, in hbb. Kew, Berlin, Paris, Delessert. Flower is of *N. ampla*.

N. lotus Lunan, Hort. Jam. 2: 271, 1814 (*fid.* Caspary, l. c.). Not Linnaeus 1753.

N. Candolleana, Lehmann 1853 a, as to the flower, *fid.* original specimen from hb. Lehmann in hb. Berlin; the leaf is of *N. ampla*.

N. Planchonii, Caspary MS. as to the leaf, *fid.* specimen in hb. Berlin; flower is of *N. mexicana*, q. v.

DESCRIPTION.—*Flower* 65 to 155 mm. in diameter, open imperfectly on two or three nights from twilight until dawn, or usually closing at 2 or 3 o'clock a. m., or even by 11 p. m.; sometimes a passage is opened directly into the stigmatic basin, but often the inner petals remain closed over the stamens and do not open at all.—*Buds* oblong, obovate, not acuminate.—*Sepals* 4, subcoriaceous, short-oblong, ovate, acute or obtuse, sub-cucullate, obtusely sub-carinate on the back, nerveless; outside yellowish at base, suffused with red, pale brownish-green above; without spots, or rarely with dull purple lines; inside pale greenish-yellow with 7 to 8 veins.—*Petals* 12 to 32, usually 16 or 20, greenish-yellow. Outer petals oblong, elliptic, rather obtuse, 9-veined; petals of second whorl uncinat-cucullate at apex; petals of third whorl attached to the receptacle 3 mm. above the second, close to the inner petals and stamens, shortly ovate-lanceolate, attenuate above; inner petals gradually narrower and more attenuate above.—*Stamens* 43 to 83, inserted at the summit of the receptacle; outer four petaloid, grading inward to those with linear filaments narrower than their anthers; all of the stamens are pale yellowish. Pollen smooth, with equatorial and parallel circles.—*Carpels* 11 to 24. Styles spirally coiled inward, shorter and more slender ones alternating with longer and stouter ones, suggesting two alternating whorls. Stigma funnel-shaped, orange yellow. Axile process ovate-cylindric, obtuse.—*Fruit* depressed globose, truncate, covered by the persistent sepals, petals and outer stamens; stigma deeply funnel-shaped.—*Seed* with 11 to 21 meridians of hairs; raphe prominent.—*Peduncles* terete.

First leaf of germinating plant filiform, followed by 8 to 12 submerged leaves. Second leaf oblong, elliptic or ovate, with one primary vein on each side; petiole winged below; roots two. Fourth or fifth leaf usually sub-cordate; other submerged leaves cordate, with 3 to 4 primary veins on each side. Early floating leaves elliptic to short-oblong, fissi-cordate; lobes obtusely acuminate; margin irregularly sinuate-

dentate with unequal, distant teeth; primary veins 4; under side dull greenish, suffused with red-brown at apex; upper surface bright green with a narrow red border; marked above and beneath with radiating blue-black spots.—*Mature leaf* of adult plant 40 cm. long, elliptic to orbicular, fissi-cordate, more or less coriaceous; margins coarsely and unequally sinuate-dentate, with obtuse teeth becoming obsolete at apex of leaf; lobes touching or distant; margins of sinus irregularly sinuate-dentate. Primary veins 7 to 11; length of principal area: length of radius = 1:1.07 to 1.5. Upper surface dull greenish, more or less suffused with red-brown, especially toward the margin; both surfaces marked with a greater or less number of blackish spots.—*Petiole* terete, without ring of hairs at top; main air-canals 4, the two upper ones larger.—*Roots* 6 to 7 from each leaf-base.

The *caudex* in the native country vegetates throughout the year and becomes very long and sub-fusiform. Young plants cultivated in central Europe cease growing in winter, forming ellipsoid tubers of the size of a hen's egg or larger.—*Stolons* from tuber cylindric, with 1 to 4 triangular scale-leaves at base; later leaves as in seedling plant.

GEOGRAPHIC DISTRIBUTION.—In still and slow-flowing waters; tropical America between 18° N. and 22° S., 38° W. and 78° W. Jamaica; Martinique; Guiana; Surinam; Brazil (Caspary, l. c.). Porto Rico (Espinosa 1881). Type collected by Dr. Rodschied in the Essequibo River, British Guiana, in herb. Grisebach (not seen).

EXAMPLES.—Coll. Mosén, No. 3339, Prov. S. Paulo, Brazil; coll. Jenman, coast lands of British Guiana, Nov., 1889, No. 5748; coll. Poeppig, No. 2930 and 3033; coll. Burchell, No. 5556. Most of these are marked "*N. blanda*" in hbb. Kew, British Museum, Delessert, &c.

NOTES.—The above description is taken from Caspary's account in *Flora Brasiliensis*. He had the plant under cultivation, introduced by Dr. Moore from Spanish Town, Jamaica, in 1854. We have only seen young plants, in the garden of Oakes Ames, North Easton, Mass., R. M. Grey, gardener. One of these specimens was sent to us by the kindness of Mr. Grey, but, the summer being cool, it did not flower.

The seeds of this species are used for food by American natives.

Nymphaea blanda G. F. W. Meyer. (Plate XXI.)


Sepals densely marked with very slender crimson-brown lines, oblong-ovate, rather obtuse, sub-acuminate. Styles linear-clavate, about 8 mm. long. Peduncle covered throughout (or just below the flower) with septate hairs (glabrous in the var.). Leaves small, membranaceous, entire, cordate-cleft, suborbicular or orbicular-elliptic, apex very broadly rounded; lobes slightly produced, sub-acuminate and sub-hastate; pale green, very narrowly peltate (scarcely 1 mm.). Petiole villous at top, or here and there, or throughout, or (in the var.) glabrous.

Nymphaea blanda, G. F. W. Meyer 1818. Schomburgk 1848. Seeman 1852. Dalton 1853. Caspary 1878. Hemsley 1888. Conard 1901 a.

N. Rudgeana β *Ampsonum*, Grisebach 1857. Not *N. rudgeana* Meyer 1818.

N. Fenzliana, Lehmann 1853 a and b; 1854.

N. glandulifera, Rodschied in Meyer 1818.



NYMPHÆA JAMESONIANA.

1, 2, Flower from front and back; s, sepal. 3, 4, 5, Innermost, outer, and outermost stamens. 6, 7, Leaves. 8, Part of leaf from beneath.

DESCRIPTION.—*Flower* 81 to 95 mm. across.—*Sepals* 35 to 44 mm. long by 13 to 20.5 mm. wide, widest below the middle.—*Petals* 16; outer ones 38 mm. long by 15 mm. wide, oblong, ovate; outside sepaloïd along the middle, margins and inside yellowish. Inner petals gradually smaller; innermost oblong-lanceolate, acute.—*Stamens* about 65, outer 4 largest, 25 mm. long, with filaments petaloïd, longer than and twice as wide as anthers; inner stamens gradually smaller, the filament becoming short, and narrower than the anther, innermost 14 mm. long; all the stamens are yellowish.—*Carpels* 26; styles 9 to 11 mm. long, incurved and purplish-brown at apex.—*Peduncle* clothed with septate hairs.

Leaf small, entire, membranaceous, elliptic-orbicular, narrowly peltate, green above and below; lobes distant, sub-hastate, sub-acute; margins of sinus gently curved; primary veins 6 on each side.—*Petiole* clothed with long septate hairs in the upper part or throughout.

Tuber oblong or ovate, small, covered with brownish hairs.

GEOGRAPHIC DISTRIBUTION.—Mouth of Essequibo River, Guiana, in ponds and streams, collected by Rodschied about 1814. Swamps near city of Panama, coll. Seeman. Guatemala; Jamaica (Hemsley, l. c.).

NOTES.—The description above is taken from Caspary (l. c.), who studied Meyer's type collected by Rodschied in hb. Grisebach, and Parker's collection in hb. Hooker & Lindley.

Var. fenzliana (Lehmann) Caspary. (Plate XXI.)

Peduncles and petioles glabrous.

N. Fenzliana Lehmann, l. c.

N. blanda var. *Fenzliana* Caspary, l. c., *fid.* types in hbb. Kew, Berlin.

DESCRIPTION.—*Flower* 96 mm. across.—*Sepals* 40 to 42 mm. long by 12 to 16 mm. wide, oblong, ovate, sub-acuminate, pale green outside, very densely marked with slender red-brown lines 3 to 4 mm. long; inside yellowish.—*Petals* 16, pale yellowish; outermost 4 petals 38 to 40 mm. long by 13 to 15 mm. wide, acute; innermost shorter and narrower, sub-lanceolate.—Outer *stamens* lanceolate, with anthers 8 mm. long, scarcely appendiculate.—*Carpels* 23; styles about 8 mm. long, 1 mm. wide at clavate apex.

Leaf floating, coriaceous-membranaceous, entire, sub-orbicular, fissi-cordate, green on both sides; margins of sinus curved; lobes slightly produced, sub-acuminate; primary veins 5 to 6 on each side, not prominent.

Rhizome small, ovate-globose, 20 mm. long.

GEOGRAPHIC DISTRIBUTION.—Collected in Guatemala near San Juan de Nicaragua in 1841.

NOTES.—Known only from the types in hb. Vienna and hb. Benthams (now Kew), from which Caspary's description was drawn.

Nymphaea lasiophylla Martius & Zuccarini. (Plate XXII.)

Sepals with a few large black spots, ovate-oblong, sub-acute, sub-acuminate. *Styles* 6 to 7 mm. long. *Leaves* large, entire, cordate to orbicular, cleft at base, broadly peltate (i. e., 8 to 16 mm.); lobes rather obtuse. *Flowers* 9.3 to 11.8 cm. in diameter. *Petals* 16. *Stamens* above 42. *Carpels* 15 to 20.

Nymphaea lasiophylla, Martius & Zuccarini 1832. Planchon 1852 *b* (name only); 1853 *b* (name and locality only). Caspary 1878.

DESCRIPTION.—*Sepals* 48 to 50 mm. long by 18 mm. wide.—*Petals* white, oblong, sub-elliptic; outermost 20 mm. wide by 50 mm. long; innermost 4 lanceolate, 8 mm. wide by 42 mm. long; all acute.—*Stamens* unequal; outermost petaloid, lanceolate; middle and inner ones linear, with anthers wider than the filaments; outermost slightly appendiculate.—*Styles* 6 to 7 mm. long, 1 mm. wide at apex; stigma yellowish; axile process minute.—*Leaf* coriaceous, sub-orbicular, entire; under side reddish, with brown-purple lines; lobes distant or touching, more or less produced, obtuse; sinus margins curved or nearly straight; primary veins 7 to 11.—*Petioles* terete, smooth, reddish. (Pubescence of under side of leaf mentioned by Martius & Zuccarini is a layer of algæ. Caspary, l. c.)

GEOGRAPHIC DISTRIBUTION.—Collected by Martius, No. 2377, near Joazeiro in Lagodisso, province of Bahia, Brazil (9° 40' S., 42° 10' W.) in March and April. Otherwise unknown. Type seen in hb. Munich.

Nymphaea gardneriana Planchon. (Plate XXIV.)

Sepals densely marked with long slender fuscous lines, oblong-ovate, distinctly acute, acuminate. *Petals* 16 to 20, outermost oblong-ovate, innermost oblong-lanceolate. *Stamens* 46 to 62, outer filaments petaloid, inner filiform and short. *Carpels* 15 to 18; rays of stigma rounded at apex; styles linear-clavate, very long (12 to 16 mm.), apex 1 to 1.25 mm. in diameter, dark purple; axile process minute. *Leaf* floating, 6.5 cm. long, slightly coriaceous or sub-membranaceous, peltate (pelta 5 to 8 mm. wide), ovate or orbicular-hastate, rarely orbicular, apex rounded or sub-retuse; sinus open, broadly triangular; lobes acute or obtuse; margin entire, often crisped; primary nerves 5 on each side (rarely 4); glabrous, irregularly marked above and beneath with dark violet spots.

Nymphaea Gardneriana, Planchon 1852 *b*; 1853 *a* and *b*; *fid.* specimens coll. Gardner, No. 2476, about 1840, Paranagua, Brazil. Caspary 1878.

N. fragrans, Gardner MS. in hb. Benthams, now Kew.

N. Passiflora, Lehmann 1853 *a* and *b*; 1854; *fid.* specimen marked in Lehmann's handwriting in hb. Kew.

DESCRIPTION.—*Flower* 92 to 115 mm. across.—*Sepals* 11 to 19 mm. wide by 40 to 55 mm. long; outside nerveless, greenish, with long slender fuscous lines.—*Petals* acute, usually sub-acuminate; innermost oblong-lanceolate; outermost reddish-yellow, innermost reddish-brown (in dried specimens).—*Stamens* reddish-brown; outermost petaloid, innermost slender.

Leaf small; veins slightly immersed beneath.

Rhizome small, 16 mm. in diameter, sub-globose, covered with long gray-brown hairs.

GEOGRAPHIC DISTRIBUTION.—Paranagua; Province Piauh, Brazil (10° 45' S., 48° 40' W.); Plain of Mbatolio, Paraguay, coll. Balansa, No. 521.



NYMPHAEA STENASPIDOTA AND N. GARDNERIANA.

N. stenaspidota. 1. Whole plant; 2. sepal; 3. Flower; 4. Part of leaf; upper surface.

N. gardneriana. 5. Flower; 6, 7. Upper part of ovary and innermost stamens; 8, 9. in Leaves; 10. Upper surface of leaf.

Nymphaea jamesoniana Planchon. (Platé XXIII.)

Flower 87 to 107 mm. in diameter. Sepals green, densely marked from base to apex with long narrow dark crimson lines, 3 to 7 mm. long by 0.1 to 0.05 mm. wide; oblong-ovate, rather obtuse. Petals 16. Stamens 52 to 65. Carpels about 30; styles 6 to 10 mm. long, clavate, purplish-brown at apex. Leaves sub-coriaceous, ovate-cordate, cleft at base, sub-sagittate or elliptic, more or less peltate; margins entire; lobes obtuse or acute; under surface marked with dark purple forked and branching lines.

Nymphaea Jamesoniana, Planchon 1852 *b*; 1853 *a* and *b*; *fid.* original specimen in hb. Delessert. Caspary 1878. Hemsley 1888.

N. sagittariaefolia, Lehmann 1853 *a* and *b*; 1854; *fid.* specimen marked in Lehmann's handwriting in hb. Kew.

DESCRIPTION.—*Sepals* 13 to 21 mm. wide by 40 to 46 mm. long.—*Petals* 16, oblong; those of the outer three whorls obtuse, of the inner whorl acute; all brownish-yellow (in dried specimens), sub-membranaceous.—*Stamens* like petals in color and texture; outermost with an acute triangular appendage, innermost obtuse; outermost filaments four times as wide as anthers, innermost filaments and anthers about equal in width.

Leaf thin and membranaceous; lobes approximate or distant; primary veins 6 on each side, very slender, slightly immersed at base, elsewhere level; principal area half as long as radius of leaf.

GEOGRAPHIC DISTRIBUTION.—Savannah of Guayaquil ($2^{\circ}11'25''$ S., $80^{\circ}2'10''$ W.) (Caspary 1878). Ecuador (Hemsley 1888). Ditches at Hatillo, Añasco, Porto Rico, coll. P. Sintenis, No. 5688, Dec. 7, 1886.

NOTES.—Fruit, seed, tuber and habits unknown.

Nymphaea stenaspikota Caspary. (Plates XXI, XXIV.)

Sepals densely marked with long slender fuscous striae, oblong-ovate, somewhat acute, never acuminate. Petals 20 to 24, short-oblong, obtuse. Stamens 60 to 67, resembling those of *N. gardneriana*, but with narrower anthers. Carpels 18, clavate, 4 to 5 mm. long. Leaves ovate-triangular, sagittate, small, rounded at apex, entire, scarcely peltate (1 mm.); sinus margins straight.

Nymphaea stenaspikota, Caspary 1878, *fid.* specimens coll. Gardner, No. 2476, and 3568, in hbb. Berlin, Kew, British Museum.

DESCRIPTION.—*Flower* 91 to 100 mm. in diameter.—*Sepals* 18 to 19 mm. wide by 46 mm. long.—*Inner petals* bearing abortive anthers, very short, elongate-ovate or lanceolate.—*Stamens* like those of *N. gardneriana*, but narrower; outermost anthers 1.5 mm., innermost 1 mm. wide.

Lobes of leaf acute, produced; sinus large, triangular; otherwise as in *N. gardneriana*.

Tuber ovate or sub-globose, small, 15 mm. in diameter, covered above with very long brownish hairs.

GEOGRAPHIC DISTRIBUTION.—In a small lake at Conceição, province Goyaz, Brazil ($12^{\circ}15'$ S., 57° W.), collected by Gardner in 1841.

Nymphaea tenerinervia Caspary. (Plate XXI.)

Sepals with a few scattered linear black marks, ovate-oblong, shortly acuminate, sub-acute. Petals 16 (?), sub-membranaceous, outer ones oblong, innermost sub-lanceolate, acute. Stamens about 40, three-fourths as long as the petals; outer filaments petaloid, median filaments about as wide as the anthers, innermost filaments very short and slender. Carpels numerous; styles short (5 mm. long), clavate, 1 mm. in diameter above, incurved. Leaves ovate-cordate, entire, sub-acute, narrowly peltate, slightly coriaceous; lower surface usually with small, black, oblong, radially placed spots; lobes distant, obtuse, inner margin convex. Top of peduncle and petiole, and thence downward on petiole, clothed with slender multiseptate hairs.

Nymphaea tenerinervia, Caspary 1878, plate 36, and MS. in hbb. Munich, Berlin, etc.

N. tenuinervia, Caspary, l. c. in text.

N. pulchella, Lehmann MS. in hb. Königsberg. Not DeCandolle 1821 b.

N. Maximiliani, Lehmann 1853 a, as to the leaf; flower is of *N. odorata gigantea*, q. v.

DESCRIPTION.—*Flower* 86 to 89 mm. in diameter, or larger.—*Sepals* 15 to 20 mm. wide by 41 to 51 mm. long, subcoriaceous, sub-translucent, shining. Innermost filaments narrower than the anthers.—*Veins of leaf* immersed beneath, the midrib alone prominent; lobes slightly produced.

GEOGRAPHIC DISTRIBUTION.—On St. Francisco River, province of Bahia, Brazil (40° W., 9° 50' S.), near Joazeiro, collected by Martius, April, 1819.

Nymphaea oxypetala Planchon. (Plate XXV.)

Sepals without striæ, lanceolate, oblong below, long caudate-acuminate, apex twisted or hooked. Petals 20 to 30, shorter than the sepals, lanceolate, acuminate, very acute. Stamens 84 to 106 or more, outermost lanceolate with filaments 4 times wider than anthers, inner ones linear, innermost with filament about as wide as anther. Carpels 20 to 28, styles very long, linear-clavate, 24 to 26 mm. long. Submerged leaves alone known; thin, membranaceous, sub-lunate-reniform, sub-hastate or obovate, cleft at base, not peltate; lobes very long; margin subrepand, slightly crisped; primary nerves 3 to 7 on each side; petiole slender.

Nymphaea oxypetala, Planchon 1852 b; 1853 a and b. Caspary 1878.


N. Raja, Lehmann 1853 a and b; 1854 (name only).

DESCRIPTION.—*Flower* 123 to 160 mm. across. Peduncle slender.—*Sepals* 11 to 17 mm. wide by 61 to 74 mm. long.—Outer *stamens* short-appendiculate (1.5 mm.), acute; inner ones obtuse; all the anthers longer than the filaments.

GEOGRAPHIC DISTRIBUTION.—Guayaquil, Ecuador (2° 11' 25" S., 79° 59' 10" W.), coll. Jameson, March, 1845, No. 334. Types seen in hbb. Delessert, Boissier, British Museum, Berlin.

Nymphaea gibertii (Morong), new comb.

Leaves oval, entire, rounded at apex; lobes moderately spreading, obtuse; under surface covered with short branching fuscous lines. Flower white, inodorous, 6 to 7 cm. in diameter. Sepals oblong-ovate, 3 to 3½ cm. long, somewhat acute, with numerous fuscous lines on outer surface. Petals in 3 series [12], a little shorter than the



NYMPHÆA OXYPETALA.

1, 2, Flower. 3, 4, Outermost and innermost stamens. 5, Three carpellary styles. 6, 7, Leaves. 8, Globose idioblasts.

sepals, marked with faint purplish lines, the outer ones sepaloid on the back, with broad white margins. Stamens in 4 series; outermost with anther cells 6 to 7 mm. long. Carpels about 18.

Castalia Gibertii, Morong 1893, in Morong & Britton.

Leuconymphaea Gibertii, Morong MS. on co-type in hb. Acad. Nat. Sci. Phila.

GEOGRAPHIC DISTRIBUTION.—Paraguay, collected on the Pilcomayo River above Asuncion by Gibert in 1858 (in hb. Kew), and by Dr. Thos. Morong 1888-90, in hbb. New York, etc. Flower, May and June.

NOTES.—The imperfect published description of this species does not give certain evidence as to which section of the genus it belongs in; but from the lines on the sepals, the seriate arrangement of petals and stamens, and the locality in which it was found, we suppose it belongs here.

NAMES NOT ELSEWHERE ENTERED.

Nymphaea albo-rosea, Teijsm., ex Regel., Ind. Sem. Hort. Petrop. (1866) 102, *fid.* Index Kewensis. *Quid?*

N. advena, Soland. = *Nuphar*.

N. arifolia, Salisb. = *Nuphar*.

N. Cahlara, Donn, Hort. Cantabr. ed. vii, 159 = *N. stellata* Willd., *fid.* Index Kewensis.

N. ceramica, Rump., Amb. 6: 173, pl. 72 = *Mcnyanthes indica* Willd., *fid.* Roxburgh 1824.

N. crenata, Amadeo, Bot. & Veg. Materia Medica of Porto Rico (Ph. J., 3 ser., vol. 18. London 1888, p. 761 ff.). *Quid?*

N. crenulata, Raf., in Med. Repos. N. York, 5: 354 (1808) name only; *fid.* Index Kewensis. *Quid?*

N. exumbonata, Rupr., in Bull. Phys. math. Ac. Petersb. 12: 219 (1854) = *N. alba*, *fid.* Index Kew.

N. hastata, Michx. = *Nuphar*.

N. hirta, Kurz ex Teijsm. & Binn., in Tijds. Nedl. Indie 27: 38 (1864); *fid.* Ind. Kewensis. *Quid?*

N. Kalmiana, Sims = *Nuphar*.

N. longifolia, Michx. = *Nuphar*.

N. lutea, Linn., Thunb., Walt. = *Nuphar* spp.

N. macrophylla, Small = *Nuphar*.

N. microphylla, Pers. = *Nuphar*.

N. minima, Reichb. = *Nuphar*.

N. nelumbo, Linn. = *Nelumbo nucifera*, Gaertn.

N. odorata, Willd., Hort. Berol. t. 39 = *N. nitida*, Sims, *fid.* Index Kewensis.

N. officinalis, Gater., Pl. Montaub. 99 = *N. alba*, *fid.* Index Kewensis.

N. orbiculata, Harper = *Nuphar*.

N. pentapetala, Walt. = *Nelumbo lutea* Willd.

N. polysepala, Greene = *Nuphar*.

N. pumila Hoffm. = *Nuphar*.

N. punctata, Kar. & Kir., in Bull. Soc. Nat. Mosc. (1841), 376, *fid.* Index Kewensis. *Quid?*

N. Reichardiana, Hoffm., Beitr. z. Kenntniss von Central-ostafrika. Inaug. Dissert. Jena, 1889 (not seen). *Quid?*

N. rubrodisca = *Nuphar*.

N. rufescens, Willd. ex. Casp., in Journ. Sc. Math. Lisboa n. 16 (1873), reimpr. 8, name only, *fid.* Index Kewensis. *Quid?*

N. sagittata, Pers. = *Nuphar*.

N. sagittifolia, Walt. = *Nuphar*.

N. suaveolens, Dum., in Bull. Soc. Bot. Belg. 3: 7 (1864) = *N. alba*, *fid.* Index Kewensis.

N. sumatrana, Miq. Fl. Ind. Bat. Suppl. 387, *fid.* Index Kewensis. *Quid?*

N. umbellata, Salisb. = *Nuphar*.

N. Victoria, Schomb. = *Victoria*.

CHAPTER VI.

DISTRIBUTION.

On account of their aquatic habits, requiring still water, mostly fresh, and enduring comparatively little sedimentation, the areas in which water-lilies occur are at times scattered. They are found here and there almost all over the world. New Zealand and the Pacific Slope of North America have no representatives of the genus *Nymphaea*. The *Castalia* group is wholly restricted to the northern hemisphere, and *Brachyceras* to the tropics and subtropical regions, but both are found all round the globe. *Lotos* is mostly tropical, and is restricted to the Eastern Hemisphere, where it ranges from Sierra Leone and Senegambia to the Philippines, while *Hydrocallis* is native to the tropics of the New World. *N. gigantea* occurs only in tropical Australia and New Guinea.

Nymphaea is, generally speaking, a genus of the low lands. The Atlantic coastal plain of North America is the home of *N. odorata*, and *N. flava* is found in brackish water in the Little River, Florida. *N. oxypetala* was collected at Guayaquil, Ecuador. In the West Indies, the Philippines, and Australia they occur along the coastal swamps, and at river mouths. The delta of the Nile is a favorite haunt of *N. lotus* and *caerulea*. On the other hand, both of these species are reported from central Africa, and similar ones from the interior of India. *N. tetragona* and *alba* ascend 1500 meters in Kashmir, and our own *N. odorata* ascends 600 meters in the eastern United States.

The distribution of single species is often very wide, and the variations correspondingly great, insomuch that the limitation of species is, in our present state of knowledge, more than usually arbitrary. Careful studies of plants from many localities under cultivation and hybridization are needed to place this branch of our subject on a better footing. Another uncertain feature is the range of the *Hydrocallis* species. Their native countries are all so little known botanically that most of them must be left out of account in these generalizations. Outside of the *Hydrocallis* group, probably the most restricted species is *N. mexicana*, known only from Florida, Texas and Mexico. *N. tetragona*, on the other hand,

is, as now constituted, the most widespread species; it extends from Siberia through Kashmir and China to Australia (?), and is known from Granite, Idaho, and Ontario Province, Canada, in North America. *N. lotus* is also very widespread, but further investigation is needed to determine the relation of the various forms. In *N. thermalis* of the warm springs of Hungary we have its most northern representative. And its existence here is a problem of extreme interest. The Grosswardein locality was first recorded by Waldstein and Kitaibel (1802). Plants were removed from there by Paul Kitaibel in 1800 and planted in the warm springs of Lucasbad at Budapesth. In the former place the temperature of the water is 33.75° to 41.25° C., and the water is quite pure; at the latter station the water is only 26° C., and is charged with sulphur and other mineral matters. Nevertheless the plant grew equally well in both places, and flowered freely from May to October. The Lucasbad station was, I believe, destroyed by building operations about 1890 (Schilbersky, 1889).

Kitaibel, Boissier, Neilreich, Kerner, Engler, and Simonkai (1890) considered *N. thermalis* as identical with *N. lotus* of Egypt, but Simkovics (1883) agrees with DeCandolle in pronouncing it a distinct species. If it could be shown, as some have believed, that the plant was originally introduced here by man, perhaps by the Turks, the question of identity would be settled. But Simonkai considers this theory impossible, since the plant was of no material use; and Staub (1891)¹ agrees that it is almost certainly a relic of a pre-glacial vegetation, when the whole of Europe enjoyed a comparatively warm climate. When the plants of this period were driven back toward the equator by colder conditions, this one remained in the favorable temperature of the thermal springs. Along with it has continued a snail, *Melanopsis parreyssi* Mühlf., very near of kin to *M. costata* Fér. of Egypt. According to Staub, the genus *Melanopsis* was common in Europe in the Drift period; and he considers that the warm springs of Grosswardein are older than the Drift. It is also notable that there were in recent geological times throughout Europe waterlilies resembling the Lotos group (Schenck, 1888; Staub, l. c.) which may have been the ancestors alike of the Egyptian and the Hungarian plants. There are the best of reasons, therefore, for considering *N. thermalis* as truly native in its present habitat. And if we can believe that its specific characters were demarcated as early as the Drift period, and have not changed

¹ It must be noted that Staub's paper, as it appears in Engler's Jahrbuch, is full of the most egregious errors concerning the relationships and distribution of living species of *Nymphaea*; we hope they are misprints!

since, we must follow those botanists who make this name a synonym of *N. lotus* L.

The questions of the place and time of origin of the genus *Nymphaea* itself are obscure, although several fossils of this and allied genera are known. All of these have been found in Europe. They establish the existence of distinctly Nymphaeaceous types as early as the lower cretaceous. Indeed, at that time the three tribes Nelumboneae, Cabombeae, and Nymphaeinae were already well marked. Saporta (1894 *b*) records *Braseniopsis venulosa* (a form very near to *Brasenia peltata*), two species of *Nelumbium* and a Nymphaeaceous plant from Valle-de-Sobreiros, Portugal. The last-mentioned plant was represented by rhizomes found in a schistose marl. The leaf cushions were distinct and slightly prominent; the petiolar scar showed the traces of many irregularly distributed air-canals; below this were one to four root-scars of irregular size and arrangement. Alternating with the leaf bases are much smaller peduncular scars, with air-canals as above; these occupy the place of leaves in the phyllotactic spires. We do not know whether this stem was erect or horizontal, but the plant can most readily be considered as a generalized form, from which the tetrasepalous Nymphaeinae, and perhaps *Nuphar* also, have been derived. Another remarkable fossil from the same beds appears to be a fruit with the stigma and general shape of *N. alba* but wholly superior! If this interpretation be correct, it is a most interesting find.

In the tertiary, the Nymphaeaceous stock reached a very high development. The genus *Anoctomeria* Sap. (1865 *a, b*), of which we may take *A. brongniartii* (Casp.) Sap. as the type, had flowers and fruits resembling those of *N. alba*, but twice as large. It had an outer row of three floral leaves, and within this a second alternating row of three; the rest of the floral leaves were spirally arranged. It was probably apocarpous; at any rate, the fruit broke up readily into elliptic or lunate pieces, though Saporta says these correspond with the bases of the petals. The rhizome was cylindrical and horizontal, and marked with large rhomboidal leaf-cushions. These have the curved scar of a broad stipular plate in front as in *Castalia* and *Victoria*. The petiole scar shows two large air-canals and two smaller ones above these. The root scars are arranged as in *Eucastalia*. The leaf was large (28 to 40 cm. long), entire, fissicordate, not peltate. There were 15 to 18 primary veins, which branch and dichotomize to form a very fine network; they form no primary areas, but run pretty distinctly to the margin of the leaf. Thus we see in the rhizome, stipules, leaf-margin and shape of fruit a marked resemblance to

Eucastalia, and in air-canals and venation to Lotos, Nelumbo or Victoria; but the trimerous symmetry has not come down to us in any living form. *Anoectomeria brongniartii* (Casp.) Sap. (1865 a, b) (= *Nymphaea Arethusae* Brongn., 1822, not of Weber, 1850; = *Nymphaeites Brongniartii* and *Arethusae* Casp., 1856) flourished in Eocene times, being plentiful in the littoral chalk marls of the Marseilles basin. *A. media* Sap. (1894 c) occurs in the Aquitanian (Miocene), and *A. nana* Sap. in the tertiary of Alsace (Mieg, etc., 1890), although Schenk (1888) speaks of the genus as restricted to the Oligocene. *Nymphaea polyrhiza* Sap. (1865 a) (= *N. eocenica* Sap.,




FIG. 76.—*Nymphaea dumasii* Sap. (after Schenk, 1888).

1861, in part) from the Aquitanian of St. Jean de Garguier, resembles *Anoectomeria* in the trimerous flower, and should on that account be removed from the genus *Nymphaea*; it also has a large number of air-canals in the petiole. In other ways, however, it is near to *N. gyp-sorum* Sap. (1865 a).

On some other species statements are conflicting. *N. calophylla* was at first (Saporta, 1861) said to have denticulate leaves, but in 1894 (b) the same writer describes the leaves as entire. The venation of this, as

of most other tertiary *Nymphaeas*, was similar to that of *Anoectomeria*, and very suggestive of the Lotos group; but they had the rhizome and stipules of *Eucastalia*. Saporta considers that their type has become entirely extinct. In this list are included also *N. gyp-sorum* Sap., *N. americana* Sap., *N. nolini* Sap., *N. rousseti* Sap., and *N. dumasii* Sap. (Fig. 76). *Nymphaea minuta* Sap. is near of kin to *N. tetragona*, and *N. cordata* Sap. to the smaller forms of *N. alba*, while *N. latior* Sap. resembles the large *N. alba* of Greece. Wessel and Weber (1855) compare their *N. lignitica* (= *Nymphaeites lignitica* Casp.) from the lignites of Rott in the lower Rhine region with *N. alba*, with regard to the shape of the leaf. *N. parvula* Sap. and *charpentieri* Heer (= *Nymphaeites charpentieri* Casp.; = *Nelumbium nymphaeoides* Ettingsh.) had double flowers like those of *N. alba* (Saporta, 1879). *Nymphaeites microrhizus* Sap. is a small form

with two air-canals in the petiole and one root per leaf; the figure gives it a certain resemblance to *N. mexicana*. *Nymphaeites palaeopygmaeus* Sap. had also two main air-canals and three to five roots, but Saporta considered it near to *Anoectomeria*. *Nymphaeites weberi* Casp. (= *Nymphaea Arethusae* Weber, 1850, not of Brongn., 1822; = *Carpolites granulatus* Weber) and *Nymphaeites ludwigii* Casp. (1856) probably are akin to the *Nymphaea calophylla* group. *Nymphaea dubia* Wat. was shown by Bureau (1888) to be really a *Nuphar*; and of *Nymphaea blandusiae* Ung., *doliolum* Ludw., *doris* Heer, and *Nymphaeites saxonica* Fried. we have learned nothing but the names.

During the warmer portions of the Tertiary the genus *Nymphaea* extended far into the arctic zone. *N. arctica* Heer (1869) of Spitzbergen has left quite complete remains. Its rhizome and leaf suggest *N. alba*; there were four main canals in the petiole and a number of evident ones surrounding these. The sepals were elliptic, with slender longitudinal veins. There were about 12 carpels, and the fruit was much enlarged below the narrow (6 mm. wide) depressed stigma. It certainly belongs to the *Castalia* group. *Nymphaeites thulensis* Heer was found in the same locality, but poorly preserved. In Grinnell Land also Captain Feilden of the English North Polar Expedition found *N. arctica* (Heer, 1878 a, c) and an allied fragment named *Nymphaeites tener* (Heer, 1878 b).

From such forms and such localities doubtless all of the *Castalias* of Europe and America are alike derived. The genus *Nymphaea* probably originated in western Europe and spread over the Arctic continent. Very early, though fossil evidence does not indicate when, the syncarpous and apocarpous groups were separated. Of the latter, *N. gigantea*, from its absence of styles and restricted distribution in the ancient Australian flora, is most primitive. The lowest *Brachyceras* types are the short-styled and pale-flowered American forms *N. elegans* and *flavo-virens*, from which we ascend through *N. caerulea* and *stellata* to *zanzibariensis*, the most gorgeously colored, largest-flowered, longest-styled species of the group, and also the farthest removed from the original center of distribution.

Among *Syncarpiae*, the *Castalia* group is most primitive, and of these we have already mentioned *N. mexicana* as the lowest, with *N. tetragona* as a close second. In Europe the *Lotos* section was segregated off from these at a very early date, probably through forms somewhat similar to *N. calophylla* and *gypsorum*. *N. lotus* is nearest to the parent stock, and *N. rubra* most removed. *N. thermalis* remains to testify to the minimum age of the type. *N. candida* has kept near home and has probably

CHAPTER VII.

HYBRIDS AND GARDEN VARIETIES.

Beginning with *Nymphaea devoniensis* in 1851, a continually increasing number of forms of waterlily has become known to cultivators. The origin of these was in some cases accidental, in others due to artificial hybridization. In the first case there may have been cross-pollination by insects, or variation or mutation—all equally problematical to the systematist and uncertain for the general student. In the second case, careless or ignorant methods leave room for much doubt as to parentage, and very often the facts are withheld or distorted for trade purposes. Only in very few cases, therefore, is our knowledge of the origin of the various garden varieties at all reliable or useful.

For example, *N. devoniensis*, which appears on plate 4665 of the Botanical Magazine, and was first described by Paxton in Gardeners' Chronicle for July 10, 1852, is said in the former article to have been produced by crossing *N. rubra* with *N. lotus*—a red species with a white. The seeds were obtained in autumn of 1850 at Chatsworth, England, and the plant is said to have flowered from April to October, 1851. But the points of difference of the so-called hybrid from *N. rubra* are more robust growth, more floriferous habit, and a very slightly lighter color. In other words, there is almost no trace of the influence of *N. lotus*. Since Hooker and Thomson stated that just such a plant is common and native in India, its hybrid origin is generally disbelieved. It is probably a self-fertilized seedling of *N. rubra*. As to the color of leaves and flowers, we had in the summer of 1901 three flowering plants of *N. rubra* (?) raised from one and the same tuber. One was grown in a half-barrel of earth in a tank 1.4 meters square, in company with *N. marliacea-chromatella*, *N. tetragona*, and the water-poppy; the flower was of a light magenta red, and the leaves brownish green. Another was in a half-barrel in a pond with plenty of leaf-room, and had deep red-brown leaves and pure magenta flowers. The third was in a tub of earth 1.6 meters in diameter and 60 cm. deep, with plenty of leaf-room; it resembled the second, but had larger leaves and flowers, and the latter still deeper in color. There is, therefore, great variation, according to conditions of growth.

On the other hand, *N. ortgiesiano-rubra*, exhibited at Chiswick in May, 1852, by M. van Houtte, and described by Planchon (1852 aa), is in many respects intermediate between the two parent types. The seed was obtained in the summer of 1850 by M. Ortgies in Van Houtte's aquaria, by removing the stamens from a flower of *N. rubra* and dusting the stigma with pollen of "*N. ortgiesiana*." The comparison of hybrid and parents is well shown in Planchon's parallel column descriptions. The hybrid has bright rose-pink flowers, but they open wide as in *N. ortgiesiana*. The styles are yellow, washed with red in *N. ortgiesiana*, reddish orange in the hybrid, dark brownish red in *N. rubra*. The color of the stamens and upper surface of the leaves is fairly intermediate, but the under surface of the leaf and the character of the stigma are as in *N. rubra*. The robust temperament of *N. ortgiesiana* is reproduced in the hybrid, but it is more floriferous than either parent, probably because no strength is used up in the production of seed. In short, *N. ortgiesiano-rubra* is a well-marked hybrid. Several other hybridizations are recorded by Planchon (l. c.) as productive of seed in 1852, but no further results reached the public.

In 1853 M. Bouché, Inspector of the Royal Botanic Garden of Berlin, obtained another hybrid, named by Planchon (1854) *N. boucheana*. It is to all appearance intermediate between *N. lotus* and *N. ortgiesiano-rubra*, but is of the same parentage as the latter. A slightly different form of *N. lotus*, viz., *N. dentata*, was used as pollen parent. The pale pink petals bordered with pure pink, the yellow stamens, and the bright green leaves show a preponderating influence of *N. lotus*. The sterility of *N. boucheana* attests its hybrid origin.

N. kewensis was next to appear. It was published in Gardeners' Chronicle in 1887 (p. 366), and in Botanical Magazine in April, 1888 (tab. 6988). The cross was made at Kew in 1885 by Mr. Watson, with *N. lotus* as seed parent and pollen of *N. devoniensis*. The hybrid has a large number of broad petals of an even rosy pink all over; the stamens are orange colored; the leaves are pure dark green above. In recent years, crossing and re-crossing has been carried on in this group, especially in America, until every shade of color may be had between the white and red types; differences are also noted in shape of petal, size of flower, and color of leaf. They are propagated readily and quite accurately from the tubers, and names have been given to every distinguishable form. *N. ortgiesiano-rubra* and *boucheana* are not found under those names, but very similar plants are cultivated. The name *kewensis* is still retained, though the original plant "died without issue"; the present stock was



NYMPHÆA PENNSYLVANIA.

obtained independently in America. Hybrids of the Lotos group are known in Germany under an entirely distinct set of names from those used in this country.

In 1885-1890 M. Latour-Marliac, of Temple-sur-Lot, France, drew the attention of flower-lovers everywhere by his magnificent hybrids in the Castalia group—the hardy waterlilies. Probably no one else has done so much for waterlily culture. His earliest achievements won universal admiration; but these have been followed by annual additions of ever increasing splendor. At present, however, the possibilities in that direction seem to be about exhausted. So great was Marliac's lead in this work, and so carefully did he guard the secret of his success, for trade reasons, that only within the last three years have any comparable results been attained, and this only by using Marliac stock for breeding. The parentage of the Marliac hybrids is a matter of speculation. In several cases, however, one or both parents can be indicated with considerable certainty; but which was male and which female will, I fear, never be known. The first members of this series were the yellows, *N. marliacea-chromatella*, *N. odorata sulfurea* and *N. tetragona helvola*. All are derived from *N. mexicana*. They are altogether sterile. Of some of the pinks *N. odorata rosea* is one parent, and of those with red tints at the center of the flower *N. alba rubra* is one source.

Within the Brachyceras group, hybridization has been carried on almost exclusively in America. Here Mr. Tricker is the acknowledged leader, so far as the public good is concerned. His *N. pulcherrima*, derived on one side from *N. caerulea*, has been for several years in general cultivation. The new hybrids of *N. flavo-virens* with pollen of *N. zanzibariensis* sent out under the rather unwieldy names *Mrs. C. W. Ward* and *Wm. Stone*, are easily the finest tender day-blooming hybrids yet available. Both have the general habit of *N. flavo-virens*, and in the tuber they follow this parent exactly; but the color of the flower and leaf is beautifully intermediate. *N. pennsylvanica* and *N. elegans* × *zanzibariensis*, raised in 1901 at the University of Pennsylvania Botanic Garden from seeds of the previous summer, are fairly intermediate in forms, coloring of all parts, and number of floral organs between their respective parents.

In spite of many attempts, no cross has yet succeeded between members of different subgenera of *Nymphaea* as grouped in this paper. We realize that this is in opposition to M. Marliac's published statements in which he claims *N. rubra* as the source of the red color in his hardy red waterlilies. But so far as naked-eye examination goes (and we acknowl-

edge that is weak argument) the kind of color shown by the hybrids is totally different from that of *N. rubra*, and no trace of the latter species is to be found in any part of the plant. We are also forced to take issue concerning the supposed hybrids between *Lotos* and *Hydrocallis*,¹ raised by Mr. Ames at North Easton, Mass. (Ames, 1900; Grey, 1900). I have the greatest confidence in the accuracy of Mr. Ames, and of his able gardener, Mr. Grey, and the latter assures me that the seed-flowers were carefully castrated and kept netted from insects. But the so-called hybrids show absolutely no trace of the influence of a *Hydrocallis* parent, and it is easier to believe that parthenogenesis or asexual budding from the endosperm or perisperm has occurred in the highly fertile *N. lotus* flower than to imagine a hybrid parentage with one parent obliterated. The case demands, and might well repay, a rigid investigation. Similar crosses of distantly related species have been repeatedly claimed, and by such authorities as Planchon, Tricker, and Sturtevant, but they have either failed to reach the public or have shown no trace of the pollen parent; sometimes, indeed, there is strong evidence of the pollen of some related species.

Natural hybrids, i. e., those produced without human intervention, are of frequent occurrence whenever kindred species are in the same pond. Caspary and others have recorded hybrids of *N. alba* and *candida* from Europe, and intermediate forms between *N. odorata rosca* and *N. tuberosa* spring up in our gardens; *N. odorata caroliniana* and *N. o. luciana* are of such origin. *N. flavo-virens* always becomes mixed with *N. zanzibariensis* if the two are near each other.

From the fragmentary nature of our knowledge it is impossible to draw any general conclusions on the laws of heredity in waterlilies. So far as we can see, some characteristics are regularly blended in the hybrid offspring, while others are carried over *in toto*, or even exaggerated, from one or other parent. Thus, the spotting of the calyx so characteristic of *N. caerulea* is not a whit diminished in *N. pulcherrima* and *N. pennsylvania*, while in both the color of petal and size, shape and number of all of the floral parts are decidedly intermediate. In *N. Wm. Stone*, as stated above, the caudex is exactly like that of the seed parent, *N. flavo-virens*, in size, shape, character of leaf-bases, hardiness, and keeping qualities. In *Brachyceras* all known hybrids are sterile, except *N. capensis* × *zanzibariensis* raised in our botanic garden, which is highly fertile, and of which a new

¹ Mr. Ames' *N. ampla*, which I saw in 1901, is *N. rudgeana* Mey., collected by Mr. Grey in Cuba. The so-called crosses may be "false-hybrids."

generation of hybrids is coming on. All of the hardy yellow hybrids are entirely sterile, and crosses of *N. tetragona* with *Eucastalia* types are also sterile; as examples of these *N. laydekeri rosea* and *N. pygmaea alba* Marliac may be mentioned. Even *N. alba* \times *candida* is greatly enfeebled in seed-producing capacity. But *N. alba* and *N. a. rubra*, though much more distinct than the last two to the casual observer, are perfectly fertile together and have fertile progeny. *N. odorata* and *tuberosa* hybrids are not self-fertile, but can be crossed with pure species. In the *Lotos* group, some forms are sterile, others fertile. Planchon found *N. ortgiesiano-rubra* to be impotent as to the ovules, but capable of fertilizing *N. lotus* or *N. rubra*. In those now in cultivation, *N. devoniensis* is nearly sterile, but *N. omarana*, which closely resembles *N. ortgiesiano-rubra*, often produces seed. In general, the nearer the hybrid approaches in color to the highly fertile *N. lotus*, the more productive it is. Several seedlings of *N. omarana* have been raised, of which *N. Geo. Huster* deserves special mention. Its flowers are of an extremely deep dark red, more so than *N. rubra* itself, as cultivated here. If the original seed was fertilized by pollen of the same flower, which it is impossible to know, we would have a case of "separation of characters" according to Mendel's theory; but even if *N. rubra* was the pollen parent, the determining elements of the color of the flower in this seedling seem to have lost all trace of the influence of a white ancestor.

We have expressed a belief in the occurrence of variations under cultivation without mixture of blood. Probably *N. odorata exquisita* is such a variant from *N. odorata rosea*, as also *N. froebelii* from *N. alba rubra*, *N. devoniensis* from *N. rubra*, and *N. gladstoniana* from *N. alba*; *N. gladstoniana* is quite fertile, and has seeds and arils like *N. alba*. Whether *N. alba candidissima* belongs in this class or among the hybrids is uncertain. It is absolutely sterile, and may be a cross of *N. candida* with the large *N. alba* of Greece. Quite comparable with these varietal changes in natural forms are some suddenly appearing peculiarities of hybrids. For example, *N. robinsoni* can be easily recognized by a peculiar crimped notch and fold about the middle of each side of the sinus of the leaf; *N. gloriosa* is uniformly pentamerous; and one of a set of plants of *N. gladstoniana* \times *mexicana* raised by Mr. Tricker habitually twists the petiole so as to turn the apex of the leaf instead of the sinus toward the center of the plant. *N. laydekeri rosea prolifera* is a fasciated strain, which stools out around the crown to a remarkable degree, whereas the type makes no lateral buds at all.

Without going farther into isolated details, enough has been said to show that a wide and interesting field lies open to the student in crossing and inverse crossing of waterlilies. It is unfortunate that Caspary's extensive investigations in this line have not been formulated, but his notes, exquisite color sketches, and large collection of pressed specimens are preserved in the Royal Herbarium of Berlin. Among them are such crosses as *N. capensis* \times *caerulea*; *N. capensis* \times (*capensis* \times *caerulea*); *N. caerulea* \times [*caerulea* \times (*capensis* \times *caerulea*)]; *N. caerulea* \times {*caerulea* \times [*caerulea* \times (*capensis* \times *caerulea*)]}; *N. flavo-virens* \times [*capensis* \times (*caerulea* \times *micrantha*)].




FIG. 77.—*Nymphaea pulcherrima* Tricker. Sepal, three successive petals; three successive stamens, vertical section of ovary. Two-thirds natural size.

Duplicate specimens of many of these hybrids were distributed to several other herbaria. Time did not permit us to make a study of these. We hope they will be worked over by some scholar, and the interesting results made known. We have, for the convenience of students and cultivators, brought together, in the following pages, some account of the hybrids and garden varieties that have come more directly under our notice.



NYMPHÆA CAPENSIS X *ZANZIBARIENSIS*.

Section I. *Nymphaeae apocarpiae*.Subgenus II. *BRACHYCERAS*.

1. *N. STELLATA* × *CAERULEA*. Mentioned by Caspary (1877) as a sterile hybrid.
2. *N. CAERULEA* × *CAPENSIS* (Focke 1881). Raised by Caspary in 1862. It resembles *N. caerulea* very closely and is generally sterile, though Caspary succeeded in fertilizing it with pollen of other individuals of the same stock and generation, and obtained a second generation of hybrids. These resembled those of the first generation, except one individual, which produced styles as in *N. capensis*, and petals of a deeper color than those of either parent. The small violet-black spots on the calyx of *N. caerulea* are more plentiful in the hybrids. *N. pulcherrima* (Tricker 1897) gives every evidence of having this parentage; the spotting of calyx and under side




FIG. 78.—*Nymphaea pennsylvanica*. Sepal, petals, stamens, and section of ovary. Two-thirds natural size.

of leaf, the purple margin of the leaf beneath, and the conical buds are reproduced as in *N. caerulea*. The sinuate leaves with acuminate lobes are like those of *N. capensis*. The color of petals and number of floral leaves are fairly intermediate. Sepals 4, petals 20 to 22, stamens 137 to 140, carpels 24. Sterile. (Fig. 77.)

3. (*N. CAERULEA* × *CAPENSIS*) second generation × *CAERULEA* (Caspary 1862). Spots of calyx confluent into large areas.

4. *N. CAERULEA* × (*CAERULEA* × *CAPENSIS*). Raised by Caspary (1862).

5. *N. CAERULEA* × *ZANZIBARIENSIS* (= *N. pennsylvanica* Conard 1901 b) (Plate XXVI; Fig. 78). Flowers light blue, open from 8 a. m. to 5 p. m., that is, combining the earliest and latest limits of the two parents. Spotting of calyx and lower surface of leaves as in *N. caerulea*. Shape of bud, shape, number and color of floral organs, and

outline of leaves strikingly intermediate. The seedlings are like those of *N. caerulea* until the first floating leaf; this is spotted with brown above and suffused bluish beneath as in *N. zanzibariensis*. Sterile. Raised at the Botanic Garden, University




FIG. 79.—*Nymphaea capensis* \times *zanzibariensis*. Sepal, four petals, staminode, stamens, vertical section of ovary. Two-thirds natural size.




FIG. 80.—*Nymphaea elegans* \times *zanzibariensis*. Sepal, three petals, stamens, vertical section of ovary. Two-thirds natural size.

of Pennsylvania, from seed obtained in 1900; flowered 1901. Sepals 4, petals 23, stamens 140, carpels 26.

6. *N. CAPENSIS* \times *ZANZIBARIENSIS* (Plate XXVII; Fig. 79). Flowers light blue. Floral parts very numerous. Sepals broad, resembling those of *N. zanzibariensis*.



NYMPHÆA ELEGANS X *ZANZIBARIENSIS*.

Leaves dull purplish violet beneath, less brilliant than in *N. zanzibariensis*. Self fertile. The types are very much alike, but the hybrid is fairly intermediate. Raised in the Botanic Garden of the University of Pennsylvania from seed obtained in 1900; flowered 1901. Sepals 4, petals 32, stamens 225, carpels 32. *N. stellata eastoniensis* (Garden and Forest 9:475) appears to belong here, the cross having been effected by insects. It is described as having steel-blue flowers, with less of the stellate form, and leaves "more deeply toothed" than the type. It was raised by C. Blomberg, gardener to O. Ames, North Easton, Mass., from seed obtained in 1895 from "*N. stellata*" (doubtless *N. capensis*); flowered 1896.




FIG. 81.—*Nymphaea* "Wm. Stone." Sepal, petals, stamens, section of ovary. Two-thirds natural size.

7. *N. ELEGANS* × *ZANZIBARIENSIS* (Plate XXVIII; Fig. 80). Flowers light blue with a violet tint, much bluer than *N. elegans*. Bud, sepals, and petals shaped as in *N. elegans*, but much larger. Length of styles and appendages of stamens intermediate. Leaves colored as in *N. zanzibariensis*, but intermediate in shape. Sterile. Raised in the Botanic Garden, University of Pennsylvania, from seed obtained in 1900; flowered 1901. Sepals 4, petals 21, stamens 150.

8. *N. ZANZIBARIENSIS* × ———? (= *N. zanzibariensis* × *capensis*, Conard 1901 a). Leaves as in *N. zanzibariensis*, but without brown spots above. Flowers rich blue, open from 9 a. m. to 4 or 5 p. m.; petals and sepals narrower than in *N. zanzibariensis*. Petals 15 to 20, stamens 60 to 100. Very floriferous, but sterile. Cultivated at Horticultural Hall, Fairmount Park, Philadelphia, and formerly at University of Pennsylvania. Said to have been originally obtained from Mr. Trikef.

9. *N. FLAVO-VIRENS* × *ZANZIBARIENSIS* (Plate XXIX; Fig. 81) (= *N. Greyae*, 1891; *N. Wm. Stone* Tricker; *N. astraea* R. M. Grey; *N. gracilis purpurea*, *N. g.*

azurea Sturtevant). Sepals, petals and leaves shaped as in *N. flavo-virens*, but the last two intermediate in color. Stamens and carpels intermediate. Tuber in all respects like *N. flavo-virens*. Petals 20, stamens 70, carpels 21. Sterile. First obtained by Benj. Grey of Malden, Mass., and named in his honor.





FIG. 82.—*Nymphaea* "Mrs. C. W. Ward." Sepal, petals, stamens, section of ovary. Two-thirds natural size.

10. *N. FLAVO-VIRENS* × *ZANZIBARIENSIS* ROSEA (= *N. maurii* Henshaw; *N. Mrs. C. W. Ward* Tricker; *N. astraea rosea* R. M. Grey; *N. gracilis rosea*, *N. g. r. perfecta*, *N. g. rubra* Sturtevant). Like No. 9, but with flowers pink instead of blue. Sterile. First obtained by Samuel Henshaw, New Brighton, N. Y., about 1892. There are slight differences in the quality of the pink color as grown by different persons; it usually contains a shade of blue, but Mr. Sturtevant has nearly a pure pink (*perfecta*); his *rubra* variety is rather deeper in color than any others we have seen. (Fig. 82.)



NYMPHÆA FLAVOVIRENS X *ZANZIBARIENSIS*.

Section II. *Nymphaeae syncarpiae*.

Subgenus III. CASTALIA.

CHAMAENYPHAEA \times XANTHANTHA.

11. *N. TETRAGONA* \times *MEXICANA* ($=$ *N. pygmaea helvola* Marliac; *N. tetragona helvola* Conard 1901 a; Froebel Cat. 1901). In shape and size of all the parts like *N. tetragona*, with the color in leaves and flowers of *N. mexicana*. The caudex bears many lateral buds, but no runners. Sterile. Produced by Marliac about 1890; introduced into America about 1892.

CHAMAENYPHAEA \times EU-CASTALIA.

12. *N. TETRAGONA* \times *ALBA*? ($=$ *N. pygmaea alba* Marl., in part). Resembles *N. tetragona* in shape and size of flowers, but the leaves are broader and more rounded. The caudex bears no side shoots. Sterile. Sent out by Marliac as *N. pygmaea alba* in 1893; but in other places he uses this name apparently as synonymous with *N. tetragona*.

13. *N. TETRAGONA* \times *ALBA RUBRA*? ($=$ *N. Laydekeri rosea* Marliac; *N. Laydekeri* Hort.). Closely resembles *N. tetragona*, except in color of flowers; these are of a delicate pink color on opening, changing to rose and deep carmine-rose on succeeding days; this character is drawn from *N. alba rubra*. Sterile and without side shoots. Introduced by Marliac about 1891.—*N. laydekeri rosca prolifera* Tricker is a fasciated form of the above, producing a great many lateral buds. Introduced by Henry A. Dreer Co., 1901. *N. laydekeri lilacea* André (1895 a, col. plate) ($=$ *N. lilacea* Gard. and For. 1895, p. 277; *N. lilacina* l. c. 1897, p. 316; *N. Laydekeri lilacea* Tricker in Dreer Cat. 1902) has flowers of a soft rosy lilac, shaded bright carmine, with yellow stamens; otherwise as above. Raised by Marliac; introduced into the United States in 1895.

EU-CASTALIA \times XANTHANTHA.

14. *N. ODORATA* \times *MEXICANA* ($=$ *N. odorata sulfurea* Marliac; *N. sulfurea* Hort.). The flowers are intermediate in size, shape of parts, and color between the two parents; the leaf combines the copious brown blotching of *N. flava* with the deep red under surface of *N. odorata*. Rhizome slender, nodose, yellow. Sterile. Obtained by Marliac about 1888, and exhibited by Lagrange at the Trocadéro in 1889. Published with colored plate in *Revue Horticole* 1890 b. About 1899 a larger form was sent out by Marliac under the name of *N. sulfurea grandiflora*.

15. *N. ODORATA ROSEA* \times *MEXICANA*? ($=$ *N. arc-en-ciel* Marliac 1901). Known to us only by catalogue description, but apparently of this parentage. "Leaves variegated with several lively and distinct tints. * * * The sweet scented flowers are of a salmon-white color, with sepals splashed with rose color."

16. *N. ALBA* \times *MEXICANA*? (= *N. marliacea chromatella* Marliac; *N. chromatella* Hort.; *N. tuberosa flavescens* of Kew). Leaves orbicular, much blotched with brown, 8 to 20 cm. across; when crowded they may rise as much as 20 cm. above the water, and are not blotched. Flowers bright yellow; petals numerous, broad, concave. Very strong grower, but sterile. Said by Marliac to have the parentage cited above, but believed by some to be *N. tuberosa* \times *mexicana*. Structurally it bears some resemblance to *N. tuberosa*, and sometimes the brown stripes of the petioles of this species appear on the hybrid; the question cannot yet be decided. Raised by Marliac about 1888.

17. *N. ALBA RUBRA* \times *MEXICANA*? Several of the Marliac hybrids undoubtedly have this parentage, but most distinctly *N. robinsoni* (*N. robinsoniana* Hort.), *seignoretii*, *aurora*, and *fulva* (= *N. laydekeri fulva* Tricker 1897). The leaves are much mottled with reddish-brown as in *N. mexicana*. The outer petals are more or less yellow, shading through rose to deep red on the inner ones; the stamens are red or orange. Thus we have a beautiful blending of the colors of the parents. *N. robinsoni* is peculiar in having a crimped notch about the middle of each margin of the sinus. There are also differences in the details of the coloring of the flowers. They were first published in *Revue Horticole* in 1895, *N. robinsoni* and *seignoretii* with a colored plate, p. 258, and the other two on p. 568. In the former article *N. andreana* and *lucida* (= *N. laydekeri lucida* Tricker 1897) are also mentioned, and in the latter place is *N. laydekeri fulgens* with a colored plate. All are productions of Marliac. *N. andreana* appears on a colored plate in the same journal in 1896, pp. 352-353. The last three also agree in having the leaves mottled with brown, but the yellow color is not nearly so evident in the flower; they may represent a second cross. *N. chrysantha* (Marliac 1901) is described in almost the same words as *N. aurora*, and *N. arethusa* (Henry A. Dreer Co. 1902) is spoken of as "an improved *Laydekeri fulgens*."

EU-CASTALIA.

(To *N. alba* we refer the following garden forms: *N. alba maxima*; *N. a. plenissima*; *N. gladstoniana*, raised by Richardson of Lordstown, Ohio; *N. casparyi alba* Carrière, *Rev. Hort.* 1888, p. 300. To *N. alba rubra* belongs *N. froebelii*. To *N. odorata rosea* we refer *N. odorata rubra*; *N. rosacea*; *N. exquisita*. To *N. odorata gigantea* we refer *N. gracillima alba* Marliac Cat. 1901; *N. caroliniana nivea* Marliac Cat. 1901; *N. eburnea* André, *Rev. Hort.* 1895, p. 568. To *N. odorata minor* belong *N. odorata pumila* and *N. union*. To *N. tuberosa* we refer *N. tuberosa richardsoni*; *N. t. plena*.)

18. *N. ALBA* \times *CANDIDA*? (= *N. alba candidissima* Hort.; *N. candidissima* Hort.). A large, white, free-flowering variety; very robust. Sterile.

19. *N. ALBA* \times *ODORATA*? (= *N. marliacea albida* Marliac). The flower is pure white, stamens yellow, sepals flushed pink; fragrant. Leaves large, deep red beneath. On account of the color of the sepals, and a tendency to pink on the stamens, the pollen parent may have been *N. o. rosea*, and the plant, in that case, belongs with *N. m. carnea* and *rosea* (No. 20), which it resembles in every respect except color. Sterile. Introduced by Marliac about 1889.

20. *N. ALBA* × *ODORATA ROSEA*? (*N. marliacea carnea*; *N. m. rosea*; *N. Wm. Doogue*). Differs from No. 19 only in color of flower, which is from light pearly pink to deep rose; all are strong, luxuriant growers but sterile. Under the first two names it was introduced by Marliac about 1889; *Wm. Doogue* was obtained by Henry A. Dreer Co. ten years later.

21. *N. ALBA* × *ODORATA ROSEA*? (*N. colosseae* Marliac 1901). Flowers and leaves very large; petals flesh colored. Blooms from early spring until frost. Sweet scented. It may be a second hybrid, *N. alba candidissima* × *odorata rosea*.

22. *N. ALBA RUBRA* × ———. A large number of hybrids and variants have been introduced recently possessing the characteristic red shading of the Swedish waterlily, and without distinct indications of other parentage. Perhaps *N. candida* has been used (as the flowers are often cup-shaped), or they may be second or third or multiple crosses; the latter is highly likely. Some of the types are fairly distinct, even to an amateur, but most of them can be recognized only by the professional. In *N. marliacea flammea*, *N. m. ignea*, and *N. gloriosa* there is a faint blotching of the leaf which can come only from *N. mexicana* or *N. tetragona*. We have not noted any such character in *N. ellisiana*, *sanguinea*, *marliacea rubra punctata*, *laydekeri purpurea*, *Wm. Falconer*, *James Gurney*, or *James Brydon* (= *N. brydonacea elegans*).

23. *N. ODORATA ROSEA* × *TUBEROSA*? (= *N. caroliniana*, *c. perfecta*, *c. rosea*; *N. tuberosa superba*; *N. odorata caroliniana*, *o. carolinensis*, *o. superba*, *o. luciana*, *o. suavissima*). This hybrid is a much stronger grower than *N. odorata rosea*, but otherwise resembles it. The cross easily occurs, but was first cultivated by Dr. Bahnsen of Salem, North Carolina, about 1890.

24. *N. TUBEROSA* × *ODORATA ROSEA*? (= *N. tuberosa rosea*; *N. brakeleyi rosea*). Flowers pink. The plant has nearly the habit of *N. tuberosa*, but the rhizome is less tuberiferous. *N. tuberosa rubra* (Sturtevant 1901) is said to be *N. brakeleyi rosea* × *N. rubra*; but from the description it is more probably (*N. tuberosa* × *odorata rosea*) × *alba rubra*. The "rosy red" flowers and "bright red stamens" indicate this. The plant was not flowering when I saw it in Mr. Sturtevant's garden (June, 1902); the leaves were small, entire, and petioles dark red.

Subgenus IV. LOTOS.

25. *N. LOTUS* × *RUBRA*. Successive crosses between these species have been very often made, and every possible gradation between them has been obtained. They differ in color and size of leaf and flower and relative breadth of petal and degree of opening of the flower; the hybrids vary also in texture of leaf and in distribution of color on the petals. In *N. sturtevantii* the leaves are crimped at margin far more than in either parent; and the color of *N. Geo. Huster* is darker than any strain we have seen of *N. rubra*. According to Focke (1881) *N. rubra* with *N. lotus* or *ortgiesiana* gives the same product whichever is used as pollen parent, and the same is true of *N. lotus* and *dentata*. But in *N. rubra* and *dentata* the hybrid progeny resembles the female parent in respect to relative length and breadth of early leaves and floral leaves.

With regard to color, the forms now in cultivation, with originator, date of origin, and reputed parentage, may be arranged in series, thus :

1. *N. dentata magnifica* (*N. omarana* × *dentata*) Bisset 1902.
2. *N. dentata grandiflora* Sturtevant 1901. White.
3. *N. eastonensis* (*N. omarana* × *smithiana*) Ames 1900.
4. *N. jubilee*, Dreer 1899. Delicate pinkish white. *N. Queen Elizabeth* (*N. devoniensis* × *ortgiesiana*) 1855 (*fl.* Focke).
5. *N. smithiana*, Tricker 1893. *N. indica Isis* (cf. Moenkemeyer 1897). *N. laelia* (*N. colombiana* × *smithiana*), and *N. l. colorans* (ditto) Ames 1900.
6. *N. delicatissima*, Tricker 1894. Light pink.
7. *N. deaniana*, Tricker 1894. *N. boucheana* (*N. rubra* × *dentata*) Bouché 1853 (cf. Planchon 1854). *N. indica Spira* (cf. Moenkemeyer 1897).
8. *N. kevuensis* (*N. dentata* × *devoniensis*). Raised at Kew, 1885 (cf. Botanical Magazine, tab. 6988). Pink to red.
9. *N. sturtevantii* (*N. devoniensis* seedling) Sturtevant 1884. *N. indica Hofgartner Graebener* (cf. Moenkemeyer 1897). *N. rubicunda* (*N. sturtevantii* × *lotus*) Ames 1900.
10. *N. omarana*, Plate XXX (*N. dentata* × *sturtevantii*), Bisset 1894. Magenta. *N. ortgiesiano-rubra* (*N. ortgiesiana* × *rubra*) Ortgies 1852 (cf. Planchon 1851 aa). *N. mariae lagrangei* (*N. lotus* × *dentata*) Lagrange (cf. André 1899). *N. niobe* (*N. ampla* × *rubra*) Ames 1900 (cf. page 222 above).
11. *N. diana* (*N. sturtevantii* × *ampla*) Grey 1900 (cf. above, p. 222). *N. indica Brahma* (Froebel Cat. 1901).
12. *N. devoniensis* (*N. rubra* × *lotus*) at Chatsworth, Eng., 1851. *N. arnoldiana* Oliver, about 1899.
13. *N. columbiana*, Tricker 1894. *N. diana grandiflora* (*N. sturtevantii* × *ampla*) Ames 1900 (cf. above, p. 222).
14. *N. George Huster* (*N. omarana* seedling) Dreer 1899. Dark red.
15. *N. Frank Trelease*, Gurney 1900.


Focke (1881) mentions, without further comment than is here given, a considerable list of crosses involving species of the *Lotos* group. We append the list, referring back to p. 221 for our views on those cases where two subgenera are involved.

- N. Queen Elizabeth* × *dentata* gave red and rose-colored flowers.
N. Queen Elizabeth × *caerulea* gave violet flowers.
N. rubra × *ortgiesiana* = *N. ortgiesiano-rubra*.
N. ortgiesiana × *rubra* = *N. ortgiesiano-rubra*.
N. rubra × *lotus* = *N. lotus* × *rubra*.
N. lotus × *dentata* = *N. dentata* × *lotus*.
N. alba × *ortgiesiano-rubra* gave seedlings which never matured. A reported cross of *N. devoniensis* and *Victoria regia*, Focke says is mistaken.

Planchon (l. c.) mentions the following attempts at hybridization, but we can find no further record of the plants :

- N. thermalis* × *rubra*; young plants obtained.
N. thermalis × *scutifolia*; young plants obtained.
N. alba × *ortgiesiana*; young plants obtained.
N. dentata × *ortgiesiano-rubra*; seedlings obtained.
N. alba × *ortgiesiano-rubra*; three seedlings obtained.







NYMPHÆA OMARANA.

Unsuccessful attempts were made with *N. scutifolia* \times *dentata* and the reverse; *N. scutifolia* \times *rubra* and reverse; *N. odorata* \times *rubra*, and *N. ortgiesiana* \times *caerulea*. It is notable that all of these failures involved two subgenera.

It would be interesting, could we trace any definite and constant relations among hybrids. A diagram of the pedigree of some of the best known varieties may aid in this. We select *N. omarana* and the "rose and red" flowered hybrids of *N. Queen Elizabeth* and *dentata*. In each couple we place the pollen parent above.



According to this a single infusion of *N. rubra* has sufficed to produce a rich magenta color in the fourth generation. But in Mr. Bisset's new *N. dentata magnifica* (*N. omarana* \times *dentata*), the tide is completely turned and the flower is pure white. The next instance, however, is like that of *N. omarana*, viz.:



Is red, then, a dominant color in the Mendellian sense, and is it therefore primitive? Discussion would at present be wholly speculative and had best be omitted. A wide field for investigation is opened up. But none of our garden stock can be warranted pure enough to start on. We need fresh importations of the natural species, and a careful comparison of a large number of sister plants. The custom of gardeners is to discard all seedlings whose foliage does not give indications of the desired results; consequently only certain types have been preserved for us.

CHAPTER VIII.

CULTURE AND USES.

The use of waterlilies for food and ornament among the ancient Egyptians has already been referred to. This still continues to some extent in Egypt, but, on the West Coast of Africa, *Nymphaea* seeds constitute an important article of food. Travelers describe seeing the native women and children coming in at evening to the villages laden with the ripening fruits. These are laid in heaps until all of the soft parts decay. The seeds are then easily washed out clean, and are dried and stored away. They contain so much starch, oil, and proteid that they should form a very nutritious diet. When dry the seed coat is brittle and the kernel slightly shrunken, so that the two are easily separated. The kernels may be ground into a kind of flour or may be boiled whole. The resting tubers, in the dry season, are almost solid starch, and are eaten boiled or roasted like potatoes. The species used in West Africa are *N. caerulea* and *lotus*. In Madagascar, *N. lotus* and *capensis* are similarly used, and the seeds of *N. gigantea* are eaten by the Australians. In Central America also waterlily seeds are used for food. *Victoria cruziana* is known as "water corn" (*Mais del agua*) in Paraguay on account of its large farinaceous seeds.

In the days of empirical medicine and the "doctrine of signatures" the medicinal virtues of *Nymphaea* were highly overrated. Its leaves were said to be antipyretic, and a decoction of the dried leaves and rhizomes was supposed to be powerfully anaphrodisiac. Although it still holds a place in the United States Dispensatory, and is mentioned by Tavera (1901) in his medical botany of the Philippines, it is probably never used. The whole plant is very astringent and bitter, on account of the presence of tannin and gallic acid (cf. Grüning, 1881; Niederstadt, 1883; Fridolin, 1884). Whatever value it has is due to these constituents.

But it is as ornamental plants that *Nymphaeas* have achieved their present wide-spread fame, especially in Europe and North America. The English colonies in India and Australia are also giving them considerable attention, and a beautifully arranged pond has long been a feature of the Botanic Garden of Buitenzorg in Java. Their culture began in the large

estates and botanic gardens of England, with the introduction of *N. odorata* in 1786. From that time until 1812 several species were brought to English gardens. Then there was a period of inactivity until the appearance of *Victoria* about 1840 aroused great interest in aquatics. From 1850 to 1860 this wave reached its maximum, when Planchon, Lehmann, and Hooker described several species, and Caspary began his immortal work on the genus. There followed a lull until near 1880. Probably *N. zanzibariensis* served to bring its congeners before the public again. Another wave of waterlily culture set in, which probably has not yet reached its maximum. So magnificent are the results recently achieved, and of so lasting a nature, that this branch of gardening is likely to be of importance as long as flowers are grown for the beautifying of public or private grounds.

For cultural purposes we may divide the genus into two groups—the hardy and the tender varieties. In the first group *Castalia* stands alone. All others are tender in our climate. In the *Botanical Magazine* and *Flore des Serres* brief cultural directions are given for each species described; these are almost wholly intended for tender varieties when grown under glass. But since the extended culture of these plants can only be carried on where the climate will admit of their being for three months at least out of doors, we shall speak only of the latter condition. Out-door culture of tropical forms is of very recent date. So recently as 1891 Herr Borsig's water garden in Berlin was noted as of especial interest. He warmed the pond with waste hot water from his factory. Mr. Vilmorin described the place in *Revue Horticole*, and the article was reproduced in translation in the *London Garden*, and in *Garden and Forest* (1891, p. 375). In *Garden and Forest* for 1888 (pp. 241-242) cultivation of waterlilies in shallow ponds is urged as both possible and desirable in the eastern United States. In the garden trade the hardy species were slower than the tender ones in getting recognition. *Gardeners' Chronicle* in 1848 informs a correspondent concerning *N. alba* that "the roots of these things may sometimes be had in the nurseries, but they are not usually kept." In 1849, however, it is stated that *N. rubra*, *caerulea*, *stellata*, and *ampla* may "be had from any of the large nurserymen." Vick's Catalogue for 1883 mentions only *N. odorata*. At present sixty-four varieties are entered in the catalogue of one of the leading American dealers.

The care of them is very simple. The pond or tank may be only a large bucket or a half-barrel; in such accommodations *N. tetragona*, *N. t. helvola*, *N. marliacéa chromatella*, or even *N. caerulea*, will get along and

bloom ; the first two will do quite well. But the best thing is a brick and cement pool 60 cm. deep and of as large a size as one can get room for ; after one season's trial the tank will seem too small, at any rate. A single course of brick will be sufficient for a small tank, but a double course is better. Mr. Arnold, of Sharon Hill, gets beautiful results with a pool where the earth was simply scooped out and an even coat of cement laid directly on the ground. In any case it is best to protect the edges of the pond in winter by a coat of litter ; if a weak construction is used this is absolutely necessary, as a leak caused by frost would let the water out and the resting rhizomes would be fatally frozen. A natural pond, if not frequented by muskrats, is excellent for hardy varieties, but it would be rare to find one north of Washington warm enough for the tender kinds. *N. alba candidissima*, *odorata gigantea*, and *colossea* will do well in water as deep as one or two meters. Select a place for the tank where it will get full sunlight all day. Waterlilies are usually but little shaded in their native haunts, and the tropical species need all the light possible when in our northern climes. It is desirable to have the water-level constant, and to change the water just enough to keep it fresh.

For planting the rhizomes it is only necessary with the stronger hardy varieties in natural waters to tie a stone close to the rhizome and throw it in where the depth will be suitable. If one would be more careful, the rhizomes may be planted in weak splint baskets of earth and put in place. By the time the plant needs more room the basket will be falling to pieces, or at least, will be easily broken, and the roots will have full liberty. Such planting may be done at almost any time of year, but preferably in fall or spring. Sometimes on account of weakness, sometimes because of excessive dominance, it is desirable to keep the plants within prescribed bounds ; in that case permanent pots, boxes, or tubs must be provided. This is necessary in artificial ponds. Nothing less than a half-barrel is really worth while. A tub 100 to 130 cm. in diameter and 45 to 50 cm. deep gives the best results for all of the larger species, but I have seen *N. elegans* and *gigantea* blooming in tubs only 40 cm. across, and *N. zanzibariensis* will produce pretty little flowers in a "six-inch" pot ! Square board boxes of any size may be made to suit circumstances.

The character of the soil for these pots or tubs is of prime importance ; it must be very rich. Various prescriptions for its preparation have been given. R. Müller (1885) recommends a mixture of three parts soil, two parts compost, and two parts peat for hardy *Nymphaeas*. We find nothing equal to well-rotted cow manure for fertilizer, and Mr. Tricker's

(1897) preparation of good garden soil or sod compost with one-third to one-half of manure gives the finest possible results. Swamp muck is not at all to be recommended. If well-rotted cow manure can not be had, bone dust may be substituted in the proportion of "a six-inch pot full to a barrow load of soil" (Tricker, l. c.). Even in such strong materials a good plant of any of the larger tender forms will completely exhaust the nutrient in a half-barrel of soil before the end of the season; hence the desirability of larger tubs for the best results. The plants should be placed with the crown on a level with the surface of the soil. This should be covered with 1 to 3 cm. of clean sand to keep the manure down and to prevent the activities of certain aquatic worms which often carry up much fine matter to the surface of the tub and tend to bury the plant. For the hardy varieties the tub must be placed deep enough in the water to be safe from actually freezing. Tender varieties need to be within 15 to 25 cm. of the water surface in order to take advantage of the greater warmth of the upper strata. The area of water surface required per plant depends upon the species and the size of the tub it is planted in. I have seen *N. rubra*, *N. marliacea chromatella*, and *N. tetragona* in a tank 120 cm. square, with the water-poppy flourishing in whatever space remained; and all four species bloomed freely all summer. Each of the Nymphaeas had one flower every day, and sometimes two, and the water-poppy sometimes had a dozen flowers at once! But they were badly crowded. *N. tetragona* will be satisfied with a space 60 cm. square; most of the hardy varieties require a space 100 to 120 cm. square for a single shoot; and the tender varieties will cover a space 3 to 5 meters across.

Once placed as above described, the plants need no attention throughout the season except to keep up the water supply and trim off dead leaves and flowers. They should bloom at the rate of a new flower every two or three days, or perhaps one every day. As each flower lasts two to five days, the display is always fine. Of course the varieties differ in production of flowers, and the situation and other circumstances have their effects. Hardy species should not be moved for two or three years at least, but the tender ones must be wintered with considerable care. Large blooming plants may be lifted with a ball of earth 30 to 60 cm. in diameter, potted, and kept in a warm tank with plenty of light. They will then bloom all winter, and may be planted out again. It is best, however, to let old plants of the tender day-blooming species die. The night-bloomers should be taken up in late October or early November, potted in sand or planted under the bench of the conservatory, and allowed

slowly to dry off. In about a month they will almost certainly produce strong tubers, which should be kept in dry sand but not allowed to become absolutely desiccated. In March or April tubers of all of the tender varieties should be planted in sand in a warm tank. As each stolon gets its first floating leaf it should be carefully detached from the tuber and potted off, and the tuber replanted for the development of additional stolons. With tender day-blooming species (apocarpous) it is important to obtain two or more plants in the spring. One of these should be kept in a 6-inch or 8-inch pot, and dried off about mid-summer to form a tuber for the next season, as the flowering plants usually die. Hardy varieties are propagated from the rhizomes, by cutting and planting out in spring.

Propagation by seed is also easy, but is not possible for hybrids. The ripening fruits are covered with muslin bags; the mouth of the bag is tied fast around the peduncle, and the bag should also be tied to a stick for safe keeping. After the fruit has burst and its parts decayed, the bag is taken in and the seeds washed from the debris. Should the pods burst unexpectedly and the seeds be found floating on the pond, they may be dipped up with a fine wire sieve tied on a pole. Seeds of the *Castalia* group must be kept in water in a cool place until ready for sowing. Other seed may be dried and kept in the usual way. It is advisable to sow *Castalia* seeds as soon as ripe; their germination is at best irregular, and it is unusual to get flowering plants the first year. The tender varieties may be sown in flat pans, barely covered with sand, and placed in warm tanks in February. The young plants should be pricked off into small pots and kept moving rapidly; they will produce plants of the largest size the first season. Planting out in the pond must be delayed until all danger of frost, or even of a cold rain storm, is over. The first of June often proves too early in this latitude. *N. gigantea* is especially tender. The labeling of seeds and plants in water can only be successfully done on metal labels. Thin copper or brass on which one writes with a stylus, or with asphalt varnish, makes the only satisfactory and durable label.

Some hints on hybridizing have already been given, but it may be worth while to recapitulate. No haphazard work pays. It is better to get no seeds than to go to the pains of raising a batch of supposed hybrids and find they are all pure species. The flower to be used for seed should be covered with a fine net (finer than mosquito bar) before it begins to open; do it on the previous day. As soon as it opens (or before) all of the stamens must be plucked out. For the greatest accuracy the pollen

flower should also be kept netted before and after it opens ; this is to avoid any mixing of pollen by insects. Now, on the day the seed-flower first opens, the net is removed for a moment while, with a brush, pollen from the chosen male parent is stirred around in the stigmatic fluid. The net is replaced, and in a week or so the result will be indicated by a swelling of the ovary if successful, or by decay of the flower and peduncle if no fertilization was effected. Some consider that the pollen should be applied at the close of the first period of opening of the seed-flower. I have succeeded very well in the *Brachyceras* group at that time or earlier, but have no successful experience in any other group.

Several enemies attack waterlilies and work great havoc. In the seed beds, algæ may grow up and choke the little plants ; the use of less manure and more sand in the pots is a preventive measure, and weak Bordeaux mixture will kill the algæ. After the first transplanting, a damping-off fungus sometimes carries off numbers of seedlings ; the leaves become transparent in ever-increasing areas until they are all gone. This must be prevented by care in pricking off ; if the plants are not wounded, and are not weakened by the shock of moving, they will outstrip the fungus. Snails, too, sometimes devour the leaves, or cut them off and leave them floating on the tank ; pick out the offenders and throw them away. The first floating leaves are often seriously weakened by swarms of aphides. A strong spray from hose or syringe will wash them off, and a few sun-fish or paradise fish will effectually prevent their return to the leaves.

As to enemies of mature plants, I can do no better than to quote Mr. Tricker's summary from the *Cyclopedia of American Horticulture* (1901, p. 1104) :

Aphides are sometimes troublesome. The best remedy is their natural enemy, the "lady bugs" or "lady birds." A colony of these voracious insects makes short work of the aphides, as do also the lace-winged flies. An insect of recent acquaintance with Nymphaeas is a leaf-miner, the larva of a small fly, which cuts channels through the leaf in all directions. Sometimes only a few of these are in evidence, at other times the leaves are fairly alive with them. The trouble is easily detected. The marks suggest Japanese writing or the efforts of youthful artists. A simple and effective remedy is kerosene emulsion, applied with a fine spray at evening after the flowers are closed. Another troublesome insect has its home in Florida, and has come North to spend the summer in a favored clime. This is a leaf-cutter, *Hydrocampa proprialis*. The larva cuts out pieces of the leaf and hides between two pieces, which make a kind of tent. In this tent the larva moves about. At first it moves slowly, but as it nears maturity the larva becomes ravenous and then eats the surface of the

leaves near the center, and cuts off much larger pieces of the leaf for camping-out purposes. The best remedy for this pest is a lamp trap for the mature insect. Frogs and dragon-flies will catch numbers of them.

Nymphaeas are also subject to a fungous disease, a leaf spot which is easily discerned after a spell of warm humid weather. After such a spell of weather, followed by bright sunshine, the leaves are scorched and crumpled up, and, as a result, the plant is sadly crippled by being denuded of its foliage; new leaves are weak and smaller, and so too are the flowers, if indeed there are any. This disease must be checked at once or the plants will be severely set back, if not ruined. The only remedy is Bordeaux mixture, or any of the various mixtures with sulphate of copper as the basis. Use a fine spray, and dilute the mixture to half the strength recommended for most plants. It is best to spray twice with a weak solution rather than to spray once with too strong a solution and damage the foliage.

Finally, the ravages of muskrats eating the rhizomes of hardy species in winter must be mentioned. Three fine collections, in my small acquaintance, have been seriously injured or destroyed in this way. Traps and a bounty on hides are two practical aids to the gardener. But here, as in so many cases all along life's journey, "eternal vigilance" is the price of success. And the success, once it is attained, more than repays the labor of love which it costs.

BIBLIOGRAPHY.

- Abbott, C. C. 1888. *Nymphaea tuberosa* in Eastern Waters, in G. & F. 2: 263.
- Abel, L. 1901. Winterharte Nymphaeen und Nelumbien, in Wiener illustrierte Gartenzeitung, 26: 130-134 (not seen).
- A. G. (American Gardening). 1893, 14: 112 (not seen).
- 1894, 15: 415 (not seen).
- 1897, 18: 471 (not seen).
- 1900, 21: —.
- Alton, William. 1789. Hortus Kewensis, 2: 226-228. London.
- 1811. Hortus Kewensis, Second Edition 3: 292-294. London.
- Alpinus, Prosperus. 1592. De Plantis Aegypti liber etc. Venice.
- Alpinus, Prosperus, and Veslingius, Joannes. 1735 a. Rerum Aegyptiacarum. Leyden. (Opera posthuma, Pars I.)
- 1735 b. De Lasercpitio et Loto Aegyptia (in Opera posthuma, Pars II).
- Ameling, E. 1893. "Ueber mittlere Zellgrößen" in Flora, 77: 176-207. Marburg.
- Ames, O. 1900. "An Interesting Group of New Hybrid Blooming Nymphaeas," in American Gardening 21: 644, No. 301, Sept. 29.
- André, Ed. 1882. *N. zanzibariensis*, in Revue Horticole, p. 317-318.
- 1884. *N. alba* var. *rubra*, l. c., p. 384.
- 1895 a. Nouveaux Nymphéas, l. c., p. 258.
- 1895 b. Les Nymphéacées de Temple-sur-Lot, l. c., p. 568.
- 1896. Nouveaux Nymphéas rustiques, l. c., p. 352-353.
- 1897. Nouveaux Nymphéas rustiques de M. Latour-Marliac, l. c., p. 513.
- 1899. '*Nymphaea Mariae Legrangei*,' l. c., p. 136.
- Andrews, Henry C. The Botanist's Repository. London, 1799-1811.
- Appel, O. 1895. Kritische und andere bemerkenswerthe Pflanzen aus der Flora von Coburg, in Mitth. Thür., N. F., 8: 16-20 (not seen). Ref. in Bot. Jahrsber. 1895, 2: 208.
- Arcangeli, G. 1889. Sulla struttura dei semi della *Nymphaea alba*, in Nuov. Giorn. Bot. Ital., 21: 122-125. Firenze 1889.
- 1890 a. Sulla Emergenze e spine dell' Euryale e sulle cladoscloreidi delle Ninfceae, l. c. 22: 266-271. Firenze 1890.
- 1890 b. Sulla foglie delle Piante acquatiche e specialmente sopra quelle della *Nymphaea* e del Nuphar, l. c., 441-446.
- Arnott, G. A. W. See WIGHT, R.
- Athenaeus. The Deipnosophists; trans. C. D. Yonge; 3 vols. London, 1854. Also text and notes of J. Schweighaeuser, in 14 vols., 1805.
- Aublet, J. B. C. F. 1775. Histoire des plantes de la Guiane française. London and Paris, 1775, 4 vols. 3: 533.
- Bacon, A. 1874. Insects destroyed by vegetables, in Bulletin of the Torrey Botanical Club, 5: 51-52. Dec., 1874.
- Bailey, F. M. 1899. The Queensland Flora. Brisbane.
- Badillon, H. 1871. Histoire des Plantes, 3: 77-104.
- Baldacci, A. 1894. Affinità della Aristolochiacee e dei generi aristolochiacei, in Bull. Soc. Bot. Ital., 1894, p. 49-54. Ref. in Bot. Jahrsber. 1894, 2: 253.
- Barber, C. A. 1889. On a Change of Flowers to Tubers in *Nymphaea Lotus*, var. *monstrosa*, in Annals of Botany 4: 105-115, with pl. 15.
- Bartélemy, A. 1874. De la respiration et de la circulation des gaz dans les végétaux, in Annales des Sciences Naturelles, Botanique, Série V, 19: 131-175.

- Bauhin, Caspar.** 1623. *Pinax theatri botanici, sive Index* in Theophrasti, Dioscoridis, Plinii et Botanico-
 rum qui a saeculo scripserunt, etc. Basil. Also, Basil, 1671 (the edition I used).
- Bauhin, Johannes.** 1670. *Histoire des Plantes de l'Europe, et des plus usitées qui viennent d'Asie, Afrique et Amerique.* 2 vols. Lyons.
- Baum, H.** 1902. *Nymphaea Guineensis*, in *Die Gartenwelt*, Aug. 30, 1902, p. 565, with figure (not seen). Ref. in *Journ. Roy. Hort. Soc. London.* 27: 772. Dec., 1902.
- 1903. *Kunene-Zambesi Expedition*, in *Auftr. des kolonial-wirtschaftlichen Comité*
 herausgeg. von Prof. O. Warburg. Berlin. Ref. in *Bot. Cent.* 1903, 93: 492-494.
- Beardslee, H. C.** 1877. Some *Nymphaeas*, in *Botanical Gazette* 2: 144.
- Behm, Fl.** 1887. *Fän botaniska excursioner i Jemtland och Herjedalen [Sweden]*, in *Botaniske*
Notiser, 1887, p. 176-184 (not seen). Ref. in *Bot. Jhrsbr.*, 1887. 2: 396.
- Bello y Espinosa, D. D.** 1881. *Apuntes para la flora de Puerto-Rico*, in *Anales Sociedad Espa-*
ñola de Historia Natural, 10: 231-304. Madrid. Presented Sept. 1, 1880.
- Bellonus, Petrus.** 1605. See *CLUSIUS*, 1605.
- Bentham, G., and Hooker, J. D.** 1862. *Genera Plantarum*, vol. I. London, 1862-67; Part 1. 1862,
 pp. 1-434.
- Bentham, G., and Müller, F. von.** 1863. *Flora Australiensis*, 1: 61-62. London, 1863.
- Besler, B.** 1613. *Hortus Eystettensis*.
- Blanco, P. F. M.** 1878. *Flora de Filipinas*, 2: 222-223. Manila.
- Blass, J.** 1891. *Untersuchungen über die physiol. Bedeutung des Siebtheils der Gefässbündel*, in
Pringsheim's Jhrbchr. f. wiss. Bot. 22: 253-292.
- Bleicher, G.** See *MIEG*, M.
- Blume, C. L.** 1826. *Kruidkundige Waarnemingen*, in *Linnaea* 1: 643-668.
- Bock, Hieronymus.** 1551. *Kreuter Buch. Darin unterscheidet Namen und Würckung der Kreuter*,
 etc. Strassburg.
- Bodaeus à Stapel.** 1644. See *THEOPHRASTUS*, 1644.
- Bolus, H., and Wolley-Dod, A. H.** 1903. A list of the flowering plants and ferns of the Cape
 Peninsula, etc., in *Trans. S. African Philosoph. Soc.* 14: 207-373. Ref. in *Bot. Cent.*
 1904, p. 405.
- Boissier, Edm.** 1867. *Flora Orientalis* 1: 104. Basel and Geneva.
- 1882. *Plantes sèches trouvées sur des momies par M. le Dr. Schweinfurth (Extrait d'une*
lettre du 17 décembre 1881, adressée à Edm. Boissier), in *Archives des Sciences Phy-*
siques et Naturelles, Troisième Période, 7: 147-149. Geneva.
- 1888. *Flora Orientalis, supplement*, 22-23.
- Bonavia, E.** 1894. *The Flora of the Assyrian Monuments and its outcomes.* Westminster.
- Bonnier, G.** 1890. *Observations sur les Berbéridées, Nymphaeacées, Papavéracées et Fumariacées*
de la Flore de France, in *Revue Générale de Botanique* 2: 276, 446, 549.
- Bontius, Jacobus.** 1658. See *PISO*, 1658.
- Borbás, V. von.** 1881. *Ueber Nuphar sericeum* Láng in *Botan. Centralbl.* 6: 421-423.
- Boreau, Alex.** 1859. In *Mémoires de la Société Académique de Maine et Loire.* 6: 37-8. Angers.
- Brand, F.** 1894. *Ueber die drei Blattarten unserer Nymphaeaceae*, in *Bot. Centralbl.* 57: 168-171.
 Cassel, 1894.
- Branner, J. C., and Coville, F. V.** 1888. A list of the plants of Arkansas, corrected by W.
 Trelease, in *Annual Report of the State Geologist*, 1888, vol. 4, part 2.
- Braun, H.** 1890. *Neue Funde aus Ungarn*, in *Oesterr. Bot. Ztschr.* 1890, p. 27-30, 60-68, 136-137
 (not seen). Ref. in *Bot. Jhrsbr.* 1890. 2: 394. #
- Breynius, Jacobus.** 1680. *Prodromi fasciculi rariorum plantarum primus [1680] et secundus*
 [1689], etc., ed. Joh. Philip. Breynii. Gedani, 1739.
- Britten, J.** 1888 a. *The Nomenclature of Nymphaea, etc.*, in *Journ. of Botany, Brit. and For.*, 26:
 6-10. London, January, 1888.
- 1888 b. *Recent tendencies in American botanical nomenclature*, I. c., p. 257-262.
- Britten, J., and Holland, R.** 1879. *A dictionary of English plant names, Part II. (English Dialect*
Society: London, 1879.)

- Britton, N. L. 1889 a. Catalogue of the plants of New Jersey, in Geolog. Survey of N. J., Final Report of the State Geologist, 2: 43. Trenton, 1889.
- 1889 b. The A. A. A. S. Botanical Club's Trip to the Lakes of Muskoka, Ontario, Aug. 31 to Sept. 2, 1889, in Bull. Torr. Bot. Cl. 16: 285-290. New York, 1889.
- 1890. On the naming of "Forms" in the New Jersey Catalogue, in Bull. Torr. Bot. Cl. 17: 121-126.
- Britton, N. L., and Brown, Ad. 1897. An Illustrated Flora of the Northern United States, Canada, and the British Possessions, 2: 42-45. New York, 1897.
- Britton, N. L., Coulter, J. M., Rusby, H. H., etc. 1894. List of Pteridophyta and Spermatophyta growing without cultivation in Northeastern North America, in Memoirs of the Torrey Bot. Cl. 5: 153-154. Nymphaeaceae by Thos. Morong, May 5, 1894.
- Britton, N. L., Stern, Poggenburg, etc. 1888. A Preliminary Catalogue of Anthophyta and Pteridophyta reported as growing spontaneously within 100 miles of New York City. New York, Apr. 25, 1888.
See also MORONG, T.
See also HOLLICK, A.
- Brodhead, G. C. 1878. On the Distribution of Certain Plants in Missouri, in Bot. Gazette 3: 51.
- Brongniart, A. T. 1822. Sur la classification et la distribution des végétaux fossiles. Paris.
- 1827. Mémoire sur la génération et le développement de l'embryon dans les végétaux phanérogames, in Ann. Sci. Nat., Bot., 12: 225-296.
- 1849. Tableau des genres de végétaux fossiles, p. 117-119.
- Brown, Ad. See BRITTON, N. L.
- Brown, R. 1827. Observations on the structure of the unimpregnated ovulum, in Miscellaneous Botanical Works of Robert Brown, 1: 439-452. London, 1866 (not seen).
- Buckhout, W. A. 1891. Notes from a Pennsylvania Garden, in Garden and Forest, 4: 69.
- Buckley, Edm. 1897. Universal Religion; a course of lessons, historical and scientific, on the various faiths of the world. Chicago.
- Bunge, D. A. See MEYER, D. C. A.
- Bureau, E. 1888. Études sur la Flore fossile du calcaire grossier parisien, in Mém. publ. par la Soc. Philomath. à l'occasion du cent. de la fécondation, 1788-1888, 2 pl. Paris (not seen). Ref. in Bot. Jhrsber. 1888, 2: 249.
- Burman, N. L. 1768. Flora Indica 4: 241. Leyden.
- Burmah, J. 1759. Plantarum Americanarum Fasc. 9, p. 205.
- Cambessedes, J. 1844. See JACQUEMONT, 1844.
- Campbell, D. H. 1902. On the affinities of certain anomalous dicotyledons, in American Naturalist, 36: 7-12. Jan., 1902.
- Carrière, E. A. 1878. *N. sphaerocarpa*, in Revue Horticole.
- 1879 a. Prolifération d'un *Nymphaea rubra*, in Rev. Hort. p. 74-75.
- 1879 b. *Nymphaea Caspary*, l. c., p. 230.
- 1880. *N. Caspary*, l. c., p. 403.
- 1884. *N. flava*, l. c., p. 479-480.
- 1888. *N. Casparyi alba*, l. c., p. 300.
- Caspary, Robert. 1854. [On growth of leaves.] Versammlung der Naturforscher in Göttingen, Tageblatt, p. 28. Sept. 20. Ref. in Flora, 1854, p. 642.
- 1855. De *Nymphaeae albae* varietatibus, in Catal. sem., hort. Berol. 1855. Flora, 1856, p. 488-496. Walpers Annales botanices systematicae, 4: 162-166. 1857.
- 1856. Les Nymphaeacées Fossiles, in Annales des Sciences Naturelles, Botanique, Sér. 4: 6: 199-222. Paris, 1856.
- 1857 a. In Koelner Zeitung, Beilage, 14 Febr. (not. seen).
- 1857 b. Bericht über die Verhandlungen der botanischen Sektion der 33. Versammlung deutscher Naturforscher und Aerzte, gehalten in Bonn vom 18. bis 24. September, 1857, in Botanische Zeitung, 15: 784-792, and in Flora, 1857, p. 717-718.
- 1858. Monographie der Hydrilleen, in Jhrbchr. f. wiss. Botanik 1: 377-513; pl. xxv-xxix.
- 1859. Botanische Verhandlungen der niederrheinischen Gesellsch. f. Natur und Heilkunde zu Bonn im Jahre 1858, in Flora, 1859, p. 118-119, 139, 143-144.

- Caspary, Robert.** 1862, in *Berliner Monatsber.*, p. 464 ff. (not seen).
 — 1863, in *Oesterr. Bot. Ztschr.* (not seen).
 — 1865. *Nymphaeaceae* in Miquel's *Annales Musei Botanici Lugduno-Batavi*, 2: 241-253. Amsterdam, 1865-66.
 — 1870, in *Schr. Phys.-ock. Ges. Königsberg*, p. 62 (not seen).
 — 1870, in *Abh. Naturf. Ges. zu Halle*, 11: 251 ff. (not seen).
 — 1871. *Nymphaea alba* L. var. *sphaerocarpa* Casp. subvar. *rubra* käuflich, in *Botan. Ztg.*, p. 874.
 — 1872. *Nymphaeaceae* a Frederico Welwitsch in Angola lectae, in *Journ. de Scienc. Math., Phys., e Nat. da Acad. Real das Sci. de Lisboa*. Dec., 1873, p. 312-327.
 — 1877. *Nymphaea zanzibariensis*, n. sp., etc., in *Bot. Ztg.* Mar. 30, 1877, p. 200-203.
 — 1878. *Nymphaeaceae*, in de Martius' *Flora Brasiliensis* 4: part 2, p. 129-184. Leipzig, June, 1878.
 — 1879. Hvilken utbredning hafva *Nymphaeaceae* i Skandinavien? in *Botaniska Notiser*, 1879, p. 65-93. Stockholm (not seen). Ref. in *Bot. Jhrsber.* 1879, 2: 229-230; 1880, 2: 562.
 — 1880. *Nymphaeaceae*, in *Reliquiae Rutenbergianae* I. in *Abhandl. herausgeg. vom Naturwiss. Verein zu Bremen*, 7: 10-11.
 — 1882. *N. Zanzibariensis*, in *Wittmacks Gartenzeitung*, 1882, p. 1-6.
 — 1883. Bericht ueber die Untersuchungen der Seen der Kreise Graudenz, Kulm und Thorn, 1882, in *Schr. d. Phys.-Oekonom. Gesellsch. zu Königsberg*, 1883, 24 Jhrg., 1 Abth. p. 83-87 (not seen). Ref. in *Bot. Jhrsber.* 1883, 2: 280.
 — 1884. Bericht ueber die 22. Versamml. des Preuss. Bot. Vereins zu Marienberg in Westpreussen am 9 Oct., 1883, 1. c., 1884, 1 Abth. p. 45-111 (not seen). Ref. in *Bot. Jhrsber.* 1884, 2: 277.
 — 1886. Ber. ü. die 23. Versamml. des Preuss. Bot. Ver. zu Memel am 7 Oct., 1884, 1. c., 1885, p. 40 (not seen). Ref. in *Bot. Jhrsber.* 1886, 2: 419.
 — 1888. *Nymphaeaceae*, in Engler & Prantl's *Natürlichen Pflanzenfamilien*, vol. 3, part 2, p. 1-10. Published Jan. 17, 1888.
Celakovsky, L. 1867. *Prodromus der Flora von Böhmen*.
Celsus, A. Cornelius. *Of Medicine*, trans. James Greene, M. D., Ed. III., revised by Geo. Futvoye. London, 1838.
Chabraeus, Dominicus. 1677. *Stirpium sciagraphia et icones ex museo Chabr.* Geneva.
Chamberlain, J. C. See COULTER, J. M.
Chamisso, Ad. de. 1831. De plantis in Expeditione Romanzoffiana observatis disserere pergitur. *Arcticae*, in *Linnaea* 6: 588.
Champollion le jeune. *Panthéon Egyptien*.
Chapman, A. W. 1883. *Flora of the Southern United States*.
Chevalier, Aug. 1900 a. Mon exploration botanique du Soudan français, in *Bull. du Muséum d'Histoire naturelle*, Paris, 1900, No. 5, p. 248-254.
 — 1900 b. Mon exploration botanique de la Sénégambie, 1. c. No. 6, p. 302-308.
Chiffot, J. B. J. 1902. Contributions à l'étude de la Classe des Nymphéinées. *Annales de l'Univ. de Lyon, Nouv. Sér. I, Sciences, Médecine*. Fasc. 40, 294 pp.
 — 1903. Sur la structure de la graine de *Nymphaea flava* Leitn., in *Compt. Rend.* 136: 1584-1586. Ref. in *Bot. Cent.* 93: 200.
Cler, O. 1873. Ueber einige Pflanzen aus dem Ural, in *Schr. d. Uralsch. Gesellsch. der Liebhaber der Naturwiss.* 1: 28 (not seen). Ref. in *Bot. Jhrsber.*, 1873, p. 601.
Clusius, Carolus. 1576. *Rariorum aliquot stirpium per Hispanias observatorum Historia*, lib. 2. Antwerp.
 — 1601. *Rariorum Plantarum Historia*. Antwerp.
 — 1605. *Exoticorum libri decem*, etc.: item Petri Bellonii observationes. Antwerp.
Commelin, Caspar. 1696. *Flora Malabarica, sive horti Malabarici catalogus*, etc. Leyden.
Conard, H. S. 1901 a. *Nymphaea*, in *Bailey's Cyclopedia of American Horticulture*, 3: 1101-9.
 — 1901 b. A new tender *Nymphaea*, in *American Gardening*, 22: 745. Nov. 2.

- Conard, H. S. 1902. Note on the embryo of *Nymphaea*, in *Science*, 15: 316, Feb., 1902. Ref. in *Bot. Gazette*, 33: 389-390.
- 1903. *Nymphaea* (sub-gen. *Brachyceras*) in Africa, in *Annuaire du Conservatoire et du Jard. Bot. de Genève*. May 15.
- Constantin, J. 1885. Sur la structure des feuilles du *Nymphaea rubra* et du *Nuphar luteum*, in *Bull. Soc. Bot. de France*, 32: p. xv (not seen).
- 1886. Études sur les feuilles des Plantes aquatiques, in *Ann. Sci. Nat. Bot. Sér. 7*, 3: 94-162.
- Constantinus, Robertus. See THEOPHRASTUS.
- Cook, M. T. 1902. Development of the Embryo-sac and Embryo of *Castalia odorata* and *Nymphaea advena*, in *Bull. Torr. Bot. Cl.* 29: 211-220, pl. 12, 13. April.
- Cooke, T. 1901. Flora of the presidency of Bombay, Part I. Bombay.
- Coulter, J. M. 1890, in Contributions from the U. S. Nat. Herb., June 28, 1890, p. 30-65.
- 1891. Manual of the Phanerogams and Pteridophytes of western Texas, in *Contrib. from the U. S. Nat. Herb.* 2: 11-12.
- See also BRITTON, N. L.
- Coulter, J. M., and Chamberlain, C. J. 1903. Morphology of Angiosperms. New York.
- Coville, F. V. See BRANNER, J. C.
- Curtiss, A. H. 1902. The Yellow Water-lily of Florida, in *Plant World*, 5: 106-9, with Fig. June (not seen).
- Dahmen, Max. 1892. Anatomisch-physiologische Untersuchungen über den Funiculus der Samen, in *Pringsheim's Jhrbchr. f. wiss. Bot.* 23: 462.
- Dalton, W. 1853. History of British Guiana, 2: 241.
- De Bary, A. 1884. Comparative Anatomy of the Phanerogams and Ferns.
- De Candolle, A. P. 1895. Sur la graine des *Nymphaea*, in *Soc. Philom. Bull.* 3: 68. Paris.
- 1821 a. Sur les affinités naturels de la famille des Nymphaeacées, in *Mém. Soc. Phil.* 1: 208-244. Geneva (not seen).
- 1821 b. Regni Vegetabilis Systema Naturale, 2: 49-59.
- 1824. Prodrômus Systematis Naturalis Regni Vegetabilis, Part 1, p. 114-116.
- De Halácsy, E. 1900. Conspectus Florae Graecae, 1: 37.
- Delessert, B. Icones selectae. Paris, 1820-46.
- Delile, A. R. 1802. Observations sur les Lotus d'Egypte, in *Annales du Muséum d'Histoire Naturelle*, 1: 372-382. Paris.
- 1813. Florae aegyptiacae illustratio, in *Description de l'Egypte*. Paris.
- Delpino, F. 1869. Alcuni appunti di geogr. botanica, in *Bull. d. Soc. geogr. ital.*, Fasc. 3, p. 17 (not seen).
- 1871. Eintheilung der Pflanzen nach dem Mechanismus der dichogamischen Befruchtung, und Bemerkungen über die Befruchtungsvorgänge bei Wasserpflanzen, in *Bot. Ztg.* 29: 443-445, 447-459, 463-467.
- Dennert, E. See WIGAND, A.
- Diodorus Siculus, the Historical Library of. Trans. G. Booth. London, 1700.
- Dioscorides, Pedanios. De Materia Medica libri quinque. Ed. Curtius Sprengel. Leipzig, 1829. 2 vols.
- Dodonaeus, Rembertus. 1583. Stirpium historiae pemptades sex. Antwerp.
- Don, Geo. 1831. A general History of dichlamydeous plants, 1: 126.
- Donn, J. 1831. Hortus Cantabrigiensis, 12th edition, by Geo. Sinclair. London, p. 251.
- Douliot, H. See VAN TIEGHEM, PH. 1888.
- Dryander, J. 1801. Description of *N. caerulea*, in *Bot. Mag.* tab. 552.
- Duchartre, P. E. 1858. In *Journ. Soc. imp. et cent. d'horticult.* 4: 175, with plate (not seen).
- 1877. In *Journ. Soc. Hort.* p. 817 (not seen).
- Durand, Th., and Schinz, H. 1898. Conspectus Florae Africae, 1: 55-56. Brussels, Berlin, and Paris.
- See also WILDEMAN, ÉM. DE.
- Duppa, R. 1813. Illustrations of the Lotus of Antiquity. London.
- 1816. Illustrations of the Lotus of the ancients and Tamara of India. London. (Only 25 copies of this were printed; I have seen neither of Duppa's works.)

- Dutt, M. N. 1895. Mahabharata. Prose English translation, 1895-97.
- Dyer, Sir Wm. Thistleton. Flora Capensis (not seen).
- Edgeworth, M. P. 1845. Descriptions of some unpublished species of plants from North West India, in Trans. Linn. Soc. London. 20: 23-91, 1851. Read June 3, 1845.
- Eichler, A. W. 1875. Blüthendiagramme, vol. 1.
- 1878. Blüthendiagramme, 2: 186.
- Ellwell. Pāli Vocabulary (not seen).
- Endlicher, S. L. 1836. Genera Plantarum. Vienna, 1836-50 (not seen).
- Endlicher, S. L., and Unger, F. 1843. Grundzüge der Botanik, p. 92, Fig. 94. Wien.
- Engler, A. 1879. Versuch einer Entwicklungsgeschichte der Pflanzenwelt. Vol. 1, 1879; vol. 2, 1882.
- 1895. Die Pflanzenwelt Ost-Afrikas und der Nachbargebiete, Theil C. Berlin, p. 178.
- 1898. Syllabus der Pflanzenfamilien, p. 115.
- 1901. Beiträge zur Flora von Afrika, in Engler's Bot. Jahrb., 30: 308.
- Eriksson, J. 1876. Ueber den Vegetationspunkt der Dikotylen-Wurzeln. Eine vorläufige Mittheilung, in Bot. Ztg., 34: 641-644.
- 1877. Ueber das Urmeristem der Dicotylenwurzeln, in Jahrbücher f. wiss. Botanik, 11: 380-435, pl. 18-27. 1878.
- Espinosa. See BELLQ Y ESPINOSA. 1881.
- Ettingshausen, K. von. 1877. Die fossile Flora von Sagor in Krain, in Denkschr. d. math.-naturw. Cl. d. Kais. Akad. d. Wissensch. in Wien., 37: 186.
- 1888. Die fossile Flora von Leoben in Steiermark, l. c. 54: 319-384.
- Falkenberg, P. 1874. Stämmbau der Monocotylen. Vorl. Bericht, in Nachr. v. d. kgl. Ges. d. Wiss. zu Göttingen, 17. Sept. 1874; also Bot. Ztg. 1874, p. 731.
- 1876. Vergleichende Untersuchungen über den Bau der Vegetationsorgane der Monocotyledonen. Stuttgart.
- Fischer, H. 1890. Beiträge zur Vergleichenden Morphologie der Pollenkörner. Breslau.
- Flacourt, Etienne de. 1661. Histoire de la grande isle Madagascar. Troyes et Paris, 1661 [also Paris, 1658].
- Flahault, Ch. 1878. Recherches sur l'accroissement terminal de la racine chez les Phanérogames, in Ann. Sci. Nat., Bot., Sér. VI, 6: 1-168.
- Fliche, P. See MIEG, M.
- Flora. 1833, p. 648-651. [Discussion of *N. alba minor*.]
- Focke, W. O. 1881. Die Pflanzen-Mischlinge. Berlin, p. 24-27.
- Forbes, F. B., and Hemsley, W. B. 1899. An enumeration of all the plants known from China proper, Formosa, Hainan, etc., in Journ. Linn. Soc., Botany, 26: 457-538, etc.
- Frank, A. B. 1868. Beiträge zur Pflanzenphysiologie, p. 150 (not seen).
- 1872. Ueber die Lage und Richtung schwimmender und submerser Pflanzenteile, in Cohn's Beiträge z. Biol. d. Pflanz., 1: 31-86, Heft. 2.
- Freidenfelt, T. 1900. Studier öfver örtartade växters rötter, in Botaniska Notiser, Heft 5, 15 pp. (not seen). Ref. in Bot. Centralbl. 86: 156-161; 1901.
- Friend, H. 1882. A Glossary of Devonshire Plant Names. London. English Dialect Society.
- Fridolin, A. 1884. Vergleichende Untersuchungen der Gerbstoffe des *N. alba*, etc. Inaug. Dissert. Dorpat., 94 pp. (not seen).
- Fries, E. M. 1836. Botanisch-antiquarischer Ausflug zu den Nymphaeaceen der Griechen. Upsala, 1836 (not seen). Ref. in Bot. Ztg. 3: 463-464 (1845).
- 1846. Summa Vegetabilium Scandinaviae, 1846-49 (not seen).
- 1858. Kürzere briefliche Mittheilungen, in Bot. Ztg., p. 23.
- Fritsch, K. 1852. Kalender der Flora des Horizontes von Prag (not seen).
- Fuchs, Leonhartus. 1551. Plantarum effigies; Lugduni apud Arnolletum. [Smaller edition from the Historia Stirpium; folio, 1552; Pritzel.]
- Gaertner, J. 1788. De Fructibus et Seminibus Plantarum 1: 72-73.
- Galenus, Claudius. De simplicium medicamentorum temperamentis ac facultatibus, and De alimentorum facultatibus, in Opera Omnia, ed. C. G. Kuhn, 20 vols. Leipzig 1826.

- Garden, The (London). 1873. *N. odorata*, 4: 368 (poor).
 ——— 1879. *N. alba rubra*, 15: 235.
 ——— 1882. *N. tuberosa*, 21: 130.
 ——— 1883 a. *N. Devoniensis*, 23:—Apr. 14.
 ——— 1883 b. 23: 334.
 ——— 1891. 39: 519 (not seen).
 ——— 1897. *N. tuberosa*, 52: 44 (bad).
 ——— 1899. *N. odorata*, 55: 179.
 Gave, P. 1892. In Proc. Société Dauphinoise, 2d series (not seen)
 G. C. (Gardeners' Chronicle). 1852. *N. devoniensis*, p. 435.
 ——— 1887. *N. Kewensis*, p. 366.
 ——— 1899. *N. fennica*, p. 138 (Mch. 4).
 ——— 1900. *N. gigantea*, p. 77 (with poor wood cut).
 ——— 1901 a. Hybrid Water Lilies, p. 157, Mch. 9. Condensed from The Garden of Feb. 9.
 ——— 1901 b. [Exhibit at Royal Horticultural], p. 141, 155, 160.
 ——— 1901 c. Mr. Maurice Pritchard's Christchurch, p. 222-223; also p. 327.
 Georgi, J. G. 1775. Bemerkungen einer Reise im Russischen Reich im Jahre 1772. 1: 220. St. Petersburg, 1775 (not seen).
 ——— 1800. Beschreibung des russischen Reichs. 3: part 4, p. 1845.
 Gerard, John. 1636. The Herball or Generall Historie of Plantes. Gathered by John Gerard, very much enlarged and amended by Thomas Johnson. (Original ed., 1597, Pritzel).
 Gerard, J. N. 1890 a. *Nymphaea pygmaea alba*, in G. & F., 3: 374.
 ——— 1890 b. The Water Garden, in G. & F., 3: 480.
 ——— 1891. The Water Garden, in G. & F., 4: 453.
 ——— 1892. The Water Garden, in G. & F., 5: 332-3.
 ——— 1893. The Water Garden, in G. & F., 6: 347.
 ——— 1894. *N. Sturtevantii*, in G. & F., 7: 354-356 (with good half tone of flower).
 Gerardus, L. 1761. Flora Gallo-provincialis.
 Gerlicke, H. 1879. Einiges aus dem Bochmerwalde, in Abh. d. Naturforsch. Gesell. zu Goerlitz, 16: 214-261 (not seen). Ref. in Bot. Jhrsber. 1879, 2: 258.
 Geyler, H. Th. 1882. Verzeichniss der Tertiärflora von Flörsheim a. M., in Ber. ü. d. Senckenberg. naturf. Gesellsch. 1882-83, p. 285-286 (not seen).
 G. & F. (Garden and Forest). 1888. *Castalia Leibergi*, 1: 186, June 13.
 ——— 1893 a. *N. gigantea*, 6: 40-41 (with good half tone).
 ——— 1893 b. *N. tuberosa*, 6: 415-416 (with good half tone of flower).
 ——— 1894 a. *N. odorata*, 7: 60.
 ——— 1894 b. Plant notes, 7: 326.
 Giles, Herbert Allen. 1884. Gems of Chinese Literature. London.
 Gilg, E. 1903. Nymphaeaceae in "Kunene-Zambesi-Expedition," p. 234-236. Cf. Baum 1903.
 Gmelin, J. G. 1769. Flora Sibirica, 4: 183, tab. 71. St. Petersburg.
 Godfrin, J. 1880. Etude histologique sur les téguments séminaux des Angiospermes. Nancy (not seen).
 Godman, F. D., & Salvin, O. 1888. Biologia Centrali-Americana. Botany, 1: 24-26, by W. B. Hemsley.
 Goebel, K. 1886. Zur Entwicklungsgeschichte des unterständigen Fruchtknotens, in Bot. Ztg., 44 Jhrg., p. 729-738.
 ——— 1887. Outlines of classification and special morphology, trans. by H. E. F. Garnsey.
 ——— 1893. Pflanzenbiologische Schilderungen, 2: 215-373, Wasserpflanzen.
 Goodale, G. L. 1886. Wild Flowers of America, Boston, 1886 (pl. 38).
 Goodyear, W. H. 1891. The Grammar of the Lotus (not seen).
 Graebener, L. 1887. Noch einmal die *Nymphaea Zanzibariensis* Casp. var. *flore rubro*, in Wittmack's Gartenflora, 36: 258-259.
 Gray, Asa. 1850. Plantae Wrightianae, 1: 7, in Smithsonian Contributions to Knowledge, vol. 3. Washington, 1852.
 ——— 1876. *Nymphaea flava*, in Silliman's Journal, 11: 416.

- Gray, Asa. 1889. Manual of the Botany of the Northern United States, 6th ed. Preface by S. Watson, Dec. 26, 1889.
See also TORREY, J.
- Gray, Asa, S. Watson and B. L. Robinson. 1895. Synoptical Flora of North America, 1: part 1, p. 75. Oct. 10, 1895, fascicle 1.
- Greene, E. L. 1887 a. Bibliographical notes on well-known Plants; III, *Nymphaea* and *Nuphar*, in Bull. Torr. Bot. Cl. 14: 177-179 (September).
—— 1887 b. Bibliographical Notes on well-known Plants; VI, *Nymphaea* and *Nuphar*, l. c., p. 257-258 (December).
—— 1888. Bibliographical Notes on well-known Plants; VII, *Castalia* and *Nymphaea*, l. c. 15: 84-85 (March).
- Gremli, A. 1882. Neue Beiträge zur Flora der Schweiz, Heft 2, pp. 1-55. Aarau, 1882 (not seen).
Ref. in Bot. Jahrsber. 1882, 2: 540.
- Grew, Nehemiah. 1672. The Anatomy of Vegetables. London.
—— 1681. Musacum Regalis Societatis. London.
- Grey, R. M. 1900. New Hybrid *Nymphaeas*, in American Gardening, 21: 516, No. 293, Aug. 4.
- Grisebach, A. H. R. 1857. Systematische Untersuchungen ueber die Vegetation der Karaiben, in Abhandl. der Königl. Gesellsch. der Wissensch. zu Göttingen, 7: 151-286 (not seen).
—— 1864. Flora of the British West Indian Islands.
—— 1882. Flora Europaea, fragmentum. Reliquiae Grisebachianae, edited by A. Kanitz (not seen). Ref. in Bot. Jahrsber. 1882, 2: 43.
- Gronovius, J. F. 1762. Flora Virginica, ed. 2.
- Grüning, W. 1881. Beiträge zur Chemie der Nymphaeaceen. Inaug. Dissert. Dorpat. 78 pp. (not seen).
- Guettard, J. E. 1747. Observations sur les plantes. Paris (not seen).
- Guillemin, A., and Perrottet, S. 1830. Florae Senegambiae tentamen. Paris, 1830-33.
- Gwynne-Vaughn, D. T. 1896 a. A New case of polystely in Dicotyledons, in Annals of Botany, 10: 289-291.
—— 1896 b. The arrangement of vascular bundles in certain Nymphaeaceae, l. c., p. 624-625.
—— 1897. On some points in the Morphology and Anatomy of the Nymphaeaceae, in Trans. Linn. Soc. London, 5: 287-299, pl. 21-22.
- Haberlandt, G. 1877. Schutzeinrichtungen in der Entwicklung der Keimpflanze. Wien (not seen).
—— 1884. Physiologische Pflanzenanatomie.
- Hallier, Hans. 1903. Ueber die Verwandtschaftsverhältnisse bei Engler's Rosalen, etc., in Abh. aus dem Gebiete der Naturwissensch. Naturw. Verein in Hamburg, 18: 1-98. Ref. in Bot. Cent. 1904, pp. 223-224.
- Hansen, E. C. 1874. Pflanzenreste in den Schichten dänischer Torfmoore, reviewed in Naturforscher, No. 47, p. 448 (not seen).
- Hanagirt, A. 1880. Floristisches aus der Königgrätzer Gegend in Böhmen, in Oest. Bot. Ztschr., 30: 394-397 (not seen). Ref. in Bot. Jahrsber., 1880, 2: 588.
- Hanstein, J. 1858. Ueber den Zusammensetzung der Blattstellung mit dem Bau des dicotylen Holzringes, in Jahrbchr. f. wiss. Bot., 1: 233.
- Harper, R. M. 1903. Botanical explorations in Georgia during the summer of 1901, in Bull. Torr. Bot. Cl. 30: 319-342. Ref. in Bot. Cent. 93: 20. 1903. Gives *Castalia odorata latifolia*, new var.
- Harshberger, J. W. 1899. Botanists of Philadelphia and their Work. Philadelphia.
- Hartman, C. J. 1870-71. Handbok i Skandnaviens Flora, ed. 19, p. 86 (not seen).
- Harvey, F. W. 1880. Distribution of Nymphaeaceae in Arkansas, in Bot. Gazette, 5: 140.
- Harvey, W. H. 1838. The Genera of South African Plants, ed. 1, Cape Town, 1838 (not seen).
- Harvey, W. H., and Sonder, O. W. 1859. Flora Capensis, vol. 1, Dublin, 1859-60.
- Hasselquist, F. 1757. Iter palaestinum. Stockholm (not seen).
- Hausleutner, J. L. E. 1859. Ueber eine neue *Nymphaea* aus Schlesien, in Bot. Ztg., 8: 905-908.
- Heckel, Ed. 1879. Des poils et des glandes pileuses dans quelques genres de Nymphaeacées, in Compt. rend. 89: 758-759 (not seen).

- Heer, O.** 1861. *Recherches sur le climat et la végétation du pays tertiaire*. Winterthur. (German ed., *ibid.*, 1860). See also *Zeitschr. gesamt. Naturwiss.* XV: 1-42. 1859 (not seen).
- 1865. *Die Urwelt der Schweiz*, 2d ed. English trans. by J. Heywood. London, 1876.
- 1869. *Die Miocene Flora u. Fauna Spitzbergens*, in *Svenska Vetensk. Acad. Handl.* VIII, *No. 7; also *Zeitschr. gesamt. Naturwiss.*, hrsg. von C. Giebel u. W. Heintz. 39: 405-408; 1872.
- 1878 a. *Flora fossilis arctica*, vol. 5, part 1, *Die Miocene Flora des Grinnell-Landes*. Zürich.
- 1878 b. *Flora fossilis arctica*, vol. 5, part 2, *Beiträge zur fossilen Flora Sibiriens und des Amurlandes*.
- 1878 c. Notes on Plants discovered in Grinnell Land by Capt. H. W. Feilden, Naturalist of the English North-polar Expedition, in *Quart. Journ. Geolog. Soc.*, 1878, p. 66-70.
- Hemslay, W. B.** 1879. *The Hardy Red Water Lily*, in *The Garden* (London), 15: 516 (with fair colored plate).
- 1888. See GODMAN & SALVIN, 1888.
See also FORBES, F. B.
- Henfrey, A.** 1852. On the anatomy of the stem of *Victoria regia*, in *Philos. Transact.* 1852, p. 289-294 (not seen).
- Henslow, G.** 1892. A theoretical origin of Endogens from Exogens, in *Journ. Linn. Soc. London, Botany*, 29: 485-488.
- 1895. The origin of plant structures by self-adaptation to the environment. London, pp. 136-179.
- Hentze, W.** 1848 a. Beschreibung einer neuen *Nymphaea*, in *Bot. Ztg.*, 6: 601-604, Aug. 25.
- 1848 b. Weitere Mittheilung ueber die Untersuchung deutscher Seerosen, in *Bot. Ztg.*, 6: 697-702. Oct. 6.
- 1852 a. In *Ann. Sci. Nat. Bot., Sér. 3*, 18: 377.
- 1852 b. Berichtigung, in *Bot. Ztg.*, 10: 745-747. Oct. 22.
- Herodotus.** Literally translated from the Text of Baehr by Henry Cary, M. A. London, 1891.
- Hervey, E. W.** 1899. *Observations on the color of flowers*. New Bedford, Mass.; 105 pp.
- Hildebrandt, F.** 1874. *Die Verbreitungsmittel der Pflanzen*. Leipzig (not seen).
- Hildebrandt, J. M.** 1879. Von Mombassa nach Kitui, in *Zeitschr. der Gesellsch. für Erdkunde zu Berlin*, 14: 259 (not seen). Ref. in *Bot. Jhrsher.* 1879, 2: 477.
- Hill, E. J.** 1890. Notes on the Flora of the Lake Superior Region, I. The Northern Peninsula of Michigan, in *Bot. Gazette*, 15: 140-149.
- 1891. Notes on the Flora of the St. Croix Region, I. c. 16: 126-130.
- Hitchcock, A. S.** 1890. Catalogue of the Anthophyta and Pteridophyta of Ames, Iowa. Contributions from the Shaw School of Botany, No. 7, in *Trans. Acad. Sci. St. Louis*, 5: 477-532.
- Hofmeister, W.** 1858. Neuere Beobachtungen über Embryobildung der Phanerogamen, in *Jhrb. f. wiss. Bot.*, 1: 82-189.
- 1867. *Handbuch der Physiologischen Botanik*, 1: part 1, *Die Lehre von der Pflanzenzelle*. Leipzig.
- 1868. *Handbuch der Physiologischen Botanik*, 1: part 2, *Allgemeine Morphologie der Gewächse*. Leipzig.
- Holfert, J.** 1890. Die Nährschicht der Samenschalen, in *Flora*, 77: 279-313 (not seen).
- Holland, A.** See BRITTON, J.
- Holland, P.** See PLINY.
- Hollick, A., and Britton, N. L.** 1886. *Flora of Richmond County, New York; Additions and New Localities*, in *Bull. Torr. Bot. Cl.* 13: 83-84.
- Hooker, J. D.** 1872. *Flora of British India*. London; pp. 113-116.
- 1881. *Nymphaea tuberosa*, in *Botanical Magazine*, tab. 6536.
- 1883. *Nymphaea odorata minor floribus roseis*, l. c., tab. 6708.
- 1884. *Nymphaea alba var. rubra*, l. c., tab. 6736.

- Hooker, J. D. 1885. *Nymphaea stellata* var. *Zansibariensis*, l. c., tab. 6843.
 ——— 1887. *Nymphaea flava*, l. c., tab. 6917.
 ——— 1888. *Nymphaea Kewensis*, l. c., tab. 6988.
 ——— 1901. *Nymphaea flavo-virens*, l. c., tab. 7781.
 See also BENTHAM, G.
- Hooker, J. D., and Jackson, B. D. 1893. Index Kewensis. London.
- Hooker, J. D., and Thomson, Th. 1855. Flora Indica, 1: 285 pp. Ref. in Gard. Chron., 1855, p. 723.
- Hooker, W. J. 1846. *Nymphaea dentata*, in Bot. Mag. tab. 4257.
 ——— 1849. *Nymphaea ampla*, l. c. tab. 4469.
 ——— 1850. *Nymphaea micrantha*, l. c. tab. 4535.
 ——— 1851. *Nymphaea elegans*, l. c. tab. 4604.
 ——— 1852 a. *Nymphaea gigantea*, l. c. tab. 4647.
 ——— 1852 b. *Nymphaea Devoniensis*, l. c. tab. 4665.
 ——— 1854. *Nymphaea amazonum*, l. c. tab. 4823.
- Irmisch, T. 1859. Zur Naturgeschichte des *Potamogeton densus* L., in Flora 1859, p. 129-139.
- Jackson, B. D. See HOOKER, J. D.
- Jacquemont, V. 1844. Voyage dans l'Inde, 4: 11-12, Botanique. Paris, 1844.
- Jahn, E. 1896. Ueber Schwimmblätter, in Beitr. z. wiss. Bot., 1: 284-294. Ref. in Rev. Gen. de Bot., 11: 79.
- James, D. L. 1881. *Nymphaea odorata*, in Botan. Gazette, 6: 266-267.
- Janczewski, Ed. de. 1874 a. Recherches sur l'accroissement terminal des racines dans les Phanérogames, in Ann. Sci. Nat., Sér. 5, 20: 162-207.
 ——— 1874 b. Rech. sur le développ. des radicules dans les Phanérogames, l. c., p. 208-233.
- Jeffrey, E. C. 1900. The morphology of the central cylinder in the Angiosperms; Nymphaeaceae, p. 24-27. Canadian Inst. Trans. vol. 6 (not seen).
- Jekyll, G. 1901. Wall and water garden. London; 177 pp. (not seen).
- Joret, Charles. 1897. Les Plantes dans l'antiquité et au moyen age. Paris.
- Jungner, J. R. 1895. Wie wirkt träufelndes und fliessendes Wasser auf die Gestaltung des Blattes? in Bibliotheca botanica, Hft. 32 (not seen).
- Karelin, Gr., and Kirilow, J. 1842. Enumeratio Plantarum in desertis Songoriae orientalis et in jugo summorum alpium Alatau in anno 1841 collectarum, in Bulletin de la Soc. Imp. des Naturalistes de Moscou, 15: 129-180, 321-453, 503-542. Also separate: Mosquae 1842. 223 p.
- Karsten, G. 1888. Ueber die Entwicklung der Schwimmblätter bei einigen Wasserpflanzen, in Bot. Ztg., 46: 565-578; 581-589.
- Kerner, A. 1886. Schedulae ad floram exsiccata Austro-Hungaricam IV. Wien (not seen). Ref. in Bot. Jhrsber., 1886, 2: 427.
 ——— 1895. Natural History of Plants, translated by F. W. Oliver. New York, 1895.
- Kerner, J. S. 1795. Hortus sempervirens, 1795-1830; 71 volumes; 9: tab. 99, 1799 (not seen). Comp. Pritzel, 163.
- Kirchner, Oskar. Flora von Stuttgart, p. 275 (not seen).
- Kirilow, J. See KARELIN, GR.
- Kitaibel, P. See WALDSTEIN, F. A., GRAF VON.
- Klebs, G. 1885. Beiträge zur Morphologie und Biologie der Keimung, Untersuchungen aus d. bot. Inst. zu Tübingen, 1: 536-635 (not seen). Ref. in Bot. Jhrsber., 1885, 1: 513-519.
- Klinggraff, H. von. 1883. Bereisung des Schwetzer Kreises, in Ber. ü. die 5. Versamml. des Westpreuss. Bot.-zoolog. Vereins zu Kulm am 30. Mai 1882. Danzig, 1883, p. 32-57 (not seen). Ref. in Bot. Jhrsber., 1883, 3: 276.
- Klinggraff, K. J. von. 1848. Flora von Preussen (not seen).
- Klotsch, J. F. 1862. In Peter's Naturw. Reise in Mozambique. Botanik, 1: 152 (not seen).
- Koch, G. D. J. 1857. Synopsis Florae Germanicae et Helveticae, ed. 3, part 1, p. 24. Leipzig.
- Koehne, E. 1869. Ueber Blütenentwicklung bei den Compositen. Berlin. Inaug. Dissert. (not seen).

- Kohl, F. G.** 1889. Anatomisch-physiologische Untersuchung der Kalksalze und Kieselsäure in der Pflanze. Ein Beitrag zur Kenntniss der Mineralstoffe im lebenden Pflanzenkörper. Marburg.
- Kny, L.** 1901. Ueber den Einfluss von Zug und Druck auf die Richtung der Scheidewände in sich theilenden Pflanzenzellen, in *Jhrb. f. wiss. Bot.*, 37: 55-98 (pp. 90-91).
- 1900. Ueber das angebliche Vorkommen lebenden Protoplasmas in weiteren Lufträumen der Wasserpflanzen, in *Ber. d. d. bot. Gesellsch.*, 18: 43.
- Kops, J.** 1800. *Flora Latava*, 13 volumes, by Kops, van Hall, etc., with 1040 colored plates. 1800-1868. Vol. 7, 1836, p. 539 (not seen).
- Korschinski, S.** 1892. Flora des Ostens des Europäischen Russlands in ihren systematischen u. geogr. Beziehungen, Part I, in *Ber. d. Univers. Tomsk*, 5: 71-299 [Russian] (not seen). Ref. in *Bot. Jhrsber.* 1893, 2: 86.
- Krilloff, P.** 1882. Material zur Flora des Gouvernements Perm (not seen). Ref. in *Engler's Bot. Jhrbch.* 4: 147.
- Kuntze, O.** 1891. *Revisio Generum Plantarum*, vol. 2. Leipzig.
- Kurz, Sulpiz.** 1864. Korte schets der Vegetatie van het eiland Bangka, in *Tijdschr. voor Nederl. Indië*, 27: 142-235; esp. p. 177, *vide* Caspary 1865.
- Lange, J.** See **LIEBMANN, F. M.**
- Lanman, C. R.** 1888. *Sanskrit Reader*.
- Lamarck, Jean B. de.** 1802. *Encyclopédie Methodique Botanique*. Article *Nymphaea*, 4: 455 ff.
- Lawson, Geo.** 1851. The Royal water-lily of South America and the Water-Lilies of our own land, their history and cultivation. Edinburgh, 1851.
- 1889. On the Nymphaeaceae, in *Trans. Roy. Soc. Canada*, 6: 97-123. Section IV. Montreal. Ref. in *Bot. Cent.* 45: 349-351.
- 1891. Notes for a Flora of Nova Scotia, in *Proc. and Trans. Nova Scotia Inst. of Science*, Halifax, 1: 84-110. 1891 (not seen). Ref. in *Bot. Jhrsber.* 1892, 2: 95.
- Lechartier, M. G.** 1867. Sur le mouvement des gaz dans les plantes aquatiques, in *Compt. Rend.*, 65: 1087-1091.
- Ledebour, K. F.** 1842. *Flora Rossica*, 1: 84. Stuttgart (not seen).
- Lehmann, J. G. C.** 1852 a. *Index Seminum in Horto Botanico Hamburgensi collectorum anno 1852*, p. 9 (not seen).
- 1852 b. In *Hamburger Garten- und Blumen-Zeitung* (Otto's), 8: 372.
- 1853 a. "Die Gattung *Nymphaea*," in *Otto's Hamburger Garten- und Blumen-Zeitung*, 9: —. Review by Seeman in *Bonplandia*, 1: 131-133.
- 1853 b. In *Amtl. Ber. ü. d. 29. Versamml. d. Gesellsch. deutsch. Naturforsch. u. Aertzte z. Wiesbaden*, Sitz. d. 22. Sept. (not seen).
- 1854. *Index Seminum in Horto Botanico Hamburgensi collectorum anno 1853*, in *Ann. Sci. Nat. Bot. Sér. 4*, 1: 323-327. Paris, 1854.
- 1857. Bemerkungen über einige Arten der Gattung *Nymphaea*. Auszug aus einem Briefe von Prof. L. etc., in *Flora*, 1857, p. 233-236.
- Leitner.** 1838. *Nymphaea flava* (name only), in *Audubon's Birds of America*, Pl. 411, large folio edition.
- Lemaire, C.** 1853. In *Jardin fleuriste*, 3: pl. 240-241.
- Lesquereux, Leo.** 1860. Botany and Paleontology, in *Second Report of a Geological reconnaissance of the middle and southern counties of Arkansas, during 1859-60*, p. 295-399. Philadelphia.
- Liebmänn, F. M., and Lange, J.** 1874. *Flora Danica*, Supplem. vol. I, fasc. III, p. 7, tab. 141.
- Lindberg, S. O.** 1881. In report of Societas pro Fauna et Flora Fennica zu Helsingfors, Sitz. vom 1. Oct. 1881, in *Bot. Centralbl.* 10: 268. 1882.
- Lindley, J.** 1853 a. In *Paxton's Flower Garden*, 2: 63, tab. 50.
- 1853 b. *N. Devoniensis*, l. c. 3: 123-124, tab. 98.
- See also **PAXTON, Jos.**
- Link, H. F.** 1831. *Handbuch zur Erkennung der nutzbarsten und am häufigsten vorkommenden Gewächse*. Berlin. 2: 405.

Linnaeus, C. 1753. *Species Plantarum*.

——— 1762. *Species Plantarum*, ed. 2. vol. 1. *

See also WILLDENOW, C. L.

Lloyd, F. E., and Tracy, S. M. 1901. The insular Flora of Mississippi and Louisiana, in *Bull. Torr. Bot. Cl.*, 28: 61-101.

Lobelius, Matthias. 1576. *Plantarum seu stirpium historia. Cui adnexum est Adversariorum volumen.* Antwerp.

Loennroth, K. J. 1856. In *Botaniska Notiser*, p. 124 (*vide* Hooker, 1884).

London, J. C. 1855. *Encyclopedia of Plants.* London, p. 462-464.

Lubbock, J. 1862. A contribution to our knowledge of seedlings, 1: 114-118. London.

——— 1894. On stipules, their forms and functions, II. Read June 21, 1894. *Journ. Linn. Soc.* London, 30: 463-532 (p. 468-9).

Ludwig, Christian Gottlieb. 1737. *Definitiones generum plantarum in usum auditorum.* Leipzig.

Ludwig, F. 1891. Zur Biologie der phanerogamischen Süßwasser-flora, in Zacharias' *Die Thier- und Pflanzenwelt des Süßwassers.* Leipzig. vol. 2 (not seen).

Lyon, H. L. 1901 a. Preliminary note on the embryogeny of *Nelumbo*, in *Science*, 13: 470.

——— 1901 b. Observations on the embryogeny of *Nelumbo*, in *Minnesota Botanical Studies*, Ser. 2, part 3, p. 643-655, pl. 48-50. July 20.

Lyte, Henry. 1578. *A Nieuwe Herball* (*vide* Britten and Holland 1879).

MacCarthy, G. 1885. A botanical tramp in North Carolina, in *Botan. Gazette* 10: 384-385.

Macdonell. *Sanskrit Dictionary* (not seen).

Macfadyen, J. 1837. *The Flora of Jamaica*, Vol. 1; *Ranunculaceae to Leguminosae.* London, 1837. p. 19-20. a

MacIntosh, C. 1885. *The Book of the Garden*, 2: 711-712, 743.

Mackintosh. 1876. Sections of Petioles of *Nymphaea*, in *Quart. Journ. of Microscop. Science*, 16: 108-9, new series (not seen). Ref. in *Bot. Jhrsber.* 1876, 1: 379.

MacMillan, C. 1892. *The Metasnermae of the Minnesota Valley.* Minneapolis, Dec. 29, 1892. p. 227-228.

Macoun, J. 1891. *Catalogue of Canadian Plants*, 5: 300, in *Geol. and Nat. Hist. Survey of Canada.* Montreal.

Magnin, A. 1893. *Recherches sur la végétation des lacs du Jura*, in *Revue Générale de Botanique* 5: 241-257, 303-316, 515-517.

Malpighi, Marcello. 1687. *Opera omnia, seu thesaurus locupletissimis botanico-medico-anatomicus*, etc. Leyden.

——— 1697. *Opera posthuma.* London.

Marianus, F. J. 1790. *Florae fluminensis seu descriptionum plantarum praefectura fluminensis sponte nascentium etc.* MS. prepared in 1790, in *Archivos do Museu Nacional do Rio de Janeiro*, vol. 5 for 1880. Rio de Janeiro, 1881.

Martius & Zuccarini. 1832. *See* ZUCCARINI, 1832 a.

Marty, L. 1902. Un *Nymphaea* fossile, in *Feuilles des Jeunes Naturalistes*, No. 375, p. 45-49. Ref. in *Bot. Cent.* 89: 442-443.

Masters, M. T. 1869. *Vegetable Teratology.*

——— 1878. *Nymphaea alba* var. *rosea*, in *Gard. Chron.*, new series, 9: 696; June 1.

——— 1902 a. Air canals in the leaf and in the flower-stalk of *Nymphaeas*, I. c., 3d series, 31: 134, 165.

——— 1902 b. The arrangement of the air canals in the stalks of *Nymphaeas*, in *Journ. Roy. Hort. Soc.* 26: 840-843. London (not seen).

Matthioli, Pietro Andrea. 1598. *Opera, quae extant, omnia; hoc est: Commentarii in sex libros Pedacii Dioscoridis Anazarbei de materia medica etc.; nunc a Casparo Bauhino post diversarum editionum collationem infinitis locis aucti, etc.* Basil, 1598. (Original ed. Venice 1554, *vide* Pritzel.)

Meehan, Thos. 1880. *Native Flowers and Ferns of the United States*, Ser. 2, 1: 121-124.

Mela, A. J. 1897. *Nymphaea Fennica*, eine neue europäische Scerose, in *Acta Societatis pro Fauna et Flora Fennica*, 14: No. 3. Helsingfors.

- Mellink, J. F. A. 1886. Zur Thyllenfrage, in *Bot. Ztg.*, No. 44. Ref. in *Bot. Jhrsber.*, 1886, 1: 880; 2: 498.
- Meyer, A. 1898. *Erstes mikroskopisches Practicum*. Jena.
- Meyer, D. C. A., and Bunge, D. A. 1829. *Flora Altaica*. Berlin.
- Meyer, G. F. W. 1818. *Primitiae Florae Essequiboensis*. Göttingen.
- Michaux, F. A. 1803. *Flora Boreali-Americana*, 1: 311.
- Mieg, M., Bleicher, G., and Fliche, P. 1890. Contribution à l'étude du terrain tertiaire d'Alsace et des environs de Mülhouse, in *Bull. Soc. Geol. France*, 3 sér., 18: 392-422 (not seen). Ref. *Bot. Jhrsber.* 1890, 2: 226.
- Millsaugh, C. F. 1893. Pink water lilies, in *Bull. Torr. Bot. Cl.*, 20: 21-22.
- Miquel, F. A. G. 1859. *Flora Indiae Batavae*, 1: part 2.
- Moenkemyer, W. 1897. *Sumpf- und Wasser-Pflanzen*.
- Mollisch, H. 1882. Zur Kenntniss der Einlagerung von Kalkoxatcrystallen in der Pflanzenmembran, in *Oest. Bot. Zeitschr.*, No. 12, p. 382-5 (not seen).
- Moorcroft, Wm. *Travels*, 2: 136 (not seen). Ref. in *Gard. Chron.*, 1842, p. 495.
- Morong, Thos. 1888. A new Water-lily, in *Botanical Gazette*, 13: 121-125.
- Morong, Thos., and Britton, N. L. An Enumeration of the Plants collected by Dr. Thos. Morong in Paraguay, 1888-1890, in *Ann. N. Y. Acad. Sci.* 1893, p. 48-49.
- Müller, C. 1890. Ein Beitrag zur Kenntniss der Formen des Ollenenchyms, in *Ber. d. d. bot. Gesellsch.* 8: 150-166.
- Müller, F. von. 1858. *Fragmenta phytographiae Australiae* 1: 61. Melbourne, 1858-59.
- 1861. *Fragmenta phytographiae Australiae* 2: 141-2. Melbourne, 1860-61.
- 1862. *Annual Report of the Government Botanist and Director of the Botanic Garden of Melbourne*, 1862-63, p. 11.
- 1875. *Descriptive Notes on Papuan Plants*, 1: 13, 95.
- 1887. *New Australian Plants*. Ref. in *Bot. Jhrsber.* 1887, 2: 214.
- 1889. *Systematic Census of Australian Plants, etc., Fourth Supplement*. Melbourne. Ref. in *Bot. Jhrsber.* 1889, 2: 135.
- See also BENTHAM, G.
- Müller, F. Max. 1881. *Sacred Books of the East*, vol. 10. Dhammapada. Oxford.
- Müller, H. 1883. *Fertilisation of Flowers*, trans. by D. W. Thompson. London. 1883. p. 93.
- Müller, R. 1885. Die winterharten Nymphaeen, in *Garten-Zeitung*, p. 566-567.
- Müller-Beeck. 1886. Verzeichniss der essbaren Pflanzen Japans, published by Verein zur Beförderung des Gartenbaues in den kgl. Preuss. Staaten (not seen). Ref. in *Bot. Jhrsber.* 1886, 2: 131.
- Nägeli, K. von. *Beitr. z. wiss. Botanik*, vols. 1-4, 1858-68; 1: 121 (not seen).
- *Zeitschr. f. wiss. Botanik*, 1844-1846. Hft. 3 and 4 (not seen).
- Nash, G. V. 1895. Notes on Some Florida plants, in *Bull. Torr. Bot. Cl.*, 22: 141-161.
- Nehring, A. 1892. Die Flora des diluvialen Torflagers von Klinge bei Kottbus, in *Naturw. Wochenschr.*, vol. 7, No. 24, 25, 45.
- Neilreich, A. 1867. *Diagnosis Plantarum Vascularium in Hungaria et Slavonia hucusque observatarum, quae in Koch Synopsi non contentae sunt*. Wien. In *K. K. Zool.-Bot. Gesellsch. Verhandl.* XVII. Beilage.
- Nicolai, O. 1865. Das Wachsthum der Wurzel, in *Schriften der Königlichen physikalisch-ökonomischen Gesellschaft zu Königsberg*, Jahrgang 6, p. 33-76, taf. 2, 3.
- Niederstadt. 1883. *Landwirt. Versuchsstation*, 29: 247-50 (not seen).
- Nobbe, Fr. 1876. *Handbuch der Samenkunde*. Berlin (not seen).
- Nuttall, Thos. 1818. *The genera of North American Plants, and a catalogue of the species, to the year 1817*. Philadelphia, 2 vols.
- Oborny, A. 1877. Die Flora des Znaimer Kreises, in *Verhandl. d. Naturforsch. Verein in Brünn*, 17: 114.
- Oliver, Daniel. 1868. *Flora of Tropical Africa*, 1: 52-53.
- Paine, J. A. 1865. *Catalogue of the Plants of Oneida Co., N. Y.*, in *Report of the Regents of the University of New York*, p. 132.

- Palácky, J.** 1897. Zur Flora von Centralasien, in Oest. Bot. Ztschr. 47: 361-7, 400-405 (not seen).
Ref. in Bot. Jhrsber. 1897, 2: 186.
- Parkinson, John.** 1640. Theatrum Botanicum. London.
- Parlatore, F.** 1881. Tavole per una anatomia delle piante aquatiche. Florenz (not seen). Ref. in Bot. Jhrsber. 1881, 1: 448.
- Paxton, Jos.** 1845? *Nymphaea rubra*, in Magazine of Gardening, 11: 265.
- 1852. *N. Devonensis*, in Gard. Chron., July 10.
- Paxton, Jos., and Lindley, J.** 1853 a. *N. micrantha*, in Flower Garden, 1: 140-141, No. 190.
- 1853 b. *N. elegans*, l. c. 2: 118-169, No. 393.
- 1853 c. *N. elegans*, l. c. 2: 182.
- 1853 d. *N. gigantea*, l. c. 3: 74-75, No. 546.
- Payer, J. B.** 1857. Traité d'organogénie comparée de la fleur. Paris.
- Perrottet, S.** See GUILLEMIN, A.
- Peter, A.** 1901. Botanische Wandtafeln. 39. Nymphaeaceae. Berlin (not seen).
- Petit, L.** 1888. Le pétiole des Dicotylédons, etc., in Mém. de la soc. des sci. phys. et nat. de Bordeaux, 3me sér. t. III (not seen).
- Pickering, Chas.** 1879. Chronological History of Plants. Boston.
- Pilleterius, Casparus.** 1610. Plantarum tum patriarum quam exoticarum in Walachria, Zeelandiae insula, nascentium synonymia. Middelburg (not seen). (Cf. Ned. krudk. Arch. 1877, Ser. 2, vol 2 p. 359.)
- Piso, Gulielmus.** 1648. Historia Naturalis Brasiliae. Leyden and Amsterdam.
- 1658. Hist. Nat. Brasil., ed. 2, with Jacobi Bontii Historiae naturalis et medicae Indiae orientalis, etc.
- Planchon, F. E.** 1850 a. *Nymphaea dentata*, in Flore des Serres 6: 293-296, tab. 627-628. Ghent, 1850-51.
- 1850 b. *N. rubra*, l. c. p. 297-299, tab. 629 (poor).
- 1850 c. *N. scutifolia*, l. c. p. 341, tab. 675.
- 1850 d. *N. rubra* (culture of), l. c. p. 481 c-d.
- 1850 e. *Victoria regia*, l. c. p. 193-224, 249-254.
- 1851 a. *N. caerulea*, l. c. 7: 19-20, tab. 653. Ghent, 1851-52.
- 1851 b. *N. gigantea*, l. c. p. 293 (description).
- 1851 c. *N. thermalis*, l. c. p. 295, tab. 706-707.
- 1852 a. *N. rubra*, l. c., 8: 25 tab. 759-760 (good). Ghent, 1852-53.
- 1852 aa. *N. Ortgiesiano-rubra*, l. c. p. 67-73, tab. 775-6.
- 1852 b. Enumeration succincte des espèces de la famille des Nymphéacées, l. c. p. 117-20; also in Rev. Horticole, 1853, p. 62-68.
- 1852 c. *N. stellata*, in Flore des Serres, 8: 285-286, tab. 854.
- 1852 d. *N. gigantea*, l. c. p. 293, tab. 751.
- 1852 e. *N. Ortgiesiana*, l. c. p. 67-73.
- 1853 a. In Revue Horticole, Feb. 16.
- 1853 b. Études sur les Nymphéacées, in Ann. Sci. Nat. Bot., sér. 3, 19: 17 ff. Paris, 1853.
- 1854. *N. Boucheana*, in Flore des Serres, 10: 167, pl. 1033-1034.
- 1856. *N. blanda*, in Flore des Serres, 11: 21. Ghent, 1856.
- See also TRIANA, J.
- Plank, E. N.** 1896. A Botanical Journey in Texas, I, in Gard. & For., 9: 62-63.
- Pleyte, W.** 1875. De Egyptische Lotus (Nederlandisch Kruidkundig Archief: Verslagen en Mededeelingen der Nederlandsche Botanische Vereeniging, July 16, 1875. Tweede Serie. 2e Deel. Nijmegen 1877). Ref. in Bot. Jhrsber. 1876, p. 691.
- Pliny, Caius, Secundus.** The Historie of the World, commonly called Natural Historie of C. Plin. Sec., trans. Philemon Holland. London 1601.
- Plukenet, Leonard.** 1691. Phytographia, sive stirpium illustriorum et minus cognitârum Icones. London; vol. I, 1691; II, 1692; III, 1696.
- 1696. Almagestum Botanicum. London.

- Plukenet, Leonard.** 1700. *Almagesti Botanici Mantissa*. London.
 — 1705. *Amaltheum Botanicum* (ed. 2, by Davies, Payne, etc., London 1769, is the one I have seen).
- Poggenburg.** See BRITTON, N. L.
- Presl, J. W. & K. B.** 1822. *Deliciae Pragenses*, p. 224.
- Prichard, J. C.** 1838. *Egyptian Mythology*.
- Pringle, C. G.** 1890. Notes on the Mexican Water Lilies, in *Gard. and Forest*, 3: 415.
 — 1897. Notes of Mexican Travel, XII; My Summer in the Valley of Mexico, in *Gard. & For.* 10: 42-43.
- Pritzel, G. A.** 1872. *Thesaurus Literaturae Botanicae*. Leipzig.
- Pursh, F.** 1814. *Flora Americae Septentrionalis*, 2: 368-369.
- Raciborski, M.** 1894. Die Morphologie der Cabombeen und Nymphaeaceen, in *Flora*, 78: 214-279; 79: 92-108. 1894. Ref. in *Bot. Jhrsber.* 1894. 2: 280-81.
- Rafinesque, C. S.** 1830. *Medical Flora and Botany of the United States*. Philadelphia, 2: 44-45.
- Rawlinson, Geo.** 1882. *History of Ancient Egypt*. Boston. (The botany of this book is grossly in error.)
- Ray, John.** 1670. *Catalogus Plantarum Angliae et Insularum, Adjacentium*. London.
 — 1682. *Methodus Plantarum nova*, etc. (Ed. 4, emendata et aucta; London 1733, I have seen.)
 — 1688. *Historia plantarum*, etc. London; vol. I, 1686; II, 1688; III, 1704.
 — 1690. *Synopsis methodica stirpium britannicarum*. London.
- Reichenbach, H. G. L.** 1830. *Flora Germanica*. Leipzig.
 — 1842. *Flora Saxonica*.
- Reichenbach, H. G. L. & G. H.** 1845. *Icones Florae Germanicae et Helveticae*, 7: 34, tab. 67, 68, 69, 70, 71. Leipzig.
- Rein, J. J.** 1886. Japan nach Reisen und Studien, in *Auftr. der kgl. preuss. Regierung*, vol. 2. Leipzig (not seen). Ref. in *Bot. Cent.* 31: 275-279, and in *Bot. Jhrsber.* 1886, 2: 132-5.
- Relhan, R.** 1785. *Flora Cantabrigiensis*, p. 206 (not seen).
- Renault, M. B.** 1882. *Cours de Botanique Fossile* (not seen).
- Revue Horticole.** 1849. p. 264-265, 379-380.
 — 1851 a. *Nymphaea dentata*, p. 349-355.
 — 1851 b. *N. elegans*, p. 456-458.
 — 1852 a. *N. alba*, p. 165.
 — 1852 b. *N. gigantea*, p. 390.
 — 1853. *N. Ortgiesiano-rubra*, p. 110.
 — 1854 a. *N. stellata* (var. *bulbifera*, Planch.), p. 150-151.
 — 1854 b. *N. gigantea*, p. 462.
 — 1855 a. Culture du *N. gigantea*, p. 91.
 — 1855 b. *N. stellata*, p. 261-263.
 — 1879. *N. caerulea*, p. 277-278.
 — 1881 a. *N. odorata rubra*, p. 323.
 — 1881 b. *N. odorata rubra*, p. 406.
 — 1890 a. *N. zansibariensis flore rubro*, p. 266.
 — 1890 b. *N. odorata sulfurea*, p. 540.
 — 1897. Variétés nouvelles de *Nymphaea stellata zansibariensis*, p. 328.
- Rimbach, A.** 1902. Physiological observations on the subterranean organs of some Californian Liliaceae, in *Bot. Gaz.* 33: 401-420. June.
- Robertson, C.** 1889. Flowers and Insects, I; in *Bot. Gazette* 14: 120-126.
 — 1890. New North American Bees of the genera *Halictus* and *Prosopis*, in *Trans. Amer. Entom. Soc.* 17: 315-318 (not seen). Ref. in *Bot. Jhrsber.* 1890. 1: 508.
- Robinson, B. L.** 1896. New or Little-known Plants: *Nymphaea tetragona*, Georgi; in *Gard. & For.* 9: 134.
 See also GRAY, ASA.
- Robinson, W.** 1865. *Nymphaea gigantea*, in *Gard. Chron.*, 1865, p. 842.
- Roehling, J. C.** 1833. *Deutschlands Flora*, ed. 3, by Mertens & Koch. 4: 28; Vol. I, 1823; II, 1826; III, 1831; IV, 1833; V, 1839 (not seen).

- Rose, J. W. 1895. New or Little-known Plants: A Blue Water-lily from Mexico, in Gard. & For. 8: 205, 206.
- Rolland, E. 1896-99. Flore populaire ou histoire naturelle des plantes dans leur rapports avec la linguistique et le folk-lore. Paris, vol. 1, 1896; vol. 2, 1899 (not seen). Ref. in Bot. Centralbl. 86: 281-285, 1901.
- Roxburgh, Wm. 1806. *N. rubra*, in Salisbury's Parad. Lond. 1: tab. 14.
- 1814. Hortus Bengalensis. Serampore (not seen).
- 1824. Flora Indica.
- Royer, Ch. 1870. Considérations sur les parties souterraines des Plantes, in Bull. Soc. Bot. France 17: 147-153, 168-172; p. 170.
- Rozet. — Flore de la Côte-d'Or: Nymphéacées (not seen).
- Ruprecht, F. J. 1859. Decas plantarum sive Tabulae botanicae X et itinerario D. Maack seorsim editae. St. Petersburg, Akademie der Wissenschaften; folio, 10 tab. 10 foll. (not seen). (Pritzl, 1872.)
- Rusby, H. H. See BRITTON, N. L.
- Russow, E. 1884. Ueber die Auskleidung der Intercellularen, in Sitzber. d. Dorpater Naturf. Ges., 7: 158-172, and in Bot. Ztg. 1885, p. 491. Ref. in Bot. Jahrsber. 1884, 1: 201, 210.
- Sachs, J. von. 1882. Text book of Botany, trans. by S. H. Vines, ed. 2. London.
- 1887. Vorlesungen über Pflanzenphysiologie, 2 ed. p. 545.
- Saelan, Th. 1879. In Meddelanden af Soc. pro Fauna et Flora Fennica, heft 6, 1881, p. 185-272. Sitzung Dec. 6, 1879 (not seen). Ref. in Bot. Jahrsber. 1883, 2: 555.
- Sagot, P. 1881. Catalogue des Plantes Phaen. et Crypt. vasc. de la Guyane Française, in Ann. Sci. Nat., 6 sér., 11: 134-180. Paris.
- Saint-Hilaire, A. F. C. P. (Aug. de). 1833. Voyage dans le district des diamans, 2: 425 (not seen).
- Salisbury, R. A. 1806 a. "Nymphaeaceae," in Koenig and Sims' Annals of Botany, 2: 69-76. Pub. May 1, 1805.
- 1806 b. Paradisus Londinensis 1: tab. 14. London 1806-7. 2 vols.
- Salvin, O. See GODMAN, F. D.
- Sambuc, C. — Contribution à l'étude de la Flore et la matière médicale de la Sénégambie, p. 27 (not seen).
- Saporta, G. de. 1861. Examen analytique des flores tertiaires, in Heer: Rech. sur le climat et la végétation du pays tertiaire, transl. into French by C. T. Gaudin. Zurich.
- 1865 a. Études sur la végétation du sud-est de la France à l'époque tertiaire, in Ann. Sci. Nat., sér. 5, Bot., 3: 5-152.
- 1865 b. Études sur la végétation du sud-est de la France à l'époque tertiaire, l. c., 4: 5-264.
- 1877. Découverte de plantes fossiles tertiaires dans le voisinage immédiat du pôle nord, in Compt. Rend., 85: 562.
- 1879. Die Pflanzenwelt vor dem Erscheinen des Menschen. Braunschweig 1881.
- 1893. Sur un couche à Nymphéinées récemment exploré et comprise dans l'aquitainien de Mânosque, in Compt. Rend. 117: 607-610. Paris.
- 1894 a. Nouvelles Contributions à la flore mésozoïque; Imp. de l'Acad. royale des Sc., Lisbon.
- 1894 b. Nouveaux détails concernant les Nymphéinées: Nymphéinées infracrétacées; in Comptes Rend. 119: 835-837.
- 1894 c. Nouveaux détails concernant les Nymphéinées: Nymphéinées tertiaires, l. c.,
- Sargent, C. S. 1888. Plant Notes; *Nymphaea tuberosa*, in Gard. and For., 1: 368-9 (with excellent line drawings).
- Savigny, J. C. 1798. Decad. Egypt., 3: 74 (not seen).
- 1802. Description du *Nymphaea caerulea*, in Annales du Muséum National d'Histoire Naturelle, 1: 366.
- Scaliger, J. C. See THEOPHRASTUS.
- Schaffner, John H. 1904. Some morphological peculiarities of the Nymphaeaceae and Helobiae, in Ohio Naturalist, 4: 83-92. Columbus, O.

- Schenck, H. 1884. Bildung von centrifugalen Wandverdickungen. Inaug. Dissert. Bonn, 42 pp. (not seen).
- 1885. Die Biologie der Wassergewächse. Bonn, 1885. 162 pp. Ref. in Bot. Jhrsber. 1885, 1: 734-6.
- Schenck, A. 1888. In Zittel: Handbuch der Palaeontologie, II Abth., 6 Lief., Dicotylae. Munich and Leipzig.
- Schilbersky, K. 1889. Der Standort von *N. thermalis* DC. bei Budapest, in Termeszettud. Közlöny, 21: 370-4. Budapest (not seen). Ref. in Bot. Jhrsber. 1889, 2: 296.
- Schilling, A. J. 1894. Anatomisch-biologische Untersuchungen der Schleimbildung der Wasserpflanzen, in Flora, 78: 280-360.
- Schinz, H. See DURAND, TH.
- Schmalhausen, J. 1875. Aufzählung der im Gouvernement von St. Petersburg vorkommenden Bastard- und Zwischenformen, in Bot. Ztg. 1875, p. 539.
- Schomburgk, R. 1848. Reisen in Britisch Guyana in den Jahren 1840-44. Vol. 3. Versuch einer Fauna und Flora von Britisch Guiana, p. 838-839.
- 1875. Handbook of Southern Australia (not seen).
- Schonger, J. B. 1882. "Kleine Beiträge," in 8. Jhrsber. d. Bot. Vereins zu Landshut, 1882, p. 171-97 (not seen). Ref. in Bot. Jhrsber. 1882, 2: 483-4.
- Schuchardt, T. 1853. Beiträge zur Kenntniss der deutschen Nymphaeae, in Botan. Zeitung, 11: 497-510. July 15.
- Schulz, Aug. 1890. Beiträge zur Kenntniss der Bestäubungseinrichtungen und Geschlechtsvertheilung bei den Pflanzen, II, in Bibliotheca Botanica, Heft 17, p. 9. Cassel, 1890.
- Schumacher, H. C. F., and Thonning, P. 1829. Beskrivelse af Guineiske Planter, in Dansk. Vid. Selsk. Afh. IV, 1829, p. 1-236.
- Schumann, K. Neue Untersuchungen ueber den Blütenanschluss, Leipzig. 519 pp. (not seen). Ref. in Bot. Jhrsber. 1890, 1: 345-9.
- 1894. Die Untersuchungen des Herrn Raciborski ueber die Nymphaeaceae, etc., in Ber. d. deutsch. Bot. Gesellsch. 12: 173-178. Ref. in Bot. Jhrsber. 1894, 2: 281.
- 1904. Praktikum für morphologische und systematische Botanik. Fischer, Jena. *Nymphaea alba*, *Nuphar luteum*, pp. 229-235.
- Schweinfurth, G. 1882. See BOISSIER, 1882.
- 1883 a. Neue Beiträge zur Flora des alten Aegyptens, in Berichte der deutschen botanischen Gesellschaft, 1: 544-546.
- 1883 b. The Flora of Ancient Egypt, in Nature, 28: 109-114, with figure.
- 1884 a. Further Discoveries in the Flora of Ancient Egypt, in Nature, 29: 312-315, Jan. 31.
- 1884 b. Neue Funde auf dem Gebiete der Flora des alten Aegyptens, in Engler's Bot. Jhrbch., 5: 189-202. No. 2.
- 1884 c. Ueber Pflanzenreste aus altaegyptischen Gräbern, in Ber. d. deutsch. bot. Gesellschaft, 2: 351-371.
- 1886. Die letzten botanischen Entdeckungen in den Gräbern Aegyptens, in Engler's Bot. Jhrbch. 8: 1-16, No. 1, nach Bulletin de l'Institut Egyptien, 10 Sér., No. 6, Cairo, 1886, mit Verbesserungen und Zusätzen des Verf. Ref. in Bot. Jhrsber. 1886, 2: 36-38.
- Schwendener, S. 1895. Die jüngsten Entwicklungsstadien seitlicher Organe und ihr Anschluss an bereits vorhandene, in S. d. k. Pr. Akad. d. Wiss. zu Berlin, p. 645-63 (not seen). Ref. in Bot. Jhrsber. 1895, 1: 30.
- Sebire, A. 1899. Les Plantes utiles du Sénégal. Paris.
- Seeman, B. 1852. The Botany of the Voyage of H. M. S. "Herald" during the years 1845-51. London, 1852-57. Part 2, p. 78 (not seen).
- Semenow, N. M. 1854. Einige Bemerkungen ueber die moskowischen Scerosen, in Bull. de la Soc. Imp. des Naturalistes de Moscou, 27: 226-232.
- Sernander, E. 1894. Om våra röda näckrosor, in Botaniska Notiser, 1894, p. 85-88 (not seen). Ref. in Bot. Jhrsber. 1895, 2: 196.
- Siber, W. 1883. Unsere Wasserpflanzen, in Wittmack's Gartenzeitung, 32: 211-215, 260-264.
- 1887. *Nymphaea sibirica* Casp. fl. rubra, l. c. 36: 83-84, pl. 1240; also p. 230.

- Sibthorpe, J. 1813. *Flora Graeca*. 2: tab. 167.
- Simkovič, L. 1883. Ueber eine ganze ungarische Pflanze, in *Term. tud. Közl.* 1883, heft 168, p. 340-345 (not seen). Ref. in *Bot. Jhrsber.* 1883, 2: 359-360.
- Simonkai, L. 1890. Die Pflanzenwelt von Grosswardein und seiner Umgebung. Nagyvárad Termeszetrájsza. Zur Erinnerung an die 25. Wanderversammlung ungar. Aertze und Naturf. Budapest, 1890, p. 47-134 [Hungarian] (not seen). Ref. in *Bot. Jhrsber.* 1890, 2: 398-399.
- Sims, John. 1805 a. *Nymphaea lotus*, in *Botan. Magazine*, tab. 797.
- 1805 b. *N. odorata*, l. c., tab. 819.
- 1809. *N. versicolor*, l. c., tab. 1189.
- 1810. *N. rubra*, l. c., tab. 1280.
- 1811 a. *N. nitida*, l. c., tab. 1359.
- 1811 b. *N. rubra* var. *rosca*, l. c., tab. 1364.
- 1813. *N. pygmaea*, l. c., tab. 1525.
- 1814. *N. odorata* var. *minor*, l. c., tab. 1652.
- 1819. *N. stellata* β , l. c., tab. 2058.
- Sloane, Hans. 1707. A voyage to the Islands Madeira, Barbados, Nieves, S. Christophers and Jamaica, etc. London. Vol. I, 1707; II, 1725.
- Smith, J. D. 1891. *Enumeratio plantarum Guatemalensium*, II. Oquawka 1891; 66 pp. (not seen). Ref. in *Bot. Jhrsber.* 1891, 2: 63.
- 1893. *Enumeratio plantarum Guatemalensium*, III. Oquawka. 111 pp. Ref. in *Bot. Jhrsber.* 1893, 2: 152-5.
- Smith, J. E. 1800. *Compendium Florae Britannicae*. London (not seen).
- 1804. *Flora Britannica*. London, 1800-04 (not seen).
- 1809. *Florae graecae Prodromus*. 1806-1813.
- 1819. *Nymphaea* in Rees' *Cyclopaedia*, 25:
- 1825. *English Flora*, 3: 13 (not seen).
- Solereder, H. 1898. *Systematische Anatomie der Dicotyledonen*. Stuttgart. 1 Lieferung, p. 54-59.
- Sommerauer, J. 1833. *N. biradiata*, described in *Flora*, p. 625.
- Sonder, O. W. See HARVEY, W. H.
- Spach, Ed. 1846. *Histoire naturelle des végétaux. Phanerogames*. Paris, 1834-48, 14 vols. Atlas to the same, 1846 (not seen).
- Sprengel, Kurt. 1817. *Geschichte der Botanik*. 1817-18, 2 vols (not seen).
- 1825. *Caroli Linnæi Systema vegetabilium*. Ed. 16, 4 vols. I, 1825; II, 1825; III, 1826; IV, 1827 (not seen).
- Stahl, E. 1888. *Pflanzen und Schnecken*. Jena.
- Staub, M. 1891. Die Gegenwart und Vergangenheit der Seerosen, in *Engler's Jhrbuch*, 14: Beibl. 31, p. 1-13, 1891.
- Sternberg, G. 1826. *Essai d'un exposé geognostico-botanique de la Flore du monde primitif*, trans. into French. Leipzig and Prag.
- Sterns, E. E. 1888. Re-discovery of *Nymphaea elegans*, Hook., at a new Station, in *Bull. Torr. Bot. Cl.* 15: 13-15.
- Steudel, E. T. 1841. *Nomenclator Botanicus*, ed. 2, part 2, L. to Z.
- Sturm, J. W. 1852. *Nymphaea semiaperta* Klinggr., eine für Bayern neue Pflanze bei Nürnberg aufgefunden, in *Abhandl. der naturhist. Gesellsch. z. Nürnberg*, 1: 143-149 (not seen). Ref. in *Bot. Ztg.* 10: 588.
- Sturtevant, E. L. 1889. In *Gard. & For.* 2: 106.
- Sweet, R. 1827. *Hortus britannicus*. London.
- Sydow, P. 1877. *Nymphaea semiaperta* Klinggr. bei Grossbeeren, in *Verh. Bot. Ver. Brandenburg*, 19: 93 (not seen). Ref. in *Bot. Jhrsber.* 1878, 2: 580.
- T. D. H. 1892. Water-lilies at Yarmouthport [Mass.] in *Gard. & For.* 5: 441-442.
- Tallack, J. C. 1902. *Nymphaea Robinsoni*, in *Gard. Chron.*, p. 56, July 26.
- Tanalev, A. G., and Thomas, E. N. 1904. Root Structure in the central cylinder of the hypocotyl, in *New Phytologist*, 3: 104. Ref. in *Bot. Cent.* 96: 21.

- Tassi, F.** 1884. *Degli effetti anestesici nei fiori*, Nota, Siena, 4 pp. (not seen). Ref. in Bot. Jhrsber., 1885, 1: 27.
- Tavera, T. H. P.** 1901. *The medicinal plants of the Philippines*, transl. by Jerome B. Thomas, Jr. Philadelphia.
- Theophrastus Eresius.** *De Historia Plantarum* * * * item rariorum plantarum iconibus illustravit Joannes Bodaëus à Stapel * * * Accesserunt Julii Caesaris Scaligeri in eosdem libros animadversiones, et Roberti Constantini annotationes, etc. Amsterdam, 1644.
- Thomas, E. N.** See TANSLEY, A. G.
- Thomson, Th.** See HOOKER, J. D.
- Thunberg, C. P.** 1800. *Prodromus Plantarum Capensium*, quas in promontorio Bonae Spei Africes, Annis 1772-75 collegit C. P. T. Pars Posterior, Upsaliae.
- 1807. *Flora Capensis*. Upsal, 1807-13 (not seen).
- Tittmann, J. A.** 1821. *Die Keimung der Pflanzen, durch Beschreibung u. Abbildung einzelner Samen- und Keimpflanzen erläutert*. Dresden (not seen). Ref. in Flora, 2: 449-460 (453-458 quotes verbatim the parts relating to *N. alba*).
- Torrey, J.** 1831. *Catalogue of North-American genera of plants*, 1: 101, tab. 42-3 (*fid.* Walp. Ann. Bot. Syst. 2: 25).
- 1843. *Flora of New York* (not seen).
- Torrey, J., and Gray, A.** 1838. *Flora of North America*. New York, 1838-43 (not seen).
- Tournefort, Joseph Pitton.** 1700. *Institutiones rei herbariacae*. Paris.
- Tratinnick, C. L.** 1822. *Ueber den Cyamus und Lotus der Aegyptier und der Griechen* (Flora, No. 37, 8 Oct. 1822, p. 557-591, 593-608).
- Treat, Mary.** 1877. *Home Observations in Florida*, in Harpers' Monthly Magazine, 55: 365-367.
- Trécul, A.** 1845. *Recherches sur la structure des Nymphaeacées*, in Journ. de Pharm., 7: 465-467 (not seen).
- 1852. *Études anatomiques et organogéniques sur la Victoria regia et anat. comp. du Nelumbium, du Nuphar et de la Victoria*. Mémoire pres. à l'acad. des Sc. Nov. 2. Printed in Ann. Sci. Nat.—Bot. 1: 144-172. 1854.
- 1854. See above, 1852.
- Trelease, W.** See BRANNER, J. C.
- Treub, M.** 1876. *Le méristème primit. de la racine dans les Monocotyledones*. Leyden (not seen).
- Treviranus, L. C.** 1838. *Physiologie d. Gewächse*, 2: 614 "Keimung" (not seen).
- 1847. *Observationes circa germinationem in Nymphaea et Euryale*, in Abh. math. phys. Klasse kgl. bayer. Akad. Wiss. 5: 395-404. München (not seen).
- Triana, J., and Planchon, J. E.** 1862. *Prodromus florae Nova-Granatensis*, in Ann. Sci. Nat. Bot. sér. 4, 17: 5-190.
- Tricker, Wm.** 1897. *The Water Garden*. New York.
- Trimen, H.** 1872. *Notes on some Scandinavian Plants*, in Journal of Botany, 18: 329.
- Tschirch, A.** 1889. *Angewandte Pflanzenanatomie*, 1: 302 (not seen).
- Turczaninow, N.** 1842. *Flora Baicalensi-Dahurica*, in Bull. de la Soc. Imp. des Naturalistes de Moscou, 15: 93.
- Turner, Wm.** 1548. *The Names of Herbes*. (Edited by James Britten for English Dialect Society, London, 1881; this I have seen.)
- Uechtritz, R. von.** 1885. *Resultate der Durchforschung der schlesischen Phanerogamen-Flora im Jahre 1884*, in Jhrsber. d. Schlesischen Gesellsch. für vaterländische Cultur. Breslau, 1885, p. 1-33 (not seen). Ref. in Bot. Jhrsber. 1885, 2: 329.
- Unger, F.** 1855. *Anatomie und Physiologie der Pflanzen*, p. 235. Pest, Wien und Leipzig (not seen).
- 1856. *Ueber fossile Pflanzen d. Süsswasser-Kalkes und Quarzes*. In Sitzber. d. mathem.-naturwiss. Classe der Wiener Acad., 22: 697-700.
- See also ENDLICHER, S. L.
- Vaillant, Sebastian.** 1717. *Discours sur la structure des Fleurs, etc.* Delivered at Paris, June 10, 1717. Leyden, 1718.

- Van Rheeде, Heinric Adrian.** 1692. Hortus indicus malabaricus, etc. Amsterdam, vol. I, 1678; II, 1679, etc.; XI, 1692; etc.
- Van Tieghem, Ph.** 1871. Mémoire sur la racine, in Ann. Sci. Nat. sér. 5, Bot., 13: 267.
- 1886 a. Sur l'appareil secreteur et les affinités de structure des Nymphaeacées, in Bull. de la Soc. Bot. de France, 33: 72-76 (not seen).
- 1886 b. Sur la croissance terminale de la racine dans les Nymphaeacées, l. c., p. 264-265 (not seen).
- 1898. Traité de Botanique, 1: 65-67, 694 ff.
- Van Tieghem, Ph., and Doullot, H.** 1888. Recherches comparatives sur l'origine des membres endogènes dans les plantes vasculaires, in Ann. Sci. Nat. Bot., sér. 7, 8: 127-132, 435-438.
- Ventenat, E. P.** 1803. Jardin de la Malmaison, 1: tab. 6. Paris.
- Vealingsius, Joannes.** See ALPINUS.
- Vesque, Julien.** 1881. De l'anatomie des Tissus appliquée à la classification des Plantes, in Nouvelles Archives du Muséum, 2d sér., 4: 51-53.
- Vick, J.** 1879. *N. odorata* in Vick's Magazine, 2: 196. Rochester, N. Y.
- 1886. *N. odorata* in Vick's Magazine, 19: 9. Rochester, N. Y.
- Vilmorin, M. L. de.** 1897. Les Nymphaea rustiques, in Rev. Hort., p. 17-22.
- Vuyck, L.** 1901. Prodromus Florae Batavae, vol. 1, Nymegen (not seen).
- Wächter, W.** 1897. Beiträge zur Kenntniss einiger Wasserpflanzen, in Flora, 83: 367-397; 84: 343-348.
- Waldstein, F. A., Graf von, and Kitabel, P.** 1802. Descriptiones et icones plantarum rariorum Hungariae. Vienna, 1802-12, 3 vols.
- Walpers, W. G.** 1842. Repertorium Botanices Systematicae, 1: 106-108.
- 1848. Annales Botanices Systematicae, 1: 22. 1848-49.
- 1851. Annales Botanices Systematicae, 2: 25. 1851-52.
- 1852. Annales Botanices Systematicae, 3: 814. 1852-53.
- 1857. Annales Botanices Systematicae, 4: 153-167.
- Walter, Thos.** 1788. Flora Caroliniana, 154-155. London.
- Waters, G. F.** 1886. Germination of Pond-lily seeds, in Science, 7: 395-396.
- Watson, S.** 1883. In Proc. Am. Acad., 17: 318 (not seen).
- 1887. List of Plants collected by Dr. Edw. Palmer in the State of Jalisco, Mexico in 1886, in Proc. Am. Acad. of Arts and Sciences, 22: 397.
- See also GRAY, ASA.
- Watson, W.** 1893. Notes on Water-lilies, in Gard. & For., 6: 364-366.
- 1894. *Nymphaea Parkeriana*, in Gard. & For., 7: 164.
- Weber, C. A.** 1892. Ueber *Cratolepura holsatica*, eine interglaciale Nymphaeacee, und ihre Beziehung zu *Hololepura Victoria* Casp., sowie zu recenten Nymphaeaceen, in Neues Jhrbch. f. Min., Geol., u. Paläont. 1: 114 ff. (not seen).
- 1893. Ueber die diluviale Vegetation von Klinge in Brandenburg, und über ihre Herkunft, in Engler's Jhrbch., Beiblatt, No. 46, vol. 17.
- Weber, C. O.** 1850. Ueber die Süßwasserquartze von Muffendorf bei Bonn, in Haidinger Naturwissenschaftliche Abhandlungen, 4: part 2, p. 14, pl. IV, fig. 18 (not seen).
- Weberbauer, A.** 1894. Beiträge zur Samen-anatomie der Nymphaeaceae, in Engler's Jahrbücher, 18: Heft. 3, 52 pp.
- Weinhart, Max.** 1890. Beiträge zur Flora von Schwaben und Neuburg, etc., in 30. Ber. des Naturwiss. Ver. für Schwaben und Neuburg. Augsburg, 1890, p. 277-282 (not seen). Ref. in Bot. Jhrsber. 1890, 2: 349.
- Weiss, G. A.** 1878. Allgemeine Botanik, I, Anatomie der Pflanzen. Vienna.
- Wessel, P., und Weber, C. O.** 1855. Neuer Beitrag zur Tertiär-Flora der niederrheinischen Braunkohlenformation, in Dunker u. Meyer, Palaeontographica, 4: 4.
- Wheeler, W. A.** 1900. A Contribution to the knowledge of the flora of southeastern Minnesota, in Minn. Botan. Studies, 2 ser., part 4, 353-416.
- Whewell, Wm.** History of the inductive Sciences (not seen).
- Wiedemann, Alfred.** 1897. Religion of the Ancient Egyptians. London.

- Wigand, A., and Dennert, E.** 1888. *Nelumbium speciosum* W. Eine monographische Studie, in Bibliotheca Botanica, Hft. 11.
- Wight, R.** 1840. *Icones Plantarum Indiae Orientalis*. Madras, 1840-1856.
- 1850. *Illustrations of Indian Botany*. Madras, 1841-50.
- Wight, R., and Arnott, G. A. W.** 1834. *Prodromus Florae Peninsulae Indiae Orientalis*. London, pp. 16-17.
- Wildeman, Em. de, and Durand, Th.** 1900. *Illustrations de la Flore du Congo*, in *Annales du Musée du Congo*, Sér. 2.-Botanique, vol. I, fasc. 2, p. 2.
- *Reliquiae Dewevreanae*, l. c., sér. 3, vol. I, fasc. 1, p. 7.
- Wilkinson, J. Gardner.** The manners and customs of the ancient Egyptians. Ed. Samuel Birch. Boston, 1883.
- Willdenow, C. L.** 1797. *Caroli a Linné Species Plantarum*, etc., editio quarta. Berlin, vol. I.
- 1816. *Hortus Berolinensis*, tab. 39 (not seen).
- Williams, Monier.** 1856. *Sakoontala; or The lost Ring*, from the Sanskrit of Kālidāsa; 3d edition. Hertford.
- Wisselingh, C. van.** 1887. Sur les revêtements des espaces intercellulaires, in *Archives Néerlandaises*, 21: 19-34 (not seen). Ref. in *Bot. Centralbl.* 29: 360 (1887); in *Bot. Ztg.* 1887, No. 14, p. 222; in *Bot. Jhrsher.* 1887, 2: 512.
- Withering, Wm.** 1776. A botanical arrangement of all the vegetables naturally growing in Great Britain, p. 489 (not seen).
- Wolley-Dod, A. H.** See BOLUS, H.
- Wood, Alph.** 1880. *Class Book of Botany*, with a Flora of the United States and Canada.
- Woodville, W., and Wood.** 1806. *Castalia*, in *Rees' Cyclopaedia*, 6:
- Zimmerman, A.** 1891. Beiträge zur Morphologie u. Physiologie der Pflanzenzelle, Hft. 2, p. 158. Tübingen.
- Zittel, K. A.** 1890. *Handbuch der Palaeontologie*. See SCHENK, 1888.
- Zuccarini, J. G.** 1832 a. *Plantarum novarum vel minus cognitarum descriptio*, fasc. 1., in *Abhandlungen der Mathematisch Physikalischen Classe der Königl. Bayerischen Akademie der Wissenschaften*. 1: 287-396. München.
- 1832 b. In *Flora*, II Beibl., p. 75.

INDEX.

NOTE.—Synonyms and horticultural names are in *italics*. Asterisk (*) after a number indicates a figure. Numbers in heavy-faced type refer to the taxonomic description of a species or group; such descriptions always treat in order (1) diagnosis, (2) synonymy, (3) detailed description of flower, leaf and stem, (4) geographic distribution, (5) notes of miscellaneous information.

	PAGE		PAGE
Aerial leaves	54	Apocarpiae, propagation	230
Aestivation	98	root	28
Agrostis	8	stamens	83, 85
Ahl	8	stem	30
Air-canals, function of	60, 118	Apogotropism of peduncles	114
gases in	117-118	petioles	114
in leaf	70	Arcangel ¹ on Idloblasts	60, 61, 70
peduncles	59*, 78-79	leaves	54
petals	82	stomata of water-leaves	77
petioles	58, 59*, 60, 62, 76	Archesporium	101-102*
development of	96	Aril	90-91*
of seedling	112	development of	104
roots	31-33, 37*	Arum	16
sepals	81-82	Astomatic area	68
Alpinus	16, 17, 20, 21, 23	Athenæus	13-14, 17
Ambel	23	Axile process	80, 88
Ameling on cell dimensions	69	Bacon on dead insects in flowers	122
Amenhotep	6, 8, 9	Ballon on floral diagram of Nuphar	100
Ames, O.	222	Barthélemy	72
Analytic Key	126-127	on air-canals of petioles	58, 60
Anecphyia	187	movement of gases	117-118
flower	80	respiration	117-118
symmetry of	101	Bauhin, C.	15, 19, 22, 25
phylogeny	218	Bauhin, J.	22
pollen	85	Beardslee	192
seed	90	Bellonus, P.	16
stamens	85	Bes	9
Anoectomeria	215, 216, 217	Besler	10
fruit	87	Blue lotus	5, 7, 8, 146
phylogeny	218	Bock, Hieronymus	14, 18
brongniartii	215, 216	Bodaeus & Stapel	20
media	216	Bolssier on <i>N. thermalis</i>	214
nana	216	Bonavia	7
Anther, development of	101-102	Bontius	21
Anthotaxy	42, 43	Boolak Museum	9
Aphides	240	Botanical Magazine	5
Apical growth of roots	36-37	Brachyceras	131
Appendiculate	127, 131	distribution	213
Apocarpiae (see <i>Nymphaeae apocarpiae</i>)	187	flower	80
carpels	85-89	submergence of, after anthesis	123
flower	78	germination	106
odor of	121	hand-pollination	240
leaf	65, 66, 77	hybrids	221, 222, 225-228
girdler-like veins	115	leaf	64
ovary	86*	ovary	86*
peduncle	62, 78, 79	peduncle	70
petiole	61	petals sepaloid	100
collar of	62	phylogeny	217, 218
phylogeny	217, 218		

	PAGE		PAGE
Brachyceras, pistil	86, 89, 90	Castalia, stipules	54
pollen	85	development of	96
pollination	122	water leaves	74, 76, 77
seedling	109	<i>Castalia</i>	125, 127, 200
stamens	83, 84, 85	<i>alba</i>	176
symmetry of flower	101	<i>ampla</i>	184
Bract	99, 100, 101	<i>caerulea</i>	141
Bracteole	100, 101	<i>edulis</i>	108, 199
Brand on stomata of water leaves	77	<i>elegans</i>	131
Brasenia	24	<i>flava</i>	163
mucilage on	112	<i>gibertii</i>	211
Brasenia peltata	215	<i>gigantea</i>	128
Braseniopsis venulosa	215	<i>leiberghii</i>	168
Braun on inflorescence	100	<i>lotus</i>	194
Breynius, J.	23, 24	<i>flora rubra</i>	199
Britten	14	<i>magnifica</i>	199
and Holland	16	<i>mystica</i>	194
Buckhout	182	<i>odorata</i>	180
Buckley	7	<i>forma rosca</i>	186
		<i>latifolia</i>	250
		<i>minor</i>	168
		<i>rosca</i>	186
Cabombeae, geologic history	215	<i>pudica</i>	180
phylogeny	218	<i>pygmaea</i>	168
pistil	87	<i>reniformis</i>	186, 189
Calcium oxalate in idtoblasts	61	<i>sacra</i>	198
Carpels	80, 84-90	<i>scutifolia</i>	141, 153
Carpellary style	86*, 88, 90	<i>speciosa</i>	176
<i>Carpolliten granulatus</i>	217	<i>stellaria</i>	128, 140, 141
Caspari	21, 24, 25, 64, 66, 70	<i>tetragona</i>	168
development of leaf	97	<i>tuberosa</i>	186, 189
embryos of Nuphar	104	Caudex	39, 50*
hybrids	224	Chabreaeus	22
inflorescence	100	<i>Chamaelotus</i>	102, 200
leaf-traces	53	Chamaenymphaea	167
ovary	86, 87	leaf	54
<i>pachycystis</i>	90	peduncle	76
phyllotaxy	42	phylogeny	218
pollen	85	pistil	86
pollination	122	receptacle	79
root-cap	20	seed	90
seedlings	107	stem	89
stem structure	46	Chamaenymphaea × Eucastalia	229
tubers	47	× <i>Xanthantha</i>	229
vitality of seeds	106	Champollion	7
Castalia	163, 215	Chemical constituents	235
adjustment of peduncles to water level	118	Chilnot on <i>N. micrantha</i>	147
buoyancy of leaves and buds	114	seed	93
culture	236	stamens	84
distribution	213	<i>Chlorocarpa</i>	174, 175, 178
flower	77, 80	Chou Tun-I	3
odor of	121	Cleistogamy	27
symmetry of	101	of Euryale	121
fruit	89	<i>N. amazonum</i>	27, 121
protection of	124	<i>N. rudgeana</i>	27, 121
geologic history	217, 218	Clusius	18
germination	106	Collar (of petiole)	62, 71
hybrids	221, 229-231	Collenchyma in leaves	69-70, 76
leaf	65, 66	peduncles	78
ovary	84	petioles	57*, 58, 73
peduncle	78, 79	Colocasia	13, 16, 17, 18
petiole	56	Colors attractive to insects	121
phylogeny	218	Commelia	23
pollination	121, 122	Conard on embryo	105
seed	90	Constantin on water-leaves	112
vitality of	106, 230		
stamens	83, 84		

	PAGE		PAGE
Contractile roots	113	Euryale, cleistogamy of	121
structure of	83*, 85	leaf	87, 77
Cook on development of megaspore	102	phylogeny	218
embryo	104	root-hairs absent	111
Cork formation in stem	47*-48	stem structure	46
Cortex of roots	31-34		
stems	44-45	Faba Aegyptia	15*, 16, 18, 20
Cotyledons in germination	107-109, 108*	Fagus leaf	72
seed	94*	False hybrids	222
Cultivation, care of plants	233-239	Fischer on pollen	85
extent of	235	Flécourt	22
history of	235-236	Floral clock	119
planting	237	diagram	80*, 100, 101
soil	237-238	Flower	27, 77-80
tank for	238-238	adjustment to water level	118
<i>Cyananthos</i>	127	anesthesia of	121
<i>Cyanea</i>	86, 87, 127, 131	development of	97-99*, 101
		duration of	119-120
Dahmen on funiculus	104	in relation to pollination	121-123
Date-palm	9	odor of	121
DeBary on root cap	20	opening and closing of	119-121
DeCandolle on <i>Cyanea</i>	86	submergence after anthesis	123-124
<i>N. thermalis</i>	214	symmetry of	100, 101
Delpino on pollination	122	Focke on hybrids	232-233
Dhammapada	4-5	Food uses	3, 7, 10-12*, 17, 22, 170, 196, 235
Diaphragms in air-canals of roots	37, 38*	Forgetful lotus	11
Diodorus Siculus	7-8, 11	Frank on position of lamina	114-115
Dioscorides	11-13, 15, 16	Friend	16
Diseases	240-241	Fruit	87, 89-90
Dissection of stem apex	95	protection of	123-124
Distribution	213-214, 217-218	ripening of	27
Dodonaeus	18-19	Fuchsia	14
Double flowers	101	Funeral wreaths	8, 9
Duppa	6	Funiculus, development of	103
		structure and contents	104
Egyptian lotus	1*, 6, 7*, 9, 11, 12, 13, 14, 16, 17, 18, 20		
Eichler	80, 89-100	Galenus	14
Elwell	5	Gaudichaud	80
Embryo	94*, 104-107, 105*	Geologic history	214-217
Embryo sac	102*, 103	Geotropism of roots	113
Endosperm	94*, 105-100	stems	114
absorption of	109	Gerard	20
Endodermis	34-35	Germination	106-110, 108*
Enemies	240-241	Gilles	8
Engler on <i>N. thermalis</i>	214	Gilg, B., description of <i>N. zenkeri</i>	107-108
symmetry of flower	101	Goebel on development of flower	97, 98
Epicotyl	107, 109, 111	function of air-canals	60
Epidermis of root	30, 81	hairs	73
<i>Erythrocarpa</i>	174, 175, 178	respiration	118
<i>Erythrostigma</i>	175	seedlings	107, 109
Eucastalia	171-173, 215, 216	symmetry of flower	101
floral movements	120	Gollan, Wm.	106
fruit	90	Grew, N.	25
germination	106	Grey, R. M.	222
hybrids	223, 280-281	Grosswarden	214
leaf	64, 78, 77	Gwynne-Vaughan on stoles	30, 49, 52
petioles	58	structure of seedling	111-112
phyllotaxy	42		
phylogeny	218	Habits	27, 218
pistil	86, 88	Hairs on leaf	72*-73
pollen	85	ovary	87
roots	28	peduncle	78
seed	90	petiole	56-57, 73*
seedling	110	seed	90, 92-93
stipules	54	stem	73*
Eucastalia × <i>Xanthantha</i>	229, 230		

	PAGE		PAGE
Hairs on stem apex	43-44	Irmisch	73
of seedling	172	Ischirch	60
stipules	56		
Hanstein	60	Jahn on causes of shape of leaf	115
Hapl	8	Jones, Sir Wm.	5
Hardiness	236	Joret	0
Harshberger	101, 182		
Heat evolved in flowers	123	Kalidasa	4
Heliotropism	113	Karsten on adjustment to water level	115
Henslow on root-cap	29	Kerner on opening and closing of <i>N. alba</i>	120
Hercules	43	pollen	85
Heredity	222, 238	<i>N. thermalis</i>	214
Herodotus	10, 16	Key to species	126-127
Hofmeister	72	Kitalbel, P.	214
on embryo sac of <i>Nuphar</i>	103, 104	Klebs on seedlings	107
Holland, Philemon	13, 18	Kny on cuticle of air-canals	60
Hooker on vivipary of <i>N. micrantha</i>	74	Koehne on fusion of floral leaves with ovary	98
Hooker and Thomson	219, 141, 193	Kohl	60, 61, 70
Hybridising	230-240	Kotschy collection from Nubia	146
Hybrids, history of	219-221	Kuntze	25
limitations in production of	221, 222		
natural	222	Labeling	239
sterility of	222, 223	Langman	5
Hydrocallis	300	Leaf	27, 64-67, 63*, 74, 77
distribution	213	adjustment to water level	114-115
flower	78, 80	air-canals in	70
odor of	121	buoyancy of	114
submergence after anthesis	123	development of	95-97
symmetry of	101	hairs on	72-73
hybrids	222	kinds of	54
leaf	64, 66, 77	of germinating tuber	75*, 190*, 195*
peduncle	78	seedling	107-110*, 108*
petiole, air-canals of	58	structure of	112
phylogeny	218	structure of	67*, 68*, 72, 76, 77, 115, 116
plastid	86, 88	vascular system of	70, 71*
pollen	85	venation	66, 67, 115
pollination	122	Leaf-cutter	240-241
receptacle	79	Leaf-gap	51, 53-54
roots	28	Leaf-scar	47, 48*
seeds	90	Leaf-spot	241
stamens	84	Leaf-trace	51-54
stem	39, 41	Leaves as food for animals	39
Hydrocampa proprialis, leaf-cutter	240-241	Lechartier on function of air-canals	60
Hydrocharis	24	experiments on respiration	117, 118
morus-ranae	115	Lehmann on vivipary	74
Hypocotyl	107, 111	Leptopleura. See <i>Lytopleura</i> .	
		<i>Leucoanthos</i>	200
Idioblasts, crystals in	61	<i>Leuconymphaea</i>	25, 125
in carpels	84, 85, 87, 88	<i>gibbata</i>	211
leaf	60, 70	<i>reniformis</i>	189
peduncle	70	<i>Lilium longiflorum</i>	10
petals	83	<i>Limnanthemum</i>	23, 24
petiole	60-62	<i>Lobellus</i>	15*, 16, 18, 20, 22
roots	32, 33	<i>Lotophagi</i>	11
development of	37	<i>Lotos</i>	199, 198*, 216
sepals	81, 82	carpels	84, 86, 87, 103*
stamens	84, 85	distribution	213, 217
stem	46	flower	77, 80, 198*
stipules	56	movements of	120, 121
water-leaves	77	odor of	121
<i>Inappendiculatae</i>	127, 163, 192	submergence after anthesis	123
Inflorescence	99, 100	symmetry of	101
Insects attracted to flowers	121	fruit	89, 90
affecting pollination	122-123	geologic history	214, 217
found dead in flowers	122-123	germination	106, 195*
<i>Iris pseudacorus</i>	16	hybrids	221-223, 231-232

	PAGE		PAGE
<i>Lotos</i> leaf	64-66, 76, 77, 195*	Natural hybrids	222
girder-like veins	119	Nefer Tām	6*, 8, 10
hairs on	73	Nellirelch on <i>N. thermalle</i>	214
notes	103*	Nelumbium, geologic history	215
peduncle	78, 79	<i>Nelumbium nymphaeoides</i>	216
idioblasts in	62	Nelumbo	188, 216
petiole, air-canals of	58, 62	early notices of	4, 9, 11, 12, 13, 14, 15, 10, 18, 20, 21, 23, 24, 25
idioblasts in	62	leaves	77
thyll-like bodies in	62	primary root	28
vascular system of	62	<i>Nelumbo lutea</i>	211
phylogeny	217, 218*	nucifera	4, 6, 10, 11, 211
pollen	85	Nelumboneae, geologic history	215
pollination	121, 122	phylogeny	218
roots	28	pistil	87
seed	92	Nemphar	18
seedlings	108*, 100	Nenufar	14, 16, 19, 21, 25
species, discussion of	193	Nicolai on root-cap	29
stamens	83, 84, 193*	Nodal structure, <i>N. fava</i>	51*, 53-54
stem	39, 41	Nuphar	49, 211, 215, 217
stolons	41, 52*-53	bract subtending flower	99
<i>Lotos</i>	131, 163, 200	early notices of	12, 14, 15, 17, 18, 20, 22, 24
<i>Lotus</i>	6-13, 16, 18, 146	embryo	104
<i>Lotus aegyptia</i>	17, 18, 19, 21	embryo sac	103, 104
<i>niliacum</i>	17	floral diagram	100
<i>Lotus</i> , blue	5, 7, 8, 146	fruit	87
Egyptian	1*, 6, 7*, 9, 11-14, 16-18, 20	petiole structure	70, 77
genus of Leguminosae	12	phylogeny	218
sacred	4, 6	root-cap	29
<i>Lotus-eaters</i>	11	root-hairs	111
Lubbock on stipules	54-56	Nuphar advena, embryo	104
Ludwig	25	embryo-sac	104
Lyte	16	<i>Nuphar aegyptium</i>	17
<i>Lytleptura</i>	87, 127	<i>Nuphar lutea</i> , crystals in idioblasts	37
Macdowell	5	early notices of	14, 19, 25
Mackintosh on air-canals of petioles	58	embryo sac	104
MacMillan	25	Nutrition	116
Mahabharata	4	Nymphaea	9, 10, 11, 12, 13, 14, 15, 17, 18, 20, 21, 22, 23, 24, 25, 188
Malpighi	25	floral diagram	80*
Marillac	221	medicinal value	11, 12, 19, 21, 22, 235
Marsilia	24	<i>Nymphaea abbreviata</i>	145
Masters on air-canals of petioles	58	<i>acutifolia</i>	170
Matthioli	15*-16, 18, 20	<i>advena</i>	211
Medicinal uses	235	<i>acutifolia</i>	175, 178
Megaspore, development of	102	<i>Nymphaea alba</i>	172, 174, 175-179, 180, 189, 215, 216, 217
<i>Melanopsis costata</i>	214	carpels	84
<i>parreyasi</i>	214	development of flower	97, 98, 101
Mellinck	60, 62	leaf	95, 96
Mendel's theory	223, 233	dissection of stem apex	96
<i>Menyanthes indica</i>	211	distribution	171, 177, 213
Meyer, test for cork	48	early notices of	11, 12, 14, 15*, 10, 17, 18, 19, 20, 21, 22, 23, 24, 25
Microspores	85*	floral movements, time of	120
Mieg, etc.	216	under anaesthetics	121
Millsbaugh	186	flower	80
<i>Mimusops schimperi</i>	9	malformed	100
Mollisch on crystals	61	submergence of, after anthesis	124
Movements of floral parts	119-121	symmetry of	100, 101
Mucilage hairs on seedlings	112	hairs	72*
Müller, C., on collenchyma	58	hybrids	222, 223, 232
Müller, H., on pollination	122	introduction to cultivation	236
Müller, R., on soil	287	leaf	54, 66, 69, 72, 73, 75, 77
Mummy	8, 9	Nägeli on leaf-traces	53
Muskrats	287, 241	notes on	177-179, 188
Nägeli on leaf-traces	53	odor of flower	121
Nash 1895	187, 188		

	PAGE		PAGE
<i>Nymphaea alba</i> , petiole	56, 60	<i>Nymphaea amazonum</i> , phylogeny	218
phyllotaxy	42	pistil	88
phylogeny	218	seedling	110*
pollen	85	root hairs on	110*, 111
pollination	121, 122	stomata on leaves of ..	112
relation to <i>N. candida</i>	171, 174, 178	seeds	90, 92
respiration	117	stamens	83
roots	28	tuber	40*
seed	90, 91, 92, 93*	<i>Nymphaea amazonum goudotiana</i>	204
stamens	83, 84	<i>Nymphaea amazonum</i>	205
stem	38	submersa	34, 204
synonymy	211	<i>Nymphaea amellana</i>	216
thyll-like bodies in petiole	62	<i>Nymphaea americana</i>	25
variants	230	<i>Nymphaea ampla</i> (Plate V)	134-136, 205, 222
<i>Nymphaea alba</i>	172	culture	236
<i>canadensis</i>	180	early notices of	21, 24, 25
<i>candidissima</i>	223, 230	flower	78, 80
culture	237	leaf	64, 66
floral movements	119	notes	135, 136, 139
leaf	67, 68, 72	phylogeny	218
scarf	147*, 148*	seed	92
peduncle	78	<i>Nymphaea ampla</i>	136, 145, 146
pistil	88	<i>plumieri</i>	135, 136
root structure	36	<i>Nymphaea ampla pulchella</i>	136-137
stem	38	<i>speciosa</i>	136
structure	145, 146	<i>Nymphaea ampla</i> β <i>hookeri</i>	136
cork formation	47	<i>rudgeana</i>	205
<i>X odorata rosea</i>	231	<i>salzmanni</i>	136
<i>depressa</i>	178	<i>andreaeana</i>	230
<i>flora pleno odorata</i>	180	<i>aro-en-ciel</i>	229
<i>intermedia</i>	176	<i>Nymphaea arectica</i>	217
<i>Kashmiriana</i>	172	<i>Nymphaea arethusa</i>	230
<i>maxima</i>	230	<i>arethusae</i>	216, 217
<i>melocarpa</i>	175, 178	<i>arifolia</i>	211
<i>minor</i>	108, 172	<i>arnoldiana</i>	232
<i>oblongistigma</i>	172, 174	peduncle	78
<i>occurpa</i>	172, 174, 178	<i>astraea</i>	139, 227
<i>oviformis</i>	178	<i>rosea</i>	228
<i>plenissima</i>	230	<i>aurora</i>	78, 230
<i>polystigma</i>	175	<i>banksii</i>	130
<i>purpurea</i>	179	<i>bashkiriana</i>	172
<i>rosea</i>	178, 179	<i>bassiniana</i>	172, 174
<i>Nymphaea alba rubra</i> (Plate XV)	179	<i>della</i>	141, 198
flower	77	<i>bernieriana</i>	153, 156, 157
hybrids	78, 221, 223, 229, 231	<i>biradiata</i>	172, 174
variants	223, 230	<i>Nymphaea blanda</i> (Plate XXI)	206-207
<i>X mexicana</i>	230	phylogeny	218
<i>Nymphaea alba sphaerocarpa</i>	174, 178	seed	92
<i>platystigma erythrocarpa</i>	178, 179	stamens	84
<i>rosea</i>	178, 179	<i>Nymphaea blanda</i>	189, 200, 205, 206
<i>rubra</i>	179	<i>Nymphaea blanda fenzlana</i> (Plate XXI)	207
<i>urceolata</i>	178	<i>Nymphaea blanda</i> β <i>amazonum</i>	200, 205
<i>Nymphaea alba</i> \times <i>candida</i>	175, 223, 230	<i>Nymphaea blaudusiae</i>	217
<i>X mexicana</i>	230	<i>Nymphaea boucheana</i>	220, 232
<i>X odorata</i>	230	<i>brasilensis</i>	23
<i>rosea</i>	231	<i>brakeleyi rosea</i>	231
<i>Nymphaea albo-rosea</i>	211	<i>brownii</i>	131
<i>albo-viridis</i>	200	<i>brydonacea elegans</i>	231
<i>Nymphaea amazonum</i> (Plate XIX)	200-204	<i>cachemiriana</i>	172, 174
cleistogamy in	27, 121	<i>Nymphaea caerulea</i> (Plate VIII)	141-146, 142*, 217
flower, duration of	119, 120	anther	102
submergence of	123	carpels	85, 142*
fruit	80	culture	236
leaf	64-69, 72, 73, 77	distribution	145, 218
peduncle	78	early notices of	6-13, 17, 20
petiole	57, 59*, 60	embryo	105*

	PAGE		PAGE
<i>Nymphaea caerulea</i> , flower	80, 142*	<i>Nymphaea capensis</i> , flower, movements of	119
color of	129	hybrids	224-225
development of	97, 98	leaf	64, 65
duration of	119	notes	156-157, 160
submergence of	123	phylogeny	218
malformed	100	pollen	85
fruit	142*	roots	28
germination	106	seed	90, 92
hybrids ...221, 222, 224, 225, 226, 233		seedling, root-hairs of	111
leaf	64-66, 75*	stomata on	112
development of	95*	tuber	40*
notes	141, 145, 149, 147	used as food	235
150, 156, 100, 182		<i>Nymphaea capensis</i> madagascariensis	157
ovule, development of	102	zanzibariensis (Plate XI), 157-161, 158*	
peduncle	50*, 78	forma azurea	161
petiole	59*	rosea	161
development of	96	(See <i>N. zanzibariensis</i> .)	
phyllotaxy	43	<i>Nymphaea capensis</i> ×, leaf	71*
phylogeny	218	× <i>zanzibariensis</i> (Plate XXVII) ..	222
pollen	85*	223, 224*	227
pollination	122	pollination	122
root	28	time of floral	
root-cap	29*, 30	movements ...	119
seed	91, 92	<i>Nymphaea caroliniana</i>	231
seedling	110*	<i>nivea</i>	230
root-hairs on	111	<i>perfecta</i>	231
stomata of	112	<i>rosea</i>	231
stamens	142*	<i>caspari</i>	179
stem structure	44, 46*	<i>caspari</i>	179
tuber	40	<i>caspari</i>	179
used for food	235	<i>alba</i>	179, 230
<i>Nymphaea caerulea</i>	146, 147, 151, 153	<i>ceramica</i>	211
<i>albida</i>	146, 147	<i>Nymphaea charpentieri</i>	216
<i>Nymphaea caerulea</i> <i>albiflora</i>	145	<i>Nymphaea chromatella</i>	230
<i>Nymphaea caerulea</i> ×, petiole	59*	<i>chrysantha</i>	230
× <i>capensis</i>	225	<i>coerulea</i> : <i>N. caerulea</i> ..	
malformed flower	100	<i>colossae</i>	231, 237
× <i>zanzibariensis</i> (Plate XXVI) 225-226		<i>columbiana</i>	232
time of floral		<i>Nymphaea cordata</i>	216
movements ...	110	<i>Nymphaea coteka</i>	198
<i>Nymphaea cahlara</i>	211	<i>oremata</i>	211
<i>Nymphaea calliantha</i>	151*, 153	<i>orematula</i>	211
<i>tenula</i>	152-153	<i>cubogermen</i>	174
<i>calophylla</i>	210, 218	<i>cyanea</i>	140, 153
<i>candida</i> (Plate XV)	173-175, 173*	<i>decaniana</i>	232
compared with <i>N. fennica</i> ..	170, 171	<i>delicatissima</i>	232
distribution	171, 173-174	<i>dentata</i>	194, 196
early notices of	14, 18, 19, 20	flower	77, 78
flower	80	movements of	119
hybrids	222, 223, 231	hybrids	161, 220, 231-233
leaf	173*	leaf	75, 77
notes	174-175, 178	peduncle	50*, 78
phylogeny	217, 218	petiole, vascular system of ..	63*
seed	90, 92	pollen	85
sepals	81	seed	92
stem	38	vitality of	106
varieties	174-175	seedling, leaf-structure	112
<i>Nymphaea candida</i> <i>oocarpa</i>	175	root-hairs of	111
<i>semiaperta</i>	171, 175	tuber	40
<i>sphaeroides</i>	175	<i>dentata grandiflora</i>	232
<i>Nymphaea candida</i> × <i>alba</i>	175	<i>magnifica</i>	232
<i>Nymphaea candidissima</i>	230	<i>devontensis</i>	193, 195*, 199, 200
<i>candolleana</i>	185, 205	floral movements	119
<i>Nymphaea capensis</i> (Plate X) ..136, 141, 140, 153-157, 154*		history of	210, 220, 223, 232
early notices of	22-24	peduncle	78
flower	80, 154*	<i>diana</i>	232

	PAGE		PAGE
<i>Nymphaea diana grandiflora</i>	232	<i>Nymphaea flava</i> , stem, structure, 43, 45, 46, 49, 50*, 53, 54	55*, 56
<i>discoloridis</i>	175, 178	stipules	48-49, 53
<i>discolor</i>	141	<i>Nymphaea flavo-virens</i> (Plate VI)	137-139, 138*, 217
<i>Nymphaea dollololum</i>	217	floral movements	119
<i>doris</i>	217	hybrids	221, 222, 224, 228
<i>dubla</i>	217	leaf	64-66, 74-76, 75*
<i>dumasii</i>	216*	peduncle, adjustment to water	
<i>Nymphaea castaneensis</i>	232	level	119*
<i>cburaca</i>	230	petals	138*
<i>edgeworthii</i>	140	phylogeny	218
<i>edulis</i>	198, 199	pistil	86, 138*
<i>Nymphaea elegans</i> (Plate IV)	131-134, 132*, 217	pollen	85*
culture	237	root	28
flower	80, 132*	contractile	33*, 35, 113
movements of	119	structure	31, 33, 34, 37*, 38*
hybrids	227	root-cap	29-30
leaf	64, 66, 75*	seed	90, 92*
phylogeny	218	stamens	83, 138*
pistil	86, 132*	stem	30
seed	90, 93	stolons	41
seedling, root-hairs* of	111	tuber formation	47
stomata on	112	<i>Nymphaea flavo-virens</i> × <i>sambartensis</i> (Plate XXIX),	227-228
stamens	83, 132*	root, contrac-	
tuber	40*	tile	113
<i>Nymphaea elegans</i> × <i>sambartensis</i> (Plate XXVIII) ..	221	root, structure	35
"	226*, 227	<i>Nymphaea flavo-virens</i> × <i>sambartensis rosea</i>	228
floral movements	119	leaves ..	75*
germination	106	<i>Nymphaea foetida</i>	201
root epidermis	30	<i>foliis obovatis maximis</i>	135
structure, 31-36, 38*		<i>cordatis integerrimis</i>	168
<i>Nymphaea ellisiana</i>	231	<i>fragrans</i>	208
<i>emirrensis</i>	153, 156, 157	<i>Frank Trelease</i>	232
<i>eoecica</i>	216	<i>froedelii</i>	223, 230
<i>erythrocarpa</i>	176, 177, 178	<i>fulva</i>	230
<i>esculenta</i>	198, 199	<i>Nymphaea gardneriana</i> (Plate XXIV)	308
<i>esqueleta</i>	61, 230	<i>Nymphaea George Huster</i>	223, 231, 232
<i>esumbonata</i>	211	<i>Nymphaea gibbertii</i>	210-211
<i>Nymphaea fennica</i>	170-171	<i>gigantea</i> (Plate III)	188-191
flower	77, 78	culture	237, 239
leaf	77	distribution	180, 213
phylogeny	218	flower	78
sepals	81	duration of	119
stem	40, 41	malformed	100
<i>Nymphaea fenziiana</i>	200, 207	leaf	64-66, 75*
<i>flava</i> (= <i>N. mexicana</i>)	163, 164*	petiole	58, 59*
distribution	213	phyllotaxy	42
flower, duration of	119	phylogeny	217, 218
submergence after anthesis	123, 124	pistil	86
fruit	87, 89, 90, 164*	seed	92
hybrids	78, 229	stamens	83, 85
leaf	65*-69, 72, 75*, 76	tuber	40*
development of	95	used as food	235
nodal structure	51*, 53-54	<i>Nymphaea gigantea forma alba</i>	130
peduncle	59*	<i>rosea</i>	130
perennating body	74-75	<i>Nymphaea gigantea violacea</i>	130-131
petiole	57*-61, 59*	<i>Nymphaea gladstoniana</i>	223, 230
development of	96-97	peduncle	78
phyllotaxy	43	seed	90, 93
pollen	85	seedling	109
root structure	30, 31, 83-85	× <i>mexicana</i>	223
seed	90, 91, 93, 94	<i>glandulifera</i>	206
seedling	109, 165*	<i>gloriosa</i>	223, 231
mucilage hairs on	112	<i>goudotiana</i>	204
stamen	84*, 164*	<i>gracilis</i>	136, 137, 139
stem	40		
hairs on apex of	43, 44		

	PAGE		PAGE
<i>Nymphaea gracilis</i> , petiole (= <i>N. flavo-virens</i>)	59*	<i>Nymphaea lotus</i> , phylogeny	218
seed (= <i>N. flavo-virens</i>)	92*	pollen	85
<i>azurea</i>	139, 227-228	root	28
<i>purpurea</i>	139, 227	contractile	113
<i>rosea</i>	228	hairs	111
<i>perfecta</i>	139, 228	structure	30-34, 30
<i>rubra</i>	139, 228	seed	90, 92
<i>gracillima alba</i>	230	seedling leaves	110*, 112*
<i>groyae</i>	139, 227	stamen, development of	101-102
<i>guianensis</i> . (See <i>N. guianensis</i> .)		stem structure	43-46
<i>guianensis</i>	74, 140, 147, 149, 150	stipules	55, 56
<i>Nymphaea gysperum</i>	216, 217	stolon	48, 49
<i>Nymphaea hastata</i>	211	tuber	40*
<i>Nymphaea heudelotii</i>	147-150, 148*, 153	used as food	106, 235
<i>nana</i>	149*-150	varieties	193, 196, 197
<i>Nymphaea hepatica</i>	164	<i>Nymphaea lotus</i>	135, 198, 199, 205
<i>hirta</i>	211	<i>angusta</i>	193
<i>hookeriana</i>	141	<i>lutea</i>	193
<i>indica</i>	22, 23, 24	<i>monastraea</i>	243
<i>brahma</i>	232	<i>oblonga</i>	193
<i>Hofgartner Graebener</i>	232	<i>stuhlmanni</i>	101
<i>leis</i>	232	<i>a. acyphlla</i>	104
<i>spira</i>	232	<i>a. lotus</i>	193
<i>integrifolia</i>	201	<i>β con difolia</i>	193
<i>intermedia</i>	172	<i>γ pubescens</i>	193
<i>James Brydon</i>	231	<i>Nymphaea lotus</i> × <i>rubra</i>	231-232
<i>James Gurney</i>	231	× <i>sturtianii</i>	193
<i>Nymphaea jamesoniana</i> (Plate XXIII)	209	<i>Nymphaea lucida</i>	230
<i>Nymphaea juddii</i>	232	<i>lutea</i>	14, 16, 18-22, 25, 103, 167, 211
<i>holimiana</i>	211	<i>macrophylla</i>	211
<i>howensis</i>	232	<i>maculata</i>	141, 180
history of	220-221	<i>madagascariensis</i>	157
<i>hosteletschii</i>	172, 174	early notices of	22
<i>laetia</i>	232	seed	92, 93
<i>colorata</i>	232	<i>malabarica</i>	23, 140
<i>Nymphaea lasiophylla</i> (Plate XXII)	207-208	<i>mariae lagranget</i>	232
<i>latior</i>	216	<i>maritima albidia</i>	230
<i>Nymphaea laydackeri</i>	229	<i>carnea</i>	231
<i>fulgens</i>	230	<i>chromatella</i>	219, 221, 230
<i>fulva</i>	230	culture	236, 238
<i>Maacke</i>	229	floral movements	119
<i>Milne</i>	229	idioblasts in petiole	62
<i>laetia</i>	230	leaf	54, 60
<i>purpurea</i>	231	peduncle	78
<i>rosea</i>	223, 229	root structure	30*, 31,
<i>prolifera</i>	223, 229	33, 34	
<i>leiboldiana</i>	186, 183	<i>flammea</i>	231
<i>Nymphaea lignitica</i>	216	<i>ignea</i>	231
<i>Nymphaea Niacina</i>	229	<i>rona</i>	231
<i>Milne</i>	229	<i>rubra punctata</i>	231
<i>Nacata</i>	136	<i>maurii</i>	130, 228
<i>longifolia</i>	211	<i>maximiliani</i>	186, 210
<i>Nymphaea lotus</i> (Plate XVI)	194-196, 199	<i>Nymphaea mexicana</i> (Plate XIII)	163-167, 164*, 205, 217
distribution	196, 213-215	distribution	167, 213
early notices of	3-12, 16, 18, 20, 21-25	floral movements	119
embryo	105*	hybrids	221, 229, 230, 231
embryo-sac	108	leaf	54, 65, 67, 68, 72, 75*
flower, development of	97-100, 99*	perennating body	41, 42*, 74, 75
submergence after anthesis	123	petiole	57, 59*, 61
symmetry of	100	phylogeny	218
transformed to tubers	106	pollen	85
<i>funiculus</i>	104	stolon	41
hybrids	108, 219, 220, 222, 223, 231, 232	(See also <i>N. flava</i> .)	
notes	193, 196, 197, 199, 200	<i>Nymphaea maritima</i>	131, 137, 139
peduncle	78	<i>Nymphaea micrantha</i> (Plate IX)	144-147
petiole	58, 59*	hybrids	224

	PAGE		PAGE
<i>Nymphaea micrantha</i> , vivipary	74	<i>Nymphaea odorata gigantea</i> , leaf of seedling	110*
<i>Nymphaea microphylla</i>	211	petiole	59*
<i>millettii</i>	172	phylogeny	218
<i>minima</i>	211	variants	230
<i>minor</i>	172	<i>Nymphaea odorata glabra</i>	188
<i>lutea</i>	22	<i>luciana</i>	222, 231
<i>Nymphaea minuta</i>	216	<i>maxima</i>	192
<i>Nymphaea</i> Mrs. C. W. Ward	130, 221, 228*	<i>Nymphaea odorata minor</i>	183-188, 184*
leaf	75*	flower	78, 184*
tuber	40	movements of	119
<i>nacchelli</i>	198	leaf	54, 64
<i>Nymphaea nallini</i>	216	petiole	61
<i>Nymphaea neglecta</i>	172, 174	pistil	87, 184*
<i>nelumbo</i>	211	root epidermis	30
<i>nervosa</i>	136	stem	38
<i>niobe</i>	232	variants	230
<i>nitida</i>	175, 211	<i>Nymphaea odorata minor floribus roseis</i>	186
<i>nocturna</i>	201	<i>pumila</i>	230
<i>nouchali</i>	198	<i>Nymphaea odorata rosea</i>	186
<i>nubica</i>	146	flower	77
<i>obtusiloba</i>	161	hybrids	221, 222, 230
<i>Nymphaea odorata</i>	3, 179-182, 181*	leaf	72
aril	91*, 104	petiole	61
distribution	182, 213	variants	223, 230
embryo	101-105*	<i>Nymphaea odorata rosea</i> × <i>mexicana</i>	229
embryo sac	102*, 103	× <i>tuberosa</i>	231
flower, duration of	119	<i>Nymphaea odorata rubra</i>	180, 230
odor of	121	<i>naviculata</i>	231
submergence after anthesis,	123, 124	<i>sulfurea</i>	221, 229
germination	107	petiole	59*
hybrids	223, 229, 233	phyllotaxy	43
introduction to cultivation	236	<i>superba</i>	231
leaf	54, 65-73, 71*, 181*	<i>villosa</i>	56, 188
development of (Plate II)	95, 96	<i>villosissima</i>	188
megaspore	102	<i>Nymphaea odorata</i> × <i>mexicana</i>	229
nodes	182, 192, 197	<i>Nymphaea officinalis</i>	211
ovule	102*	<i>amarana</i> (Plate XXX)	193, 232
peduncle	59*, 62, 78	fertility	223
petals	83, 181*	floral movements	119
petiole	50-58, 60-62, 73*, 76*	pedigree	233
phyllotaxy	42	<i>orbiculata</i>	211
phylogeny	218	<i>originesiana</i>	194
pistil	87-90, 181*	hybrids	220, 231, 232, 233
pollen	85	<i>originesiana-rubra</i>	232
pollination	121, 122	fertility	223
root	28	history	220
hairs	111	<i>Nymphaea ovalifolia</i>	150*-161
origin of	36	<i>oxypetala</i> (Plate XXV)	210
structure	31-36, 32*	distribution	210, 213
seed	90-94	leaves	54
sepals	81, 82, 181*	phylogeny	218
stem (Plate II)	88	stamens	84
dissection of apex	95-97	<i>Nymphaea parkeriana</i>	186
plagiotropism of	114	<i>parviflora</i>	176, 177, 178
structure	43*-46, 44*	<i>parva</i>	19, 22
stipules (Plate II)	55*, 56	<i>Nymphaea parvula</i>	216
<i>Nymphaea odorata</i>	211	<i>Nymphaea passiflora</i>	208
<i>carolinensis</i>	231	<i>pauciradiata</i>	172, 174
<i>caroliniana</i>	222, 231	<i>pennsylvanica</i> (Plate XXVI)	221, 222, 225*-226
<i>chloritica</i>	180	floral movements	119
<i>esquistia</i>	223	<i>pentapetala</i>	211
<i>Nymphaea odorata gigantea</i>	186-188, 187*, 210	<i>permiata</i>	172
culture	237	<i>petrolana</i>	153
flower	187*	<i>planchonii</i>	164, 206
leaf	65	<i>poecilia</i>	141
		<i>Nymphaea polyrhiza</i>	216

	PAGE		PAGE
<i>Nymphaea polysepala</i>	211*	<i>Nymphaea rudgeana</i> , petiole	59*
<i>pringlei</i>	186	phylogeny	218
<i>pseudopyramaea</i>	148	seed	92
<i>Nymphaea pubescens</i> (Plate XVII)	141, 188-189	stamens	84
early notices of	23	<i>Nymphaea rudgeana</i> β <i>amazonum</i>	200, 206
leaf	64	<i>rufescens</i>	140, 147, 211
notes	193, 197, 199	<i>sagittariaefolia</i>	209
seed	92	<i>sagittata</i>	198, 199, 211
<i>Nymphaea pulchella</i>	130, 210	<i>sagittifolia</i>	211
<i>pulcherrima</i>	146, 221, 222, 224*, 225	<i>sanguinea</i>	180, 231
<i>pumila</i>	211	<i>scutifolia</i>	141, 153, 156
<i>punctata</i>	140, 172, 211	hybrids	233
<i>pygmaea</i>	168	<i>seignoretii</i>	78, 280
ovary	84	<i>semiaperta</i>	172, 174
stamens	84	<i>semilateralis</i>	198, 199
<i>pygmaea alba</i>	168, 223, 229	<i>serrata</i>	131
<i>helvola</i>	220	<i>sinuata</i>	205
<i>Queen Elizabeth</i>	232	<i>smithiana</i>	232
hybrids	232-233	<i>spectosa</i>	130
pedigree	233	<i>sphaerocarpa</i>	179
<i>Queen Elizabeth</i> \times <i>caerulea</i>	232	<i>rybra</i>	179
<i>dentata</i>	232	<i>spiralis</i>	180
<i>reichardiana</i>	211	<i>splendens</i>	170-178
<i>reniformis</i>	180-189	<i>Nymphaea stellata</i>	140-141, 193, 217
<i>repanda</i>	131	culture	230
<i>rhodantha</i>	141	early notices of	3, 5, 23
<i>rubra</i>	223, 230	leaf	75, 77
<i>rubra</i>	230	notes	141, 146
<i>rosacea</i>	230	phyllotaxy	42, 43
<i>rosea</i>	180, 199	phylogeny	218
<i>funiculus</i>	104	pollination	122
<i>rotundifolia</i>	170-178	respiration	118
<i>Nymphaea roussetii</i>	216	seed	92*
<i>Nymphaea rubicunda</i>	232	synonymy	140, 211
<i>Nymphaea rubra</i> (Plate XVIII)	199	vivipary	74
color in relation to insects	121	<i>Nymphaea stellata</i>	131, 141, 153
culture	230, 238	<i>bulbillifera</i>	146
flower	77-79	<i>Nymphaea stellata</i> <i>cynna</i>	140
malformed	100	<i>Nymphaea stellata</i> <i>castanensis</i>	227
movements of	119	<i>macrantha</i>	153
hybrids	193, 219-221, 223, 231, 232	<i>parviflora</i>	140
in Hindu literature	3-5	<i>Nymphaea stellata</i> <i>versicolor</i> (Plate VII)	140-141
leaf	65, 67, 68*, 71, 73, 75-77	<i>Nymphaea stellata</i> <i>canzianensis</i>	157
absorption of water by	116	<i>stellata</i> β	140
development of	93, 99	<i>Nymphaea stellata</i> \times <i>caerulea</i>	225
notes	193, 199, 200	<i>stenaspisota</i> (Plate XXI, XXIV)	209
peduncle	78	<i>stuhlmanni</i>	161-162*
petiole	57, 58, 60, 73*, 76*	flower	77, 102*
growth of	115	leaf	162*
phyllotaxy	43	<i>Nymphaea sturtevantii</i>	231-232
phylogeny	217, 218	leaf, hairs on	73
pollen	85	peduncle	78
respiration	118	petiole	57*
seed	90, 92*	<i>suaveolens</i>	211
stamens	83	<i>Nymphaea sulfurea</i> (Plate XII)	161
stolon	48, 49, 52	flower	77
<i>Nymphaea rubra rosea</i>	199	<i>Nymphaea sulfurca</i>	220
floral movements	110	<i>grandiflora</i>	220
leaf	65	<i>sumatrana</i>	211
peduncle	78	<i>Nymphaea teneriervia</i> (Plate XXI)	180, 210
<i>Nymphaea rubra</i> \times <i>ortgiesiana</i>	232	<i>Nymphaea tenuinervia</i>	210
<i>rudgeana</i> (Plate XX)	25, 135,	<i>Nymphaea tetragona</i> (Plate XIV)	3, 167-171,
136, 164, 200, 204-206, 222		168*, 210, 217, 219	
cleistogamy	27, 121	culture	236-238
floral movements	119, 120	distribution	170, 213, 214
leaf	64	flower	78, 80, 168*

	PAGE		PAGE
<i>Nymphaea tetragona</i> , flower, movements of	119	<i>Nymphaea tuberosa parva</i>	180, 192
odor of	121	stem	88
submergence after anthesis,	124	<i>plena</i>	280
fruit	90	<i>richardsoni</i>	280
germination	108	development of leaf	97
hybrids	223, 229, 231	<i>rosea</i>	281
leaf	54, 64-66, 77	<i>rubra</i>	281
of seedling	110*	<i>superba</i>	281
structure of	67*-69, 72, 73, 76	<i>Nymphaea tuberosa</i> × <i>odorata rosea</i>	281
ovary	84	<i>Nymphaea tusilaginifolia</i>	186
peduncle	50*	<i>umbilicalls</i>	211
petiole	56-60, 59*, 78*	<i>undulata</i>	136
phylogeny	218	<i>union</i>	230
plsttl	86	<i>urceolata</i>	170-178
pollen	85	<i>venusta</i>	176-178
stamens	84, 168*	<i>versicolor</i>	131, 140
stem	40	flower	78
used as food	170	<i>victoria</i>	211
varieties	170	<i>violacea</i>	130
<i>Nymphaea tetragona angusta</i>	170	<i>vivipara</i>	74, 146
<i>helvola</i>	221, 229, 236, 237	<i>voenzelti</i>	172
<i>lata</i>	170	<i>William Doogue</i>	231
<i>Nymphaea tetragona</i> × <i>alba</i>	229	<i>William Falconer</i>	231
× <i>alba rubra</i>	229	<i>William Stone</i> (Plate XXIX)	139, 221, 222, 227*-228
× <i>mexicana</i>	229	<i>Nymphaea zanzibariensis</i>	157, 217, 236
<i>Nymphaea tetragonanthos</i>	168	culture	227
<i>thermalls</i>	194, 196, 197	embryo sac	103
carpels	84	flower	77, 78, 80, 158*
distribution	214	movements of	119, 120
leaf	75, 77	funiculus	104
phylogeny	214, 217	germination	107
seed	92	hybrids	221, 222, 226, 227
stamens	84	introduction into Europe	106
× <i>rubra</i>	232	leaf	64-68
× <i>scutifolia</i>	232	structure	69, 70, 72
<i>trispala</i>	80, 135	notes	141
<i>tropaeolifolia</i>	136, 205	peduncle	78, 79
<i>Nymphaea tuberosa</i>	189*-192	idioblasts in	62
carpels	84, 87, 88	petiole	59*, 61
flower, movements of	119	idioblasts in	62
submergence of	124	vascular structure of	63*
hybrids	222, 223, 230, 231	phyllotaxy	42
leaf	54, 65, 67-69, 72, 76*, 190*, 191*	phylogeny	218
peduncle	59*, 78	plsttl	86, 158*
idioblasts in	62	pollen	85
petiole	56, 57, 59*-61	root	28
idioblasts in	62	hairs	111
vascular system of	63*	seed	90
phyllotaxy	42	seedling leaves	110*
phylogeny	218	structure	112
pollination	121, 122, 192	stamens	83, 158*
root structure	30-35	tuber	40*
seed	90, 92	<i>Nymphaea zanzibariensis rosea</i> , leaves	75*
sepals	81, 82, 189*	tuber	40*
stamens	84, 189*	<i>Nymphaea zanzibariensis</i> ×	227
stem	38, 80*	floral movements	110
apex, dissection of	95	ovary	87, 88
hairs on	73*	peduncle	78
structure	44-46	petiole	57, 58, 61
stigma	84*, 189*	sepals	81
stolon structure	49	stipules	55*
stomata	192	× <i>capensis</i>	227
tubers	38, 190*, 192	<i>Nymphaea zenkeri</i>	197*-198
variants	230	<i>Nymphaeaceae</i> , flower, symmetry of	101
<i>Nymphaea tuberosa flavescens</i>	230	leaf, development of	97
<i>maxima</i>	189, 192		

	PAGE		PAGE
Nymphaeaceae, roots, adventitious	28	Phylogeny	217-218
primary	28	Picciola on pollination	122
Nymphaeae apocarpae (see Apocarpae)	137	Pickering	5, 6, 7
hybrids	225-228	Piso	21
syncarpae (see Syncarpae)	163	Platia	24
hybrids	220-232	Platll. (See Carpels.)	
Nymphaelinae, geological history	215	Plagiotropism of stems	114
phylogeny	218	Planchon on <i>Cyanca</i>	86
Nymphaeites arethuseae	216	dead insects in flowers	122
brongniartii	216	hybrids	220, 223, 232
charpentieri	216	malformed flower	100
Nymphaeites lignitica	216	pneumatocyst	60
ludwigii	217	viviparous leaves	74
microrhizus	216, 217	Planting	237-239
palaeopygmaeus	217	Plecty	6, 8
polyrhizus	218	Pliny	12, 13, 16-18, 23
saxonica	217	on disappearance of flowers at night	119
tener	217	Plukenet	23
thulensis	217	Plutarch	9
weberi	217	Pneumatocyst	60
Nymphaea	125	Podophyllum	24
Odors of flowers	121	Pollen	85*
Opening and closing of flowers	11-13, 17, 21, 23, 119-121	Pollination, arrangements for	121-123
Ornithogalum	23	artificial	240
Osiris	8	Pond for culture	237, 238
Ovary	84-88, 86*	Prichard	10
development of	98-99	Primary root	28, 108*, 109-111, 110*
morphology of	80-87, 98	Principal area	66
Ovules	87	vein	66
development of	102*-104	Proclus	9, 10
Pachycyst	70	Propagation	239
Padma	4, 5	Proterogyny	121
Papyrus	8, 9	Pseudostomata	72
Parkinson	20, 23	Quercus leaf	72
Parlatore on air-canals of petiole	58	Rachiborski on inflorescence	99
Paxton on vivipary	74	phyllotaxy	42-43
Payer	80	Radikefer, suggestion on <i>N. mexicana</i>	107
on development of flower	97-99, 101	Ramses II	6-9
leaf	95	Ranunculus sceleratus	115
Peduncle	78, 79	Ray, John	22
air-canals of	59*, 78, 79	Receptacle	79, 86*
apogeiotropism of	114	morphology of	98
development of	99	Respiration	117-118
idioblasts in	62	Rimbach on contractile roots	113
in fruit	123-124	Robertson	188, 192
vascular structure of	53, 54, 59*, 63, 79	on pollination	121, 122
Pelta	65	Rose	5
Pentstemon, phylogeny of	218	Root	27-28
Perennating body of <i>N. mexicana</i>	41, 42*, 74, 75	air-canals in	31-33
Perisperm	93, 94*, 105	development of	37*, 38*
absorption by embryo	109	apical growth	30-37
Petals	80, 82, 83, 90	structure	29*-30
air-canals in	82	branching of	28
development of	98-99	cap	28
morphology of	100-101	structure	20-30
Petiole	56	contractile	28, 33*, 35, 113
adjustment to water-level	114, 115	cortex of	31-34, 32*
air-canals	58, 59*-60, 62, 76*, 90, 112	epidermis of	30*-31
apogeiotropism	114	geotropism of	113
development of	96, 97	hairs	100, 111
idioblasts in	60-62	idioblasts in	32-33
structure of	56, 57*-60, 62, 73*, 76	development of	37
vascular system of	59*, 62-64, 63*, 76-77	structure	31-36, 32*
Phyllotaxy	42, 43	Roots of seedlings	109

	PAGE		PAGE
Roots, origin of	28, 36	Stolons of <i>Lotos</i> group	41, 48, 49, 52*, 53
number of	28 ^c	<i>N. flava</i>	48, 49, 53
vascular system of	35-36*	<i>N. flavo-virens</i>	41
Rowan, Mrs.	131	<i>N. mexicana</i>	41
Russow on cuticle of air-canals	60	<i>N. tuberosa</i>	49
Sagot	54	Stomata	54, 67, 68, 77, 192
Sakountala	4	development of	97
Salix leaf	72	on back of leaf	185
Saporta	215, 216	seedling leaves	112*
Schenck	216	sepals	81
on crystals	61	stamens	84, 85
<i>N. thermalis</i>	214	Sturtevant	182
Schillborsky	214	Submergence of flower after anthesis	123-124
Schilling	72, 73	Suspensor	104, 105*
Schulz on pollination of <i>N. alba</i>	121, 122	Symmetry of flower	100, 101
Schumann on inflorescence	99	<i>Symphylopleura</i>	87
Schweinfurth	6-9	Syncarplae (see <i>Nymphaeae syncarplae</i>)	168
Sedum	11	ovary	86*
Seed	90-94*, 92*, 93*	phylogeny	217, 218
as food	3, 10-12, 235	pistil	86, 87, 89
collection of	239	stamens	84
distribution of	27	Tank for culture	236-238
germination of	106-107, 109-110	Tassi on anesthesia of flowers	121
keeping of	230	Tavera	235
vitality of	106-107	Tetrasepaleae, phylogeny	218
Seedlings	107-110*, 108*	Theophrastus	11, 10, 20, 23
structure of	110-112	Thyll-like bodies	61, 62, 77, 79
Sepals	79, 81, 82, 89, 90	in sepals	81
air-canals in	81, 82	Thylosis	48*
development of	97-99	Tittmann on seedling	107
morphology of	100-101	Tournefort	24, 25
Shedding of epidermis of root	30-31	Tragus	14, 16
Siber on conditions for germination	106	Transpiration	116-117
Slukovics on <i>N. thermalis</i>	214	Tratinick	5, 6
Simonkal on <i>N. thermalis</i>	214	Treat, Mrs. Mary, on <i>N. flava</i>	40
Sloane	24	Trécul	37, 49
Soar, J. J.	56	Treviranus on seedling	107
Soll for culture	237, 238	Tricker, Wm.	221
Solereder	60, 61	on germination	106, 107
Specific names, use of	136	culture	237, 238, 240, 241
Stahl on mucilage hairs	73	Trileptalis	24
Stamens	83-85, 84*	Trisepaleae, phylogeny	218
development of	98, 101, 102	Tubers	40*, 47, 190*
morphology of	101	as food	3, 7, 10, 17, 22, 235
Starch in peduncles	78	drawn down by contractile roots	118
petioles	58	early leaves from	75*
roots	34	of seedling	108*, 110
seed	93, 94	Turner, Wm.	14
stems	46, 113	Unger	6
stipules	56	Vallant	25
Staub on <i>N. thermalis</i>	214	Vallaneria spiralis	124
Stiles	30, 49, 52, 53	Van Houtte	74
Stem	27, 31-42, 39*	Van Rheebe	23
apex, dissection of	95	Van Tieghem on crystals	61
development of tissues in	97	root cap	20
geotropism of	114	Varietal names, use of	136
hairs on	73*	Vascular system of leaf	70, 71*
starch stored in	113	node	51*, 53, 54
structure	43*-48, 44*, 46*	peduncle	53, 54, 59*, 63, 79
of seedling	112	petiole	59*, 62-64, 63*, 70-77
vascular system of	49-54, 50*	root	35-36*
Stigma	84*, 88	seedling	111, 112
Stipules	54-55*	stem	49-54, 50*
development of	96		
structure of	55, 56		

	PAGE		PAGE
Venation of leaves	66, 67, 115	Water poppy	238
Vernation of leaves	66, 67*	Waters on germination of <i>N. odorata</i>	107
Vesling	20, 23	Weberbauer on seeds	90-94, 104
Victoria	211, 215, 216	Weiss on idlioblasts	60
heat evolved in flower	123	Wessel and Weber	216
inflorescence	99	Whewell	8
introduction of	236	Wiedemann	6, 8, 9
leaf	65, 67, 77	Wilkinson	1*, 6*, 7*-10
phylogeny	218	Williams	4
pollination	122		
root hairs absent in	111*	Xanthantha	163
seed	93	flower	77
stem structure	46	leaf	64
Victoria cruziana as food	233	ovary	84
Victoria fitzroyana	128	peduncle	78
Victoria regia	232	petiole, air-canals of	58
introduction of seeds into England	106	phylogeny	218
leaf	69	pistil	86
Vitality of seeds	106, 107	pollination	122
Vivipary	74	receptacle,	70
		seed	90
Wächter	75	stems	84
on effect of removing roots and leaves	116	stem	39
on stomata of water-leaves	77, 112	Xanthantha	163
Waldstein and Kitthel	214	Xanthostigma	173
Water, absorption by leaf	116		
course of, in plant	116-117	Zea mays, vascular structure of	64
Water corn	235	Zizyphus	11
leaves	54, 74-76*, 77, 110*, 112*, 190*, 195*	Zuccarini	107
level, adjustment of parts to	114-115, 118-119*		



